

**SECOND OPERABLE UNIT
REMEDIAL INVESTIGATION REPORT
SYOSSET LANDFILL
SYOSSET, NEW YORK**

December 1995

Prepared for

**Town of Oyster Bay
Department of Public Works
150 Miller Place
Syosset, New York 11791**

Prepared by

**Geraghty & Miller, Inc.
125 East Bethpage Road
Plainview, New York 11803
(516) 249-7600**

**as a Subconsultant to
Lockwood, Kessler & Bartlett, Inc.
One Aerial Way
Syosset, New York 11791**

370961




**SECOND OPERABLE UNIT
REMEDIAL INVESTIGATION REPORT
SYOSSET LANDFILL
SYOSSET, NEW YORK**

January 25, 1996


Geraghty & Miller, Inc. prepared this report as a subconsultant to Lockwood, Kessler & Bartlett, Inc. and is submitting this report to the Town of Oyster Bay Department of Public Works for work performed at the Syosset Landfill, Syosset, New York. The report was prepared in conformance with Geraghty & Miller's strict quality assurance/quality control procedures to ensure that the report meets industry standards in terms of the methods used and the information presented. If you have any questions or comments concerning this report, please contact one of the individuals listed below.

Respectfully submitted

GERAGHTY & MILLER, INC.



Lauren E. Sjogren
Project Scientist/Regional Data Quality
Assurance Manager



Michael F. Wolfert
Project Advisor

LES/MFW:vk

G:\PROJECT\LOCKESBANY0029.099\REPORTS\RI95.DOC



CONTENTS

| | <u>Page</u> |
|---|-------------|
| EXECUTIVE SUMMARY | E-i |
| 1.0 INTRODUCTION..... | 1-1 |
| 1.1 BACKGROUND..... | 1-1 |
| 1.2 SITE DESCRIPTION..... | 1-2 |
| 1.3 PURPOSE AND SCOPE..... | 1-2 |
| 1.4 OVERVIEW OF SITE CONDITIONS..... | 1-4 |
| 2.0 METHODOLOGY..... | 2-1 |
| 2.1 OFF-SITE GROUNDWATER STUDY..... | 2-1 |
| 2.1.1 Drilling Methods | 2-3 |
| 2.1.1.1 Air-Rotary (Barber) Method..... | 2-5 |
| 2.1.1.1.1 Exploratory Borings..... | 2-5 |
| 2.1.1.1.2 Surface Casings..... | 2-7 |
| 2.1.1.2 Modified Mud-Rotary Method | 2-8 |
| 2.1.1.3 Hollow-Stem Auger Method | 2-9 |
| 2.1.2 Formation Sampling..... | 2-9 |
| 2.1.3 Field Testing for Leachate Indicators | 2-10 |
| 2.1.4 Termination Depths of Exploratory Borings | 2-11 |
| 2.1.5 Geophysical Logging..... | 2-12 |
| 2.1.6 Monitoring Well Construction..... | 2-14 |
| 2.1.7 Surveying of Monitoring Wells | 2-16 |
| 2.1.8 Well Development..... | 2-16 |
| 2.1.9 Well Repair/Well Deletions | 2-17 |
| 2.1.9.1 Repair of Monitoring Well SY-7..... | 2-17 |
| 2.1.9.2 Deletion of Monitoring Wells W-3, W-4, and SY-5 from the Groundwater Sampling Program..... | 2-18 |



CONTENTS (continued)

| | <u>Page</u> |
|---|-------------|
| 2.1.10 Measurement of Water Levels..... | 2-18 |
| 2.1.10.1 Regional Water Levels | 2-19 |
| 2.1.10.2 Site Water Levels | 2-19 |
| 2.1.11 Groundwater Sampling Program..... | 2-19 |
| 2.1.11.1 Revised Parameter List..... | 2-20 |
| 2.1.11.2 Quality Control Samples | 2-21 |
| 2.1.11.3 Well Evacuation and Sample Collection..... | 2-22 |
| 2.1.11.4 Decontamination of Sampling Equipment..... | 2-23 |
| 2.1.11.5 Data Validation | 2-23 |
| 2.2 OFF-SITE SUBSURFACE GAS STUDY | 2-24 |
| 2.2.1 Gas Well Installation and Construction | 2-24 |
| 2.2.2 Gas Monitoring | 2-25 |
| 2.3 SUBSURFACE GAS WELL INSTALLATIONS AND MONITORING FOR THE ON-SITE REMEDIAL DESIGN PROGRAM..... | 2-26 |
| 3.0 RESULTS..... | 3-1 |
| 3.1 HYDROGEOLOGY | 3-1 |
| 3.1.1 Regional Horizontal Direction of Groundwater Flow | 3-2 |
| 3.1.2 Site-Specific Horizontal Direction of Groundwater Flow | 3-3 |
| 3.1.2.1 Shallow Zone | 3-3 |
| 3.1.2.2 Intermediate Zone | 3-3 |
| 3.1.2.3 Deep Zone..... | 3-5 |
| 3.1.3 Vertical Direction of Hydraulic Gradient..... | 3-5 |
| 3.1.4 Comparison of Horizontal and Vertical Hydraulic Gradients | 3-6 |
| 3.2 GROUNDWATER QUALITY | 3-8 |
| 3.2.1 Volatile Organic Compounds | 3-8 |
| 3.2.2 Leachate Indicator Parameters | 3-11 |



CONTENTS (continued)

| | <u>Page</u> |
|---|-------------|
| 3.2.3 Metals (Total and Dissolved) | 3-11 |
| 3.2.4 Contaminants of Concern..... | 3-13 |
| 3.3 CONTAMINANT DISTRIBUTION..... | 3-14 |
| 3.3.1 Shallow Zone | 3-14 |
| 3.3.2 Intermediate Zone | 3-15 |
| 3.3.3 Deep Zone..... | 3-17 |
| 3.3.4 Comparison of Zones | 3-18 |
| 3.4 CONTAMINANT MIGRATION..... | 3-18 |
| 3.5 FATE AND TRANSPORT OF CONTAMINANTS | 3-23 |
| 3.5.1 Potential Routes of Migration | 3-24 |
| 3.5.1.1 Vadoze Zone..... | 3-24 |
| 3.5.1.2 Phreatic Zone | 3-24 |
| 3.5.1.3 Advection | 3-25 |
| 3.5.1.4 Dispersion or Diffusion | 3-25 |
| 3.5.2 Characterization and Behavior of Contaminants | 3-26 |
| 3.5.2.1 Sorption..... | 3-26 |
| 3.5.2.2 Volatilization | 3-27 |
| 3.5.2.3 Transformation..... | 3-27 |
| 3.5.2.4 Precipitation - Oxidation Reduction | 3-29 |
| 3.5.3 Analysis of Exposure Pathways..... | 3-29 |
| 3.6 POTENTIAL IMPACTS FROM RECHARGE BASINS | 3-30 |
| 3.6.1 Leachate Indicator Parameters | 3-30 |
| 3.6.2 VOCs | 3-30 |
| 3.7 OFF-SITE SUBSURFACE GAS..... | 3-31 |



CONTENTS (continued)

| | <u>Page</u> |
|--------------------------------------|--------------------|
| 4.0 CONCLUSIONS | 4-1 |
| 4.1 OFF-SITE GROUNDWATER STUDY | 4-1 |
| 4.2 SUBSURFACE GAS STUDY | 4-5 |
| 5.0 REFERENCES | 5-1 |

TABLES

| | |
|-------|--|
| 2-1. | Summary of Field and Laboratory Measurements of Leachate Parameters of Groundwater Samples Collected During Drilling of Exploratory Borings SY-3DD and PK-10D During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York. |
| 2-2. | Summary of Construction Details of New and Preexisting Monitoring Wells Installed at and Near the Syosset Landfill, Syosset, New York. |
| 2-3. | Summary of Survey Data, Syosset Landfill, Syosset, New York. |
| 2-4. | Summary of Water-Level Elevation Data Collected on October 29, 1993 from Nassau County Observation Wells in the Vicinity of the Syosset Landfill During the Second Operable Unit Remedial Investigation, Syosset, New York. |
| 2-5. | Summary of Water-Level Elevation Data Collected from Site Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York. |
| 2-6. | Revised Parameter List for the Second Operable Unit Remedial Investigation Groundwater Sampling Program, Syosset Landfill, Syosset, New York. |
| 2-7. | Summary of Construction Details for Gas Monitoring Wells, Syosset Landfill, Syosset, New York. |
| 3-1a. | Summary of Horizontal Hydraulic Gradient Data for Shallow, Intermediate, and Deep Hydrogeologic Zones, Based on Potentiometric Surface Maps (Figures 3-4 to 3-9), Second Operable Unit Remedial Investigation of the Syosset Landfill, Syosset, New York. |
| 3-1b. | Summary of Vertical Hydraulic Gradient Data, Second Operable Unit Remedial Investigation of the Syosset Landfill, Syosset, New York. |



TABLES (continued)

- 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells during the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-5. Summary of Gas Well Monitoring Data, Syosset Landfill, Syosset, New York.

FIGURES

- 1-1. Site Location.
- 1-2. Locations of Groundwater Monitoring Wells, Gas Monitoring Wells, Soil Borings, and Lines of Hydrogeologic Section, Syosset Landfill, Syosset, New York.
- 2-1. Locations of Nassau County Monitoring Wells and Public Supply Wells Within Approximately 2 Miles of the Syosset Landfill, Syosset, New York.
- 3-1. North-South Hydrogeologic Cross Section A-A'.
- 3-2. East-West Hydrogeologic Cross Section B-B'.
- 3-3. Regional Potentiometric Surface of the Shallow Zone of the Magothy Aquifer in the Vicinity of the Syosset Landfill on October 29, 1993, Syosset, New York.
- 3-4. Potentiometric Surface of the Shallow Zone of the Magothy Aquifer on October 28, 1993, Syosset Landfill, Syosset, New York.
- 3-5. Potentiometric Surface of the Shallow Zone of the Magothy Aquifer on November 24, 1993, Syosset Landfill, Syosset, New York.
- 3-6. Potentiometric Surface of the Intermediate Zone of the Magothy Aquifer on October 28, 1993, Syosset Landfill, Syosset, New York.



FIGURES (continued)

- 3-7. Potentiometric Surface of the Intermediate Zone of the Magothy Aquifer on November 24, 1993, Syosset Landfill, Syosset, New York.
- 3-8. Approximate Direction of Groundwater Flow in the Deep Zone of the Magothy Aquifer on October 28, 1993, Syosset Landfill, Syosset, New York.
- 3-9. Approximate Direction of Groundwater Flow in the Deep Zone of the Magothy Aquifer on November 24, 1993, Syosset Landfill, Syosset, New York.
- 3-10. Concentrations of Volatile Organic Compounds Detected in Site Monitoring Wells Screened in the Shallow Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-11. Concentrations of Volatile Organic Compounds Detected in Site Monitoring Wells Screened in the Intermediate Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-12. Concentrations of Volatile Organic Compounds Detected in Site Monitoring Wells Screened in the Deep Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-13. Concentrations of Leachate Parameters Detected in Site Monitoring Wells Screened in the Shallow Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-14. Concentrations of Leachate Parameters Detected in Site Monitoring Wells Screened in the Intermediate Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-15. Concentrations of Leachate Parameters Detected in Site Monitoring Wells Screened in the Deep Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-16. Concentrations of Metals Detected in Site Monitoring Wells Screened in the Shallow Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.
- 3-17. Concentrations of Metals Detected in Site Monitoring Wells Screened in the Intermediate Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.



FIGURES (Continued)

- 3-18. Concentrations of Metals Detected in Site Monitoring Wells Screened in the Deep Zone of the Magothy Aquifer, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

APPENDICES

- A. January 20, 1993 Letter to Lockwood, Kessler & Bartlett, Inc. Regarding Proposed Screen Settings.
- B. March 11, 1993 Letter to Lockwood, Kessler & Bartlett, Inc. Regarding Collapse of Well Boring PK-10I.
- C. Sample/Core Logs.
- D. Statistical Procedure Used to Establish Termination Criteria.
- E. Geophysical Logs.
- F. Monitoring Well Construction Logs.
- G. Analytical Results of Development Water from Monitoring Well PK-10D.
- H. Water Sampling Logs/Chain-of-Custody Forms.
- I. Analytical Results of Analyte-Free Water Samples from IEA Laboratories, Inc.
- J. Gas Well Construction Logs.
- K. Memorandum from Lockwood, Kessler & Bartlett, Inc. Regarding the Installation and Monitoring of On-Site Subsurface Gas Monitoring Wells as Part of the First Operable Unit Remedial Design Program.
- L. Background Information Text and Related Tables and Figures from OU-1 RI Report.
- M. Regional Background Groundwater Quality.
- N. Correction Factors Used for Gamma Logs.
- O. July 13, 1995 Industrial Area Survey Memo.



APPENDICES (Continued)

- P. November 9, 1995 Groundwater Sampling Results Memo.



**SECOND OPERABLE UNIT
REMEDIAL INVESTIGATION REPORT
SYOSSET LANDFILL
SYOSSET, NEW YORK**

EXECUTIVE SUMMARY

Geraghty & Miller, Inc. was retained by the firm of Lockwood, Kessler & Bartlett, Inc., (LKB), under contract to the Town of Oyster Bay (Town), Syosset, New York, to conduct the Second Operable Unit (OU-2) Remedial Investigation (RI) of the Syosset municipal landfill site (Syosset Landfill) in Syosset, New York. The OU-2 RI focussed on the potential off-site environmental impacts of the Syosset Landfill, whereas the Interim, or First Operable Unit (OU-1) RI focussed on on-site environmental impacts from the Syosset Landfill.

The Syosset Landfill is located in central Nassau County in the Town of Oyster Bay, Syosset, New York. The site is rectangular in shape and encompasses approximately 38 acres. The offices and facilities of the Town of Oyster Bay Department of Public Works are located adjacent to the landfill to the east and occupy approximately 15 acres. The Town controls access to the site, and the entire landfill area is enclosed by a 6-foot high cyclone fence. The site is bounded by the Long Island Expressway and Miller Place to the southeast, Cerro Wire & Cable Corporation to the southwest, and the Long Island Railroad (LIRR) to the northwest. A residential area and the South Grove Elementary School border the site to the northeast. Topographically, the site is relatively flat and at a similar elevation to the surrounding area.

The OU-2 RI was conducted from October 1992 to March 1994 and consisted of an Off-Site Groundwater Study and an Off-Site Subsurface Gas Study. During the OU-1 RI, leachate-impacted groundwater was detected beneath the Syosset Landfill at the northern (downgradient) property boundary and elevated concentrations of methane were detected at the southwestern part of the landfill. The purposes of the Off-Site Groundwater Study were to determine the off-site extent of a leachate plume that may be emanating from the landfill, confirm the direction of groundwater flow, and



determine the plume thickness. The purpose of the Off-Site Subsurface Gas Study was to determine the extent of off-site subsurface gas migration from the landfill.

The scope of work for conducting the Off-Site Groundwater Study and Off-Site Subsurface Gas Study included the following:

- Installation of nine monitoring wells at four locations (three locations off-site [eight wells] and one location on-site [one well]).
- Measurement of water levels in 18 Nassau County observation wells in the vicinity of the Syosset Landfill.
- Performance of two rounds of water-level measurements in site monitoring wells before each of the two groundwater sampling rounds.
- Collection of two rounds of groundwater samples from nine new monitoring wells and 12 preexisting on-site monitoring wells. Samples were analyzed for VOCs, metals (total and dissolved), and leachate indicator parameters.
- Installation of three new off-site subsurface gas monitoring wells.
- Collection of data from the three new off-site and four preexisting on-site gas monitoring wells during 3 days of relatively low or falling barometric pressure.

In addition to the scope of work described above, five new on-site gas monitoring well clusters (two wells per cluster) were installed and monitored as part of the OU-1 Remedial Design Program, which was conducted concurrently with the OU-2 RI.

The Syosset Landfill is underlain by more than 1,000 feet of unconsolidated deposits of sand, silt, gravel, and clay, which rest unconformably on Precambrian bedrock. The unconsolidated deposits are separated into three formations: the Upper Glacial Formation (top), the Magothy Formation



(middle), and the Raritan Formation (bottom). At the Syosset Landfill site, the Magothy Formation is the most significant in terms of potential contaminant migration in groundwater. The Upper Glacial Formation is completely unsaturated (dry) beneath the site; the Lloyd Sand Member of the Raritan Formation is separated from the Magothy Formation by the Raritan Clay, which is approximately 160 feet thick, and, in addition, the Lloyd Sand Member lies at too great a depth to be considered as a potential contaminant migration pathway. Site monitoring wells tap or screen three zones (shallow, intermediate, and deep) of the Magothy Formation. Wells screened in the intermediate zone include on-site "deep" wells installed during the OU-1 RI (and considered intermediate for the purposes of the OU-2 RI) and intermediate wells installed during the OU-2 RI.

Hydrogeologic conditions encountered during the OU-2 RI are generally consistent with the OU-1 RI and published data. The regional potentiometric surface map of the shallow zone of the Magothy Formation indicates that the position and orientation of the regional groundwater divide is virtually the same as it was during the OU-1 RI and is south of the landfill. Regional shallow groundwater flow was documented to be in a north-northeasterly direction near the site and is also consistent with the OU-1 RI findings. The site-specific horizontal direction of groundwater flow in the shallow, intermediate, and deep zones of the Magothy Formation is generally to the north. However, in the shallow zone on-site, groundwater also flows from the west and east parts of the site toward the center of the landfill before moving north toward the Town park. The direction of the vertical hydraulic gradient is predominately downward in the study area. The vertical hydraulic gradient is approximately four times steeper than the horizontal hydraulic gradient; this is consistent with the proximity of the site to the regional groundwater divide.

Based on leachate indicator concentrations and metals concentrations, landfill-impacted groundwater has migrated to two of the three off-site well cluster locations (Town park and Roadway property); however, the recharge basin location apparently does not show landfill impacts based on these parameters. The greatest impacts off-site are in the intermediate zone of the Magothy Formation.

The significantly steeper vertical hydraulic gradient, as compared to the horizontal gradient, has resulted in landfill-derived contaminants moving off-site into the intermediate zone (Wells PK-10I and



RW-12I). The total concentrations of VOCs in off-site intermediate wells at the Town Park (PK-10I) and at the Recharge Basin (RB-11I) are consistent with the total VOC concentrations detected in the on-site shallow monitoring wells. These concentrations are also consistent with regional background degradation of groundwater quality. In particular, this is true for Well RB-11I, which is located outside the easternmost limiting groundwater flowline from the landfill. The total concentration of VOCs in RW-12I is anomalously high, several times higher than the concentrations encountered in any other monitoring well during either the on-site or off-site RIs. The high concentrations of volatile organic compounds (particularly PCE and TCA) in Well RW-12I appear to be from a source(s) located in the Industrial Park west of the LIRR tracks. This conclusion is based on the fact that RW-12I is located hydraulically downgradient of the westernmost edge of the landfill and is located hydraulically downgradient of, and adjacent to, an industrial area located west of the LIRR tracks. This conclusion is further supported by the lack of degradation of PCE and TCA in Well RW-12I; the identification of properties within the previously unsewered Industrial Park who used and/or are using PCE and TCA and have had reported releases; regional hydrogeologic data indicating the Industrial Park is upgradient of Well RW-12I; and the low levels of these compounds found on-site in both the soil and groundwater during the OU1 RI.

Landfill gas (primarily methane) was detected in one of the gas wells on the southwestern part of the landfill and is consistent with the findings of the OU-1 RI. Landfill gas was not detected in the three new off-site subsurface gas monitoring wells and does not appear to be migrating off-site. (See appendix K for the results of gas monitoring conducted separately by LKB as part of the OU-1 Remedial Design Program.)

G:\PROJECT\LOCKESBANY0029.099\REPORTS\EXECSUM.DOC



**SECOND OPERABLE UNIT
REMEDIAL INVESTIGATION REPORT
SYOSSET LANDFILL
SYOSSET, NEW YORK**

1.0 INTRODUCTION

Geraghty & Miller, Inc. was retained by the firm of Lockwood, Kessler & Bartlett, Inc. (LKB), under contract to the Town of Oyster Bay (Town), Syosset, New York, to conduct the Second Operable Unit (OU-2) Remedial Investigation (RI) of the Syosset municipal landfill site (Syosset Landfill) in Syosset, New York (Figure 1-1). The OU-2 RI focused on the potential off-site environmental impacts of the Syosset Landfill. LKB provided overall project management for the OU-2 RI, and will provide the engineering services necessary to complete the Feasibility Study (FS) portion of the OU-2 Remedial Investigation/Feasibility Study (RI/FS) process for the Syosset Landfill site, if required. The OU-2 RI was performed in accordance with the protocols and methodologies detailed in the Site Operations Plan (SOP) (Geraghty & Miller, Inc. 1992), which was approved by the U.S. Environmental Protection Agency (USEPA) on May 15, 1992. The SOP was developed and prepared in accordance with the OU-2 RI Work Plan (Geraghty & Miller, Inc. 1991) to ensure that the RI would be completed in a manner consistent with the National Contingency Plan (NCP). This OU-2 RI Report describes the activities and findings of the OU-2 RI.

1.1 BACKGROUND

The Interim, or First Operable Unit (OU-1) RI, which was conducted from April 1987 to September 1989, focused on on-site environmental impacts from the Syosset Landfill. The OU-1 RI Report (Geraghty & Miller, Inc. 1989) contains extensive background information about the site and this information has been provided in Appendix L of this report for the reader's convenience. The FS portion of the OU-1 RI was conducted by LKB. The OU-1 RI/FS was officially completed in September 1990 when the USEPA issued the Record of Decision (ROD) for the site on September 27, 1990.



1.2 SITE DESCRIPTION

The Syosset Landfill is located in central Nassau County in the Town of Oyster Bay, Syosset, New York (Figure 1-1). The site is rectangular in shape and encompasses approximately 38 acres (see Figure 1-2). The offices and facilities of the Town of Oyster Bay Department of Public Works are located adjacent to the landfill to the east and occupy approximately 15 acres. The Town controls access to the site, and the entire landfill area is enclosed by a 6-foot high cyclone fence.

As shown on Figures 1-1 and 1-2, the site is bounded by the Long Island Expressway and Miller Place to the southeast, Cerro Wire & Cable Corporation to the southwest, and the Long Island Railroad (LIRR) to the northwest. A residential area and the South Grove Elementary School border the site to the northeast. Topographically, the site is relatively flat and at a similar elevation to the surrounding area.

Two basins owned by Nassau County border the site to the northeast and the north. Nassau County recharge basin RB-284 borders the site to the northeast and Nassau County storm-water basin SWB-571 borders the site to the north. Another Nassau County storm-water basin, SWB-218, is located about 700 feet northeast of RB-284. Storm-water runoff from the neighboring residential area collects in these basins and then the water either evaporates or recharges the underlying Magothy aquifer.

1.3 PURPOSE AND SCOPE

The OU-2 RI consisted of an Off-Site Groundwater Study and an Off-Site Subsurface Gas Study. During the OU-1 RI, leachate-impacted groundwater was detected beneath the Syosset Landfill at the northern (downgradient) property boundary and elevated concentrations of methane were detected at the southwestern part of the landfill. The purposes of the Off-Site Groundwater Study were to determine the off-site extent of a leachate plume that may be emanating from the landfill, confirm the direction of groundwater flow, and determine the plume thickness. The purpose of the



Off-Site Subsurface Gas Study was to determine the extent of off-site subsurface gas migration from the landfill.

The scope of work for conducting the Off-Site Groundwater Study and Off-Site Subsurface Gas Study included the following:

- Installation of nine monitoring wells at four locations (three locations off-site [eight wells] and one location on-site [one well]).
- Measurement of water levels in 18 Nassau County observation wells in the vicinity of the Syosset Landfill.
- Performance of two rounds of water-level measurements in site monitoring wells before each of the two groundwater sampling rounds.
- Collection of two rounds of groundwater samples from nine new monitoring wells and 12 preexisting on-site monitoring wells. Samples were analyzed for VOCs, metals (total and dissolved), and leachate indicator parameters.
- Installation of three new off-site subsurface gas monitoring wells.
- Collection of data from three new gas monitoring wells during 3 days of relatively low or falling barometric pressure.

In addition to the scope of work described above, five new on-site gas monitoring well clusters (two wells per cluster) were installed and monitored as part of the OU-1 Remedial Design Program, which was conducted concurrently with the OU-2 RI.



1.4 OVERVIEW OF SITE CONDITIONS

As previously stated, the OU-1 (Interim) RI was conducted to evaluate the on-site environmental impacts of the Syosset Landfill. The OU-1 RI consisted of three separate studies: the On-Site Groundwater Study, the Landfill Dimension Study, and the Subsurface Gas Study (on-site). Field work for the OU-1 RI began in April 1987 and was completed in June 1988; thereafter, landfill gas and water levels were monitored on a monthly basis until September 1989. The overall scope of work for the OU-1 RI consisted of the following field activities:

- Installation of nine groundwater monitoring wells to supplement six preexisting groundwater monitoring wells.
- Installation of 19 gas monitoring wells.
- Drilling of four borings through the fill.
- Collection and analysis of fill samples.
- Collection and analysis of groundwater samples.
- Collection and analysis of landfill gas samples.
- Pressure testing of gas monitoring wells.
- Monthly monitoring of landfill gas and groundwater levels.

The findings of the OU-1 RI are summarized below.

The Syosset Landfill is underlain by more than 1,000 feet of unconsolidated deposits of sand, silt, gravel, and clay, which rest unconformably on Precambrian bedrock. The unconsolidated deposits are separated into three formations: the Upper Glacial Formation (top), the Magothy Formation (middle), and the Raritan Formation (bottom). The upper 60 to 100 feet of unconsolidated sand and gravel deposits in the vicinity of the landfill comprises the Upper Glacial Formation. Before landfilling began, up to 90 feet of this formation was removed during sand mining at the site. The Magothy



Formation, which is comprised of finer sands, silts and clays directly underlies the Upper Glacial Formation and is in hydraulic connection with it. This formation (Magothy) was not fully penetrated during either the OU-1 or OU-2 RIs. However, based on published data, the Magothy Formation is approximately 540 feet thick beneath the site and may extend as deep as 630 feet below land surface. The Raritan Formation is the third, and deepest unconsolidated formation beneath the site and rests on the bedrock surface. Comprising this formation is the Raritan Clay Member, which is approximately 160 feet thick and occurs directly beneath the Magothy, and the Lloyd Sand Member, which is approximately 240 feet thick and rests on the bedrock surface more than 1,000 feet below land surface.

At the Syosset Landfill site, the Magothy aquifer is the most significant in terms of potential contaminant migration in groundwater. The Upper Glacial Formation is completely unsaturated (dry) beneath the site; the Lloyd Sand Member of the Raritan Formation is separated from the Magothy aquifer by the Raritan Clay, which is approximately 160 feet thick, and, in addition, the Lloyd Sand Member lies at too great a depth to be considered as a potential contaminant migration pathway.

Water-level measurements were collected during the OU-1 RI on a regular basis in both on-site monitoring wells (installed under the direction of ERM and Geraghty & Miller) and off-site Nassau County monitoring wells. These data were used to prepare potentiometric surface maps that depicted the horizontal direction of groundwater flow regionally in the shallow zone of the Magothy aquifer and on-site in the shallow and "deep" zones of the Magothy aquifer. (These "deep" monitoring wells are considered intermediate depth monitoring wells for the purposes of the OU-2 RI.) As indicated on these maps, the dominant horizontal component of shallow groundwater flow was in a northeasterly direction in the Magothy aquifer at and in the vicinity of the site (with a more northerly groundwater flow direction in the "deep" zone at the site), and the regional groundwater divide was located south of the site. A comparison of the horizontal and vertical hydraulic gradients indicated that the vertical gradient is more pronounced than the horizontal gradient, thus confirming that the site is in a deep-flow recharge zone.

During the OU-1 RI, groundwater quality underneath and at the downgradient edge of the landfill was found to be impacted by leachate, as evidenced by elevated concentrations of indicator



parameters (chloride, ammonia, alkalinity, hardness, total dissolved solids [TDS], specific conductance, iron, and ammonia). The concentrations and distribution of the leachate indicator parameters suggested the existence of an off-site plume of leachate-impacted groundwater. Although volatile organic compounds (VOCs) were detected in some groundwater monitoring wells, the concentrations were within a range detected in monitoring wells screened at similar depths in the Magothy Formation in other areas of Nassau County (Dvirka and Bartilucci Consulting Engineers 1986). Further, the distribution of VOCs was not consistent with a contiguous body (plume) of groundwater contamination with the landfill as the source.

The landfill consists of approximately 38 acres and appears to be divided into two lobes with the deepest lobe located in the western part of the site (with a maximum thickness of 90 feet) and the other lobe near the eastern part of the site (with a maximum thickness of 70 feet). These depths represent the most current information available and were determined during the OU-1 Remedial Design Program (Converse Consultants East, PC 1993). Detectable concentrations of VOCs, base/neutral extractable compounds, polychlorinated biphenyls (PCBs), and metals were found during the OU-1 RI in some samples of fill in a distribution indicative of random disposition of industrial, commercial, and residential waste.

The only available data on waste deposition at the site is provided in the ERM Northeast Report (ERM 1983). According to ERM (1983), from 1933 to 1967, the Syosset Landfill accepted the following types of waste: commercial, industrial, residential, demolition, agricultural, sludge, and ash. After 1967, the site accepted only industrial and scavenger cesspool waste until the site closed in 1975.

During the OU-1 RI, the concentrations of landfill gas were found to be consistently highest in the gas monitoring wells located along the long axis of the landfill and in the southwestern corner of the site. Landfill gas concentrations were lower in wells located along the northern, eastern, and southern boundaries of the site; frequently, concentrations of landfill gas were undetectable, or nearly so, at these boundary areas. Landfill gases did not appear to be migrating vertically upwards under significant



(detectable) pressure and appeared to be limited in horizontal extent. VOCs were detected in samples of landfill gas, but not in consistent concentrations or distributions.



2.0 METHODOLOGY

In this section, the methodologies employed for conducting the Off-Site Groundwater Study and Off-Site Subsurface Gas Study are discussed. These methods were described in detail in the SOP (Geraghty & Miller 1992). Any variances from the SOP are discussed.

2.1 OFF-SITE GROUNDWATER STUDY

The Off-Site Groundwater Study was conducted to determine the off-site extent of a leachate plume that may be emanating from the landfill, confirm the direction of groundwater flow, and determine the plume thickness. During the off-site groundwater study, nine new monitoring wells were installed and two rounds of groundwater quality samples were collected from the nine new wells and from 12 of the 15 preexisting on-site wells.

Prior to commencing the drilling program, Delta constructed a decontamination (decon) pad near the center of the landfill. The decon pad was constructed of poured concrete with a sloped surface that funneled water to a drain. Drilling rigs and down-hole equipment (including drill casings and surface casings) were steam cleaned over the pad before and after drilling at each location. The drillers also staged supplies and equipment that was not being used near the decon pad and surrounded the area with a 3-foot high wire mesh fence.

Drill cuttings from each of the four drilling locations were disposed of at a designated location on-site. Disposal details are provided in Sections 2.1.1.1 (Air-Rotary Barber Method), 2.1.1.2 (Modified Mud-Rotary Method), and 2.1.1.3 (Hollow-Stem Auger Method).

The nine monitoring wells were installed at four locations by Delta Well & Pump Company, Inc. (Delta) of Ronkonkoma, New York, and their subcontractor, Catch Inc. (Catch) of Weedsport, New York. Eight of the wells (PK-10S, PK-10I, PK-10D, RB-11S, RB-11I, RB-11D, RW-12I, and RW-12D) were installed at three off-site locations and one well (SY-3DD) was installed at an on-site location. The locations of the nine new and 15 preexisting monitoring wells are shown on Figure 1-2.



A Geraghty & Miller field hydrogeologist was present during all drilling activities to ensure that the protocols specified in the SOP were followed. The field hydrogeologist's responsibilities included collecting and logging soil samples, monitoring drilling and decontamination operations, recording groundwater data, deciding on final drilling depths and screen intervals (in consultation with the Geraghty & Miller project manager and director, the USEPA, the Town, and LKB), preparing boring logs and well completion diagrams, and recording well installation procedures. The USEPA provided oversight at key points during the drilling program (e.g., steam cleaning, geophysical logging, setting the well) through their consultant Camp, Dresser & McKee, Inc. (CDM).

The SOP specified that 11 monitoring wells would be installed at five locations: two on-site locations (near Well Clusters SY-3 and SY-6) and three off-site locations (Nassau County Recharge Basin No. SWB-218, the Town Park, and Roadway Express, Inc. [Roadway]). At the on-site locations, a deep well was to be installed next to each of the two existing on-site monitoring wells; and three new wells (shallow, intermediate, and deep) were to be installed at each off-site location. However, during a meeting held on February 18, 1993 with the USEPA, the Town, LKB, and Geraghty & Miller, it was agreed that two of the 11 monitoring wells would be deleted from the drilling program. The two wells to be deleted were the shallow well proposed at the Roadway property (RW-12S) and the deep upgradient well proposed adjacent to existing Monitoring Well Cluster SY-6 (SY-6DD). The reasons for these deletions are given below.

Monitoring Well RW-12S was deleted from the drilling program at the suggestion of the USEPA with the concurrence of the Town, LKB, and Geraghty & Miller. This decision was made during the February 18, 1993 meeting based on a review of the OU-1 RI potentiometric surface maps which indicated that the groundwater flow direction was more easterly in the shallow zone of the Magothy than the flow direction observed in the "deep" zone of the Magothy aquifer. Therefore, the consensus at the meeting was that a shallow well was not needed at this location (Roadway). Monitoring Well SY-6DD was deleted from the drilling program because the analytical results of the groundwater samples collected for leachate indicator testing during the drilling of Exploratory Boring SY-3DD indicated that the highest leachate concentrations were detected at a depth that correlates



with the screen zone of the existing "deep" well at Monitoring Well Cluster SY-6. Therefore, this existing "deep" well was judged to be a suitable upgradient monitoring well.

During the February 18, 1993 meeting, a decision was also made to collect groundwater samples from Well PK-10I (located at the Town Park) immediately following installation to determine the presence/absence of VOCs. Well PK-10I was selected for sampling as it monitors the vertical interval of the aquifer containing the highest concentrations of leachate indicator parameters; if VOCs were present off-site, they would likely be detected in this part of the aquifer. The purpose of sampling Well PK-10I in advance of the scheduled groundwater sampling rounds was to reevaluate the number and locations of monitoring wells for the drilling program based on whether VOCs were present and at what concentrations. Samples were collected on May 4, 1993, but the well had to be resampled on June 2, 1993 because data validation indicated a laboratory quality control problem. The June results were also validated and were judged acceptable; however, the data were inconclusive because although VOCs were detected, they were found at relatively low concentrations. Therefore, on July 16, 1993, another meeting was held with the USEPA, the Town, LKB, and Geraghty & Miller and it was agreed that the drilling program should be continued as specified in the SOP. On July 26, 1993, drilling resumed at Nassau County Storm-Water Basin No. SWB-218.

2.1.1 Drilling Methods

Three drilling methods were employed during the Off-Site Groundwater Study: (1) the air-rotary (Barber) method, (2) the modified mud-rotary method, and (3) the hollow-stem auger method. The air-rotary method was used for drilling the two exploratory borings and installing a deep well at these locations, as well as for installing 10-inch diameter surface casings for three of the six borings drilled by the modified mud-rotary method. The modified mud-rotary method was used to drill and install the remaining wells except for one of the two shallow wells, which was installed by the hollow-stem auger method.



The Town obtained permission from Nassau County and Gordon Floral Realty, Inc. (Gordon) to drill and install off-site monitoring wells at Nassau County Recharge Basin No. SWB-218 (Wells RB-11S, RB-11I, and RB-11D) and the property leased by Roadway (Wells RW-12I and RW-12D). A security guard was supplied by Delta to ensure public safety at these two off-site drilling locations, as well as at the Town park, the third off-site drilling location. The security guard arrived on-site at the end of each work day before the drillers left the site and did not leave until the drillers returned the following day. Round-the-clock security coverage was also provided on the weekends and holidays. Thus, each drilling site was monitored continuously until work was completed and safe site conditions were restored at each off-site drilling location. In addition, a temporary fence was placed around each active off-site drilling site and signs were posted to warn the public of the on-going work. After the monitoring wells were installed at the three off-site drilling sites, the sites were restored to their original condition to the extent practicable.

At the February 18, 1993 meeting, "Greenstuff," an environmental lubricant, was approved by the USEPA for lubricating the drill rods. Hydrant water was used by the drillers to maintain hydraulic head in well borings to suppress sand heave, to mix drilling mud and grout, and for steam cleaning. Samples of this hydrant water were periodically collected by the Geraghty & Miller field hydrogeologist for analysis of VOCs to monitor the quality of water being used during the drilling process. Samples were sent to EcoTest Laboratories, Inc. (EcoTest) of North Babylon, New York for analysis by USEPA Method 601. VOCs were not detected in any of the hydrant water samples collected.

The three drilling methods used to install the nine monitoring wells are briefly described in the following sections, and detailed information on problems that were encountered in the field or variances to the SOP protocols is provided. A detailed description of the drilling methods can be found in the SOP.



2.1.1.1 Air-Rotary (Barber) Method

The air-rotary drilling method (Barber rig) was used to drill the two exploratory borings (SY-3DD and PK-10D) and to install deep monitoring wells in each of them. As previously stated, this method was also used to install surface casings for three of the six monitoring well borings drilled by the modified mud-rotary method.

2.1.1.1.1 Exploratory Borings

The purpose of drilling the two exploratory borings was to provide on-site and off-site vertical characterization of water quality and lithology. The air-rotary drilling method was selected for this task because representative groundwater and lithologic samples can be collected using this method (see the OU-2 RI Work Plan for the rationale for using this method). The water-quality and lithologic data collected from the exploratory borings were used to determine the depths of the monitoring wells and screen settings. Details on the criteria used to terminate the exploratory borings are provided in Section 2.1.4 (Termination Depths of Exploratory Borings), and details on field testing for leachate indicators are provided in Section 2.1.3 (Field Testing for Leachate Indicators). Drilling of the two exploratory borings was performed by Catoh, Delta's subcontractor.

From November 9, 1992 to December 1, 1992, Catoh drilled the first on-site exploratory boring (SY-3DD) next to existing Monitoring Well Cluster SY-3 to a depth of 540 feet below land surface (see Figure 1-2). During a site meeting on October 30, 1992 between representatives of the USEPA and Geraghty & Miller, it was agreed that the location of this boring would be moved approximately 50 feet west of the originally proposed location to minimize noise levels for residents living adjacent to the landfill.

Boring SY-3DD was advanced by rotating successively smaller diameter steel casings to the termination depth. Catoh started drilling with a 16-inch diameter casing until it could not be advanced further because of frictional resistance. The next casing was 10 inches in diameter and was inserted to



the bottom of the 16-inch diameter casing (i.e., the bottom of the boring); drilling then continued until the 10-inch diameter casing could not be advanced further because of frictional resistance. This process was repeated using 8-inch diameter casing, followed by 6-inch diameter casing, until the termination depth was reached. The SOP had specified starting with 14-inch diameter steel casing, but this size was not available when the drilling began.

After each 20-foot section of casing was advanced and another section of casing had been welded to the length of casings in the boring, the cuttings from inside the casing were removed using compressed air from the drill rig. However, beyond a depth of approximately 300 feet, extremely fine-grained sand from the formation began heaving inside the casing, and water from a hydrant located on Gordon Drive had to be used to wash the sand heave out of the boring. This was accomplished by pumping the water through the drill rods as the bit was lowered back into the bottom of the boring, washing out the sand heave in the process.

Because of the resistance encountered during the drilling of SY-3DD, the 8-inch diameter casing could not be advanced to the termination depth (540 feet). Therefore, the boring was completed using 6-inch diameter casing in accordance with the SOP, and a 2-inch diameter well was installed in SY-3DD with the approval of the USEPA.

From December 9 to 31, 1992, the off-site exploratory boring (PK-10D) at the Town Park was drilled. Drilling proceeded smoothly at this location, sand heaving was more easily controlled, and Catox was able to advance the 8-inch diameter casing to completion depth (499 feet) by flushing out the boring after each 20-foot section of drill casing had been installed. Boring PK-10D was completed as a 4-inch diameter well.

The cuttings for both borings were stored in pits next to each boring. After each boring was completed, Delta removed the cuttings from the pits and disposed of them at a designated location at the landfill. The native soil originally removed to create the pits was used to refill them, but clean fill was needed to supplement the native soil to fill the pit for PK-10D.



2.1.1.1.2 Surface Casings

The Barber rig was also used to install 10-inch diameter, black-steel, surface casings for three of the six well borings (PK-10S, RB-11I, and RB-11D) that were drilled by the modified mud-rotary method. This work was performed by Catoh before Delta began mud-rotary drilling to prevent the loss of drilling mud to the permeable coarse sand and gravel deposits that extend from land surface to a depth of approximately 140 feet. The Barber rig was not used to install the surface casings for the two mud-rotary borings (RW-12I and RW-12D) at the Roadway property because an access agreement for drilling had not been executed between the Town and the property owner (Gordon) before Catoh demobilized their rig and equipment from the site. In addition, PK-10I needed to be relocated (following Catoh's departure) due to problems at the original drilling site for this boring/well (see Section 2.1.1.2 [Modified Mud Method]). Therefore, with the approval of the USEPA, the surface casings for these three borings/wells were installed using a combination of two drilling methods: hollow-stem auger and cable tool. Delta subcontracted United Well and Pump Corporation (United), Bohemia, New York to perform the cable tool drilling for PK-10I, while Delta performed the cable tool drilling for RW-12I, RW-12D and also the hollow-stem auger drilling at all three of these locations. The hollow-stem auger rig was used to advance 12-inch inside diameter augers as deep as possible (approximately 50 feet). Then, the cable tool rig was used to install and advance 10-inch diameter surface casing through the auger flights as far as possible (approximately 107 feet for Well RW-12I, 105 feet for Well RW-12D, and 128 feet for Well PK-10I). This combination of techniques effectively cased-off the upper permeable deposits at these three boring/well locations.

Catoh also installed a 10-inch diameter surface casing next to existing upgradient Well Cluster SY-6; this casing was for the deep well (SY-6DD) that was to be drilled by the modified mud-rotary method at this location. However, as discussed in Section 2.1 (Off-Site Groundwater Study), Well SY-6DD was deleted from the drilling program since existing Well SY-6D could serve the same purpose which was to monitor the deep zone upgradient of the landfill. Delta sealed the surface casing at this location using a tremie pipe to pump cement/bentonite grout from the bottom of the casing to land surface and also welded a steel plate over the top of the casing.



2.1.1.2 Modified Mud-Rotary Method

The modified mud-rotary drilling method was used to drill six of the nine well borings during the OU-2 RI (PK-10S, PK-10I, RB-11I, RB-11D, RW-12I, and RW-12D). This work was performed by Delta, the prime drilling contractor, using a Failing F-10 rig. The modified mud-rotary method consisted of drilling most of the well boring using the conventional mud-rotary drilling method and then converting to the reverse rotary method for the final 30 feet of drilling. The purpose for converting to the reverse rotary method was to avoid the formation of a mudcake on the borehole wall in the screen zone. The reverse rotary method uses potable water, instead of mud, as a drilling fluid. When the modified mud-rotary method is used, wells can be developed more easily.

The screen zones for the seven monitoring wells not drilled by the air-rotary method were preselected based on the water-quality and lithologic profiles (sample/core logs and geophysical logs) from the two exploratory borings (SY-3DD and PK-10D). These screen settings were proposed by Geraghty & Miller in a January 20, 1993 letter to LKB (Appendix A) and were subsequently approved by the USEPA. The proposed screen settings for the shallow, intermediate, and deep monitoring wells were 140 to 150 feet below land surface, 350 to 360 feet below land surface, and 490 to 500 feet below land surface, respectively. Refinements to the preselected screen zones were made at the Recharge Basin (Wells RB-11S and RB-11D) based on the geophysical logs obtained from the deep boring at this location (see Section 2.1.5 [Geophysical Logging]).

Four of the five borings/wells originally proposed to be installed by the modified mud-rotary method were drilled as planned (RB-11I, RB-11D, RW-12I, and RW-12D). However, during the drilling of PK-10I at the Town Park on February 26, 1993, drilling mud circulation was lost at approximately 328 feet below land surface and could not be regained by mixing more mud or by thickening it. The well boring had collapsed by the following work day (March 1, 1993). Geraghty & Miller described the problems with Well Boring PK-10I in a March 11, 1993 letter to LKB (Appendix B); in this letter, Geraghty & Miller proposed to install the shallow well (PK-10S) at this location and to redrill the intermediate depth boring/well (PK-10I) approximately 100 feet further south. The



original PK-10I well boring was subsequently redrilled by Delta (became PK-10S) with USEPA approval using the cable tool method.

PK-10I was drilled at the proposed alternate location approximately 100 feet south of the original location. As stated in Section 2.1.1.2 (Surface Casings), the surface casing for the PK-10I replacement boring/well was installed using a combination of the hollow-stem auger method by Delta and the cable-tool method by United.

Drilling mud consisted of polymer-free, 100 percent bentonite mixed with potable hydrant water in portable, prefabricated metal bins. After the mud-rotary part of the drilling had been completed, the mud was flushed out of the hole using potable water and was pumped to a tanker truck that disposed of the drilling mud/cuttings at a designated location at the landfill. Once all the mud was removed, Delta employed the reverse rotary method to complete the final 30 feet of drilling before the borehole was geophysically logged.

2.1.1.3 Hollow-Stem Auger Method

Well Boring RB-11S at the Recharge Basin was the only well boring drilled using the hollow-stem auger method. Delta used the same rig (Failing F-10) for the auger method as for the modified mud-rotary method. The SOP had specified that three shallow monitoring wells were to be installed at the Town Park, the Recharge Basin, and the Roadway property. However, as previously discussed, the shallow well at the Roadway property (RW-12S) was deleted from the drilling program and the shallow well at the Town Park (PK-10S) was installed in the original PK-10I well boring, which had been drilled by the mud rotary method and then collapsed.

2.1.2 Formation Sampling

Formation samples were collected from the deep well borings at each of the four drilling locations (SY-3DD, PK-10D, RB-11D, and RW-12D). For the two exploratory borings (SY-3DD



and PK-10D) drilled by the air-rotary method, the Geraghty & Miller field hydrogeologist examined cuttings from the well boring on a semi-continuous basis to record the lithology. For the two deep borings drilled by the mud-rotary method (RB-11D and RW-12D), split-spoon samplers were used to collect formation samples at 20-foot intervals, and flume samples were also examined by the Geraghty & Miller field hydrogeologist on a semicontinuous basis to monitor for changes in lithology. Descriptions of the lithology were recorded on the sample/core logs provided in Appendix C.

2.1.3 Field Testing for Leachate Indicators

During drilling of the two exploratory borings (SY-3DD and PK-10D), groundwater samples were collected at 20-foot intervals and analyzed by the Geraghty & Miller field chemist for primary leachate indicators (hardness, alkalinity, ammonia) and also for secondary leachate indicators (pH, temperature, chloride, and specific conductance). The purpose of this work was to characterize the vertical water-quality profiles on-site and off-site so that the depths/screen settings for all the borings/wells could be determined. After each 20-foot section of drill casing had been installed, groundwater samples were collected with a bailer lowered through the drill rods or the annular space between the drill rods and drill casing. Samples were analyzed on-site by the Geraghty & Miller chemist.

As expected, groundwater samples that were collected from the exploratory borings were often turbid, and, as specified in the SOP, these samples were centrifuged followed by prefiltering using Whatman 2V filter membranes before they were analyzed. The leachate indicators were analyzed according to the protocols in the SOP using either a compound-specific digital titration kit (for alkalinity, hardness, and chloride) or a field meter (for ammonia, specific conductance, and pH). Temperature was also field-measured using a mercury-filled thermometer. Three replicate samples were collected from each exploratory boring (more than 20 percent of the total number of samples) and were sent to either IEA, Inc. Monroe, Connecticut or EcoTest for analysis of four of the seven leachate indicators (ammonia, alkalinity, hardness, and chloride). A summary of the field and laboratory analytical results for samples collected from both borings is presented in Table 2-1.



The results in Table 2-1 indicate that leachate parameters were detected in Exploratory Boring SY-3DD at concentrations above the established action levels (background levels) beginning at the water table; concentrations gradually increased until maximum concentrations were generally reached between 218 and 239 feet below land surface. After this interval, leachate indicator concentrations decreased until the termination depth was reached at 540 feet. In Exploratory Boring PK-10D, the concentrations of leachate parameters were generally lower than SY-3DD, except for the sampling interval between 340 and 380 feet below land surface where concentrations approached the highest concentrations detected at SY-3DD.

2.1.4 Termination Depths of Exploratory Borings

In accordance with the SOP, the termination depths of the two exploratory borings were determined using criteria established from background water-quality data obtained for monitoring and public supply wells within approximately 2 miles of the landfill (Figure 2-1). Geraghty & Miller obtained historical groundwater quality data, dating back to 1989, for leachate indicator parameters from eight Nassau County Monitoring Wells (OP-1, OP-3, P-7, P-8A, PT-2, PT-3, T-6A, and TU-1) and data, dating back to 1990, for a total of six public supply wells owned by the Plainview Water District (N4097, N6076, and N6077), the Hicksville Water District (N8249 and N6191), and the Jericho Water District (N7781). In addition, from September 24 to 28, 1992, Geraghty & Miller collected samples from all of the eight Nassau County monitoring wells listed above and all but two of the water district wells (N6191 and N7781). Samples were analyzed for leachate indicators so current data could supplement the historic data. These data were then statistically analyzed by Geraghty & Miller to establish action levels for each of the seven leachate indicators so that termination depths of the two exploratory borings (SY-3DD and PK-10D) could be determined. A different statistical method than that specified in the RI Work Plan was used to analyze the background water-quality data because the data set was smaller than expected and the specified method was not appropriate for the limited number of data points available from the wells. The rationale for using the replacement statistical method was explained in a December 3, 1992 letter from Geraghty & Miller to the USEPA (Glasser and Wolfert, pers. comm. 1992). This statistical procedure is described in Appendix D.



The action levels established for the seven leachate indicators using the replacement statistical method were lower than the action levels established using the SOP method and, therefore, being more conservative, were used to determine the termination depths of the exploratory borings. According to the RI Work Plan, Exploratory Borings SY-3DD and PK-10D were to be terminated when either of the following conditions were met:

1. The concentrations of the three primary leachate indicators (ammonia, alkalinity, and hardness) were below their respective action levels in two consecutive samples, or
2. If only one of the primary indicators remained slightly above its action level in consecutive samples, then the action levels of the three secondary leachate indicator parameters were to be evaluated. A boring was terminated when one or more of the secondary action levels were not exceeded.

2.1.5 Geophysical Logging

Natural gamma geophysical logging was conducted by Geraghty & Miller in the deep boring at each of the four drilling locations (SY-3DD, PK-10D, RB-11D, and RW-12D). Electric logging was also conducted by Geraghty & Miller in the two deep mud-rotary borings (RB-11D and RW-12D).

Gamma logging involves the measurement of naturally occurring radiation originating from geologic material opposite the borehole and provides a qualitative guide to correlating stratigraphy and evaluating permeability. Gamma radiation is emitted from certain elements that are unstable and decay spontaneously into other, more stable elements. Although other types of radiation are given off by naturally radioactive minerals (alpha and beta emissions), only gamma rays are measured in well logging because only these rays can penetrate materials such as casing and cement grout. Gamma logging has a unique advantage over electric logging because it can be performed either in cased wells or open boreholes, whereas electric logging can only be conducted in uncased boreholes filled with fluid.



The minerals commonly found in sedimentary deposits, such as clay, limestone, and sandstone, contain small amounts of radioactive potassium-40 and decay products of uranium and thorium. Potassium is an important constituent of clay, mica, feldspar, and shale, and its radioactive isotope (potassium-40) emits gamma rays. Because these materials tend to be finer grained, elevated gamma responses are often interpreted as corresponding to sediments of relatively low permeability. Coarser grained sand contains no potassium or radioactive potassium-40 and emits gamma rays at relatively low levels. Consequently, the gamma log shows more radiation (counts per second) at depths corresponding to clay or silt, and lower radiation levels (fewer counts per second) at depths corresponding to sand or sandstone layers, if the sand is mostly quartz.

Geraghty & Miller conducted the geophysical logging program using its truck-mounted EG&G Mount Sopris Model II logging system, which consists of a logger and the probe. The probe contains a scintillation-type receiver and a counting circuit. The probe, which was attached to a cable, was lowered and raised the entire length of each well while graphs were produced by the digital logger recorder, which was located in the truck. Radiation intensity for a given geologic formation was measured by the probe and expressed as the average number of counts per second. Since the logger is fully automated and the probe is factory sealed, no calibration was required.

As mentioned in Section 2.1.1.2 (Modified Mud-Rotary Method), the screen zones for all monitoring wells not drilled by the air rotary method were preselected based on the water-quality and lithologic profiles (including geophysical logs) obtained from the two exploratory borings. The preselected screen settings were adjusted for Wells RB-11S and RB-11D where the geophysical log from the deep mud rotary boring (RB-11D) indicated fine-grained material in the preselected screen zone.

Although gamma logging can be done in steel casing and is very effective in identifying low-permeability layers (clay or silt or combination), steel decreases the intensity of the gamma output. The larger the casing diameter, the more the gamma output is reduced, and a correspondingly larger correction factor is needed to adjust the gamma log to a "no casing" condition. The impact is



cumulative when casings are telescoped inside one another as they are in SY-3DD and PK-10D. Therefore, correction factors were obtained from the Mount Sopris Company for each casing diameter used. Copies of the uncorrected geophysical logs (gamma and electric) are presented in Appendix E. The corrected gamma logs are included on the hydrogeologic cross sections (see Section 3.1 [Hydrogeology]).

2.1.6 Monitoring Well Construction

The construction details for the nine new and 15 preexisting monitoring wells are presented in Table 2-2, and monitoring well construction logs are provided in Appendix F. The monitoring wells were constructed according to the protocols in the SOP. Each well was constructed of 4-inch diameter polyvinyl chloride (PVC) casing (schedule 40) and 10 feet of 4-inch diameter stainless-steel screen, except for Well SY-3DD, which was constructed of 2-inch diameter PVC casing and stainless-steel screen. As previously discussed, 2-inch diameter casing and screen were used in SY-3DD to complete that well (see Section 2.1.1.1.1 [Exploratory Borings]). The wells were sand-packed, using J. Morie Company No. 1 sand, which was placed around the screen from the bottom of the boring to several feet above the top of the screen. Another layer of finer sand (J. Morie Company No. 00) was added above the No. 1 sand to complete the sand pack and serve as a buffer between the sand pack and the grout seal. Volclay grout was pumped through a side port tremie pipe into the annular space between the borehole wall (for the mud-rotary and auger borings) or the steel casing (for the air-rotary borings) and the well casing from the top of the fine sand up to about 2 feet below land surface. Except for Well SY-3DD, each well was completed at land surface with a flush-mounted, curb box cemented in the ground around the well head. Well SY-3DD was completed aboveground (stickup) because it is located on-site in a brushy area. The 6-inch diameter steel casing used to complete the drilling of SY-3DD was cut off approximately 2.5 feet above land surface to serve as a protective stand pipe for the 2-inch diameter stickup.

According to the SOP, the steel drill casings needed to drill the exploratory borings were to be removed from the ground, except for the 10-inch diameter casing, which was to be left to case-off the



upper permeable deposits. However, both wells SY-3DD and PK-10D were constructed with most of the steel drill casing left in the ground to provide additional well integrity. Only the smallest drill casings in the exploratory borings (6-inch diameter in SY-3DD and 8-inch diameter in PK-10D) were pulled back just enough to expose the screen and a few feet of well casing during sand packing. This change to the SOP (i.e., leaving the steel drill casings in the ground) was proposed in an August 25, 1992 letter from Geraghty & Miller to LKB (Geraghty & Miller, Inc. 1992) and was subsequently approved by the USEPA. Due to concern that these drill casings for Wells SY-3DD and PK-10D might settle due to potentially unstable subsurface conditions resulting from sand heaving during drilling, Delta joined the casings together at land surface by welding concentric metal rings between the casings. In addition, metal strips ("sleepers") were welded onto opposite sides of the outermost (16-inch diameter) steel casing; these metal strips extend several feet in either direction (perpendicular to the well casing) in a trench that was backfilled.

As stated in Section 2.1.1.2 [Modified Mud-Rotary Method], Monitoring Well PK-10S was constructed in the initial PK-10I well boring that collapsed. Geraghty & Miller's recommendation to salvage the PK-10I boring (see Appendix B) was approved by the USEPA, and the collapsed PK-10I well boring was salvaged by using a cable-tool rig, which advanced 6-inch diameter casing inside the existing 10-inch diameter surface casing to a total depth of 151 feet. After the cuttings were removed by bailing them from the 6-inch diameter casing, the 10-foot section of 4-inch diameter stainless-steel screen and schedule 40 PVC casing was installed to a depth of 149 feet. The 6-inch diameter casing was then pulled back as sand pack was added in the annulus between the 4-inch diameter well and the 10-inch diameter surface casing from the bottom of the boring to 5 feet below land surface. The depth to the top of the gravel pack will be measured periodically to check for settling, and additional gravel will be added as needed. To prevent the potential settling of the well, clamps were used to secure the 4-inch diameter PVC well casing to the 10-inch diameter surface casing at land surface. The annular space of Well PK-10S was sealed using a rubber gasket set above the gravel pack, a metal plate/ring was then welded on the inside of the 10-inch diameter steel casing to cover the rubber gasket. A 1-inch diameter access port was installed in the plate for measuring the depth of the gravel and for adding gravel, if needed. A large flush-mounted manhole was used to complete the well.



2.1.7 Surveying of Monitoring Wells

On November 22, 1993, after the OU-2 RI drilling program was completed, the measuring points of the nine new monitoring wells (SY-3DD, PK-10S, PK-10I, PK-10D, RB-11S, RB-11I, RB-11D, RW-12I, and RW-12D) and five preexisting on-site monitoring wells (W-3, SY-2R, SY-2D, SY-7, and SY-6) were surveyed to the National Geodetic Vertical Datum (mean sea level) by LKB (New York State-licensed surveyors) to an accuracy of 0.01 feet. The horizontal locations of the wells were surveyed to the New York State Plane Coordinate system. These data are presented in Table 2-3. The five preexisting on-site wells were resurveyed because the measuring point had changed due to damage to the well or because the well had been repaired.

2.1.8 Well Development

Following installation, five (SY-3DD, PK-10I, PK-10D, RB-11I, and RB-11D) of the nine new monitoring wells were developed using compressed air with an oil filter installed in the air line air compressor. The four other wells (PK-10S, RB-11S, RW-12I, and RW-12D) were developed using a submersible pump. Surging action was accomplished by turning the air compressor or submersible pump on and off. A well was considered developed when the turbidity decreased to less than 50 nephelometric units (NTUs) and when more water was removed from the well than was added during drilling. Development water from the eight off-site monitoring wells was pumped into a tanker truck supplied by Delta and disposed of at a designated location at the landfill. Hay bales were used to prevent runoff from leaving the site. Development water from Well SY-3DD was pumped directly to the designated location at the landfill.

During the initial development of Well PK-10D, approximately 8,000 gallons of water were inadvertently discharged to the ground by the driller. Geraghty & Miller suspended development of this well until a tanker was brought to the site to containerize the water and dispose of it at the landfill.

This development water was found to have formed a small puddle just covering the grass (about 200 square feet) and was rapidly absorbed by the soil. To evaluate any potential hazard, Geraghty & Miller



sampled the well, at the Town's direction, before development was completed. The samples were sent to EcoTest for rush-analysis of VOCs and leachate parameters. VOCs were not expected to be detected given the depth of the well (499 feet), the intended use of the well (clean, deep monitoring point), the results of in-field leachate testing, and the fact that the well screen was set below a low-permeability unit. The analytical results (Appendix G) indicated that VOCs were not detected and the concentrations of the leachate indicator parameters that were detected (ammonia, chloride, alkalinity, and hardness) did not represent a public health concern.

2.1.9 Well Repair/Well Deletions

During the Off-Site Groundwater Study, one monitoring well (SY-7) was repaired and three monitoring wells (W-3, W-4, and SY-5) were deleted from the groundwater sampling program. These repairs and deletions are discussed in detail in the following sections.

2.1.9.1 Repair of Monitoring Well SY-7

Monitoring Well SY-7 was repaired because the parking lot in which it is located (adjacent to the TOB-DPW building at the site) was repaved and the well head (curb box) was covered with asphalt. The horizontal survey coordinates from the OU-1 RI were used to locate the well head and repairs were performed by Delta on October 15, 1993. When the well head was exposed, the steel well casing was found to be bent at an acute angle. To repair the well, Delta removed the bent section of casing and coupled a new section of casing to the well. A new curb box was then installed flush with the new level of the parking lot to complete the repair. In addition, Well SY-7 was redeveloped because sediment was found at the bottom of the well. Development was accomplished using compressed air and the water was containerized and disposed of at the landfill.



2.1.9.2 Deletion of Monitoring Wells W-3, W-4, and SY-5 from the Groundwater Sampling Program

Shallow Monitoring Wells W-3, W-4, and SY-5 were deleted from the groundwater sampling program with the approval of the USEPA because it was determined that these three wells were unnecessary monitoring points for the OU-2 RI. These wells had been installed along the center line of the long axis of the landfill for use during the OU-1 RI. Monitoring Well W-4, which had been scheduled for repair concurrently with Well SY-7, could not be located even with a systematic search using a backhoe. At this point, an evaluation was made as to whether a shallow monitoring well was actually needed for the OU-2 RI at this location. The nearby existing monitoring wells were determined to be sufficient for the purpose of the OU-2 RI and for long-term monitoring. This same rationale was applied to Well W-3, which was found damaged (the casing was bent at depth), and to Well SY-5, which could not be located, although the surface casing (stickup) was found. Well W-3 was resurveyed as discussed in Section 2.1.7 (Surveying of Monitoring Wells); it was still functional for water-level monitoring. However, this well was no longer functional for water-quality monitoring because a bailer for sampling could no longer fit in this well. Well W-3 will be abandoned according to the New York State Department of Environmental Conservation (NYSDEC) protocols during the OU-1 Remedial Design Program.

2.1.10 Measurement of Water Levels

Water-levels were measured in both the Syosset Landfill monitoring wells (on-site and off-site) and in the Nassau County monitoring wells during the Off-Site Groundwater Study so that vertical hydraulic gradients and groundwater flow directions could be determined and potentiometric surface maps could be prepared for assessing horizontal hydraulic gradients and flow directions. Details concerning the measurement of water levels are presented in the following sections.



2.1.10.1 Regional Water Levels

On October 29, 1993, Geraghty & Miller measured water levels in 18 Nassau County monitoring wells located within approximately 2 miles of the site. Water levels were measured using an electronic M-scope and following SOP protocols. Of the 18 wells in which water levels were measured, 16 had also been measured during the OU-1 RI. Well P-7, which had been measured during the OU-1 RI, was destroyed; therefore water levels were measured in a replacement well (P-7A), located approximately 2,000 feet south-southeast of P-7. Water-level elevations are summarized in Table 2-4 and were calculated from measuring point elevation data provided by Nassau County.

2.1.10.2 Site Water Levels

On October 28, 1993 and on November 24, 1993, Geraghty & Miller measured water levels in the monitoring wells on- and off-site following SOP protocols. Water-level elevations are summarized in Table 2-5 and were calculated from the surveyed measuring-point elevations. Water-level measurements were made using an electronic M-scope.

2.1.11 Groundwater Sampling Program

In accordance with SOP protocols, two rounds of groundwater samples were collected by Geraghty & Miller from the nine new monitoring wells and 12 of the 15 preexisting on-site monitoring wells. The first round of groundwater samples was collected from November 1 through 5, 1993, and the second round was collected from November 29 through December 3, 1993. At the end of each sampling day, samples were shipped via overnight courier (Federal Express) to IEA Laboratories, Inc. (IEA), Monroe, Connecticut following chain-of-custody procedures. Water sampling logs and chain-of-custody forms are in Appendix H.



2.1.11.1 Revised Parameter List

The parameter list specified in the SOP was revised following a meeting held with the USEPA, the Town, LKB, and Geraghty & Miller on February 18, 1993. The revision was based on a reevaluation of the OU-1 RI water-quality data in conjunction with the then-current OU-2 RI field data (vertical water-quality profiles and lithologic logs) that had been collected from the two exploratory borings (SY-3DD and PK-10D). The revised parameter list (Table 2-6) was proposed in an April 1, 1993 letter from Geraghty & Miller (Glasser and Wolfert, pers. comm. 1993) to LKB and was subsequently approved by the USEPA. PCBs, acid-extractable compounds, and cyanide were deleted from the parameter list because, except for 4-methyl phenol, which was detected in two wells (SY-5 and SY-7) at concentrations less than 2 micrograms per liter (ug/L), and cyanide, which was detected in one well (SY-6) at a concentration of less than 0.2 ug/L, these analytes were not detected in the groundwater during the OU-1 RI. Base neutral compounds were also deleted from the parameter list because they were mostly undetected during the OU-1 RI. Phthalates, a class of base neutral compounds, were detected at slightly higher concentrations during the OU-1 RI; however, because these compounds were also detected in the method blanks and are known laboratory contaminants, these phthalates are not contaminants of concern and were therefore deleted from the parameter list.

During the OU-1 RI, VOCs were not detected at concentrations consistent with a plume that has the landfill as a source. However, VOCs were retained on the parameter list due to concern that these mobile compounds may have migrated off-site. Groundwater samples collected for the first and second sampling rounds were analyzed by IEA for analytes on the revised parameter list, including VOCs, metals (total and dissolved), and leachate indicator parameters (inorganics). The revised parameter list is presented in Table 2-6.

Two samples were collected from each monitoring well during each round for metals analysis. One sample was unfiltered for analysis of total metals and the other sample was filtered through a 0.45-micron filter membrane for analysis of dissolved metals. The purpose of these two analyses was to determine whether colloidal particles in the samples were contributing to the metals detected. When



groundwater samples containing colloidal particles are acidified, sorbed metals tend to be put into solution through cation exchange thereby increasing the total metals concentrations in the water sample (Strausberg 1983). Thus, the results of the unfiltered metals analysis do not reflect only dissolved metals in the groundwater. Rather, these results reflect the combination of dissolved metals and metals desorbed through acidification.

Samples collected from each well for measurement of field parameters (temperature, pH, and specific conductance) were divided into four aliquots and each aliquot was analyzed in the field for the three parameters by the Geraghty & Miller sampling team. These measurements were recorded on the water sampling log forms presented in Appendix H.

2.1.11.2 Quality Control Samples

Quality Control (QC) samples, consisting of trip blanks, field blanks, matrix spike, and matrix spike duplicates, and replicates, were utilized during the groundwater sampling program to monitor sampling and laboratory performance. With each daily shipment of samples to the laboratory, trip blanks, prepared by IEA, and field blanks, prepared daily by Geraghty & Miller, were sent, following chain-of-custody procedures, via overnight courier to IEA. Because trip blanks were required to be less than 24 hours older than each accompanying sample shipment sent to the laboratory, on the first day of each sampling round, IEA sent a same-day courier with a trip blank that had been prepared at the laboratory that morning. For each sampling day thereafter, IEA sent trip blank samples, via overnight courier, that were prepared the previous night. Also, with the trip blank sent on the first day of each round, the same-day courier delivered analyte-free water prepared by IEA (for field blank preparation and for decontaminating sampling equipment), as well as acid preservatives for several of the analytical parameters. The analytical parameters that required field acidification to a pH value of less than 2 were as follows: VOCs (hydrochloric acid), metals (nitric acid), ammonia (sulfuric acid), and total hardness (nitric acid). To ensure that the analyte-free water was clean, IEA analyzed samples of batched water produced for the two sampling rounds. The results of IEA's analyses show that the concentrations of parameter list analytes were below USEPA limits (Appendix I).



Replicate samples were collected by Geraghty & Miller during both sampling rounds from the same three off-site intermediate-depth monitoring wells (PK-10I [Rep-2], RB-11I [Rep-1], and RW-12I [Rep-3]) that monitor the most contaminated portion of the leachate plume (as determined by in-field leachate parameter testing during drilling of Exploratory Borings SY-3DD and PK-10D). Samples were collected for matrix spike and matrix spike duplicate analyses from Monitoring Wells SY-1 and PK-10D for both sampling rounds. CDM collected split samples from on-site Monitoring Well SY-1 (shallow) and off-site Monitoring Wells RB-11I (intermediate) and RB-11D (deep) during both sampling rounds. The parameter list being used by CDM includes the OU-2 RI parameter list plus additional parameters. CDM's list is longer than the OU-2 RI parameter list because CDM's contract laboratory does not perform analyses for customized parameter lists and only performs analyses for "packaged" lists that include predetermined parameters. The USEPA and CDM will compare the analytical results for the split samples with the results presented in this report as an independent QC check.

2.1.11.3 Well Evacuation and Sample Collection

Approximately three well volumes of water were evacuated from each monitoring well before samples were collected. Evacuation was accomplished by using either a submersible pump (2- or 4-inch diameter) or a bailer (see Water Sampling Logs in Appendix H). Four of the preexisting on-site monitoring wells (SY-1D, SY-2R, SY-6D, and SY-8) were purged using the existing permanently installed submersible pumps. The remaining monitoring wells were purged using submersible pumps that were temporarily installed and decontaminated according to the protocols in the SOP. Permanent submersible pumps have not yet been installed in the nine new monitoring wells because several different pump systems were evaluated for long-term cost-effectiveness and logistics. Based on this evaluation, the Town, in consultation with Geraghty & Miller and LKB, ultimately decided that the submersible pumps be installed as specified in the SOP because that pumping system was judged the most appropriate of the systems evaluated.



Purge water from the on-site monitoring wells was discharged to the ground. Purge water from the off-site wells was pumped to a tanker and transported to the landfill for disposal at a designated location.

For the four wells that had permanently installed submersible pumps, water samples for all parameters except VOCs were collected from the pump discharge; water samples for VOC analysis were collected from these wells using a 3/4-inch diameter PVC bailer. A Teflon bailer was used to collect samples for all parameters from the wells without permanently installed submersible pumps.

2.1.11.4 Decontamination of Sampling Equipment

In addition to the SOP specifications for decontamination procedures, Geraghty & Miller used acetone after Step 4 of the SOP protocol to decontaminate the sampling equipment during the two sampling rounds. This addition to the decontamination procedure was requested by the USEPA and agreed to by the Town, LKB, and Geraghty & Miller at the February 18, 1993 meeting.

2.1.11.5 Data Validation

The VOC and metals data were validated in accordance with the guidelines in the USEPA Region II SOPs "CLP Organics Data Review and Preliminary Review" (USEPA 1992) and "Evaluation of Metals Data for Contract Laboratory Program (CLP)" (USEPA 1992). The documentation prepared as a result of validating the data according to the USEPA Region II SOPs is presented as a separate document entitled "Data Validation Summary Report for the Second Operable Unit Remedial Investigation of the Syosset Landfill, Syosset, New York." Because the USEPA has no SOPs for validating leachate indicator parameters, Geraghty & Miller performed all QC checks possible with the information reported by IEA (holding times, duplicate results, spike results, and blank results). The results of the leachate indicator data review are also contained in that document. Overall, the data were found to be acceptable and usable with the exceptions described in the Data Validation



Summary Report. The qualifiers applied to the analytical results were based on the USEPA Region II data validation SOPs; a relatively small number of sample results required qualification.

2.2 OFF-SITE SUBSURFACE GAS STUDY

The Off-Site Subsurface Gas Study was conducted to determine the extent of off-site subsurface gas migration from the landfill because elevated concentrations of methane gas had been detected during the OU-1 RI. The methodologies used to construct and monitor the gas monitoring wells are described in the following sections.

2.2.1 Gas Well Installation and Construction

On September 28 and 29, 1993, Geraghty & Miller installed three additional gas monitoring wells (CS-20, CS-21, and CS-22) in accordance with the SOP, at the Clark Surgical Corporation (Clark) property, which is located west of the Syosset Landfill on the other side of the LIRR track. According to the OU-2 RI SOP and Work Plan, the three off-site gas wells were planned to be installed at the Great Eastern Printing Company (Great Eastern) which is located south of Clark. However, Great Eastern refused permission to perform this work and the Town, therefore, sought access from Clark. The locations of these three new gas wells and the six preexisting on-site gas wells (G-6, G-7, G-8, G-10, G-13, and G-14), which were also specified to be monitored during the OU-2 RI, are shown on Figure 1-2. CDM provided oversight for installation of Wells CS-20 and CS-21 on September 28, 1993.

An 8- to 10-inch diameter borehole was excavated for each gas well, using a shovel, post-hole digger, and an iron bar, to depths of 4.7 feet (CS-20), 5.0 feet (CS-21), and 4.25 feet (CS-22). These excavation tools were decontaminated before and after each use using Micro detergent solution followed by rinsing with distilled water. Hand-slotted, 1-inch diameter, PVC screen (2 to 2.5 feet long) attached to PVC casing of the same diameter was installed in each borehole following excavation. J. Morie Company No. 1 sand was used to fill the annular space between the screen and the borehole



wall from the bottom of the borehole to several inches above the top of the screen. Bentonite slurry was mixed by hand in a mortar pan using potable water and was emplaced above the sand pack to within 0.6 foot below land surface. To complete each well, a flush-mounted curb box assembly was cemented in place with a layer of native soil between the bottom of the curb box assembly and the top of the bentonite slurry seal to allow for drainage of runoff that could collect inside the curb box. The top of each new gas well was fitted with a 1-inch diameter PVC cap with 1/4-inch diameter silicon tubing attached for gas monitoring. The end of the silicon tubing was closed off with a metal clip to prevent venting. A summary of the construction details for the gas monitoring wells is presented in Table 2-7, and the gas well construction logs are presented in Appendix J.

2.2.2 Gas Monitoring

The three new off-site subsurface gas monitoring wells were monitored by Geraghty & Miller for methane and total organic vapors on 3 days of low or falling barometric pressure (February 25, March 1, 2, and 7, 1994). In addition to these three new gas wells, four preexisting gas monitoring wells (G-6, G-7, G-13, and G-14) were also monitored as specified. Gas wells G-8 and G-10 were specified to be monitored too, but Well G-8 was destroyed and G-10 could not be located. Monitoring was performed using a Foxboro Model 128 organic vapor analyzer (OVA), a flame-ionization detector. Total organic vapors were measured using a standard OVA probe, while methane was measured using an activated charcoal-filter probe. Before measuring the wells, the OVA was calibrated using "zero" gas and 9.8 parts per million (ppm) methane. To monitor a well, the OVA probe was inserted into the silicon tubing protruding from the PVC cap and the highest reading was recorded; this high measurement occurred within the first few seconds. In February, the wells were measured first for methane using the activated charcoal filter probe, followed by the measurement for total organic vapors using the standard probe. This order was reversed for the monitoring performed in March.



2.3 SUBSURFACE GAS WELL INSTALLATIONS AND MONITORING FOR THE ON-SITE REMEDIAL DESIGN PROGRAM

As mentioned in Section 1.3 (Purpose and Scope), five additional on-site gas monitoring well clusters were installed and monitored during the OU-2 RI as part of the OU-1 (On-Site) Remedial Design Program. The installation and monitoring protocols and the monitoring results of these wells are presented in a memorandum prepared by LKB (Appendix K).



3.0 RESULTS

The results of the Off-Site Groundwater Study and Off-Site Subsurface Gas Study, which were conducted as part of the OU-2 RI, are presented below.

3.1 HYDROGEOLOGY

During the Off-Site Groundwater Study, Wells SY-3DD and PK-10D were drilled almost to the bottom of the Magothy Formation, which is estimated to be approximately 600 feet below land surface. Well SY-3DD is 540 feet deep and Well PK-10D is 499 feet deep. The four "deep" wells installed during the OU-1 RI (On-Site Groundwater Study) were only drilled to a shallow/intermediate depth from 192 to 205 feet below land surface in the Magothy Formation. The intermediate depth monitoring wells installed during the OU-2 RI are deeper than the OU-1 RI "deep" wells and range from 358.5 to 360 feet in depth.

Based on the data obtained from the formation samples and the geophysical logging, vertical lithologic profiles were established at each of the four drilling sites (SY-3, Town Park, Recharge Basin, and Roadway). These data were used to construct hydrogeologic cross sections A-A' (Figure 3-1) and B-B' (Figure 3-2); the locations of the lines of section are shown on Figure 1-2. The gamma logs for the four deep wells, which were corrected for casing interferences for Wells SY-3DD and PK-10D (see Appendix N for explanation of how logs were corrected), are superimposed on the corresponding wells on Figures 3-1 and 3-2 to illustrate the finer-grained deposits that were encountered in the predominantly fine sandy matrix of the Magothy Formation. The finer-grained deposits, which consist mostly of clay and silt, are indicated by the deflections to the right in the gamma log and correlate well to the descriptions on the sample/core logs.

Figure 3-1, which is based on logs from on-site Wells SY-4, W-3, and SY-3DD and off-site Well PK-10D, shows the fill material, water-table surface, well screen settings, and the interpreted hydrogeologic framework. The predominant composition of the Magothy (fine-grained sediments that



include interbedded sequences of sand, with sandy clay, silt, and clay) shown on Figure 3-1 is consistent with the findings of the OU-1 RI.

The coarse-grained deposits typical of the Upper Glacial Formation, which is not saturated beneath and around the landfill, were encountered during the OU-2 RI. Based on the sample/core logs, the thickness of the Upper Glacial Formation appears to be more than 130 feet, but an exact determination of its thickness was not made because the texture and color of the Upper Glacial and Magothy Formations are frequently similar near the contact zone between them making differentiation of the units difficult.

Figure 3-2, which is based on the logs (sample/core logs and gamma logs) from the three off-site deep wells (PK-10D, RB-11D, and RW-12D), shows the water-table surface, well screen settings, and the interpreted hydrogeologic framework. The most prevalent deposits on this figure (as on Figure 3-1) are the fine-grained sediments typical of the Magothy.

3.1.1 Regional Horizontal Direction of Groundwater Flow

The water-level elevation data collected by Geraghty & Miller from the 18 Nassau County shallow monitoring wells in the vicinity of the site on October 29, 1993 (Table 2-4) were used to construct the regional potentiometric surface of the shallow zone of the Magothy aquifer (Figure 3-3). As shown on this map, the regional east-west orientation of the groundwater divide is south of the site at almost exactly the same position and orientation that was documented during the OU-1 RI. North of this divide, groundwater flows in a northerly direction, and south of the divide, groundwater flows in a southerly direction. The direction of groundwater flow from the site is in a north-northeasterly direction, as shown on Figure 3-3, which is consistent with the regional direction of groundwater flow documented during the OU-1 RI.



3.1.2 Site-Specific Horizontal Direction of Groundwater Flow

The water-level elevation collected by Geraghty & Miller from the nine new and 12 preexisting monitoring wells on October 28, 1993 and November 24, 1993 (see Table 2-5) were used to construct potentiometric surface maps of the shallow zone (Figures 3-4 and 3-5, respectively), and the intermediate zone (Figures 3-6 and 3-7, respectively). Flow maps of the deep zone for the October and November rounds (Figures 3-8 and 3-9, respectively) were also developed to depict the direction of groundwater flow. A discussion of the groundwater flow direction in each zone of the Magothy aquifer is presented in the following sections.

3.1.2.1 Shallow Zone

As shown on Figures 3-4 and 3-5, groundwater flows from the east and west boundaries of the site toward the center of the landfill; at this point, the flow converges and moves in a northerly direction toward the Town Park where Well Cluster PK-10 is located. This pattern was observed on both October 28, 1993 and November 24, 1993 and is similar, although more pronounced, to the pattern observed on October 27, 1988 during the OU-1 RI (see Figure 8 in Appendix L). This general northerly groundwater flow direction observed in the shallow zone of the Magothy is consistent with the regional flow direction depicted on Figure 3-3, but more variability is seen on the site-specific scale than the regional scale. This local variability of the groundwater flow direction observed on the site-specific scale is likely due to the greater density of data points locally, as compared to regionally, and the proximity of the site to the regional groundwater divide, which results in a correspondingly relatively flat horizontal hydraulic gradient on-site (see Section 3.1.4 [Comparison of Horizontal and Vertical Hydraulic Gradients]).

3.1.2.2 Intermediate Zone

Water-level elevation data from the four on-site "deep" wells (SY-1D [192 feet], SY-2D [200 feet], SY-3D [199 feet], and SY-6D [205 feet]) and three off-site intermediate wells (PK-10I



[362 feet], RB-11I [358.5 feet], and RW-12I [360 feet]) were used to prepare the potentiometric surface maps (Figures 3-6 and 3-7) for the intermediate zone of the Magothy aquifer. These seven wells are screened at two different levels in the intermediate zone, but were combined to prepare a composite map. Ideally, to use wells on the same map for determining the groundwater flow direction, the elevations of the screen zones should be similar. However, in many investigations of contamination, wells are installed in phases at various depths to provide specific information on contaminant distribution, with the result that the monitoring network may not be ideal for water-level mapping purposes. The alternative to preparing composite maps would be to prepare two or more maps with fewer data points per map (i.e., shallow and deeper intermediate maps with four and three data points, respectively). Unfortunately, this often results in insufficient control to confidently determine the groundwater flow direction. As such, composite maps usually are the best solution, especially if they are carefully compared to other data. In this specific case, the composite intermediate maps show a general flow direction consistent with the shallow and deep maps and appear to accurately depict flow in the intermediate zone.

As shown on Figures 3-6 and 3-7, groundwater in the intermediate zone in the eastern part of the study area flows in a northwesterly to north direction while to the west the flow is oriented slightly east of north. This groundwater pattern is virtually the same for both dates on which water levels were measured.



3.1.2.3 Deep Zone

The groundwater flow direction in the deep zone was determined by triangulating the water-level elevation data between the four deep monitoring wells (SY-3DD, PK-10D, RB-11D, and RW-12D) where water-level measurements were collected on October 28, 1993 (Figure 3-8) and November 24, 1993 (Figure 3-9). Contour maps were not prepared for the deep zone because of the sparsity of data points. The flow arrow on Figure 3-8 and the westernmost flow arrow on Figure 3-9 are the result of triangulating between wells RW-12D, SY-3DD, and PK-10D. The easternmost flow arrow on Figure 3-9 is the result of triangulating between Wells PK-10D, SY-3DD, and RB-11D, a similar triangulation was not done for Figure 3-8 because of the anomalous water-level elevation in Well RB-11D on October 28, 1993.

For both deep flow maps (Figures 3-8 and 3-9), groundwater is shown flowing in a northerly direction with a northeasterly component also apparent near the Town Park in November 1993 (Figure 3-9).

3.1.3 Vertical Direction of Hydraulic Gradient

The vertical hydraulic gradient direction (upward or downward) was determined by comparing the water-level elevations (potentiometric head) of monitoring wells within each well cluster (see Table 2-5); groundwater flows in the direction of lower potentiometric head. Due to the proximity of the study area to the regional groundwater divide, the vertical hydraulic gradient direction was expected to be downward at all six locations where wells are clustered (SY-1, SY-2, SY-3, PK-10, RB-11, and RW-12); this was found to be true at all well cluster sites on October 28, 1993, except for Well Cluster PK-10. At Cluster PK-10, the potentiometric levels were the same in PK-10I and PK-10D, indicating a lack of vertical gradient between these two wells although there was a vertical gradient downward between Wells PK-10S and PK-10I.



On November 24, 1993, a downward hydraulic gradient direction was noted at four of the six cluster locations while an upward direction was documented at Well Clusters SY-1 and PK-10 (between the intermediate and deep wells). Because only two water-level rounds, approximately 1 month apart are available, it is not known if these variances from expected conditions are long term or temporal variations; but, generally, the vertical hydraulic gradient in the study area is downward.

3.1.4 Comparison of Horizontal and Vertical Hydraulic Gradients

The horizontal and vertical hydraulic gradients were calculated using data presented in Table 2-5 and on Figures 3-4, 3-5, 3-6, 3-7, 3-8, and 3-9. By comparing the horizontal hydraulic gradient (I_H) and the vertical hydraulic gradient (I_V), a more complete understanding of hydrogeologic site conditions can be gained that is helpful in explaining the distribution and migration of contaminants from the landfill as evidenced by the water-quality data.

The horizontal hydraulic gradient was calculated by using the formula:

$$I_H = \frac{\Delta h}{L}$$

where, I_H = The horizontal hydraulic gradient (dimensionless).

Δh = The difference in potentiometric head (water-level elevation) between two groundwater contours (in feet).

L = The horizontal distance between the two groundwater contours along a flow line (in feet) shown on figures.



For both the shallow and intermediate zones, Δh was calculated by subtracting the lowest contour from the highest non-dashed contour on the potentiometric flow maps (Figures 3-4 through 3-7) along the distance (L) of three different groundwater flow lines approximately coinciding with the flow arrows shown on each figure. Thus, three values of I_H were calculated for the two dates for both the shallow and intermediate zones. For the deep zone, the same general procedure was followed, but only one value was calculated for each date due to the minimal number of data points and the need to triangulate flow direction and not contour water levels (see Table 3-1a for details). The average I_H for the shallow zone on October 28 (see Figure 3-4) and November 24, 1993 (see Figure 3-5) was 0.00065 and 0.00064, respectively. The combined average I_H for the shallow zone for both dates was 0.00065.

The average I_H for the intermediate zone on October 28, 1993 (Figure 3-6) and November 24, 1993 (Figure 3-7) was 0.00114 and 0.00108, respectively. The combined average I_H for the intermediate zone for both dates was 0.00111, which is almost twice the I_H for the shallow zone.

The horizontal hydraulic gradient for the deep zone for October 28, 1993 (Figure 3-8) and November 24, 1993 (Figure 3-9) was 0.00067 and 0.00085, respectively. The average value for both dates was 0.00076, which is similar to the shallow zone.

The vertical hydraulic gradient (I_V) was calculated using the same equation with L representing the vertical distance (in feet) between two screen zones, and Δh representing the difference in potentiometric head between two screen zones (wells) in a well cluster. A summary of the data used to calculate I_V is provided in Table 3-1b. In well clusters with three wells, I_V was calculated between the shallow and intermediate wells, and between the intermediate and deep wells. On October 28, 1993, the average I_V was 0.0042, and on November 24, 1993, the average I_V was 0.0024. I_V for November was lower due to the reversed (upward) gradients observed at Well Clusters SY-1 and PK-10. The reversed (upward) gradients were factored in the average values as negative numbers resulting in a lower average I_V . The combined average I_V for October and November is 0.0033. The I_V (0.0033)/ I_H (shallow zone) (0.00065) equals approximately 5, I_V (0.0033)/ I_H (Intermediate zone) (0.00111)



equals approximately 3, and $I_v (0.0033)/I_H$ (deep zone) (0.00076) equals approximately 4 indicating that the vertical hydraulic gradient is greater than the horizontal hydraulic gradient for the shallow, intermediate, and deep zones of the Magothy aquifer.

3.2 GROUNDWATER QUALITY

As discussed in Section 2.1.10 (Measurement of Water Levels), two rounds of groundwater samples were collected: the first round of samples was collected from November 1 through November 5, 1993, and the second round of samples was collected from November 29 through December 3, 1993. The analytical results for the samples are presented in Tables 3-2, 3-3, and 3-4 and are discussed in the following sections.

3.2.1 Volatile Organic Compounds

A summary of the analytical results for VOCs is presented in Table 3-2. The VOCs detected and their corresponding concentrations for both sampling rounds are presented on Figures 3-10 (shallow zone), 3-11 (intermediate zone), and 3-12 (deep zone). Overall, the first sampling round results, including the field replicate samples, correlate very well with the second sampling round results, both in terms of individual VOCs and their concentrations.

Of the 13 on-site wells sampled, VOCs were not detected during either sampling round in Wells SY-1 and SY-3DD. Total VOC concentrations were less than 10 ug/L for samples collected from on-site wells SY-2D, SY-2R, SY-6, SY-6D and SY-9 for both sampling rounds. The highest total VOC concentration for the on-site wells from either sampling round was 547.9 ug/L detected in Well SY-7. (This detection is not considered a result of landfill impacts [see Section 3.4]). The concentration of benzene detected in this well in November was 410 ug/L and in December was 540 ug/L. Benzene was not detected in any of the other on-site wells at concentrations greater than 2 ug/L, and it was not detected in any of the off-site wells at concentrations greater than 1 ug/L. Chlorobenzene was detected above the quantitation limit of 1 ug/L in four of the on-site wells, with



concentrations ranging from 1.3 to 9.1 ug/L. Other compounds detected in at least two of the on-site wells at concentrations greater than the quantitation limit of 1 ug/L (or 20 ug/L for SY-7) were vinyl chloride, 1,1-dichloroethane, cis-1,2-dichloroethene, trichloroethene, and tetrachloroethene.

In the on-site wells, MCLs were exceeded for the following compounds: vinyl chloride (MCL = 2 ug/L), cis-1,2-dichloroethene (MCL = 5 ug/L), chloroform (MCL = 7 ug/L), benzene (MCL = 0.7 ug/L), toluene (MCL = 5 ug/L), tetrachloroethene (MCL = 5 ug/L), chlorobenzene (MCL = 5 ug/L), and ortho-xylene (MCL = 5 ug/L). Of the 13 on-site wells sampled, at least one VOC was detected in seven wells (SY-1D, SY-3, SY-3D, SY-4, SY-6D, SY-7, and SY-8) above the federal and/or state MCLs during one or both sampling rounds. Well SY-7 contained three compounds (benzene, toluene, and ortho-xylene) which exceeded the federal and/or state MCLs. The remaining six wells contained only one or two compounds which exceeded the MCLs. The VOC concentrations detected in on-site monitoring wells during the OU-2 RI are consistent with regionally degraded groundwater quality as discussed in Appendix M.

In seven of the eight off-site wells, the total concentration of VOCs ranged from not detected in RB-11S (first sampling round) to 52.5 ug/L in RB-11I (second sampling round). However, the highest total concentration of VOCs occurred in Well RW-12I (259.7 ug/L). This detection of VOCs is several times higher than the highest concentration detected in the other monitoring wells on-site or off-site during either the OU-1 or OU-2 RIs and it appears that a source other than the landfill may exist (see Section 3.4 [Contaminant Migration]). Total VOC concentrations were less than 10 ug/L for samples collected from off-site wells PK-10D, RB-11S, and RB-11D for both sampling rounds. The compounds detected in samples collected from Well RW-12I for both sampling rounds above the quantitation limit (2 ug/L for the first round and 5 ug/L for the second round) were 1,1-dichloroethene, 1,1-dichloroethane, cis-1,2-dichloroethene, 1,1,1-trichloroethane, trichloroethene, and tetrachloroethene. The compound detected in Well RW-12I at the highest concentration was tetrachloroethene (110 ug/L) during the second sampling round. Tetrachloroethene was also detected in off-site Wells PK-10S, PK-10I, RB-11I, and RW-12D at concentrations ranging from 1.3 ug/L to 23 ug/L. Benzene was not detected in any of the off-site wells at concentrations above 1 ug/L.



Chlorobenzene was only detected in off-site Well PK-10I above the quantitation limit (1 ug/L) at a concentration of 20 ug/L. Other compounds detected in at least two of the off-site wells at concentrations greater than the quantitation limit of 1 ug/L (or at least 2 ug/L for RW-12I) were 1,1-dichloroethene, 1,1-dichloroethane, cis-1,2-dichloroethene, 1,1,1-trichloroethane, trichloroethene, and toluene.

In the off-site wells, the MCLs were exceeded for the following ten compounds: vinyl chloride (MCL = 2 ug/L), 1,1-dichloroethene (MCL = 5 ug/L), 1,1-dichloroethane (MCL = 5 ug/L), cis-1,2-dichloroethene (MCL = 5 ug/L), 1,1,1-trichloroethane (MCL = 5 ug/L), benzene (MCL = 0.7 ug/L), trichloroethene (MCL = 5 ug/L), toluene (MCL = 5 ug/L), tetrachloroethene (MCL = 5 ug/L), and chlorobenzene (MCL = 5 ug/L). Of the eight off-site wells sampled, VOCs were detected in six of these wells above the federal and/or state MCLs in one or both sampling rounds. Well RW-12I contained the most (seven) compounds (1,1-dichloroethene, 1,1-dichloroethane, cis-1,2-dichloroethene, 1,1,1-trichloroethane, trichloroethene, toluene, and tetrachloroethene) which exceeded federal and/or state MCLs. Well RW-12D had three compounds (vinyl chloride, benzene, and toluene) which exceeded the MCLs. The remaining four off-site wells contained only one or two compounds which exceeded one or both of the MCLs. The VOC concentrations detected in off-site monitoring wells (except Well RW-12I) during the OU-2 RI are consistent with regionally degraded groundwater quality as discussed in Appendix M. A supplemental round of sampling for VOCs was carried out in July 1995 and these results are given and discussed in Appendix P.

A few individual VOCs were detected in the trip blanks and field blanks analyzed. The VOCs detected in these blanks were primarily methylene chloride, acetone, and chloroform. These same compounds were also frequently detected in the laboratory method blanks associated with the trip and field blanks. All blank results are taken into consideration when validating the data and a detailed discussion about blank contamination can be found in the Data Validation Summary Report.



3.2.2 Leachate Indicator Parameters

Groundwater samples were also analyzed for leachate indicator parameters as part of the Off-Site Groundwater Study. The leachate indicator parameters include naturally occurring anions and cations, some of which can be extremely useful in determining landfill leachate impacts to groundwater (ammonia, hardness, alkalinity, iron, sodium, potassium, total dissolved solids, nitrate, sulfate, and chloride). These parameters have been employed as indicator parameters for landfill leachate in several other investigations on Long Island (Geraghty & Miller, Inc. 1985 and 1989, Saar & Braids 1983). The leachate indicator parameter sample results are summarized in Table 3-4. Selected leachate indicator parameters detected and their corresponding concentrations for both sampling rounds are presented on Figures 3-13 (shallow zone), 3-14 (intermediate zone), and 3-15 (deep zone). Overall, the results of both sampling rounds, including the field replicate samples, correlate very well both in terms of individual leachate indicator parameters detected and their concentrations. A more detailed discussion of the leachate indicator parameter results is presented in Sections 3.3 (Contaminant Distribution) and 3.4 (Contaminant Migration).

3.2.3 Metals (Total and Dissolved)

As discussed in Section 2.1.11.1 (Revised Parameter List), both filtered and unfiltered samples were collected for metals analysis. The purpose of these two analyses was to determine whether suspended particles in the samples were contributing to the metals detected since sorbed metals tend to be put into solution when the samples are acidified. The unfiltered samples were sent to the laboratory for analysis of total metals and the filtered samples were sent to the laboratory for analysis of dissolved metals. The total and dissolved metal sample results are summarized in Table 3-3. Overall, the results of both sampling rounds, including the field replicate samples, correlate very well both in terms of individual metals detected and their detected concentrations. The sample results for each metal were compared to either the New York State or federal drinking water standard (maximum contaminant level [MCL]), whichever value was lower. MCLs are included in Table 3-3; these values were used to



assist in the evaluation of potential contamination both on- and off-site. One of the 17 metals analyzed (potassium) presently does not have an MCL.

Figures 3-16 (shallow zone), 3-17 (intermediate zone), and 3-18 (deep zone) show the distribution of metals and their concentrations for both sampling rounds. Except for sodium and iron, MCLs were not exceeded for any metals in the off-site wells, but antimony, arsenic, beryllium, iron, lead, and sodium were detected in at least one of the on-site wells at concentrations above the corresponding MCL. Antimony was detected above the MCL (6 ug/L) in non-filtered samples on at least one occasion in six on-site wells at concentrations ranging from 21.0 to 91.8 ug/L. Dissolved antimony was only detected above the MCL in filtered samples collected from Wells SY-3 and SY-4. Arsenic was detected above the MCL (50 ug/L) in non-filtered samples on at least one occasion in two on-site wells (SY-3 and SY-3D) with concentrations up to 102 ug/L. Dissolved arsenic was not detected above the MCL in either well. Total beryllium was detected only once in Well SY-2R in a non-filtered sample at a concentration of 7.8 ug/L (MCL = 4 ug/L). Lead was detected above the MCL (50 ug/L) in non-filtered samples on at least one occasion in four on-site wells with total concentrations up to 128 ug/L; however, none of the dissolved lead concentrations detected in the on-site wells was above the MCL. Sodium was detected in all on-site wells, except for Well SY-3DD, during both sampling rounds above the MCL (20,000 ug/L). Concentrations ranged from 20,100 ug/L to 239,000 ug/L.

Antimony, beryllium, mercury, silver, and thallium were not detected in any of the off-site wells sampled during either sampling round. Of the metals that were detected in the off-site wells, only iron and sodium, detected in most of the samples, were detected at concentrations above the corresponding MCL.

A few metals (copper, zinc, and iron) were detected in the field blanks analyzed at concentrations above the reporting limit. All blank results were taken into consideration when validating the data, and a detailed discussion about blank contamination can be found in the Data Validation Summary Report.



3.2.4 Contaminants of Concern

Below are listed the analytical parameters which exceeded federal and/or state maximum contaminant levels during the second operable unit remedial investigation of the Syosset Landfill, Syosset, New York.

| <u>Volatile Organic Compounds</u> | <u>Metals</u> | <u>Leachate Indicator Parameters</u> |
|-----------------------------------|---------------|--|
| Vinyl chloride | Antimony | Chloride |
| 1,1-Dichloroethene | Arsenic | Sulfate |
| 1,1-Dichloroethane | Beryllium | Total Dissolved Solids |
| cis-1,2-Dichloroethene | Iron | |
| Chloroform | Lead | |
| 1,1,1-Trichloroethane | Sodium | |
| Benzene | | |
| Trichloroethene | | |
| Toluene | | |
| Tetrachloroethene | | |
| Chlorobenzene | | |
| Ortho-xylene | | |



3.3 CONTAMINANT DISTRIBUTION

In the following sections the areal distribution (on-site and off-site) of VOCs, leachate indicator parameters, and metals are discussed for the three hydrogeologic zones of the Magothy Formation (shallow, intermediate, and deep) and comparisons are made between the zones.

3.3.1 Shallow Zone

Figure 3-10 depicts VOC distribution and concentrations in the shallow zone for the November and December 1993 sampling rounds. Upgradient and downgradient (see figures for shallow groundwater zone flow directions) of the eastern half of the landfill, total VOC concentrations in each shallow well sampled was 1.7 ug/L or less for both sampling rounds. The only exception to this was Well SY-7, where total VOCs, consisting predominantly of benzene (more than 500 ug/L), were detected during each sampling round. As stated previously, this detection is not considered a result of landfill impacts (see Section 3.4 [Contaminant Migration]).

Total VOC concentrations were slightly higher in wells located on the western portion of the landfill with all results, except for one, being above 10 ug/L. The maximum total VOC concentration was 23.2 ug/L in Well SY-8 during the first sampling round.

Off-site, the total VOC concentration in Well PK-10S (10.8 to 13.9 ug/L) is similar to total VOCs on the western half of the landfill, while the total VOC concentration in Well RB-11S (not detected to 0.9 ug/L) is similar to total concentrations on the eastern half of the landfill.

Figure 3-13 depicts the distribution and concentrations of leachate indicator parameters in the shallow zone during the November and December 1993 sampling rounds. Generally, the concentrations of leachate indicator parameters are higher in wells located on the western portion of the landfill as compared to the eastern portion, although there are exceptions to the generalization. Most notably, the concentrations of some leachate indicator parameters, such as chloride and total



dissolved solids, in Well SY-7 are at levels more comparable to wells on the western portion of the landfill. This general distribution of parameters relative to the western and eastern portions of the landfill is similar to that described above for VOCs.

Off-site, leachate indicator parameter concentrations are significantly less than on-site concentrations, unlike the total VOC distribution pattern; however, leachate indicator concentrations are similar to the total VOC pattern, being less in Well RB-11S than in Well PK-10S.

Figure 3-16 depicts the distribution and concentrations of metals in the shallow zone during the November and December 1993 sampling rounds. Unlike the general pattern for VOCs and leachate indicator parameters, comparison of wells on the western portion of the landfill to wells on the eastern portion does not reveal an overall generalized pattern as for some metals, the highest concentrations are on the western portion while for other metals, the highest concentrations are on the eastern portion.

However, Well SY-3 and to a lesser extent Well SY-2R, which are downgradient of the landfill, generally show higher metals concentrations than other on-site wells. Off-site metals concentrations are substantially less than on-site concentrations, similar to the pattern for leachate indicator parameters, but unlike the total VOC distribution pattern.

3.3.2 Intermediate Zone

Figure 3-11 indicates the distribution and concentrations of VOCs in the intermediate zone in November and December 1993. Because of the limited number of data points on-site, it is not possible to discern whether concentrations are substantially different on the eastern portion of the landfill versus the western part. However, total VOC concentrations on-site are relatively low and are similar to the shallow zone, ranging in concentrations from not detected to 29.2 ug/L.

Off-site (unlike the shallow zone) at Wells RB-11I and PK-10I, total VOCs are slightly higher than on-site. The total VOCs in Well RW-12I is anomalously high with concentrations of 144.5 and 152.3 ug/L (replicate) during the first round, and 259.7 ug/L and 259.4 ug/L (replicate) during the



second round. In fact, the total concentration of VOCs in Well RW-12I is several times higher than any well sampled during either the OU-1 RI or the OU-2 RI, except for Well SY-7 in which VOCs are not believed to be landfill-derived.

Figure 3-14 displays concentrations and the distribution of leachate indicator parameters in the intermediate zone in November and December 1993. Concentrations in two of the three on-site downgradient wells (SY-1D and SY-3D) are substantially higher than concentrations in upgradient Well SY-6D, while downgradient Well SY-2D has concentrations similar to that of Well SY-6D. Leachate indicator concentrations in Well SY-3D on the western portion of the landfill are by far the highest of any on-site intermediate well.

Concentrations of leachate indicators in off-site Well PK-10I are substantially higher than in either of the other two off-site wells (RB-11I and RW-12I) and are similar to but less than concentrations in on-site Well SY-3D. Concentrations of leachate indicator parameters in Well RW-12I are in the range of concentrations found in downgradient on-site wells (with the exception of Well SY-3D), while concentrations in Well RB-11I are comparable with those found in upgradient on-site Well SY-6D.

The location of the highest off-site leachate indicator parameter concentrations (Well PK-10I) does not coincide with the location of the highest off-site concentration of total VOCs (Well RW-12I).

Figure 3-17 displays concentrations and the distribution of metals in the intermediate zone in November and December 1993. With the exception of potassium and sodium, metals concentrations in on-site upgradient (Well SY-6D) and downgradient (Wells SY-1D and SY-2D) wells are all very similar. However, downgradient Wells SY-1D, SY-2D, and SY-3D all have substantially higher potassium and sodium concentrations than upgradient Well SY-6D, with Well SY-3D having the highest. Furthermore, nearly all metals concentrations in Well SY-3D are substantially higher than any other on-site well.



Concentrations of metals in all three off-site intermediate wells (PK-10I, RB-11I, RW-12I), with the exception of potassium and sodium, are essentially the same and also very similar to concentrations found in upgradient on-site Well SY-6D. However, potassium and sodium concentrations in the off-site wells are the highest in Well PK-10I with sodium levels in Well PK-10I very similar to those at on-site Well SY-3D, while potassium levels are considerably less in Well PK-10I relative to Well SY-3D. Sodium and potassium in Well RW-12I are noticeably less than in Well PK-10I and of a similar level to on-site Well SY-2D. Well RB-11I has sodium and potassium levels lower than all other intermediate wells, including on-site upgradient Well SY-6D.

The location of the highest off-site metals concentrations (Well PK-10I) is the same as the location of the highest off-site leachate indicator parameter concentrations, but does not coincide with the location of the highest off-site concentration of total VOCs (Well RW-12I).

3.3.3 Deep Zone

Figure 3-12 depicts VOC concentrations and distributions in the deep zone in November and December 1993. VOCs were not detected in on-site Well SY-3DD and were detected at 6.5 ug/L or less in Wells PK-10D and RB-11D. Well RW-12D had slightly higher total concentrations ranging from 16.4 ug/L (first sampling round) to 31.9 ug/L (second sampling round).

Figure 3-15 shows the distribution and concentration of leachate indicator parameters in the deep zone in November and December 1993. Concentrations in Wells SY-3DD (on-site) and in Wells RB-11D and PK-10D (both off-site) are all very low, while the concentrations in off-site Well RW-12D are substantially elevated compared to the other two off-site wells. The highest total VOC and leachate indicator concentrations in the deep zone both occur in Well RW-12D.

Similar to the intermediate zone, except for potassium and sodium, metals concentrations in all deep wells (on-site and off-site) are very similar (see Figure 3-18). Sodium and potassium levels in on-site Well SY-3DD and off-site Well RB-11D are also very similar. In off-site Well PK-10D, potassium



levels are similar to Wells SY-3DD and RB-11D. However, sodium levels in Well PK-10D are three to five times higher than in Wells SY-3DD and RB-11D. Furthermore, potassium levels in Well RW-12D are two times or more the levels in the other wells, while sodium levels in Well RW-12D are three to ten times the levels in the other deep wells.

The highest total VOC, leachate indicator parameters, and metals concentrations in the deep zone all occur in Well RW-12D.

3.3.4 Comparison of Zones

Total VOC concentrations generally are significantly higher in the intermediate zone as compared to the shallow and deep zones while concentrations are lowest in the deep zone.

Leachate indicator parameter concentrations are also lowest in the deep zone. The shallow and intermediate zones show variable values over the study area with the intermediate zone having the highest concentrations.

Metals concentrations, like for total VOCs and leachate indicator parameters, are lowest in the deep zone. The shallow and intermediate zones show variable values over the study area with the intermediate zone having the highest concentrations.

3.4 CONTAMINANT MIGRATION

As discussed in Sections 3.2.1 (Volatile Organic Compounds) and 3.3 (Contaminant Distribution), the highest total VOC concentrations detected during the OU-2 RI were detected in on-site Well SY-7 (511.7 ug/L [first sampling round] and 547.9 ug/L [second sampling round]). Well SY-7 is a shallow well that only had trace levels of VOCs detected in it during the OU-1 RI. Nearly all of the total VOC concentration in this well during both sampling rounds of the OU-2 RI consisted of benzene, a gasoline component. Well SY-7 is located adjacent to pump islands where gasoline is



dispensed to Town vehicles. Beneath the pump islands are two underground storage tanks (USTs) supplying the gasoline. These two USTs were replaced in 1980 due to the age of the steel tanks and the potential for leakage. They were replaced with single wall fiberglass tanks which were last tested in 1992, complying with the requirements of the Nassau County Fire Marshall Article III regulations. These new USTs are now tested at a frequency of every 5 years. Based on this information, it seems that the VOCs detected in Well SY-7 are from the UST(s) that may have leaked in the past. This impact may be localized based on benzene concentrations in other wells.

Aside from Well SY-7, total VOC concentrations in the shallow zone on-site upgradient and downgradient of the landfill and downgradient off-site are relatively low, are very similar, and while they may be landfill derived, they are consistent with regional background degradation of groundwater (see Appendix M for a further discussion of regional degradation of water quality).

Leachate indicator parameter concentrations (Figure 3-13) show impacts to groundwater on-site and these impacts extend off-site to Well PK-10S, but apparently not to Well RB-11S. Impacts at Well PK-10S are consistent with this well being directly downgradient of the area on-site with the highest leachate indicator concentrations (i.e., between Wells SY-3 and SY-2R). The leachate impacts at Well PK-10S, however, are significantly reduced as compared to on-site.

Similar to the leachate indicator parameters, metals concentrations show impacts to groundwater on-site and these impacts extend off-site to Well PK-10S, but not to Well RB-11S. Impacts at Well PK-10S are consistent with this well being directly downgradient of the area on-site with the highest metals concentrations. The metals impacts at Well PK-10S, however, are significantly reduced as compared to on-site. In the shallow zone, several metals were detected above their respective MCLs on-site in several wells. However, off-site the only metals detected above their respective MCLs were iron at concentrations of more than 680 ug/L (the MCL for iron is 300 ug/L) and sodium at concentrations of up to 20,900 ug/L (the MCL for sodium is 20,000 ug/L) in Well PK-10S. As mentioned above, this well is located directly downgradient of the area on-site with the highest metals concentrations.

Examination of the intermediate zone groundwater flow maps (Figures 3-6 and 3-7) and the VOC distribution map (Figure 3-11) shows that Well PK-10I is downgradient of the landfill and the VOCs detected in this well are similar (type and concentration) to VOCs detected at the landfill, although they are slightly higher than total VOC concentrations found on-site. These concentrations are also consistent with regional degradation of groundwater quality.

Well RW-12I is very close to (and possibly outside of) the westernmost limiting groundwater flowline for the landfill. The total concentrations of VOCs detected in this well are nearly an order of magnitude higher than any total VOC concentration found on-site in either the intermediate or the shallow zone. Constituent levels in groundwater would normally be expected to be highest at a source of contamination and then to progressively decrease further downgradient from the source; this is not the situation with Well RW-12I. Given the fact that Well RW-12I is located hydraulically downgradient of, the western-most edge of the landfill, and adjacent to, and hydraulically downgradient of an industrial area located west of the LIRR tracks, the VOCs detected in this well may be derived from a source other than the landfill.

Although the VOCs in Well RB-11I may be landfill derived, the VOCs are consistent with regional background groundwater quality deterioration and, furthermore, Well RB-11I is outside the easternmost limiting groundwater flow line from the landfill.

The MCLs of selected individual VOCs were exceeded during one or both groundwater sampling rounds in all three off-site intermediate wells (PK-10I, RB-11I, and RW-12I) sampled. Except for Well RW-12I, these VOC concentrations are consistent with regionally degraded groundwater quality as discussed in Appendix M.

The VOC concentrations in Well RW-12I were several times higher than in any of the other wells (on-site or off-site) during either sampling round. Given the fact that Well RW-12I is located hydraulically downgradient of the westernmost edge of the landfill (i.e., near the westernmost limiting groundwater flow line), and adjacent to, and hydraulically downgradient of, an industrial area located



west of the LIRR tracks, the anomalously high concentrations of VOCs detected in this well may be derived from a source other than the landfill. The physical process that could explain how VOCs could impact Well RW-12I is hydrodynamic dispersion. Dispersion is the tendency of a solute or contaminant "to spread out from the path that it would be expected to follow according to the advective hydraulics of the flow system" (Freeze & Cherry 1979) and it is caused by the process of molecular diffusion and mechanical mixing. Mechanical mixing (mechanical dispersion) is the dominant force behind dispersion. Diffusion generally plays a minor role and is only important when groundwater velocity is extremely slow (not the case at the Syosset Landfill) and is proportional to the concentration gradient, i.e., contaminants spread from areas of high concentrations to areas of lower or no concentration. Diffusion becomes more important with higher contaminant concentrations and can cause the spread of contaminants in all directions. Mechanical dispersion occurs in both the direction of bulk groundwater flow (longitudinal dispersion) and transverse to the direction of bulk flow (transverse dispersion). Dispersion is a microscopic phenomenon that results from the different velocities and tortuous path of groundwater flow within the pore spaces of the aquifer material. The process of dispersion is a mixing process that has a qualitatively similar effect to turbulence in surface water regimes (Freeze & Cherry 1979). Thus, it is possible for contaminants (i.e., VOCs) from near the edge of the landfill to spread laterally via transverse dispersion and impact Wells RW-12I and RW-12D. However, it is also possible that contaminants (i.e., VOCs) in Wells RW-12I and RW-12D may be derived from a source other than the landfill by the same process. The same rationale regarding limiting groundwater flow lines and dispersion above generally applies to Well RB-11I, but this cluster is clearly outside the easternmost limiting groundwater flow line (by almost 400 feet) and VOCs detected in this well are even more likely to be derived from a source other than the landfill (i.e., general regional background groundwater quality deterioration).

It is apparent from the data shown on Figure 3-14 that elevated concentrations of leachate indicator parameters exist off-site at Wells PK-10I and RW-12I, suggesting that the landfill has affected groundwater at these locations. The greatest effects are at Well PK-10I, followed by Well RW-12I. Well RB-11I does not show landfill effects based on leachate indicator parameters. Although landfill



leachate effects are apparent at Well RW-12I, as stated above, this does not rule out the possibility of another source causing elevated VOC concentrations at this well.

It is apparent from Figure 3-17 that metals concentrations, especially potassium and sodium, show impacts to the intermediate zone on-site.

Metals impacts (potassium and sodium only) to the intermediate zone also extend off-site to Well PK-10I and to a lesser extent to Well RW-12I. Based on metals data, Well RB-11I does not appear to be affected by the landfill and, in fact, shows metals concentrations similar to or less than those at on-site upgradient Well SY-6D. In the intermediate zone, several metals were detected above their respective MCLs on-site, but, off-site, the only metal detected above its MCL was sodium in Well PK-10I (176,000 ug/L to 237,000 ug/L).

A review of Figures 3-12 (VOCs), 3-15 (leachate indicator parameters), and 3-17 (metals) in conjunction with the deep flow maps (Figures 3-8 and 3-9) indicates that the deep zone has not been impacted by the landfill on-site (Well SY-3DD) or at off-site Well RB-11D. The leachate indicator parameter concentrations are low in these wells and reflect ambient (unimpacted) water quality. The total concentration of VOCs in this off-site well ranges from 0.4 ug/L to 1.3 ug/L with most of the detections being estimated values. Because these values are low and predominately estimated, and because VOCs were not detected in the deep on-site well (SY-3DD), these VOC detections appear to be related to regional degradation of water quality and are not landfill-derived.

Similarly, metals concentrations in Wells SY-3DD (on-site) and RB-11D (off-site) are very similar and do not suggest an effect from the landfill. Although total VOCs are also low in Well PK-10D (1.9 ug/L to 6.5 ug/L) and leachate indicator parameter concentrations are also low in this well, sodium concentrations in Well PK-10D are three to five times higher than in Wells SY-3DD (on-site) and RB-11D (off-site), suggesting an effect from the landfill at this well.



Leachate indicator parameter concentrations at off-site Well RW-12D indicate impacts to the deep zone at this location from the landfill. VOCs in this well may be derived from the landfill; however, the concentrations (16.4 ug/L to 31.9 ug/L) are not inconsistent with regional degradation of water quality. Metals data (sodium and potassium only) show levels substantially greater than concentrations in other deep wells suggesting a landfill effect at this well from metals.

In the deep zone, the only on-site deep well (SY-3DD) had concentrations of iron exceeding the MCL of 300 ug/L for both sampling rounds, but these exceedences apply only for the total analysis not the dissolved analysis. Antimony was also detected in Well SY-3DD above its MCL of 6 ug/L during the first sampling round (25 ug/L) for the total analysis only. Off-site, iron was detected above the MCL in Wells RB-11D (total analysis only for both sampling rounds [975 ug/L and 958 ug/L]) and RW-12D (total analysis only for the second sampling round [552 ug/L]). Sodium was the only other metal to be detected in the off-site deep wells above the MCL. This metal was detected above the MCL for total and dissolved analyses in Wells PK-10D during the first sampling round at concentrations of up to 22,900 ug/L and in RW-12D during both sampling rounds at concentrations of up to 66,500 ug/L.

In summary, landfill-affected groundwater has migrated to two of the three off-site well cluster locations (Town Park [PK] wells, and Roadway [RW] property wells). Due to the significantly steeper vertical hydraulic gradient with respect to the relatively flat horizontal hydraulic gradient, landfill-derived contaminants have moved off-site in groundwater into the intermediate zone; the greatest impacts off-site are in the intermediate zone.

3.5 FATE AND TRANSPORT OF CONTAMINANTS

This section evaluates the mechanisms that control the migration and fate of contaminants in the subsurface. In this section, potential routes of migration through the vadose and phreatic (saturated) zones of the Magothy aquifer are discussed, followed by descriptions of the physical, chemical, and



biological processes that affect the fate and transport of contaminants. In addition, an initial analysis of exposure pathways is presented to provide insight on potential risks posed by the migration of VOCs.

3.5.1 Potential Routes of Migration

Generally, when contaminants are released at the surface or in the shallow subsurface, they may migrate vertically downward through the vadose, or unsaturated zone, until they reach the water table, which represents the upper surface of the phreatic, or saturated, zone. When dissolved contaminants reach the water table, groundwater flow dynamics will be the primary influence on their migration.

3.5.1.1 Vadose Zone

During precipitation events, rainfall percolates through the landfill and dissolves contaminants which then migrate vertically downward under the influence of gravity through the vadose zone. This contaminated water moves vertically downward through the vadose zone until the water-table zone is encountered. Near the Syosset Landfill, the vadose zone consists of the coarse sand deposits of the Upper Glacial Formation.

3.5.1.2 Phreatic Zone

In the Syosset Landfill study area, the phreatic zone (exclusive of the Raritan Formation which is not the subject of the study) consists of the Magothy aquifer, which is characterized as having a relatively high permeability (approximately 50 feet per day), but lower permeability than the Upper Glacial aquifer (approximately 270 feet per day) (Franke and Cohen 1972). In the unconsolidated deposits of the Magothy aquifer, groundwater moves through the interstitial porespace. Physical processes that affect the transport of dissolved contaminants in the phreatic zone are advection, dispersion, and diffusion. Chemical factors inherent to these processes will be discussed below (Characteristics and Behavior of Contaminants).



3.5.1.3 Advection

The process by which dissolved contaminants are transported by the bulk movement of flowing groundwater is known as advection. The path of migration for dissolved contaminants in groundwater near the landfill is therefore primarily in the direction of groundwater flow. As discussed in the Hydrogeology section, groundwater flow in the vicinity of the site is primarily downward and to the north.

3.5.1.4 Dispersion and Diffusion

Dispersion and diffusion are processes that spread dissolved constituents in groundwater. The spread of dissolved contaminants from the Syosset Landfill is generally due to dispersion. Dispersion is dependent on groundwater velocity and it usually occurs at much higher rates than diffusion, which is dependent on solute concentration gradients. Dispersion is a mixing process that occurs at the microscale because of the nonlinear movement (or tortuous path) of groundwater through the aquifer material. This nonlinear movement results from heterogeneities in hydraulic properties of the geologic materials, which cause contaminants to move faster through some parts of the saturated material than through others. The amount of dispersion varies with groundwater velocity and is greatest in the direction of groundwater flow. Thus, dispersion in directions transverse to flow is typically much less than dispersion in the direction of flow (Freeze and Cherry 1979). At the Syosset Landfill, the rate of groundwater flow is relatively slow in the horizontal direction because of the very flat horizontal hydraulic gradient; it is also slow in the vertical direction because the very low vertical permeability (due to the presence of lower permeability clay stringers, lenses and layers) offsets the higher downward hydraulic gradient (as compared to the horizontal hydraulic gradient).

Concentration gradients are the driving mechanism for the diffusion of contaminants in groundwater. Diffusion in solutions is the process whereby ionic or molecular constituents move in the direction of their concentration gradients or from areas of high concentrations to areas of low or no concentrations. This process stops only when chemical equilibrium occurs (the concentration gradients



become nonexistent). Typically, this process is significant only where groundwater velocities are extremely slow (not the case at the Syosset Landfill).

3.5.2 Characteristics and Behavior of Contaminants

Natural processes that affect the migration of contaminants in soil/water systems are sorption, volatilization, and transformation.

3.5.2.1 Sorption

Sorption is a physical process that retards the migration of contaminants in the subsurface. Organic compounds, such as VOCs, tend to partition between the groundwater and any solid organic carbon present in the aquifer material, and inorganic compounds tend to partition between the groundwater and clay minerals. Sorption is the reversible attachment of contaminants to solids or colloids in the subsurface. The type of attachment and the rate of sorption is dependent upon the type of contaminants and the solid/colloid. Sorption is also dependent upon the amount of available surface area or sites on the solid/colloid surface to which the contaminants may sorb. Once all of the available sites have been utilized, no more sorption will occur.

The rate of contaminant sorption is also influenced by the amount of organic carbon or clay minerals that is in direct contact with groundwater as it migrates through the pore spaces of the aquifer. If the carbon or clay is bound within the aquifer matrix or occurs at "dead end" pore spaces, then it will have little, if any, effect on the sorption of dissolved VOCs or inorganics. In general, sorption can be a significant process in controlling the rate of migration of contaminants.

The mobility of an organic compound can be evaluated by examining its aqueous solubility and the log of the organic carbon partition coefficient ($\log K_{oc}$). Aqueous solubility is a measure of the amount of a compound that will dissolve in a unit volume of water; more soluble compounds are generally more mobile. The $\log K_{oc}$ is a measure of the relative affinity of a compound for an organic



medium (organic carbon) versus an aqueous medium (water); the lower the $\log K_{oc}$, the more mobile the compound.

The mobility of metals is assessed by examining the solubility of the metal, the relative propensity of the metal to form insoluble compounds, and the ability of the metal to sorb (bind) to clays (ion exchange). Because of the range of possible reactions, the mobility of metals is usually expressed qualitatively (i.e., high, medium, low).

3.5.2.2 Volatilization

Volatilization is a process generally associated with organic compounds or ammonia and refers to the transfer of compounds from the dissolved phase to the gaseous (vapor) state. Volatilization is assessed by examining the Henry's law constant for each compound. A smaller value of the Henry's law constant correlates with a less volatile compound. In the vadose zone, VOCs and ammonia can partition into the vapor phase (volatilize) and be transported vertically and horizontally. VOCs and ammonia can also volatilize from the groundwater at the water table and migrate into the vadose zone in the vapor phase. Except for mercury, volatilization is not an important process for the transport of metals and inorganic anions because of their low vapor pressures.

3.5.2.3 Transformation

Many of the VOCs detected in groundwater at the Syosset Landfill may represent breakdown products of other, more chlorinated VOC molecules. This breakdown, or transformation, can be biological or chemical (abiotic). Inorganic chemicals may also undergo transformation depending on the chemical composition of the porous media (aquifer material), the chemical composition of ambient groundwater, and the presence of microorganisms.

The chlorinated aliphatic VOCs (for example, trichloroethene, tetrachloroethylene, cis- and trans-1,2-dichloroethene, 1,1-dichloroethene, and 1,1-dichloroethane) are susceptible to biological



transformation, but the rate of transformation can be very slow, particularly for TCE. Microorganisms in the subsurface can transform chlorinated VOCs and inorganic chemicals by the processes of oxidation or reduction. This transformation results in the production of another VOC or a net loss of VOCs from the groundwater. Generally, chlorinated aliphatic VOCs are reduced sequentially by hydrogenolysis (replacement of chlorine atoms by hydrogen) under strictly anaerobic conditions (Bechtel Environmental, Inc. 1990). For example, TCA may be dechlorinated to 1,1-dichloroethane (1,1-DCA) and PCE may be sequentially dechlorinated to TCE and 1,2-dichloroethene. Reduction of chlorinated alkanes (for example, 1,1-DCA or TCA) can also involve the loss of two halogens (dihalo-elimination), resulting in conversion to an alkene. An example is the conversion of 1,2-dichloroethane to ethene (Vogel et al. 1987). Although hydrogenolysis occurs only under anaerobic conditions, dihalo-elimination can occur under either aerobic or anaerobic conditions. Bacteria can also oxidize some chlorinated compounds. For example, bacteria can transform TCE to biodegradable hydrolysis products (alcohols) in a methane-enriched groundwater environment (Henson, Yates et al. 1988).

Abiotic transformation mechanisms of significance to chlorinated aliphatics are substitution and dehydrohalogenation. Substitution reactions include hydrolysis, which produces an alcohol. An example of dehydrohalogenation is the conversion of TCA to 1,1-dichloroethene (Vogel et al. 1987). Abiotic transformations are generally much slower than biological transformations.

Transformation rates for VOCs and inorganic chemicals are typically estimated from laboratory or small-scale field experiments. Indirect evidence for transformation is obtained from the relative distributions of constituents. Concentration ratios (for VOCs for example, PCE:TCE) are often examined to determine whether transformation has occurred. Application of this technique is limited when there is more than one source location, when different commercial products of varying grades of purity may have been released, and when the site-specific contaminants migrate at significantly different rates because of different retardation factors (e.g., sorption rates). Nonetheless, it is important to recognize the potential for transformations to occur because transformation can have a significant overall effect on the migration of contaminants in the subsurface.



3.5.2.4 Precipitation - Oxidation Reduction

Inorganic contaminants in groundwater can be removed by precipitation. The law of mass action, which states that the rate of a chemical reaction is proportional to the masses of the precipitating substances (Hem 1985), can be used to analyze which chemical equilibria may occur. In impacted aquifers, static species may precipitate as inorganic contaminants mixed with native groundwater.

Many inorganic elements can exist in different oxidation states and can undergo oxidation/reduction (redox) reactions as the plume changes from anaerobic to aerobic conditions. Some of the redox reactions are mediated by microorganisms. As the oxidation state of an element is changed, it may then precipitate as it mixes with groundwater.

3.5.3 Analysis of Exposure Pathways

Because the Syosset Landfill capping program is in progress in accordance with 6 NYCRR Part 360, and based on the results of landfill gas monitoring that indicate that landfill gases have not migrated off-site, the only potential route of exposure is the groundwater. The nearest active public supply wells are owned by the Jericho Water District (N-198, which is screened from 566 to 616 feet below land surface, and N-199, which is screened from 544 to 600 feet below land surface). These wells are located approximately 2 miles downgradient (north) of the landfill. The contaminants of concern have been defined as those chemical constituents (VOCs) that were detected above MCLs in on-site and off-site monitoring wells during the OU-1 and OU-2 RIs. It is highly improbable that these VOCs will reach public supply wells N-198 and N-199 at detectable concentrations, even assuming that these wells are within the groundwater flow path from the landfill. This analysis is based on the relatively low concentrations of these constituents, the distance of the wells from the landfill, and the mitigating effects of dispersion and biochemical processes discussed above. The risks posed by the contaminants of concern will be addressed in more detail in a future risk assessment report.



3.6 POTENTIAL IMPACTS FROM RECHARGE BASINS

3.6.1 Leachate Indicator Parameters

The concentrations and distribution of leachate indicator parameters observed during the OU-2 RI in the on-site and off-site groundwater monitoring wells are consistent with a plume of impacted groundwater derived from the Syosset Landfill, that is moving downward, and extending off-site. This contaminant profile correlates well with the horizontal and vertical groundwater flow directions observed during the OU-2 RI. As stated in the Contaminant Distribution section (3.3) of the OU-2 RI, the concentrations of leachate indicator parameters detected in the on-site wells are similar to the concentrations detected in the deeper (intermediate) off-site wells. This similarity, therefore, lacks the variability in contaminant concentrations that would otherwise indicate a contribution of these constituents from another source, such as one of the stormwater basins near the site.

On Long Island, stormwater runoff, which is mainly from roads, comprises approximately 20 percent of the recharge to the underlying aquifers, and is collected in the more than 2,000 stormwater basins scattered throughout Nassau and Suffolk Counties (Long Island Regional Planning Board 1978). The potential impacts of stormwater runoff that collects in Long Island recharge basins was addressed in a major study conducted for the Long Island Regional Planning Board (LIRPB): Long Island Segment of the Nationwide Urban Runoff Program (LIRPB 1982). It was concluded in the 1982 LIRPB report that "with the exception of lead and chloride, the concentrations of inorganic chemicals measured in stormwater runoff do not have the potential to adversely affect groundwater quality" (LIRPB 1982).

3.6.2 Volatile Organic Compounds

As discussed in Appendix M (Regional Background Groundwater Quality), except for Well RW-12I, the VOC concentrations detected in on-site and off-site monitoring wells are consistent with



regionally degraded background groundwater quality conditions for an area with land use such as near the site.

3.7 OFF-SITE SUBSURFACE GAS

A summary of the results of the OU-2 landfill gas monitoring is presented in Table 3-5. These data indicate that landfill gases were detected at relatively elevated concentrations (primarily methane) in one of the gas monitoring wells in the southwestern part of the landfill (G-7) and are consistent with the findings of the OU-1 RI. Landfill gas was not detected in the off-site gas monitoring wells and does not appear to be migrating off-site. (See Appendix K for the results of gas monitoring conducted separately by LKB as part of the OU-1 Remedial Design Program.)



4.0 CONCLUSIONS

Based on the results of the OU-2 RI, the following conclusions were developed.

4.1 OFF-SITE GROUNDWATER STUDY

1. Hydrogeologic conditions encountered during the OU-2 RI are generally consistent with conditions found during the OU-1 RI and published data.
2. The regional potentiometric surface map of the shallow zone of the Magothy Formation indicates that the position and orientation of the regional groundwater divide is virtually the same as it was during the OU-1 RI and is south of the landfill. Regional shallow groundwater flow was documented to be in a north-northeasterly direction near the site, which is also consistent with the OU-1 RI findings.
3. The site-specific horizontal direction of groundwater flow in the shallow, intermediate, and deep zones of the Magothy Formation is generally to the north. However, in the shallow zone on-site, groundwater also flows from the west and east parts of the site toward the center of the landfill before moving north toward the Town Park.
4. The direction of the vertical hydraulic gradient is predominately downward in the study area. The vertical hydraulic gradient is approximately four times steeper than the horizontal hydraulic gradient; this is consistent with the proximity of the site to the regional groundwater divide.
5. Water-quality data for Cluster 11 indicate that, based on concentrations of typical landfill leachate indicator parameters and metals, the landfill has not affected water quality at this location, which is consistent with this cluster being located considerably outside the easternmost limiting flow line from the landfill. Based on this information and the fact



that VOCs detected in this cluster are consistent with regional background groundwater quality deterioration, the VOCs here are likely not landfill derived.

6. Water-quality data for Cluster 10, which is directly downgradient of the landfill, show elevated levels of typical landfill leachate indicator parameters, as well as elevated metals concentrations, indicating landfill effects at this location. While VOCs at this cluster may be landfill derived, they are consistent with regional background groundwater quality deterioration.
7. Water-quality data for Cluster 12 show that elevated levels of typical landfill leachate indicator parameters, as well as elevated metals concentrations, are present at this cluster (which is approximately at the westernmost limiting flow line from the landfill), indicating landfill effects at this location. While VOCs in Well RW-12D may be landfill derived, the concentrations here are also consistent with regional background groundwater quality deterioration. VOCs in Well RW-12I appear to be from a source other than the landfill. This is based on an assessment of available information gathered as part of the OU-1 RI and OU-2 RI, including on-site and off-site groundwater quality data, Industrial Survey data, regional hydrogeological data, and soil boring data obtained during the OU-1 RI. This conclusion is based on the following:
 - The elevated concentrations of PCE and TCA in Well RW-12I do not appear to be from the landfill and may be caused by a more recent or currently active source since the ratio of breakdown products versus PCE and TCA at Well RW-12I (see Appendix P for further details) show a mix dominated by parent compounds not breakdown products, which is the converse of other off-site wells and the fact that VOCs are nearly 10 times higher in Well RW-12I than on-site, not what would be expected if the landfill was the source. Furthermore, the concentrations of leachate indicator parameters in Wells RW-12I and RW-12D are very similar, while VOCs in Well RW-12I are nearly 10 times



greater than in Well RW-12D. This disparity between VOCs and leachate concentrations suggests that the VOCs in Well RW-12I are due to a source other than the landfill.

- The industrial area survey (see Appendix O for details) identified five off-site properties which are potential sources of the VOCs detected in Well RW-12I. These properties are located on Robbins Lane and Aerial Way, between 1,400 and 2,100 feet southwest of Well RW-12I. Each of these properties used one or more of the VOCs detected in Well RW-12I, and two properties, Space Machine Corp. and Spiegel Associates, had releases which required soil remediation. In addition, these properties likely discharged wastewater to on-site septic systems and leaching fields prior to the construction of sewers in the 1980s. It is, therefore, reasonable to expect that releases of VOCs to groundwater have occurred at one or more of these properties.
- Regional hydrogeologic data indicate that the potential off-site sources identified in the industrial area survey are located hydraulically upgradient of Well RW-12I, and are situated between the well and the regional groundwater divide. Specifically, the regional horizontal flow direction for the Magothy Aquifer in the vicinity of the Syosset Landfill is northeast, and the regional groundwater divide is located approximately 3,100 feet south of Well RW-12I and is oriented west to east (Figure 3-3 of OU-2 RI Report). Moreover, because the vertical gradient is three to five times the horizontal gradient (Section 3.1.4 of OU-2 RI Report) in the vicinity of the landfill, releases from these potential off-site sources could migrate to the intermediate zone of the Magothy Aquifer at Well RW-12I.
- Data from on-site soil borings and monitoring wells indicate that the landfill is not the source of the elevated levels of VOCs detected in Well RW-12I. Specifically, if the landfill was the source of these VOCs, it is expected that substantial residual contamination would be present. Instead, these VOCs (specifically, PCE, TCA, TCE, 1,1-DCE, and 1,1-DCA) were only detected at low concentrations (5 to 9 ppb) in three of 44 samples from 10 soil borings, including samples of the fill and the soil directly



underlying the landfill (Tables 16 and 17 of the OU-1 RI Report). Similarly, these VOCs were only detected at low concentrations (0.1J to 30 ppb) in 27 of 56 groundwater samples from 16 on-site monitoring wells (Table 9 of the OU-1 RI Report, Table 1 of the OU-2 RI Report, and Table 1 of Appendix P).

- In summary, we can conclude that based on: the lack of degradation of PCE and TCA in Well RW-12I; the identification of properties within the previously unsewered Industrial Park who used and/or are using PCE and TCA and have had reported releases; regional hydrogeologic data indicating the Industrial Park is upgradient of Well RW-12I; and the low levels of these compounds found on-site in both the soil and groundwater during the OU-1 RI, the high concentrations of VOCs (particularly PCE and TCA) in Well RW-12I appear to be from a source(s) located in the Industrial Park west of the LIRR tracks.

In conclusion, based on leachate indicator concentrations and metals concentrations, landfill-impacted groundwater has migrated to two of the three off-site well cluster locations (Town park and Roadway property); however, the recharge basin location apparently does not show landfill impacts based on these parameters. The greatest impacts off-site are in the intermediate zone of the Magothy Formation. The significantly steeper vertical hydraulic gradient, as compared to the horizontal gradient, has resulted in landfill-derived contaminants moving off-site into the intermediate zone (Wells PK-10I and RW-12I). The total concentrations of VOCs in off-site intermediate wells at the Town Park (PK-10I) and at the Recharge Basin (RB-11I) are consistent with the total VOC concentrations detected in the on-site shallow monitoring wells. These concentrations are also consistent with regional background degradation of groundwater quality. In particular, this is true for Well RB-11I, which is located outside the easternmost limiting groundwater flowline from the landfill. The total concentration of VOCs in RW-12I is anomalously high, several times higher than the concentrations encountered in any other monitoring well during either the on-site or off-site RIs. The high concentrations of volatile organic compounds (particularly PCE and TCA) in Well RW-12I appear to be from a source(s) located in the Industrial Park west of the LIRR tracks. This conclusion is based on the fact that RW-12I is located hydraulically downgradient of the westernmost edge of the landfill and



is located hydraulically downgradient of, and adjacent to, an industrial area located west of the LIRR tracks. This conclusion is further supported by the lack of degradation of PCE and TCA in Well RW-12I; the identification of properties within the previously unsewered Industrial Park who used and/or are using PCE and TCA and have had reported releases; regional hydrogeologic data indicating the Industrial Park is upgradient of Well RW-12I; and the low levels of these compounds found on-site in both the soil and groundwater during the OU1 RI.

4.2 SUBSURFACE GAS STUDY

1. Landfill gas (primarily methane) was detected at relatively elevated concentrations in one of the gas wells on the southwestern part of the landfill and is consistent with the findings of the OU-1 RI. Landfill gas was not detected in the three new off-site subsurface gas monitoring wells and does not appear to be migrating off-site. (See Appendix K for the results of gas monitoring conducted separately by LKB as part of the OU-1 Remedial Design Program.)



5.0 REFERENCES

- Betchel Environmental, Inc. 1990. Caribe General Electric Groundwater Investigation Report, November 1990.
- Converse Consultants East, PC 1993. Settlement Study for the Syosset Landfill, First Operable Unit Remediation, Town of Oyster Bay, New York, July 1993.
- Dvirka and Bartilucci Consulting Engineers. 1986. Investigation of Contaminated Aquifer Segments, Nassau County, New York. Nassau County Department of Health, June 1986.
- Franke, O.L. and P. Cohen. 1972. Regional Rates of Ground-Water Movement on Long Island, New York. U.S. Geological Survey Professional Paper 800-C, pp. C271 - C277.
- Freeze, R.A., and J.A. Cherry. 1979. Groundwater. Englewood Cliffs, New Jersey, Prentice Hall, pp. 604.
- Geraghty & Miller, Inc. 1989. Interim Remedial Investigation Report, Syosset Landfill, Syosset, New York, August 1989.
- Geraghty & Miller, Inc. 1991. Work Plan for the Second Operable Unit Remedial Investigation at the Syosset Landfill, Syosset, New York, April 1991.
- Geraghty & Miller, Inc. 1992. Site Operations Plan, Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York, May 1992.
- Glasser, V.J. and Wolfert, M.F. Geraghty & Miller, Inc. Letter to S. Henry, U.S. Environmental Protection Agency, December 3, 1992.
- Glasser, V.J. and Wolfert, M.F. Geraghty & Miller, Inc. Letter to J.P. Lekstutis, P.E., Vice President, Lockwood, Kessler & Bartlett, Inc., April 1, 1993.
- Henson, J.M., M.V. Yates, J.W. Cochran, and D.L. Shackleford, 1988. Microbial Removal of Halogenated Methanes, Ethanes, and Ethylenes in Aerobic Soil Exposed to Methane. FEMS Microbiology Ecology, vol. 53, pp. 193 - 201.
- Isbister, J. 1966. Geology and Hydrogeology of Northeastern Nassau County, Long Island, New York. U.S. Geological Survey Water-Supply Paper 1825, pp. 89.
- Kilburn, C. and R.K. Krulikas. 1987. Hydrogeology and Ground-Water quality of the Northern Part of the Town of Oyster Bay, Nassau County, New York, in 1980. U.S. Geological Survey Water-Resources Investigations Report 85-4051, pp.61.



Long Island Regional Planning Board. 1978. Long Island Comprehensive Waste Treatment Management Plan.

Long Island Regional Planning Board. 1982. The Long Island Segment of the Nationwide Urban Runoff Program.

Vogel, T.M., C.S. Criddle, and P.L. McCarty. 1987. Transformations of Halogenated Aliphatic Compounds. Environmental Sciences and Technology, vol. 21, no. 8, pp. 722 -736.

G:\PROJECT\LOCKESBANY\0029\099\REPORTS\RI95.DOC





Table 2-1. Summary of Field and Laboratory Measurements of Leachate Parameters of Groundwater Samples Collected During Drilling of Exploratory Borings SY-3DD and PK-10D During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample Depth (feet) | Date Sampled | Action Level (a): | Primary Leachate Parameters | | | Secondary Leachate Parameters | | | |
|------------------------|-----------------|----------------------|-----------------------------|--------------------------------|---------------------------|-----------------------------------|-----------------------|--------------------------|----------------------------------|
| | | | Alkalinity (mg/L) 11 | Total Hardness (mg/L) 43 | Ammonia (mg/L) 0.12 | Conductivity (umhos/cm) 217 | pH (units) 5.75 | Chloride (mg/L) 19 | Temperature (Celcius) 14.5 |
| Well SY-3DD | | | | | | | | | |
| 118 | 11/5/92 | | (c) | 39 | 23 | 280 | 5.05 | 28 | 15 |
| 137 | 11/5/92 | | 190 | 140 | 21 | 640 | 6.35 | 36 | 15 |
| 158 | 11/6/92 | | 390 | 170 | 71 | 960 | 6.35 | 54 | 15 |
| 179 | 11/6/92 | | 840 | 380 | 160 | 1,600 | 6.95 | 120 | 15 |
| 192 | 11/6/92 | | 630 | 280 | 120 | 1,200 | 7.35 | 26 | 15 |
| 218 | 11/6/92 | | 910 | 300 | 420 | 2,000 | 7.85 | 22 | 15 |
| 239 | 11/9/92 | | 890 | 400 | 150 | 2,400 | 7.35 | 100 | 15 |
| 256 | 11/9/92 | | 540 | 330 | 200 | 1,900 | 7.05 | 180 | 15 |
| 279 | 11/9/92 | | 440 | 310 | 180 | 1,900 | 7.10 | 240 | 15 |
| 299 | 11/9/92 | | 500 | 280 | 160 | 1,700 | 6.10 | 270 | 15 |
| 318 | 11/10/92 | | 430 | 270 | 220 | 2,300 | 6.55 | 490 | 15 |
| 335 | 11/17/92 | | 360 | 200 | (b) | 2,200 | 7.87 | 390 | 15 |
| 355 | 11/17/92 | | 31 | 220 | (b) | 1,200 | 7.90 | 190 | 15 |
| 355 (d) | 11/17/92 | | 31.7 | 211 | 11.4 | NA | NA | 200 | NA |
| 375 | 11/17/92 | | 38 | (c) | (b) | 1,600 | 4.80 | (c) | 15 |
| 375 (d) | 11/17/92 | | 41.6 | 231 | 19.1 | NA | NA | 271 | NA |
| 395 | 11/17/92 | | 70 | 210 | (b) | 1,200 | 7.20 | 230 | 15 |
| 395 (d) | 11/17/92 | | 76.4 | 174 | 21.0 | NA | NA | 222 | NA |
| 417 | 11/18/92 | | 48 | 250 | 5.0 | 1,500 | 7.80 | 270 | 15 |
| 437 | 11/18/92 | | 52 | 240 | 4.0 | 1,200 | 7.70 | 220 | 15 |

See last page for footnotes.

Table 2-1. Summary of Field and Laboratory Measurements of Leachate Parameters of Groundwater Samples Collected During Drilling of Exploratory Borings SY-3DD and PK-10D During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample Depth (feet) | Date Sampled | Action Level (a): | Primary Leachate Parameters | | | Secondary Leachate Parameters | | | Temperature (Celcius) 14.5 |
|-------------------------|-----------------|----------------------|-----------------------------|--------------------------------|---------------------------|-----------------------------------|-----------------------|--------------------------|----------------------------------|
| | | | Alkalinity (mg/L) 11 | Total Hardness (mg/L) 43 | Ammonia (mg/L) 0.12 | Conductivity (umhos/cm) 217 | pH (units) 5.75 | Chloride (mg/L) 19 | |
| Well SY-3DD (Continued) | | | | | | | | | |
| 457 | 11/18/92 | | 80 | 240 | 2.4 | 1,100 | 7.70 | 180 | 15 |
| 480 | 11/25/92 | | 66 | 180 | 2.6 | 920 | 7.70 | 150 | 15 |
| 500 | 11/30/92 | | 15 | 23 | 0.41 | 56 | 7.40 | 15 | 15 |
| 520 | 12/1/92 | | 9.7 | 9.0 | 0.29 | 58 | 7.20 | 4.9 | 15 |
| 520 (e) | 12/1/92 | | 12 | 6.9 | <0.05 | NA | NA | 6 | NA |
| 520** | 12/1/92 | | 10 | 8.1 | 0.16 | 57 | 7.20 | 4.8 | 15 |
| 540 | 12/1/92 | | 13 | 12 | <0.06 | 52 | 6.80 | 5.2 | 15 |
| PK-10D | | | | | | | | | |
| 120 | 12/15/92 | | (b) | (b) | (b) | (b) | (b) | (b) | (b) |
| 140 | 12/15/92 | | 5.5 | 59 | <0.06 | 240 | 7.45 | 14 | 15 |
| 160 | 12/15/92 | | 13 | 59 | <0.06 | 240 | 7.25 | 17 | 15 |
| 180 | 12/15/92 | | 37 | 39 | <0.06 | 180 | 7.15 | 14 | 15 |
| 200 | 12/15/92 | | 39 | 92 | <0.06 | 340 | 5.25 | 18 | 15 |
| 220 | 12/15/92 | | (b) | (b) | (b) | (b) | (b) | (b) | (b) |
| 240 | 12/15/92 | | 44 | 78 | <0.06 | 400 | 5.45 | 42 | 15 |
| 260 | 12/16/92 | | (c) | (c) | (c) | (c) | (c) | (c) | 15 |
| 280 | 12/16/92 | | 37 | 93 | 0.17 | 500 | 7.55 | 47 | 15 |
| 280(e) | 12/16/92 | | 33.7 | 92.2 | 0.65 | NA | NA | 46.8 | NA |
| 300 | 12/16/92 | | 18 | 63 | 0.08 | 300 | 7.10 | 26 | 15 |
| 300 (d) | 12/16/92 | | 16 | 58 | 0.07 | 290 | 7.15 | 23 | 15 |

See last page for footnotes.

Table 2-1. Summary of Field and Laboratory Measurements of Leachate Parameters of Groundwater Samples Collected During Drilling of Exploratory Borings SY-3DD and PK-10D During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample Depth (feet) | Date Sampled | Action Level (a): | Primary Leachate Parameters | | | Secondary Leachate Parameters | | | Temperature (Celcius) 14.5 |
|------------------------|-----------------|----------------------|-----------------------------|--------------------------------|---------------------------|-----------------------------------|-----------------------|--------------------------|----------------------------------|
| | | | Alkalinity (mg/L) 11 | Total Hardness (mg/L) 43 | Ammonia (mg/L) 0.12 | Conductivity (umhos/cm) 217 | pH (units) 5.75 | Chloride (mg/L) 19 | |
| PK-10D (Continued) | | | | | | | | | |
| 300(e) | 12/16/92 | | 15 | 58.6 | 0.10 | NA | NA | 23.3 | NA |
| 320 | 12/16/92 | | 66 | 47 | 6.2 | 750 | 7.65 | 68 | 15 |
| 340 | 12/16/92 | | 250 | 220 | 19 | 1,670 | 7.45 | (e) | 15 |
| 360 | 12/17/92 | | 370 | 310 | 24 | 2,000 | 7.55 | 360 | 15 |
| 380 | 12/18/92 | | 220 | 278 | 19 | 2,100 | 7.90 | 439 | 15 |
| 400 | 12/18/92 | | 150 | 210 | 9.9 | 1,600 | 7.70 | 350 | 15 |
| 420 | 12/21/92 | | 46 | 120 | 8.6 | 720 | 7.15 | 140 | 15 |
| 440 | 12/21/92 | | 6.6 | 75 | <0.06 | 400 | 6.25 | 76 | 15 |
| 460 | 12/22/92 | | 6.8 | 160 | 0.08 | 920 | 7.10 | 160 | 15 |
| 479 | 12/28/92 | | 6.1 | 7.6 | 0.07 | 50.6 | 6.80 | 11.2 | 15 |
| 479(e) | 12/28/92 | | <1.0 | 62.2 | 0.09 | NA | NA | 7.53 | NA |
| 499 | 12/28/92 | | 9.1 | 16 | 0.07 | 74 | 7.0 | 13 | 15 |
| 499(e) | 12/28/92 | | 9.9 | 12.8 | 0.51 | NA | NA | 14.5 | NA |
| Hydrant Water | 11/6/92 | | 39 | 47 | 30 | 200 | 4.90 | 16 | 15 |
| Hydrant Water | 12/1/92 | | 45 | 33 | 0.14 | 180 | 8.70 | 15 | 15 |
| Hydrant Water | 12/17/92 | | 31 | 13 | <0.06 | 160 | 8.20 | 8.7 | 15 |

mg/L Milligrams per liter.

umhos/cm Micromhos per centimeter.

(a) Based on statistical analysis of background water-quality data.

(b) Probe malfunction.

(c) Not enough sample collected for all analyses.

(d) Replicate sample analyzed by IEA, Inc., Monroe, Connecticut.

(e) Replicate sample analyzed by EcoTest Laboratories, Inc., North Babylon, New York.

** Field replicate.

NA Not analyzed.

Table 2-2. Summary of Construction Details of New and Preexisting Monitoring Wells Installed at and near the Syosset Landfill, Syosset, New York.

| Well Designation | Completion Date | Well Diameter (inches) | Total Depth (feet below land surface) | Screen Setting (feet below land surface) | Interval Gravel Packed (feet below land surface) | Interval Sealed With Bentonite Pellets (feet below land surface) | Interval Sealed With Bentonite Slurry/Volclay (feet below land surface) | Height of Measuring Point (a) (relative to land surface) | Elevation of Measuring Point (b) (feet above mean sea level) | Well Casing and Screen Material |
|------------------|-----------------|------------------------|---------------------------------------|--|--|--|---|--|--|---------------------------------|
| SY-1 (c) | 10/19/82 | 2 | 135 | 125 - 135 (d) | 35 - 135 (d) | 34 - 35 | 8 - 34 (e) | -0.15 | 194.52 | Black steel |
| SY-1D | 2/2/88 | 4 | 218 | 182 - 192 | 179 - 218 | 177 - 179 | 2 - 177 | +2.31 | 197.36 | PVC |
| SY-2R | 2/12/88 | 4 | 150 | 115 - 125 | 112 - 150 | 110 - 112 | 2 - 110 | +1.95 | 187.12 | PVC |
| SY-2D | 2/9/88 | 3 | 215 | 190 - 200 | 187 - 215 | 185 - 187 | 2 - 185 | +2.18 | 186.33 | PVC |
| SY-3 (c) | 10/20/82 | 2 | 145 | 135 - 145 | 47 - 145 (d) | 45 - 47 | 4 - 45 (e) | -0.50 | 191.38 | Black steel |
| SY-3D | 2/25/88 | 3 | 240 | 189 - 199 | 184 - 240 | 181 - 184 | 2 - 181 | +2.45 | 194.74 | PVC |
| SY-3DD | 12/9/92 | 2 | 540 | 530 - 540 | 517 - 540 | 512 - 517 (f) | 2 - 512 | 0 | 194.23 | PVC, stainless steel |
| SY-4 | 10/20/82 | 2 | 153 | 143 - 153 (d) | 57 - 153 (d) | 54 - 57 | 4 - 54 (e) | -0.20 | 193.32 | Black steel |
| SY-5 (c) (h) | 10/20/82 | 2.5 | 135 | 125 - 135 (d) | 46 - 135 (d) | 44 - 46 | 5 - 44 (e) | +4.20 | 188.07 | Galvanized steel |
| SY-6 (c) | 10/19/82 | 2 | 145 | 135 - 145 (d) | 31 - 145 (d) | 28 - 31 | 5 - 28 (e) | -0.10 | 185.92 | Black steel |
| SY-6D | 3/9/88 | 4 | 215 | 195 - 205 | 192 - 215 | 190 - 192 | 3 - 192 | -0.30 | 185.60 | PVC |
| SY-7 (c) | 10/21/82 | 2 | 145 | 135 - 145 (d) | 52 - 145 (d) | 49 - 52 | 5 - 49 (e) | -0.25 | 197.46 | Black steel |
| SY-8 | 12/19/87 | 4 | 142 | 127 - 137 | 125 - 142 | 122 - 125 | 2 - 122 | +2.25 | 195.84 | PVC |
| SY-9 | 1/29/88 | 4 | 140 | 110 - 120 | 107 - 140 | 105 - 107 | 2 - 105 | -0.70 | 199.41 | PVC |
| W-3 | 11/10/87 | 2 | 120 | 105 - 115 | 102 - 120 | 100 - 102 | 2 - 100 | +2.63 | 190.61 | PVC |
| W-4 (h) | 11/18/87 | 2 | 120 | 104 - 114 | 102 - 120 | 100 - 102 | 2 - 100 | +2.56 | 192.82 | PVC |
| PK-10S | 3/25/93 | 4 | 149 | 139 - 149 | 5 - 149 | (i) | (i) | -0.40 | 188.70 | PVC, stainless steel |
| PK-10I | 4/14/93 | 4 | 362 | 352 - 362 | 346.5 - 363 | 341.5 - 346.5 (f) | 2 - 341.5 (g) | 0 | 187.62 | PVC, stainless steel |
| PK-10D | 12/31/92 | 4 | 499 | 489 - 499 | 477 - 500 | 472 - 477 (f) | 2 - 472 (g) | 0 | 188.23 | PVC, stainless steel |
| RB-11S | 8/26/93 | 4 | 143 | 133 - 143 | 120 - 144 | 115 - 120 (f) | 2 - 115 (g) | 0 | 189.91 | PVC, stainless steel |
| RB-11I | 8/19/93 | 4 | 358.5 | 348.5 - 358.5 | 339 - 359 | 333 - 339 (f) | 2 - 333 (g) | 0 | 190.32 | PVC, stainless steel |
| RB-11D | 8/9/93 | 4 | 503 | 493 - 503 | 487 - 509 | 480 - 487 (f) | 2 - 480 (g) | 0 | 190.60 | PVC, stainless steel |
| RW-12I | 10/7/93 | 4 | 360 | 350 - 360 | 338 - 364 | 330 - 338 (f) | 2 - 330 (g) | 0 | 197.76 | PVC, stainless steel |
| RW-12D | 9/27/93 | 4 | 500 | 490 - 500 | 482 - 508 | 475 - 482 (f) | 2 - 482 (g) | 0 | 197.72 | PVC, stainless steel |

- (a) The measuring point of each well is the top of the well casing.
(b) Survey performed to U.S. Geological Survey (USGS) datum.
(c) Well installed during the ERM-Northeast site investigation.
(d) It appears that this interval consists of formation collapse.
(e) Information not available as to whether grout or backfill (drill cuttings) was used to fill the annular space in this interval.
(f) #00 Sand used above J. Morie, Co. No. 1 Sand.
(g) Volclay grout sealant used (composed of 100 percent bentonite).
(h) Destroyed.
(i) Well PK-10S was installed in the initial PK-10I borehole, which had collapsed at 328 feet due to unstable formation; PK-10S was constructed with the gravel pack extending to within 5 feet of land surface to allow for the gravel pack to stabilize before a permanent seal was installed. PK-10S is currently sealed at the land surface with a steel plate and rubber gasket. Gravel can be monitored/added through a 1-inch diameter access port.
- PVC Polyvinyl chloride.

Information for monitoring wells installed during the second operable unit remedial investigation is indicated in bold letters.

Table 2-3. Summary of Survey Data, Syosset Landfill, Syosset, New York.

| Well | Measuring Point Elevation (feet mean sea level) | New York State Plane Coordinate North | New York State Plane Coordinate East |
|--------|---|---|--|
| SY-1 | 194.52 | 208495.76 | 2136314.26 |
| SY-1D | 197.36 | 208481.59 | 2136330.22 |
| SY-2R | 187.12 | 210037.91 | 2135556.27 |
| SY-2D | 186.33 | 210026.07 | 2135587.51 |
| SY-3 | 191.38 | 210242.45 | 2135067.38 |
| SY-3D | 194.74 | 210247.23 | 2135050.56 |
| SY-3DD | 194.23 | 210271.1702 | 2135002.6670 |
| SY-4 | 193.32 | 209431.71 | 2134825.53 |
| SY-5 | 188.07 | 209352.90 | 2135546.93 |
| SY-6 | 185.92 | 208841.74 | 2135686.91 |
| SY-6D | 185.60 | 208859.37 | 2135654.79 |
| SY-7 | 197.46 | 208673.74 | 2136465.21 |
| SY-8 | 195.84 | 210046.93 | 2134479.52 |
| SY-9 | 199.41 | 209095.12 | 2136455.36 |
| W-3 | 190.61 | 210002.45 | 2135019.45 |
| W-4 | 192.82 | 209339.17 | 2135850.95 |
| PK-10S | 188.70 | 210812.2387 | 2135658.6336 |
| PK-10I | 187.62 | 210720.9698 | 2135615.3518 |
| PK-10D | 188.23 | 210803.3541 | 2135650.1901 |
| RB-11S | 189.91 | 210943.6133 | 2136483.3404 |
| RB-11I | 190.32 | 210938.5300 | 2136465.6332 |
| RB-11D | 190.60 | 210935.7024 | 2136455.7611 |
| RW-12I | 197.76 | 210856.6549 | 2134537.6926 |
| RW-12D | 197.72 | 210880.6908 | 2134539.2033 |

Survey performed by Lockwood, Kessler & Bartlett, Inc. (LKB), Syosset, New York.

Information in bold is for measurements made by LKB in October 1993.



Table 2-4. Summary of Water-Level Elevation Data Collected on October 29, 1993 from Nassau County Monitoring Wells Within Approximately 2 Miles of the Syosset Landfill During the Second Operable Unit Remedial Investigation, Syosset, New York.

| Well Number | NYSDEC Well Number | Total Depth (feet below land surface) | Total Depth (feet below water level) | Elevation of Measuring Point (a) (feet above mean sea level) | Depth to Water (feet below measuring point) | Water-Level Elevation (feet above mean sea level) |
|-------------|--------------------|---------------------------------------|--------------------------------------|--|---|---|
| O-6A | N9353 | 101.05 | 36.78 | 140.42 | 64.27 | 76.15 |
| O-7A | N9050 | 175.50 | -- | 228.24 | (b) | (b) |
| O-8 | N1194 | 104.10 | 16.65 | 167.98 | 87.45 | 80.53 |
| O-9 | N1195 | 116.35 | 44.69 | 148.30 | 71.66 | 76.64 |
| OP-1 | N9926 | 129.90 | 43.33 | 168.18 | 86.57 | 81.61 |
| OP-2 | N9928 | 40.90 | 16.02 | 145.21 | 24.88 (c) | 120.33 |
| OP-3 | N9927 | 94.20 | 8.82 | 161.68 | 85.38 | 76.30 |
| P-7A | N10605 | 148.00 | 40.56 | 187.86 | 107.44 | 80.42 |
| P-8A | N8888 | 111.20 | 16.20 | 174.49 | 95.00 | 79.49 |
| P-9B | N9920 | 89.20 | 17.48 | 145.95 | 71.72 | 74.23 |
| PT-1A | N10604 | 139.50 | 31.93 | 190.18 | 107.57 | 82.61 |
| PT-2 | N9933 | 114.65 | 15.11 | 178.97 | 98.94 | 80.03 |
| PT-3 | N9981 | 108.40 | 19.79 | 165.66 | 88.61 | 77.05 |
| PT-4 | N9932 | 104.80 | 31.38 | 145.54 | 73.42 | 72.12 |
| T-5 | N1228 | 175.90 | 11.08 | 227.12 | 164.82 | 62.30 |
| T-6A | N10608 | 203.00 | 38.04 | 238.68 | 164.96 | 73.72 |
| | N1231 | 81.40 | 16.40 | 138.95 | 65.00 | 73.95 |
| TU-1 | N9934 | 126.50 | 30.20 | 173.93 | 96.30 | 77.63 |

(a) All wells are constructed at grade with a curb box assembly.

(b) Not recorded.

(c) Water level is anomalously high and was not used to contour the potentiometric surface map (Figure 3-3); well screen is likely plugged.



Table 2-5. Summary of Water-Level Elevation Data Collected from Site Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| -----October 28, 1993----- | | | |
|----------------------------|--|--|---|
| Well Number | Elevation of Measuring Point (feet above mean sea level) | Depth to Water (feet below measuring point) | Water-Level Elevation (feet above mean sea level) |
| <u>Shallow</u> | | | |
| SY-1 | 194.52 | 113.36 | 81.86 |
| SY-2R | 187.12 | 106.17 | 80.95 |
| SY-3 | 191.38 | 110.03 | 81.35 |
| SY-4 | 193.32 | 111.45 | 81.87 |
| SY-5 | 188.47 | (a) | |
| SY-6 | 185.92 | 104.32 | 81.60 |
| SY-7 | 197.46 | 115.71 | 81.75 |
| SY-8 | 195.84 | 114.05 | 81.79 |
| SY-9 | 199.41 | 116.77 | 82.64 |
| W-3 | 190.61 | 108.97 | 81.64 |
| W-4 | (a) | (a) | (a) |
| PK-10S | 188.70 | 108.41 | 80.29 |
| RB-11S | 189.91 | 109.12 | 80.79 |
| <u>Intermediate</u> | | | |
| SY-1D | 197.36 | 115.97 | 81.39 |
| SY-2D | 186.33 | 105.61 | 80.72 |
| SY-3D | 194.74 | 114.05 | 80.69 |
| SY-6D | 185.60 | 104.05 | 81.55 |
| PK-10I | 187.62 | 107.80 | 79.82 |
| RB-11I | 190.32 | 110.38 | 79.94 |
| RW-12I | 197.76 | 117.84 | 79.92 |
| <u>Deep</u> | | | |
| SY-3DD | 194.23 | 113.99 | 80.24 |
| PK-10D | 188.23 | 108.41 | 79.82 |
| RB-11D | 190.60 | 111.97 | 78.63 |
| RW-12D | 197.72 | 117.98 | 79.74 |

(a) Destroyed.



Table 2-5. Summary of Water-Level Elevation Data Collected from Site Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| -----November 24, 1993----- | | | |
|-----------------------------|--|--|---|
| Well Number | Elevation of Measuring Point (feet above mean sea level) | Depth to Water (feet below measuring point) | Water-Level Elevation (feet above mean sea level) |
| <u>Shallow</u> | | | |
| SY-1 | 194.52 | 113.49 | 81.03 |
| SY-2R | 187.12 | 106.23 | 80.89 |
| SY-3 | 191.38 | 110.13 | 81.25 |
| SY-4 | 193.32 | 111.61 | 81.71 |
| SY-5 | 188.47 | (a) | (a) |
| SY-6 | 185.92 | 104.49 | 81.43 |
| SY-7 | 197.46 | 115.63 | 81.83 |
| SY-8 | 195.84 | 114.17 | 81.67 |
| SY-9 | 199.41 | 117.00 | 82.41 |
| W-3 | 190.61 | 108.89 | 81.72 |
| W-4 | (a) | (a) | (a) |
| PK-10S | 188.70 | 108.49 | 80.21 |
| RB-11S | 189.91 | 109.38 | 80.53 |
| <u>Intermediate</u> | | | |
| SY-1D | 197.36 | 116.08 | 81.28 |
| SY-2D | 186.33 | 105.64 | 80.69 |
| SY-3D | 194.74 | 114.12 | 80.62 |
| SY-6D | 185.60 | 104.48 | 81.12 |
| PK-10I | 187.62 | 107.87 | 79.75 |
| RB-11I | 190.32 | 110.45 | 79.87 |
| RW-12I | 197.76 | 117.87 | 79.89 |
| <u>Deep</u> | | | |
| SY-3DD | 194.23 | 113.97 | 80.26 |
| PK-10D | 188.23 | 108.38 | 79.85 |
| RB-11D | 190.60 | 110.95 | 79.65 |
| RW-12D | 197.72 | 118.02 | 79.70 |

(a) Destroyed.



Table 2-6. Parameter List for the Second Operable Unit Remedial Investigation Groundwater Sampling Program, Syosset Landfill, Syosset, New York.

| <u>Volatile Organic Compounds</u> | <u>Metals</u> |
|-----------------------------------|--------------------------------------|
| Dichlorodifluoromethane (a) | Antimony |
| Chloromethane | Arsenic |
| Vinyl chloride | Barium |
| Bromomethane | Beryllium |
| Chloroethane | Cadmium |
| Trichlorofluoromethane (a) | Chromium |
| 1, 1-Dichloroethene | Copper |
| Acetone (b) | Iron |
| Carbon Disulfide (b) | Lead |
| Methylene chloride | Mercury |
| trans-1, 2-Dichloroethene | Nickel |
| 1,1-Dichloroethane | Potassium |
| 2-Butanone (b) | Selenium |
| cis-1, 2-Dichloroethene (b) | Silver |
| Chloroform (b) | Sodium |
| 1, 1, 1-Trichloroethane | Thallium |
| Carbon tetrachloride | Zinc |
| Benzene | |
| 1, 2-Dichloroethane | |
| Trichloroethene | |
| 1, 2-Dichloropropane | |
| Bromodichloromethane | |
| 2-Chloroethyl vinyl ether | |
| cis-1, 3-Dichloropropene | |
| 4-Methyl-2-Pentanone (b) | |
| Toluene | |
| trans-1, 3-Dichloropropene | |
| 1, 1, 2-Trichloroethane | |
| Tetrachloroethene | |
| 2-Hexanone (b) | |
| Dibromochloromethane | |
| Chlorobenzene | |
| Ethylbenzene | |
| m&p -Xylene (b) | |
| o-Xylene (b) | |
| Styrene(b) | |
| Bromoform | |
| 1, 1, 2, 2-Tetrachloroethane | |
| | <u>Leachate Indicator Parameters</u> |
| | Specific conductance (field) |
| | pH (field) |
| | Chloride |
| | Nitrate |
| | Ammonia |
| | Hardness |
| | Bicarbonate |
| | Carbonate |
| | Sulfate |
| | Total dissolved solids |

(a) This compound was deleted from the priority pollutant list.

(b) This compound was not included on the revised parameter list but was also analyzed. In May and June 1993, samples were collected by Geraghty & Miller, Inc. from Well Pk-10I for analysis of volatile organic compounds (VOCs). The laboratory analyzed these samples for the VOCs on the original parameter list included in the OU-2 RI Work Plan. However, because the laboratory (IEA Laboratories, Inc.) calibrates its analytical instruments for VOCs using commercial standards that contain a comprehensive list of VOCs that include more compounds than are contained in the parameter list, some of these additional VOCs were detected in this sample. This is the reason why these additional compounds were reported and included in this Table.



Table 2-7. Summary of Construction Details for Gas Monitoring Wells, Syosset Landfill, Syosset, New York.

| Well No. | Date Installed | Diameter of Well (inches) | Total Depth of Boring (feet below land surface) | Depth to Landfill Material (feet below land surface) | Screen Interval (feet below land surface) | Sand Packed Interval (feet below land surface) | Grouted Interval (feet below land surface) | Casing Stick Up (feet above land surface) |
|-----------------------|----------------|---------------------------|---|--|---|--|--|---|
| <u>On-Site Wells</u> | | | | | | | | |
| G-8 | 4/23/87 | 1 | 5.1 | — | 2.0 - 5.0 | 1.2 - 5.1 | 0 - 1.2 | 1.15 |
| G-10 | 4/23/87 | 1 | 4.5 | 3 | 1.4 - 4.4 | 1.0 - 4.5 | 0 - 1.0 | 1.75 |
| G-11 | 4/23/87 | 1 | 4.0 | — | 1.4 - 4.0 | 1.0 - 4.0 | 0 - 1.0 | 1.55 |
| G-13 | 4/24/87 | 1 | 4.6 | — | 1.6 - 4.6 | 1.2 - 4.6 | 0 - 1.2 | 1.60 |
| G-14 | 4/27/87 | 1 | 4.7 | — | 1.7 - 4.7 | 1.2 - 4.7 | 0 - 1.2 | 1.50 |
| <u>Off-Site Wells</u> | | | | | | | | |
| CS-20 | 9/28/93 | 1 | 4.7 | — | 2.1 - 4.7 | 1.6 - 4.7 | 1.0 - 1.6 | none |
| CS-21 | 9/28/93 | 1 | 5.0 | — | 2.6 - 5.0 | 2.6 - 5.0 | 1.6 - 2.1 | none |
| CS-22 | 9/29/93 | 1 | 4.25 | — | 1.5 - 4.25 | 1.1 - 4.25 | 0.6 - 1.1 | none |

— Landfill material not encountered.

Table 3-1a. Summary of Horizontal Hydraulic Gradient Data for Shallow, Intermediate, and Deep Hydrogeologic Zones, Based on Potentiometric Surface Maps (Figures 3-4 to 3-9), Second Operable Unit Remedial Investigation of the Syosset Landfill, Syosset, New York.

| Zone | Length of Groundwater Flow Line (L), in Inches, between Groundwater Elevation Contours ^(a) | Actual Distance (L), in Feet, between Groundwater Elevation Contours ^(a) | Change in Hydraulic Head (h) between Groundwater Elevation Contours, in Feet | Horizontal Hydraulic Gradient $I_H = \frac{h}{L}$ (Dimensionless) | Average I_H |
|------------------------------------|---|---|--|---|----------------|
| <u>Shallow</u> | | | | | |
| Figure 3-4 (October 28, 1993) | 4.8 | 1,440 | 1.0 | 0.00069 | 0.00065 |
| | 5.6 | 1,680 | 1.0 | 0.00060 | |
| | 5.0 | 1,500 | 1.0 | 0.00067 | |
| Figure 3-5 (November 24, 1993) | 4.8 | 1,440 | 1.0 | 0.00069 | <u>0.00064</u> |
| | 6.1 | 1,830 | 1.0 | 0.00055 | |
| | 4.8 | 1,440 | 1.0 | 0.00069 | |
| Overall Average I_H Shallow | | | | | 0.00065 |
| <u>Intermediate</u> | | | | | |
| Figure 3-6 (October 28, 1993) | 1.2 | 360 | 0.5 | 0.00139 | 0.00114 |
| | 5.7 | 1,710 | 1.5 | 0.00088 | |
| | 4.4 | 1,320 | 1.5 | 0.00114 | |
| Figure 3-7 (November 24, 1993) | 1.2 | 360 | 0.5 | 0.00139 | <u>0.00108</u> |
| | 6.7 | 2,010 | 1.5 | 0.00075 | |
| | 4.6 | 1,380 | 1.5 | 0.00109 | |
| Overall Average I_H Intermediate | | | | | 0.00111 |

Table 3-1a. Summary of Horizontal Hydraulic Gradient Data for Shallow, Intermediate, and Deep Hydrogeologic Zones, Based on Potentiometric Surface Maps (Figures 3-4 to 3-9), Second Operable Unit Remedial Investigation of the Syosset Landfill, Syosset, New York.

| Zone | Length of Groundwater Flow Line (L), in Inches, between Groundwater Elevation Contours ^(a) | Actual Distance (L), in Feet, between Groundwater Elevation Contours ^(a) | Change in Hydraulic Head (Δh) between Groundwater Elevation Contours, in Feet | Horizontal Hydraulic Gradient $I_H = \frac{\Delta h}{L}$ (Dimensionless) | Average I_H |
|--------------------------------------|---|---|---|--|---------------|
| <u>Deep</u> | | | | | |
| Figure 3-8 (October 28, 1993) | 2.2 | 660 | 0.44 | 0.00067 | |
| Figure 3-9 (November 24, 1993) | 2.2 | 660 | 0.56 | 0.00085 | |
| Overall Average $I_{H \text{ Deep}}$ | | | | | 0.00076 |

(a) The length of the groundwater flow lines in Figures 3-4 to 3-9 was determined by measuring the length of individual flow arrows between two groundwater elevation contours in inches with a ruler. The actual length (in feet) was calculated by multiplying the measured length in inches by the map scale (1 inch = 300 feet). Flow line lengths were measured in the order from west to east with the values shown on this table corresponding to this order from top to bottom.

Table 3-1b. Summary of Vertical Hydraulic Gradient Data, Second Operable Unit Remedial Investigation of the Syosset Landfill, Syosset, New York.

| Well No. | Elevation of Top of Screen (feet, mean sea level) | Difference (Distance) Between the Top of Well Screen for Cluster Wells (feet) | October 28, 1993 | | | November 24, 1993 | | |
|----------|---|--|---|--|---|---|--|---|
| | | | Water-Level Elevation (feet, mean sea level) | Difference in Water-Level Elevation Between Cluster Wells (feet) | Vertical Hydraulic Gradient (feet/feet) | Water-Level Elevation (feet, mean sea level) | Difference in Water-Level Elevation Between Cluster Wells (feet) | Vertical Hydraulic Gradient (feet/feet) |
| SY-1 | 69.67 | 56.82 | 81.86 | -0.47 | -0.0083 | 81.03 | +0.25 | +0.0044 |
| SY-1D | 13.05 | | 81.39 | | | 81.28 | | |
| SY-2R | 70.53 | 76.14 | 80.95 | -0.23 | -0.0030 | 80.89 | -0.20 | -0.0026 |
| SY-2D | -5.61 | | 80.72 | | | 80.69 | | |
| SY-3 | 56.88 | 53.64 | 81.35 | -0.66 | -0.0123 | 81.25 | -0.63 | -0.0117 |
| SY-3D | 3.24 | 339.01 | 80.69 | -0.45 | -0.0013 | 80.62 | -0.36 | -0.0010 |
| SY-3DD | -335.77 | | 80.24 | | | 80.26 | | |
| SY-6 | 51.02 | 60.12 | 81.60 | -0.05 | -0.00083 | 81.43 | -0.31 | -0.0052 |
| SY-6D | -9.10 | | 81.55 | | | 81.12 | | |
| PK-10S | 50.10 | 212.94 | 80.29 | -0.47 | -0.0022 | 80.21 | -0.46 | -0.0022 |
| PK-10I | -162.34 | 138.43 | 79.82 | 0 | 0 | 79.75 | +0.10 | +0.0007 |
| PK-10D | -300.77 | | 79.82 | | | 79.85 | | |
| RB-11S | 56.96 | 209.14 | 80.79 | -0.85 | -0.0041 | 80.53 | -0.66 | -0.0032 |
| RB-11I | -152.18 | 150.22 | 79.94 | -1.31 | -0.0087 | 79.87 | -0.22 | -0.0015 |
| RB-11D | -302.40 | | 78.63 | | | 79.65 | | |
| RW-12I | -152.24 | 140.04 | 79.92 | -0.18 | -0.0013 | 79.89 | -0.19 | -0.0014 |
| RW-12D | -292.28 | | 79.74 | | | 79.70 | | |

+ Indicates an upward vertical hydraulic gradient.
 -- Indicates a downward vertical hydraulic gradient.

Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-1 11/3/93 | SY-1 11/30/93 | SY-1D 11/4/93 | SY-1D 12/1/93 | SY-2R 11/2/93 | SY-2R 12/3/93 |
|---------------------------------------|-----------------|------------------|------------------|------------------|------------------|------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <1 | 1.4 J | <1 | <1 |
| Chloromethane | <1 | <1 | <1 | <1 | 0.5 J | <1 |
| Vinyl chloride | <1 | <1 | 1.6 | 1.4 J | <1 | <1 |
| Bromomethane | <1 | <1 | <1 J | <1 | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | 0.1 J | <1 | <1 | <1 |
| Acetone | <38 J | <25 J | <25 J | <26 J | <14 J | <27 J |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 | <1 J |
| Methylene chloride | <2 | <2 | <2 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | 2.9 | 2.4 | <1 | <1 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | 6.4 | 4.2 | <1 | <1 |
| Chloroform | <1 | <1 | 9.1 | 5.9 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | 0.2 J | 0.2 J |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | 0.6 J | 0.6 J | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <1 | 1.7 | <1 | <1 |
| Trichloroethene | <1 | <1 | 1.3 | 1.1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | <1 | <1 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | 2.4 | 1.7 | 0.4 J | 0.4 J |
| 2-Hexanone | <5 | R | <5 | R | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | 4.8 | 3.7 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 0 | 0 | 29.2 | 24 | 1.1 | 0.6 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.

Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-2D 11/2/93 | SY-2D 12/3/93 | SY-3 11/2/93 | SY-3 12/3/93 | SY-3D 11/2/93 | SY-3D 12/3/93 |
|---------------------------------------|------------------|------------------|-----------------|-----------------|------------------|------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | 0.2 J | <1 | <1 | <1 | <1 |
| Chloromethane | <1 | <1 | 0.4 J | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | 2.4 J | 2.2 | 0.6 J | 0.6 J |
| Bromomethane | <1 | <1 | <1 J | <1 | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | 0.6 J | 0.7 J | <1 | 0.3 J | <1 | <1 |
| Acetone | <29 J | <43 J | <18 J | <26 J | <17 J | <21 |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 | <1 |
| Methylene chloride | <2 | <2 | <2.4 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | 2.1 | 3.6 | 2.3 | 2.5 | 1.5 | 1.6 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | 0.2 J | 0.2 J | 1.6 | 1.2 | 0.7 J | 0.6 J |
| Chloroform | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-Trichloroethane | 0.7 J | 1.4 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | 0.6 J | 0.6 J | 1.8 | 1.8 |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | 0.4 J | 0.7 J | 1.5 | 1.6 | 0.9 J | 0.9 J |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 | <5 |
| Toluene | 0.2 J | <1 | 0.5 J | 0.1 J | 0.4 J | 0.2 J |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | 0.6 J | 0.5 J | <1 | <1 | <1 | <1 |
| 2-Hexanone | <5 | R | R | R | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | 0.4 J | 0.6 J | 2.3 | 2.2 | 5.5 | 5.4 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | 0.08 J | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 5.08 | 7.9 | 11.6 | 10.7 | 11.4 | 11.1 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.

Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-3DD 11/1/93 | SY-3DD 11/29/93 | SY-4 11/2/93 | SY-4 12/3/93 | SY-6 11/5/93 | SY-6 12/2/93 |
|---------------------------------------|-------------------|--------------------|-----------------|-----------------|-----------------|-----------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <1 | <1 | <1 J | <1 |
| Chloromethane | <1 J | <1 | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | 0.7 J | 0.7 J | <1 | <1 |
| Bromomethane | <1 J | <1 | <1 | <1 | <1 | <1 J |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 J |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| Acetone | <29 J | <52 J | <14 J | <24 J | <37 J | <27 J |
| Carbon disulfide | <1 | <1 J | <1 | <1 J | <1 | <1 J |
| Methylene chloride | <2 | <2 | <2 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | 1.4 | 1.8 | <1 | <1 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | 0.6 J | 0.4 J | <1 | <1 |
| Chloroform | <1 | <1 | <2.7 | <1.1 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | 0.1 J | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | 0.7 J | 0.8 J | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | <1 | <1 | 0.1 J | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | <1 | 0.2 J | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | <1 | 0.2 J | <1 |
| 2-Hexanone | R | R | <5 | R | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | 8.0 | 9.1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 J | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 0 | 0 | 11.5 | 13 | 0.3 | 0 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-6D 11/1/93 | SY-6D 11/29/93 | SY-7 11/4/93 | SY-7 12/2/93 | SY-8 11/4/93 | SY-8 12/1/93 |
|---------------------------------------|------------------|-------------------|-----------------|-----------------|-----------------|-----------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | <1 J | <20 J | <20 | <1 J | <1 |
| Chloromethane | <1 J | <1 | <20 | <20 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <20 | <20 | <1 | <1 |
| Bromomethane | <1 J | <1 | <20 | <20 | <1 J | <1 |
| Chloroethane | <1 | <1 | <20 | <20 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <20 | <20 | <1 | <1 |
| Acetone | <27 J | <39 J | <430 J | <100 | <10 J | <18 J |
| Carbon disulfide | <1 | <1 J | <20 | <20 J | <1 | <1 |
| Methylene chloride | <2.5 | <2 | <40 | <40 | <2.2 | <1 |
| trans-1,2-Dichloroethene | <1 | <1 | <20 | <20 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <20 | <20 | 1.3 | 1.2 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | <20 | <20 | 1.1 | 0.4 J |
| Chloroform | 8.8 | <4.0 | <20 | <25 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | <1 | <20 | <20 | 0.8 J | <1 |
| Carbon tetrachloride | <1 | <1 | <20 | <20 | <1 | <1 |
| Benzene | <1 | <1 | 410 | 540 | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <20 | <20 | <1 | <1 |
| Trichloroethene | <1 | <1 | <20 | <20 | 2.8 | 1.5 |
| 1,2-Dichloropropane | <1 | <1 | <20 | <20 | <1 | <1 |
| Bromodichloromethane | 0.7 J | <1 | <20 | <20 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <20 | <20 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <20 | <20 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <100 | <100 | <5 | <5 |
| Toluene | <1 | <1 | 5.2 J | <20 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <20 | <20 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <20 | <20 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | 2.4 J | 3 J | 17 | 10 |
| 2-Hexanone | R | R | 89 J | R | <5 | R |
| Dibromochloromethane | <1 | <1 | <20 | <20 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <20 | <20 | 0.1 J | <1 |
| Ethylbenzene | <1 | <1 | <20 | <20 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <20 | <20 | <1 | <1 |
| ortho-Xylene | <1 | <1 | 5.1 J | 4.9 J | <1 | <1 |
| Styrene | <1 | <1 | <20 | <20 | <1 | <1 |
| Bromoform | <1 | <1 | <20 J | <20 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <20 | <20 | 0.1 J | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <20 | <20 | <1 | <1 |
| Total VOCs: | 9.2 | 0 | 511.7 | 547.9 | 23.2 | 13.1 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-9 11/1/93 | SY-9 11/29/93 | PK-10S 11/4/93 | PK-10S 12/1/93 | PK-10I 11/4/93 | PK-10I (Rep-2) 11/4/93 |
|---------------------------------------|-----------------|------------------|-------------------|-------------------|-------------------|------------------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | <1 J | <1 J | 0.2 J | <1 J | <1 J |
| Chloromethane | <1 J | <1 | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 | 0.7 J | 0.8 J |
| Bromomethane | <1 J | <1 | <1 J | <1 | <1 J | <1 J |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | 0.8 J | 0.9 J | 0.5 J | <1 |
| Acetone | <94 J | <85 J | <14 J | <18 J | <29 J | <26 J |
| Carbon disulfide | <1 | <1 J | <1 | <1 | <1 | <1 |
| Methylene chloride | <2 | <2 | <2 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | 0.1 J | 5.4 | 6.7 | 6.6 | 6.3 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | 0.2 J | <1 | <1 | 2.7 | 2.5 |
| Chloroform | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | <1 | 2.5 | 3.3 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | 0.1 J | <1 | <1 | 0.5 J | 0.5 J |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | <1 | <1 | 0.5 J | 0.7 J | 1.2 | 1.2 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | 0.3 J | 0.8 J | 0.3 J | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | 1.3 | 1.3 | 3.3 | 3.3 |
| 2-Hexanone | R | R | <5 | R | <5 | <5 |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | 1.5 | 1.3 | <1 | <1 | 20 | 17 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 1.5 | 1.7 | 10.8 | 13.9 | 35.8 | 31.6 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | PK-10I 12/1/93 | (Rep-2) 12/1/93 | PK-10D 11/4/93 | PK-10D 12/1/93 | RB-11S 11/3/93 | RB-11S 11/30/93 |
|---------------------------------------|-------------------|--------------------|-------------------|-------------------|-------------------|--------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | 0.2 J | <1 J | <1 | <1 | <1 J |
| Chloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Vinyl chloride | 0.6 J | 0.7 J | <1 | <1 | <1 | <1 |
| Bromomethane | <1 | <1 | <1 J | <1 | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | 0.2 J | <1 | <1 | <1 | <1 |
| Acetone | <23 J | <30 J | <16 J | <25 J | <35 J | <56 J |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 | <1 J |
| Methylene chloride | <2 | <2 | <2 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | 5.4 | 5.6 | 0.4 J | 0.5 J | <1 | <1 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | 1.3 | 1.4 | 0.4 J | 0.3 J | <1 | <1 |
| Chloroform | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | 0.4 J | <1 | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | 0.9 J | 0.9 J | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <1 | <5 | <5 | <5 | <5 |
| Toluene | 0.8 J | 1.0 | 0.7 J | 5.7 | <1 | 0.8 J |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | 1.4 | 1.5 | <1 | <1 | <1 | <1 |
| 2-Hexanone | R | R | <5 | R | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | 5.2 | 5.3 | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 | 0.1 J |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 15.6 | 16.8 | 1.9 | 6.5 | 0 | 0.9 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | RB-111 11/3/93 | RB-111 (Rep-1) 11/3/93 | RB-111 11/30/93 | RB-111 (Rep-1) 11/30/93 | RB-11D 11/3/93 | RB-11D 11/30/93 |
|---------------------------------------|-------------------|------------------------------|--------------------|-------------------------------|-------------------|--------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | 1.6 J | 1.6 J | 2.6 J | 2.7 J | <1 | <1 J |
| Chloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromomethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | 1.2 | 1.3 | 1.6 | 1.5 | <1 | <1 |
| Acetone | <19 J | <14 J | <64 J | <46 J | R | <38 J |
| Carbon disulfide | <1 | <1 | <1 J | <1 J | <1 | <1 J |
| Methylene chloride | <2 | <2 | <2 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | 10 | 10 | 13 | 13 | <1 | <1 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | 2.8 | 2.9 | 2.1 | 2.2 | <1 | <1 |
| Chloroform | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-Trichloroethane | 3.4 | 3.4 | 4.8 | 4.9 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | 3.0 | 3.0 | 3.9 | 4.0 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 | <5 |
| Toluene | 0.6 J | 0.6 J | 0.3 J | 0.3 J | 1.2 | 0.4 J |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | 19 | 19 | 23 | 23 | <1 | <1 |
| 2-Hexanone | <5 | <5 | R | R | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | 0.1 J | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | 0.9 J | 0.9 J | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 41.6 | 41.8 | 52.2 | 52.5 | 1.3 | 0.4 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | RW-12I 11/5/93 | RW-12I (Rep-3) 11/5/93 | RW-12I 12/2/93 | RW-12I (Rep-3) 12/2/93 | RW-12D 11/5/93 | RW-12D 12/2/93 |
|---------------------------------------|-------------------|------------------------------|-------------------|------------------------------|-------------------|-------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <2 | <2 | <5 | <5 | <1 | <1 |
| Chloromethane | <2 | <2 | <5 | <5 | <1 | <1 |
| Vinyl chloride | <2 | <2 | 0.6 J | <5 | 9.2 | 17 |
| Bromomethane | <2 | <2 | <5 | <5 | <1 | <1 J |
| Chloroethane | <2 | <2 | <5 | <5 | <1 | <1 J |
| 1,1-Dichloroethene | 13 | 15 | 26 | 27 | <1 | <1 |
| Acetone | R | R | <130 J | <130 J | <29 J | <21 J |
| Carbon disulfide | <2 J | <2 J | <5 J | <5 J | <1 J | <1 J |
| Methylene chloride | <2 | <4 | <10 | <12 | <2 | <2 |
| trans-1,2-Dichloroethene | <2 | <2 | <5 | <5 | <1 | <1 |
| 1,1-Dichloroethane | 11 | 13 | 17 | 17 | <1 | 0.3 J |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | 5.2 | 5.7 | 5.7 | 5.9 | 2.6 | 2.3 |
| Chloroform | <2 | <2 | <5 | <5 | <1.3 | <1.4 |
| 1,1,1-Trichloroethane | 40 | 40 | 75 | 75 | <1 | <1 |
| Carbon tetrachloride | <2 | <2 | <5 | <5 | <1 | <1 |
| Benzene | <2 | <2 | 0.5 J | 0.5 J | 0.4 J | 0.9 J |
| 1,2-Dichloroethane | <2 | <2 | <5 | <5 | <1 | <1.8 |
| Trichloroethene | 6.2 | 6.3 | 9.8 | 9.9 | 0.9 J | 1.1 |
| 1,2-Dichloropropane | <2 | <2 | <5 | <5 | <1 | 1.0 |
| Bromodichloromethane | <2 | <2 | <5 | <5 | <1 | <1 |
| 2-Chloroethylvinylether | <2 J | <2 J | <5 | <5 | <1 J | <1 |
| cis-1,3-Dichloropropene | <2 | <2 | <5 | <5 | <1 | <1 |
| 4-Methyl-2-pentanone | <10 | <10 | <25 | <25 | <5 | <5 |
| Toluene | <2 | <2 | 13 | 12 | 0.7 J | 6.6 |
| trans-1,3-Dichloropropene | <2 | <2 | <5 | <5 | <1 | <1 |
| 1,1,2-Trichloroethane | <2 | <2 | <5 | <5 | <1 | <1 |
| Tetrachloroethene | 68 | 71 | 110 | 110 | 2.6 | 2.4 |
| 2-Hexanone | R | R | R | R | R | R |
| Dibromochloromethane | <2 | <2 | <5 | <5 | <1 | <1 |
| Chlorobenzene | 1.1 J | 1.3 J | 0.9 J | 0.9 J | <1 | 0.3 J |
| Ethylbenzene | <2 | <2 | <5 | <5 | <1 | <1 |
| meta and/or para-Xylene | <2 | <2 | <5 | <5 | <1 | <1 |
| ortho-Xylene | <2 | <2 | <5 | <5 | <1 | <1 |
| Styrene | <2 | <2 | <5 | <5 | <1 | <1 |
| Bromoform | <2 | <2 | <5 | <5 | <1 | <1 |
| Trichlorofluoromethane | <2 | <2 | 1.2 J | 1.2 J | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <2 | <2 | <5 | <5 | <1 | <1 |
| Total VOCs: | 144.5 | 152.3 | 259.7 | 259.4 | 16.4 | 31.9 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Trip Blank 11/1/93 | Trip Blank 11/2/93 | Trip Blank 11/3/93 | Trip Blank 11/4/93 | Trip Blank 11/5/93 | Trip Blank 11/29/93 |
|---------------------------------------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|------------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <1 | <1 J | <1 J | 0.4 J |
| Chloromethane | <1 J | <1 J | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromomethane | <1 J | <1 J | <1 | <1 J | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| Acetone | 28 JB | 34 JB | 14 JB | 14 J | 35 J | 33 J |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 | <1 J |
| Methylene chloride | 2.8 JB | 1 JB | 0.4 JB | 0.4 JB | 0.5 JB | 2.7 JB |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| Chloroform | 0.9 J | 1.1 | 0.8 J | 1.0 B | 0.8 JB | 0.8 JB |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 | <5 |
| Toluene | 0.2 J | <1 | <1 | <1 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Hexanone | R | R | <5 | <5 | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 J | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 | 0.4 J |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 31.9 | 36.1 | 15.2 | 15.4 | 36.3 | 37.3 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Trip Blank 11/30/93 | Trip Blank 12/1/93 | Trip Blank 12/2/93 | Trip Blank 12/3/93 |
|---------------------------------------|------------------------|-----------------------|-----------------------|-----------------------|
| Parameter (concentrations in ug/L) | | | | |
| Dichlorodifluoromethane | 0.4 J | <1 | <1 | <1 |
| Chloromethane | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 |
| Bromomethane | <1 | <1 | <1 J | <1 |
| Chloroethane | <1 | <1 | <1 J | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 |
| Acetone | 30 J | 14 JB | 24 J | 50 JB |
| Carbon disulfide | <1 J | <1 | <1 J | <1 |
| Methylene chloride | 0.5 JB | 0.8 JB | 0.7 JB | 0.7 JB |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <1 | <1 |
| 2-Butanone | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | <1 | <1 |
| Chloroform | 1.2 B | 1.0 B | 0.9 JB | 0.9 JB |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | 1.0 | <1 | 0.8 J | 1.5 |
| Trichloroethene | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | <1 |
| 2-Hexanone | R | R | R | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 |
| Total VOCs: | 33.1 | 15.8 | 26.4 | 53.1 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.

Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Field Blank 11/1/93 | Field Blank 11/2/93 | Field Blank 11/3/93 | Field Blank 11/4/93 | Field Blank 11/5/93 | Field Blank 11/29/93 |
|---------------------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|-------------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <1 | 1.0 J | <1 J | 0.4 J |
| Chloromethane | <1 J | <1 J | <1 | 0.4 J | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromomethane | <1 J | <1 J | <1 | <1 J | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| Acetone | 19 JB | 21 JB | 12 JB | 55 J | 29 J | 32 J |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 | <1 J |
| Methylene chloride | 4.3 JB | 0.8 JB | 0.5 JB | 0.3 JB | 0.5 JB | 2.7 BJ |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Butanone | R | R | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| Chloroform | 1.1 | 1.1 | 0.9 J | 1.2 B | 1.0 B | 0.7 JB |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | <1 | 0.4 J | <1 | 0.4 J | <1 | 0.8 J |
| Trichloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | 5.3 | <5 | <5 |
| Toluene | <1 | <1 | <1 | <1 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | <1 | <1 | <1 |
| 2-Hexanone | R | R | <5 | <5 | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 J | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 | 0.2 J |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | 0.6 J | <1 | <1 |
| Total VOCs: | 24.4 | 23.3 | 13.4 | 64.2 | 30.5 | 36.8 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.

Table 3-2. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Field Blank 11/30/93 | Field Blank 12/1/93 | Field Blank 12/2/93 | Field Blank 12/3/93 |
|---------------------------------------|-------------------------|------------------------|------------------------|------------------------|
| Parameter (concentrations in ug/L) | | | | |
| Dichlorodifluoromethane | 0.4 J | <1 | <1 | <1 |
| Chloromethane | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 |
| Bromomethane | <1 | <1 | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 |
| Acetone | 44 J | 31 JB | 34 JB | 34 JB |
| Carbon disulfide | <1 J | <1 | <1 | <1 |
| Methylene chloride | 2.8 JB | 2.1 JB | 2.4 JB | 2.1 B |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <1 | <1 |
| 2-Butanone | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | <1 | <1 |
| Chloroform | 0.7 JB | 0.8 JB | 0.9 JB | 0.8 JB |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | 1.2 | 0.8 J | 0.5 J | <1 |
| Trichloroethene | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | 0.2 J | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | <1 |
| 2-Hexanone | R | R | R | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 |
| Total VOCs: | 49.1 | 34.7 | 38 | 36.9 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Parameter (concentrations in ug/L) | MCL (a) | Sample ID: Sample Date: | SY-1 11/3/93 Total | SY-1 11/3/93 Dissolved | SY-1 11/30/93 Total | SY-1 11/30/93 Dissolved | SY-1D 11/4/93 Total | SY-1D 11/4/93 Dissolved | SY-1D 12/1/93 Total | SY-1D 12/1/93 Dissolved |
|---------------------------------------|---------|----------------------------|--------------------------|------------------------------|---------------------------|-------------------------------|---------------------------|-------------------------------|---------------------------|-------------------------------|
| | | | | | | | | | | |
| Antimony | 6 | | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | | 17.4 BJ | 18.5 | 23.9 J | 22.6 | <1.0 J | <1.0 | <1.0 J | <1.0 |
| Barium | 1,000 | | 78.6 B | 86.6 B | 88.4 BJ | 102 B | 57.0 B | 56.6 B | 62.2 BJ | 69.2 B |
| Beryllium | 4 | | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | | 18.6 J | <3.0 J | 18.7 | <3.0 | <3.0 | <3.0 J | <3.0 | <3.0 |
| Copper | 1,000 | | 29.0 | 8.9 B | 9.5 B | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 |
| Iron | 300 | | 80,000 | 20,400 | 79,900 | 23,000 | 152 | <87.0 | <87.0 | <87.0 |
| Lead | 50 | | 13.1 | <2.0 J | 9.5 J | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Mercury | 2 | | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | | 26.8 B | <11.0 | 11.2 B | 17.4 B | <11.0 | <11.0 | <11.0 | 12.1 B |
| Potassium | NS | | 5,090 | 4,490 B | 4,540 BJ | 4,750 B | 10,600 | 10,600 | 10,700 | 11,000 |
| Selenium | 10 | | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 J | <2.0 J | <2.0 J | <2.0 |
| Silver | 50 | | 2.8 B | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | | 20,100 | 20,800 | 23,000 | 23,600 | 180,000 | 179,000 | 192,000 J | 190,000 |
| Thallium | 2 | | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | | 39.3 | 21.2 | R | 23.5 | 11.9 B | 11.6 B | 14.8 B | 29.2 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | | SY-2R 11/2/93 Total | SY-2R 11/2/93 Dissolved | SY-2R 12/3/93 Total | SY-2R 12/3/93 Dissolved | SY-2D 11/2/93 Total | SY-2D 11/2/93 Dissolved | SY-2D 12/3/93 Total | SY-2D 12/3/93 Dissolved |
|---------------------------------------|---------|---------------------------|-------------------------------|---------------------------|-------------------------------|---------------------------|-------------------------------|---------------------------|-------------------------------|
| Parameter (concentrations in ug/L) | MCL (a) | | | | | | | | |
| Antimony | 6 | 36.4 B | <21.0 | 24.3 B | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | <1.0 J | <1.0 | <1.0 | <1.0 | <1.0 J | <1.0 | <1.0 | <1.0 |
| Barium | 1,000 | 64.2 B | 88.4 B | 50.3 B | 49.2 B | 57.0 B | 57.8 B | 48.7 B | 37.6 B |
| Beryllium | 4 | 7.8 | 2.5 B | 1.4 B | 1.2 B | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | <2.0 | 2.0 B | 2.8 BJ | <2.0 | <2.0 | 2.4 B |
| Chromium | 50 | 16.2 | <3.0 J | 3.7 BJ | <3.0 J | <3.0 | <3.0 J | 6.4 BJ | <3.0 J |
| Copper | 1,000 | 24.5 B | <7.0 | <7.0 | <7.0 | 12.6 B | <7.0 | <7.0 | <7.0 |
| Iron | 300 | 20,600 | 1,770 | 2,060 | 383 | 264 | <87.0 | R | <87.0 |
| Lead | 50 | 128 | <2.0 | 11.1 J | 1.7 B | <2.0 | <2.0 | 1.8 BJ | <1.0 |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | 91.1 | 21.8 B | 16.3 B | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 |
| Potassium | NS | 18,700 | 18,200 | 19,800 | 18,200 | 13,200 | 12,600 | 12,600 | 12,600 |
| Selenium | 10 | <2.0 J | <2.0 J | <2.0 | <2.0 | <2.0 J | <2.0 | <2.0 | <2.0 |
| Silver | 50 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | 239,000 | 232,000 | 227,000 | 204,000 | 70,500 | 66,600 | 65,000 | 62,500 |
| Thallium | 2 | <1.0 J | <1.0 | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | 115 | 48.6 | 29.9 J | 29.7 | 11.5 B | 10.3 B | 29.1 J | 24.7 |

ug/L

Micrograms per liter.

B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.

J Estimated value.

R Unusable value.

NS No standard.

(a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.

MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | | SY-3 11/2/93 Total | SY-3 11/2/93 Dissolved | SY-3 12/3/93 Total | SY-3 12/3/93 Dissolved | SY-3D 11/2/93 Total | SY-3D 11/2/93 Dissolved | SY-3D 12/3/93 Total | SY-3D 12/3/93 Dissolved |
|---------------------------------------|---------|--------------------------|------------------------------|--------------------------|------------------------------|---------------------------|-------------------------------|---------------------------|-------------------------------|
| Parameter (concentrations in ug/L) | MCL (a) | | | | | | | | |
| Antimony | 6 | 91.8 | <21.0 | 35.7 B | 36.7 B | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | 41.4 J | 15.0 | 75.1 | 47.4 | 94.7 J | 8.9 B | 102 | 2.5 B |
| Barium | 1,000 | 237 | 110 B | 213 | 186 B | 162 B | 101 B | 153 B | 112 B |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | 2.4 B |
| Chromium | 50 | 31.3 | <3.0 J | 5.5 BJ | <3.0 J | 7.3 BJ | <3.0 J | <3.0 J | <3.0 J |
| Copper | 1,000 | 80.1 | <7.0 | 15.4 B | <7.0 | 104 | 40.8 | 44.9 | 8.3 B |
| Iron | 300 | 295,000 | 2,550 | 70,100 | 7,900 | 34,700 | 1,810 | 23,300 | 728 |
| Lead | 50 | 62.8 | <2.0 J | 33.0 J | <1.0 | 10.7 | <2.0 | 8.8 J | <1.0 |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | 24.2 B | <11.0 | <11.0 | <11.0 | <11.0 | 17.8 B | 14.9 B | <11.0 |
| Potassium | NS | 70,500 | 68,000 | 73,600 | 66,600 | 131,000 | 132,000 | 142,000 | 132,000 |
| Selenium | 10 | <2.0 J | <2.0 | <2.0 | <2.0 | <2.0 J | <2.0 J | <2.0 | <2.0 |
| Silver | 50 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | 99,100 | 98,400 | 124,000 | 116,000 | 194,000 | 198,000 | 211,000 | 196,000 |
| Thallium | 2 | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | 181 | 16.5 B | 92.4 J | 33.0 | 76.5 | 23.3 | 66.0 J | 37.2 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | | SY-3DD 11/1/93 Total | SY-3DD 11/1/93 Dissolved | SY-3DD 11/29/93 Total | SY-3DD 11/29/93 Dissolved | SY-4 11/2/93 Total | SY-4 11/2/93 Dissolved | SY-4 12/3/93 Total | SY-4 12/3/93 Dissolved |
|---------------------------------------|---------|----------------------------|--------------------------------|-----------------------------|---------------------------------|--------------------------|------------------------------|--------------------------|------------------------------|
| Parameter (concentrations in ug/L) | MCL (a) | | | | | | | | |
| Antimony | 6 | 25.0 B | <21.0 | <21.0 | <21.0 | 23.1 B | 38.3 B | 21.0 B | <21.0 |
| Arsenic | 50 | <1.0 J | <1.0 | <1.0 J | <1.0 | 9.4 BJ | 5.2 B | 10.3 | 5.9 B |
| Barium | 1,000 | <2.0 | <2.0 | 2.5 B | 11.3 B | 129 B | 116 B | 128 B | 127 B |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | <3.0 | <3.0 J | 9.4 B | <3.0 | 7.8 B | <3.0 J | 5.3 BJ | <3.0 J |
| Copper | 1,000 | R | R | 20.1 B | <7.0 | 63.7 | <7.0 | 61.9 | <7.0 |
| Iron | 300 | 1,030 | <87.0 | 564 | <87.0 | 41,200 | 9,810 | 45,900 | 8,910 |
| Lead | 50 | 7.5 | <2.0 J | 2.7 B | <2.0 | 24.3 | <2.0 J | 65.4 J | <1.0 |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | 14.6 B | <11.0 | 34.2 B | 16.4 B | <11.0 | <11.0 | 16.0 B | <11.0 |
| Potassium | NS | 869 B | <473 | 823 B | 1,030 B | 27,800 | 26,500 | 27,600 | 27,700 |
| Selenium | 10 | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 J | <2.0 J | <2.0 | <2.0 |
| Silver | 50 | 2.3 B | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | 7,530 | 5,780 | 4,760 B | 4,730 B | 117,000 | 118,000 | 115,000 | 112,000 |
| Thallium | 2 | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | 160 | 72.9 | R | 52.4 | 99.9 | 13.1 B | 147 J | 37.5 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | | SY-6 11/5/93 Total | SY-6 11/5/93 Dissolved | SY-6 12/2/93 Total | SY-6 12/2/93 Dissolved | SY-6D 11/1/93 Total | SY-6D 11/1/93 Dissolved | SY-6D 11/29/93 Total | SY-6D 11/29/93 Dissolved |
|---------------------------------------|---------|--------------------------|------------------------------|--------------------------|------------------------------|---------------------------|-------------------------------|----------------------------|--------------------------------|
| Parameter (concentrations in ug/L) | MCL (a) | | | | | | | | |
| Antimony | 6 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | <1.0 | <1.0 | <1.0 | <1.0 | 1.2 BJ | <1.0 | <1.0 J | <1.0 |
| Barium | 1,000 | 59.6 B | 75.0 B | 91.6 B | 91.6 B | 41.8 B | 52.4 B | 37.7 BJ | 44.6 B |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | 2.3 B | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | <3.0 | <3.0 | <3.0 J | <3.0 J | 23.9 J | <3.0 J | <3.0 | <3.0 |
| Copper | 1,000 | 16.8 B | <7.0 | 38.5 | <7.0 | R | R | 7.6 B | <7.0 |
| Iron | 300 | R | 399 | 22,200 | 173 | 3,280 | 961 | 985 | 939 |
| Lead | 50 | 14.0 J | <2.0 J | 21.5 J | <1.0 | 7.5 | <2.0 | <2.0 J | <2.0 |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | <11.0 | <11.0 | <11.0 | <11.0 | 12.6 B | <11.0 | 14.3 B | <11.0 |
| Potassium | NS | 1,330 B | 1,640 B | 1,800 B | 1,660 B | 2,080 B | 676 B | 2,030 B | 2,210 B |
| Selenium | 10 | <2.0 J | <2.0 | <2.0 | <2.0 | <2.0 J | <2.0 J | <2.0 J | <2.0 |
| Silver | 50 | <2.0 | <2.0 | <2.0 | <2.0 | 3.9 B | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | 38,900 J | 49,100 J | 38,200 | 38,200 | 50,100 | 50,400 | 50,900 | 51,200 |
| Thallium | 2 | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 |
| Zinc | 5,000 | 347 J | 235 J | 611 J | 183 | 52.4 | 55.3 | R | 20.8 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | | SY-7 11/4/93 Total | SY-7 11/4/93 Dissolved | SY-7 12/2/93 Total | SY-7 12/2/93 Dissolved | SY-8 11/4/93 Total | SY-8 11/4/93 Dissolved | SY-8 12/1/93 Total | SY-8 12/1/93 Dissolved |
|---------------------------------------|---------|--------------------------|------------------------------|--------------------------|------------------------------|--------------------------|------------------------------|--------------------------|------------------------------|
| Parameter (concentrations in ug/L) | MCL (a) | | | | | | | | |
| Antimony | 6 | 27.8 B | 46.8 B | 34.4 B | 25.2 B | <21.0 | <21.0 | 25.5 B | <21.0 |
| Arsenic | 50 | 3.4 B | 1.2 B | 7.0 B | 1.7 B | <1.0 | <1.0 | <1.0 J | <1.0 |
| Barium | 1,000 | 171 B | 146 B | 179 B | 179 B | 68.6 B | 74.4 B | 65.9 BJ | 82.9 B |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | 1.5 B | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | 28.2 | <3.0 | 49.9 J | <3.0 J | <3.0 | <3.0 | <3.0 | 4.4 B |
| Copper | 1,000 | 86.1 | 9.5 B | 134 | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 |
| Iron | 300 | R | 77,800 | 181,000 | 71,200 | R | 2,540 | 2,450 | 2,480 |
| Lead | 50 | 37.9 J | <2.0 J | 21.9 J | <1.0 | 6.0 J | <2.0 J | <2.0 | <2.0 |
| Mercury | 2 | 0.77 | <0.20 | 0.31 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | 22.1 B | <11.0 | 69.6 | 14.1 B | <11.0 | <11.0 | 16.8 B | <11.0 |
| Potassium | NS | 1,650 B | 1,560 B | 2,280 B | 1,940 B | 4,740 B | 5,110 | 5,420 | 5,790 |
| Selenium | 10 | <2.0 J | <2.0 | <2.0 | <2.0 | <2.0 J | <2.0 J | <2.0 J | <2.0 |
| Silver | 50 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | 110,000 | 118,000 | 173,000 | 175,000 | 26,800 | 29,000 | 29,300 J | 29,100 |
| Thallium | 2 | <1.0 J | <1.0 J | <1.0 J | 1.8 BJ | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | 529 J | 174 J | 389 J | 139 | 1,840 J | 1,970 J | 1,900 | 1,940 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Parameter (concentrations in ug/L) | MCL (a) | Sample ID: Sample Date: | SY-9 11/1/93 Total | SY-9 11/1/93 Dissolved | SY-9 11/29/93 Total | SY-9 11/29/93 Dissolved | PK-10S 11/4/93 Total | PK-10S 11/4/93 Dissolved | PK-10S 12/1/93 Total | PK-10S 12/1/93 Dissolved |
|---------------------------------------|---------|----------------------------|--------------------------|------------------------------|---------------------------|-------------------------------|----------------------------|--------------------------------|----------------------------|--------------------------------|
| | | | | | | | | | | |
| Antimony | 6 | | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | | 39.3 J | 19.4 | 26.7 J | 19.1 | 1.9 B | 1.1 B | 3.5 BJ | <1.0 |
| Barium | 1,000 | | 144 B | 159 B | 155 BJ | 82.8 B | 38.5 B | 32.0 B | 36.3 BJ | 52.8 B |
| Beryllium | 4 | | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | | 23.3 J | <3.0 J | 24.7 | <3.0 | <3.0 | <3.0 | <3.0 | <3.0 |
| Copper | 1,000 | | R | R | 160 | <7.0 | 38.8 | <7.0 | 8.1 B | <7.0 |
| Iron | 300 | | 27,300 | 6,480 | 24,400 | 5,340 | R | 682 | 5,380 | 694 |
| Lead | 50 | | 58.8 | <2.0 | 41.8 | <2.0 | 10.1 J | <2.0 J | 6.2 | <2.0 J |
| Mercury | 2 | | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | | 22.2 B | <11.0 | 23.1 B | <11.0 | 25.0 B | 17.6 B | 17.5 B | 11.1 B |
| Potassium | NS | | 3,120 B | 2,000 B | 3,550 B | 2,130 B | 1,010 B | 986 B | 1,900 B | 1,500 B |
| Selenium | 10 | | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 J | <2.0 J | <2.0 J | <2.0 |
| Silver | 50 | | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | | 25,900 J | 30,400 J | 27,600 J | 32,500 J | 19,400 | 20,900 | 20,500 | 20,900 |
| Thallium | 2 | | <1.0 J | <1.0 J | <1.0 J | <1.0 | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | | 227 | 81.6 | 219 | 67.9 | 178 J | 155 J | 43.3 J | 53.8 J |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Parameter (concentrations in ug/L) | MCL (a) | Sample ID: Sample Date: | PK-10I 11/4/93 Total | PK-10I (Rep-2) 11/4/93 Total | PK-10I 11/4/93 Dissolved | PK-10I (Rep-2) 11/4/93 Dissolved | PK-10I 12/1/93 Total | PK-10I (Rep-2) 12/1/93 Total | PK-10I 12/1/93 Dissolved | PK-10I (Rep-2) 12/1/93 Dissolved |
|---------------------------------------|---------|----------------------------|----------------------------|------------------------------------|--------------------------------|--|----------------------------|------------------------------------|--------------------------------|--|
| | | | | | | | | | | |
| Antimony | 6 | | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | | <1.0 | <1.0 | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 | <1.0 |
| Barium | 1,000 | | 54.8 B | 60.8 B | 52.2 B | 54.8 B | 65.4 BJ | 65.4 BJ | 64.8 B | 67.9 B |
| Beryllium | 4 | | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | | <3.0 | <3.0 | <3.0 | <3.0 | 3.7 B | 4.6 B | <3.0 | <3.0 |
| Copper | 1,000 | | 9.9 B | 13.0 B | 13.7 B | 16.8 B | <7.0 | <7.0 | <7.0 | <7.0 |
| Iron | 300 | | R | R | <87.0 | <87.0 | 474 | 473 | <87.0 | 143 |
| Lead | 50 | | 3.8 J | 3.8 J | 2.6 BJ | 2.8 BJ | 3.2 | 3.3 | <2.0 | <2.0 |
| Mercury | 2 | | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | | <11.0 | <11.0 | <11.0 | 12.7 B | 16.4 B | 16.8 B | 15.0 B | <11.0 |
| Potassium | NS | | 46,100 | 50,600 | 47,300 | 50,800 | 53,400 | 53,500 | 50,400 | 52,400 |
| Selenium | 10 | | <2.0 J | <2.0 J | <2.0 J | <2.0 J | <2.0 J | <2.0 J | <2.0 | <2.0 |
| Silver | 50 | | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | | 176,000 | 193,000 | 179,000 | 189,000 | 235,000 J | 237,000 J | 220,000 | 229,000 |
| Thallium | 2 | | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | | 58.7 J | 75.8 J | 63.0 J | 65.7 J | 42.6 | 40.8 | 22.8 | 25.0 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: | | PK-10D | PK-10D | PK-10D | PK-10D | RB-11S | RB-11S | RB-11S | RB-11S |
|--------------------------|---------|---------|-----------|---------|-----------|---------|-----------|----------|-----------|
| Sample Date: | | 11/4/93 | 11/4/93 | 12/1/93 | 12/1/93 | 11/3/93 | 11/3/93 | 11/30/93 | 11/30/93 |
| | | Total | Dissolved | Total | Dissolved | Total | Dissolved | Total | Dissolved |
| Parameter | | | | | | | | | |
| (concentrations in ug/L) | MCL (a) | | | | | | | | |
| Antimony | 6 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | 9.7 B | 9.8 B | 6.3 B | 7.0 B | <1.0 J | <1.0 | <1.0 J | <1.0 |
| Barium | 1,000 | 3.0 B | 2.0 B | 4.2 B | 10.6 B | 8.6 B | 9.0 B | 8.1 B | 22.6 B |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | 2.0 B | <2.0 | 2.8 BJ | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | 9.4 B | 3.9 B | 3.5 BJ | 3.5 BJ | <3.0 | <3.0 J | 8.6 B | <3.0 |
| Copper | 1,000 | <7.0 | <7.0 | <7.0 | <7.0 | 13.9 B | <7.0 | <7.0 | <7.0 |
| Iron | 300 | R | 112 | 179 | <87.0 | 1130 | 175 | 1,270 | 114 |
| Lead | 50 | 3.4 J | <2.0 J | 1.7 BJ | <1.0 | 2.6 B | <2.0 | 3.7 | <2.0 |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | 18.2 B | <11.0 |
| Potassium | NS | <473 | 586 B | 853 B | 974 B | 1,140 B | 790 B | 1,510 B | 1,510 B |
| Selenium | 10 | <2.0 J | <2.0 | <2.0 | 2.2 B | <2.0 J | <2.0 | <2.0 J | <2.0 |
| Silver | 50 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | 22,900 | 24,600 | 15,900 | 16,600 | 7,590 | 8,020 | 7,920 | 8,040 |
| Thallium | 2 | <1.0 J | <1.0 J | <1.0 J | <1.0 | <1.0 | <1.0 J | <1.0 J | <1.0 |
| Zinc | 5,000 | 64.8 J | 51.3 J | 53.6 J | 42.1 | 30.4 | 28.2 | 53.1 | 33.1 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Parameter (concentrations in ug/L) | MCL (a) | Sample ID: Sample Date: | RB-11I 11/3/93 Total | RB-11I 11/3/93 Dissolved | RB-11I (Rep-1) 11/3/93 Total | RB-11I (Rep-1) 11/3/93 Dissolved | RB-11I 11/30/93 Total | RB-11I 11/30/93 Dissolved | RB-11I (Rep-1) 11/30/93 Total | RB-11I (Rep-1) 11/30/93 Dissolved |
|---------------------------------------|---------|----------------------------|----------------------------|--------------------------------|------------------------------------|--|-----------------------------|---------------------------------|-------------------------------------|---|
| | | | | | | | | | | |
| Antimony | 6 | | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 J | <1.0 |
| Barium | 1,000 | | 56.2 B | 39.7 B | 58.4 B | 34.9 B | 67.2 BJ | 71.7 B | 66.6 BJ | 69.8 B |
| Beryllium | 4 | | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | | 2.0 BJ | <2.0 | 3.7 BJ | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | | 15.5 | <3.0 J | 14.0 | <3.0 J | <3.0 | <3.0 | <3.0 | <3.0 |
| Copper | 1,000 | | 15.1 B | <7.0 | 12.6 B | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 |
| Iron | 300 | | 959 | 104 | 792 | 112 | 881 | <87.0 | 759 | <87.0 |
| Lead | 50 | | 4.9 | 3.2 | 4.4 | 3.3 | 4.2 | <2.0 | 4.2 | <2.0 J |
| Mercury | 2 | | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | | <11.0 | <11.0 | 14.6 B | <11.0 | 21.8 B | 12.1 B | 14.6 B | 13.9 B |
| Potassium | NS | | 1,320 B | 1,080 B | 1,260 B | 1,480 B | 1,620 B | 1,710 B | 1,560 B | 1,980 B |
| Selenium | 10 | | <2.0 J | <2.0 J | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 J | <2.0 |
| Silver | 50 | | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | | 17,400 | 18,600 | 18,200 | 17,600 | 18,500 | 18,800 | 18,700 | 18,300 |
| Thallium | 2 | | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 J | <1.0 | <1.0 J | <1.0 |
| Zinc | 5,000 | | 66.9 | 62.8 | 66.1 | 68.3 | 48.6 | 44.3 | 41.2 J | 45.6 J |

ug/L Micrograms per liter.

B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.

J Estimated value.

R Unusable value.

NS No standard.

(a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.

MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | | RB-11D 11/3/93 Total | RB-11D 11/3/93 Dissolved | RB-11D 11/30/93 Total | RB-11D 11/30/93 Dissolved | RW-12I 11/5/93 Total | RW-12I (Rep-3) 11/5/93 Total | RW-12I 11/5/93 Dissolved | RW-12I (Rep-3) 11/5/93 Dissolved |
|---------------------------------------|---------|----------------------------|--------------------------------|-----------------------------|---------------------------------|----------------------------|------------------------------------|--------------------------------|--|
| Parameter (concentrations in ug/L) | MCL (a) | | | | | | | | |
| Antimony | 6 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | 29.2 B | <21.0 |
| Arsenic | 50 | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 | <1.0 | 1.4 B | <1.0 |
| Barium | 1,000 | 9.4 B | 7.2 B | 6.9 B | 24.5 B | 46.9 B | 46.9 B | 39.8 B | 40.5 B |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | <3.0 | <3.0 J | 9.8 B | <3.0 | 6.8 B | 5.5 B | <3.0 | 7.0 B |
| Copper | 1,000 | 13.9 B | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 |
| Iron | 300 | 975 | <87.0 | 958 | <87.0 | R | R | <87.0 | <87.0 |
| Lead | 50 | 4.6 | <2.0 | 3.0 | <2.0 | 4.5 J | 2.3 BJ | <2.0 J | <2.0 J |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | <11.0 | <11.0 | 17.8 B | 12.8 B | <11.0 | <11.0 | <11.0 | <11.0 |
| Potassium | NS | <473 | <473 | 787 B | 1,210 B | 8,100 J | 8,110 J | 9,690 J | 10,100 J |
| Selenium | 10 | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 J | <2.0 J | <2.0 | <2.0 |
| Silver | 50 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | 4,260 B | 4,520 B | 4,220 B | 4,810 B | 53,500 J | 52,100 J | 59,500 J | 60,900 J |
| Thallium | 2 | <1.0 | <1.0 | <1.0 J | <1.0 | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | 41.2 | 37.2 | R | R | 57.7 J | 57.1 J | 83.2 J | 76.2 J |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Parameter (concentrations in ug/L) | MCL (a) | Sample ID: Sample Date: | RW-12I 12/2/93 Total | RW-12I (Rep-3) 12/2/93 Total | RW-12I 12/2/93 Dissolved | RW-12I (Rep-3) 12/2/93 Dissolved | RW-12D 11/5/93 Total | RW-12D 11/5/93 Dissolved | RW-12D 12/2/93 Total | RW-12D 12/2/93 Dissolved |
|---------------------------------------|---------|----------------------------|----------------------------|------------------------------------|--------------------------------|--|----------------------------|--------------------------------|----------------------------|--------------------------------|
| | | | | | | | | | | |
| Antimony | 6 | | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | | 1.5 B | 1.4 B | 1.8 B | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Barium | 1,000 | | 54.0 B | 55.1 B | 47.7 B | 48.2 B | 46.9 B | 18.3 B | 75.2 B | 49.8 B |
| Beryllium | 4 | | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | | <2.0 | 3.3 B | 2.4 B | <2.0 | <2.0 | <2.0 | 2.4 B | <2.0 |
| Chromium | 50 | | <3.0 J | <3.0 J | 3.7 BJ | <3.0 J | 11.9 | 3.1 B | <3.0 J | 3.0 BJ |
| Copper | 1,000 | | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 | <7.0 | 7.0 B | <7.0 |
| Iron | 300 | | 320 | 342 | <87.0 | <87.0 | R | <87.0 | 552 | <87.0 |
| Lead | 50 | | 2.8 BJ | 3.3 J | <1.0 | <1.0 | 7.1 J | 2.7 BJ | 7.1 J | <1.0 |
| Mercury | 2 | | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 |
| Potassium | NS | | 10,300 | 10,300 | 9,670 | 10,300 | 1,880 B | 2,040 B | 1,850 B | 1,850 B |
| Selenium | 10 | | <2.0 | <2.0 | <2.0 | <2.0 | 8.4 BJ | 5.4 | 5.4 | 5.7 |
| Silver | 50 | | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | | 60,800 | 62,000 | 57,800 | 60,300 | 55,700 | 55,000 | 66,500 | 65,000 |
| Thallium | 2 | | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | | 48.9 J | 58.9 J | 43.7 | 55.4 | 77.4 J | 95.6 J | 85.6 J | 78.4 |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Parameter (concentrations in ug/L) | Sample ID: Sample Date: | Field Blank | Field Blank | Field Blank | Field Blank | Field Blank | Field Blank | Field Blank | Field Blank |
|---------------------------------------|----------------------------|------------------|----------------------|------------------|----------------------|------------------|----------------------|------------------|----------------------|
| | | 11/1/93 Total | 11/1/93 Dissolved | 11/2/93 Total | 11/2/93 Dissolved | 11/3/93 Total | 11/3/93 Dissolved | 11/4/93 Total | 11/4/93 Dissolved |
| | MCL (a) | | | | | | | | |
| Antimony | 6 | 21.1 B | <21.0 | 26.6 B | <21.0 | <21.0 | 23.3 B | <21.0 | <21.0 |
| Arsenic | 50 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Barium | 1,000 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | 2.7 BJ | <2.0 | 2.8 BJ | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | <3.0 | <3.0 J | <3.0 | <3.0 J | 4.2 B | <3.0 J | <3.0 | <3.0 |
| Copper | 1,000 | 28.6 | 25.0 | 16.3 B | 8.6 B | <7.0 | <7.0 | 8.6 B | <7.0 |
| Iron | 300 | <87.0 | <87.0 | <87.0 | <87.0 | <87.0 | <87.0 | <87.0 | <87.0 |
| Lead | 50 | <2.0 | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 | <2.0 | <2.0 J |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 | <11.0 |
| Potassium | NS | <473 | <473 | <473 | <473 | <473 | <473 | <473 | <473 |
| Selenium | 10 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 J | <2.0 |
| Silver | 50 | 2.1 B | 2.2 B | 3.1 B | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | <121 | <121 | <121 | <121 | <121 | <121 | <121 | <121 |
| Thallium | 2 | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | R | R | 14.6 B | 12.6 B | <4.0 | 11.3 B | 5.7 B | 13.4 B |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Field Blank 11/5/93 Total | Field Blank 11/5/93 Dissolved | Field Blank 11/29/93 Total | Field Blank 11/29/93 Dissolved | Field Blank 11/30/93 Total | Field Blank 11/30/93 Dissolved | Field Blank 12/1/93 Total | Field Blank 12/1/93 Dissolved |
|---------------------------------------|---------------------------------|-------------------------------------|----------------------------------|--------------------------------------|----------------------------------|--------------------------------------|---------------------------------|-------------------------------------|
| Parameter (concentrations in ug/L) | MCL (a) | | | | | | | |
| Antimony | 6 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | <1.0 | <1.0 | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 J |
| Barium | 1,000 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Beryllium | 4 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Chromium | 50 | <3.0 | 3.2 B | 3.7 B | <3.0 | <3.0 | <3.0 | 6.1 B |
| Copper | 1,000 | <7.0 | <7.0 | 19.8 B | <7.0 | <7.0 | <7.0 | <7.0 |
| Iron | 300 | <87.0 | <87.0 | <87.0 | <87.0 | <87.0 | <87.0 | <87.0 |
| Lead | 50 | <2.0 | <2.0 J | <2.0 J | <2.0 | <2.0 | <2.0 | <2.0 |
| Mercury | 2 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | <11.0 | <11.0 | 13.5 B | <11.0 | 13.2 B | <11.0 | <11.0 |
| Potassium | NS | <473 | <473 | 671 B | 677 B | <473 | <473 | <473 |
| Selenium | 10 | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 J | <2.0 | <2.0 J |
| Silver | 50 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | <121 | <121 | <121 | <121 | <121 | 215 B | 126 B |
| Thallium | 2 | <1.0 J | <1.0 J | <1.0 J | <1.0 | <1.0 J | <1.0 | <1.0 |
| Zinc | 5,000 | 15.4 B | 14.9 B | 32.7 | 11.8 B | 10.0 B | 11.8 B | 10.1 B |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-3. Concentrations of Total and Dissolved Metals Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Parameter (concentrations in ug/L) | MCL (a) | Sample ID: Sample Date: | Field Blank 12/2/93 Total | Field Blank 12/2/93 Dissolved | Field Blank 12/3/93 Total | Field Blank 12/3/93 Dissolved |
|---------------------------------------|---------|----------------------------|---------------------------------|-------------------------------------|---------------------------------|-------------------------------------|
| | | | | | | |
| Antimony | 6 | | <21.0 | <21.0 | <21.0 | <21.0 |
| Arsenic | 50 | | <1.0 J | <1.0 | <1.0 | <1.0 |
| Barium | 1,000 | | <2.0 | <2.0 | <2.0 | 4.8 B |
| Beryllium | 4 | | <1.0 | <1.0 | <1.0 | <1.0 |
| Cadmium | 5 | | <2.0 | <2.0 | 2.2 B | 2.6 B |
| Chromium | 50 | | <3.0 | <3.0 | <3.0 J | <3.0 J |
| Copper | 1,000 | | <7.0 | <7.0 | <7.0 | <7.0 |
| Iron | 300 | | <87.0 | <87.0 | 489 | <87.0 |
| Lead | 50 | | <2.0 J | <2.0 | <1.0 J | <1.0 |
| Mercury | 2 | | <0.20 | <0.20 | <0.20 | <0.20 |
| Nickel | 100 | | <11.0 | <11.0 | <11.0 | <11.0 |
| Potassium | NS | | <473 | 605 B | <473 | <473 |
| Selenium | 10 | | <2.0 | <2.0 | <2.0 | <2.0 |
| Silver | 50 | | <2.0 | <2.0 | <2.0 | <2.0 |
| Sodium | 20,000 | | 191 B | 125 B | 272 B | 460 B |
| Thallium | 2 | | <1.0 J | <1.0 J | <1.0 J | <1.0 J |
| Zinc | 5,000 | | 11.8 B | 7.0 B | 16.9 BJ | 16.2 B |

ug/L Micrograms per liter.
 B Analyte concentration is between the instrument detection limit and the contract required quantitation limit.
 J Estimated value.
 R Unusable value.
 NS No standard.
 (a) Federal or State Drinking Water Standard (lowest value used), in micrograms per liter.
 MCL Maximum Contaminant Level.

Table 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-1 11/3/93 | SY-1 11/30/93 | SY-1D 11/4/93 | SY-1D 12/1/93 | SY-2R 11/2/93 | SY-2R 12/3/93 | SY-2D 11/2/93 |
|--|-----------------|------------------|------------------|------------------|------------------|------------------|------------------|
| Parameter (concentrations in mg/L) | | | | | | | |
| Ammonia-nitrogen | 0.43 | 0.45 | 11.8 | 9.90 | <0.04 | 0.26 | 4.94 |
| Bicarbonate alkalinity, as CaCO ₃ | 45.2 | 44.6 | 123 | 120 | 38.8 | 35.0 | 100 |
| Carbonate | <1.0 | <1.00 | <1.0 | <1.00 | <1.0 | <1.00 | <1.0 |
| Chloride | 54.4 | 52.4 | 285 | 287 | 449 | 613 | 108 |
| Hardness, as CaCO ₃ | 67.2 | 69.6 | 222 | 224 | 135 | 121 | 68.4 |
| Nitrate-nitrogen | <0.10 | 0.29 | 6.21 | 6.19 | 2.42 | 2.41 | 1.20 |
| Sulfate | 20.2 | 16.0 | 146 | 150 | 56.0 | 58.4 | 22.6 |
| Total dissolved solids | 189 | 269 | 798 | 803 | 861 | 850 | 282 |

mg/L Milligrams per liter.

NR Not requested.

CaCO₃ Calcium carbonate.

J Estimated value.

Table 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-2D 12/3/93 | SY-3 11/2/93 | SY-3 12/3/93 | SY-3D 11/2/93 | SY-3D 12/3/93 | SY-3DD 11/1/93 | SY-3DD 11/29/93 |
|--|------------------|-----------------|-----------------|------------------|------------------|-------------------|--------------------|
| Parameter (concentrations in mg/L) | | | | | | | |
| Ammonia-nitrogen | 6.98 | 67.8 | 123 | 146 | 83.6 | <0.04 | <0.04 |
| Bicarbonate alkalinity, as CaCO ₃ | 81.6 | 716 | 727 | 1,180 | 1,020 | 14.4 | 9.60 |
| Carbonate | <1.00 | 1.28 | <1.00 | 2.72 | 1.20 | <1.0 | <1.00 |
| Chloride | 97.0 | 136 | 176 | 269 | 265 | 4.20 | 4.6 |
| Hardness, as CaCO ₃ | 58.4 | 362 | 348 | 470 | 468 | 7.6 | 6.6 |
| Nitrate-nitrogen | 1.39 | <0.10 | <0.10 | 0.22 | 0.46 | <0.10 | 0.32 |
| Sulfate | 16.5 | 32.9 | 25.9 | 27.2 | 22.6 | 1.8 | 11.9 |
| Total dissolved solids | 299 | 726 | 757 | 1,240 | 1,400 | 44.0 | 54.0 |

mg/L Milligrams per liter.

NR Not requested.

CaCO₃ Calcium carbonate.

J Estimated value.

Table 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-4 11/2/93 | SY-4 12/3/93 | SY-6 11/5/93 | SY-6 12/2/93 | SY-6D 11/1/93 | SY-6D 11/29/93 | SY-7 11/4/93 |
|--|-----------------|-----------------|-----------------|-----------------|------------------|-------------------|-----------------|
| Parameter (concentrations in mg/L) | | | | | | | |
| Ammonia-nitrogen | 33.8 | 30.6 | 0.06 | 0.09 | 0.29 | 0.27 | 0.97 |
| Bicarbonate alkalinity, as CaCO ₃ | 448 | 449 | 195 | 202 | 19.8 | 9.80 | 32.2 J |
| Carbonate | <1.0 | <1.00 | <1.0 | <1.00 | <1.0 | <1.00 | <1.0 J |
| Chloride | 162 | 165 | 43.0 | 34.3 | 77.9 | 87.4 | 399 |
| Hardness, as CaCO ₃ | 346 | 347 | 176 | 181 | 84.0 | 81.0 | 260 |
| Nitrate-nitrogen | 6.10 | 1.85 | 2.57 | 2.26 | 6.03 | 6.64 | 0.31 |
| Sulfate | 77.8 | 72.0 | 10.3 | 19.8 | 71.6 | 63.0 | 62.7 |
| Total dissolved solids | 763 | 794 | 287 | 323 | 261 | 293 | 794 |

mg/L Milligrams per liter.

NR Not requested.

CaCO₃ Calcium carbonate.

J Estimated value.

Table 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-7 12/2/93 | SY-8 11/4/93 | SY-8 12/1/93 | SY-9 11/1/93 | SY-9 11/29/93 | PK-10S 11/4/93 | PK-10S 12/1/93 |
|--|-----------------|-----------------|-----------------|-----------------|------------------|-------------------|-------------------|
| Parameter (concentrations in mg/L) | | | | | | | |
| Ammonia-nitrogen | 0.36 | 0.21 | 0.13 | 0.76 | 0.61 | 0.36 | 0.06 |
| Bicarbonate alkalinity, as CaCO ₃ | 112 | 69.8 | 62.0 | 190 | 131 | 23.2 | 24.2 |
| Carbonate | <1.00 | <1.0 | <1.00 | <1.0 | <1.00 | <1.0 | <1.00 |
| Chloride | 808 | 32.3 | 32.7 | 39.3 | 47.2 | 16.2 | 13.7 |
| Hardness, as CaCO ₃ | 282 | 103 | 106 | 246 | 172 | 68.8 | 67.8 |
| Nitrate-nitrogen | <0.10 | <0.10 | <0.10 | <0.10 | 0.07 | 7.33 | 8.04 |
| Sulfate | 68.9 | 78.2 | 80.7 | 68.3 | 4,530 | 39.9 | 51.4 |
| Total dissolved solids | 1,050 | 218 | 49.0 | 346 | 312 | 162 | 181 |

mg/L Milligrams per liter.

NR Not requested.

CaCO₃ Calcium carbonate.

J Estimated value.

Table 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | PK-10I 11/4/93 | (Rep-2) 11/4/93 | PK-10I 12/1/93 | (Rep-2) 12/1/93 | PK-10D 11/4/93 | PK-10D 12/1/93 | RB-11S 11/3/93 |
|--|-------------------|--------------------|-------------------|--------------------|-------------------|-------------------|-------------------|
| Parameter (concentrations in mg/L) | | | | | | | |
| Ammonia-nitrogen | 39.1 | 39.3 | 37.9 | 41.0 | <0.04 | <0.04 | <0.04 |
| Bicarbonate alkalinity, as CaCO ₃ | 404 | 400 J | 419 | 419 | 24.6 | 17.8 | 15.6 |
| Carbonate | <1.0 | <1.0 J | <1.00 | <1.00 | <1.0 | <1.00 | <1.0 |
| Chloride | 291 | 287 | 678 | 499 | 14.0 | 14.2 | 8.0 |
| Hardness, as CaCO ₃ | 285 | 285 | 312 | 310 | 12.2 | 12.2 | 17.4 |
| Nitrate-nitrogen | 0.39 | 0.51 | 0.21 | 0.21 | 0.90 | 0.90 | 4.42 |
| Sulfate | 88.9 | 109 | 110 | 113 | 15.6 | 11.5 | <10.0 |
| Total dissolved solids | 918 | 948 | 1,020 | 1,030 | 87.0 | 85.0 | 47.0 |

mg/L Milligrams per liter.

NR Not requested.

CaCO₃ Calcium carbonate.

J Estimated value.

Table 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | RB-11S 11/30/93 | RB-11I 11/3/93 | (Rep-1) 11/3/93 | RB-11I 11/30/93 | (Rep-1) 11/30/93 | RB-11D 11/3/93 | RB-11D 11/30/93 |
|--|--------------------|-------------------|--------------------|--------------------|---------------------|-------------------|--------------------|
| Parameter (concentrations in mg/L) | | | | | | | |
| Ammonia-nitrogen | 0.09 | <0.04 | <0.04 | <0.04 | <0.04 | <0.04 | <0.04 |
| Bicarbonate alkalinity, as CaCO ₃ | 17.8 | 14.0 | 13.0 | 11.6 | 10.8 | 8.20 | 7.60 |
| Carbonate | <1.00 | <1.0 | <1.0 | <1.00 | <1.00 | <1.0 | <1.00 |
| Chloride | 6.4 | 29.7 | 29.4 | 27.9 | 28.3 | 3.40 | <3.0 |
| Hardness, as CaCO ₃ | 19.2 | 87.2 | 86.6 | 89.8 | 89.4 | 3.60 | 4.4 |
| Nitrate-nitrogen | 2.15 | 13.2 | 12.9 | 13.3 | 13.4 | 0.24 | 0.62 |
| Sulfate | <10.0 | 41.6 | 42.4 | <10.0 | 34.2 | <10.0 | <10.0 |
| Total dissolved solids | 81.0 | 186 | 179 | 252 | 216 | 17.0 | 61.0 |

mg/L Milligrams per liter.

NR Not requested.

CaCO₃ Calcium carbonate.

J Estimated value.

Table 3-4. Concentrations of Leachate Indicator Parameters Detected in Groundwater Samples Collected from Monitoring Wells During the Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | RW-12I 11/5/93 | (Rep-3) 11/5/93 | RW-12I 12/2/93 | (Rep-3) 12/2/93 | RW-12D 11/5/93 | RW-12D 12/2/93 | Field Blank 11/3/93 |
|--|-------------------|--------------------|-------------------|--------------------|-------------------|-------------------|------------------------|
| Parameter (concentrations in mg/L) | | | | | | | |
| Ammonia-nitrogen | 16.2 | 17.6 | 14.9 | 13.4 | <0.04 | 0.11 | NR |
| Bicarbonate alkalinity, as CaCO ₃ | 167 | 446 | 162 | 162 | 73.8 | 80.4 | NR |
| Carbonate | <1.0 | <1.0 | <1.00 | <1.00 | <1.0 | <1.00 | NR |
| Chloride | 106 | 106 | 118 | 117 | 122 | 139 | NR |
| Hardness, as CaCO ₃ | 169 | 166 | 164 | 161 | 132 | 144 | <1.0 |
| Nitrate-nitrogen | 2.66 | 3.47 | 4.18 | 4.04 | 1.09 | 0.10 | NR |
| Sulfate | 30.6 | 33.8 | 48.2 | 46.1 | 31.7 | 54.3 | NR |
| Total dissolved solids | 345 | 348 | 408 | 422 | 320 | 611 | NR |

mg/L Milligrams per liter.

NR Not requested.

CaCO₃ Calcium carbonate.

J Estimated value.

Table 3-5. Summary of Gas Well Monitoring Data, Syosset Landfill, Syosset, New York.

| February 25, 1994 | | | | March 2, 1994 | | | | |
|-------------------|--------------------------------------|--------------------------|-----------------------|--------------------------------------|--------------------------------------|--------------------------|-----------------------|--------------------------------------|
| Well No. | Barometer (a) (inches of mercury) | Total VOCs (b) (ppmv) | Methane (c) (ppmv) | Barometer (a) (inches of mercury) | Barometer (a) (inches of mercury) | Total VOCs (b) (ppmv) | Methane (c) (ppmv) | Barometer (a) (inches of mercury) |
| G-6 | 30.01 | — | 0.6 | 29.98 | 30.41 | — | — | 30.23 |
| G-7 | | 20 | 520 | | | 20 | — | |
| G-8 (d) | | (d) | (d) | | | (d) | (d) | |
| G-10 (e) | | (e) | (e) | | | (e) | (e) | |
| G-13 | | — | — | | | — | — | |
| G-14 | | — | — | | | — | — | |
| CS-20 | | — | — | | | — | — | |
| CS-21 | | — | — | | | — | — | |
| CS-22 | | — | — | | | — | — | |

| March 7, 1994 | | | | |
|---------------|--------------------------------------|--------------------------|-----------------------|--------------------------------------|
| Well No. | Barometer (a) (inches of mercury) | Total VOCs (b) (ppmv) | Methane (c) (ppmv) | Barometer (a) (inches of mercury) |
| G-6 | 30.17 | — | — | 30.06 |
| G-7 | | 100 | 100 | |
| G-8 (d) | | (d) | (d) | |
| G-10 (e) | | (e) | (e) | |
| G-13 | | — | — | |
| G-14 | | — | — | |
| CS-20 | | — | — | |
| CS-21 | | — | — | |
| CS-22 | | — | — | |

Measurements made in field by Geraghty & Miller, Inc. using a Foxboro Model 128 organic vapor analyzer (OVA). Instrument calibrated using zero gas and methane standards.

- (a) Barometer readings obtained from Newsday Weather Service before and after each measurement round.
 (b) Measurements made using a standard OVA probe.
 (c) Measurements made using an activated charcoal-filter OVA probe.
 (d) Well destroyed.
 (e) Well could not be located.
 ppmv Parts per million by volume.
 — Not detected.






**GERAGHTY
& MILLER, INC.**
Ground-Water Consultants

COMPILED BY: VINCE GLASSER
PREPARED BY: ELAINE DeLUCA
PROJECT NO: VINCE GLASSER

DATE: 10/88
SCALE: SHOWN
FILE NO: NO340SL03-1115

PREPARED FOR:


LOCKWOOD, KESSLER & BARLETT
Syosset, New York



SUBJECT:

SITE LOCATION, Syosset Landfill, Syosset, New York

**FIGURE
1-1**



EXPLANATION

- PK-101 ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D ▲ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-9DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED
- SITE BOUNDARY (FENCE)
- ▨ RECHARGE BASIN
- ▤ LANDFILL AREA
- A—A' LINE OF HYDROGEOLOGIC CROSS SECTION
- TOB-DPW TOWN OF OYSTER BAY—DEPARTMENT OF PUBLIC WORKS

0 500 FT




DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING:
USE TO VERIFY FIGURE REPRODUCTION SCALE

| | |
|------------------------|--------------------|
| PROJECT NO.: NY0029008 | FILE NO: 1584 |
| DRAWING: LINEWELL | PLOT SIZE: 1"=300' |
| DRAFTED BY: VC | DATE: 3/9/94 |
| CHECKED BY: SZ | DATE: |
| APPROVED BY: VG | DATE: |

LOCATIONS OF GROUNDWATER MONITORING WELLS, GAS MONITORING WELLS, SOIL BORINGS, AND LINES OF HYDROGEOLOGIC CROSS SECTION, SYOSSET LANDFILL SYOSSET, NEW YORK

FIGURE
1-2



EXPLANATION

- O-6A LOCATION AND DESIGNATION OF NASSAU COUNTY OBSERVATION WELL.
- ▲ N7781 LOCATION AND DESIGNATION OF PUBLIC SUPPLY WELL SAMPLED IN SEPTEMBER 1992 TO DETERMINE BACKGROUND WATER QUALITY.
- * INDICATES THAT WELL WAS SAMPLED IN SEPTEMBER 1992 TO DETERMINE BACKGROUND WATER QUALITY.

0 4000 FT



DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING:




USE TO VERIFY FIGURE REPRODUCTION SCALE

| | |
|------------------------|---------------------|
| PROJECT NO.: NY0840002 | FILE NO: 1584 |
| DRAWING: BASE-94 | PLOT SIZE: 1"=4000' |
| DRAFTED BY: VC | DATE: 3/11/94 |
| CHECKED BY: VUG | DATE: - |
| APPROVED BY: LH | DATE: - |

LOCATIONS OF NASSAU COUNTY MONITORING WELLS AND SELECTED PUBLIC SUPPLY WELLS WITHIN APPROXIMATELY 2 MILES OF THE SYOSSET LANDFILL, SYOSSET, NEW YORK

FIGURE
2-1





SCALE VERIFICATION


THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING

USE TO VERIFY FIGURE REPRODUCTION SCALE

| | |
|------------------------|----------------|
| PROJECT NO.: NY0029008 | FILE NO: 1584 |
| DRAWING: SEC-AAG | PLOT SIZE: |
| DRAFTED BY: GS | DATE: 11-21-85 |
| CHECKED BY: LH | DATE: |
| APPROVED BY: VJG | DATE: |

NORTH-SOUTH HYDROGEOLOGIC CROSS SECTION A-A'
SYOSSET LANDFILL, SYOSSET, NEW YORK






EXPLANATION

- PK-101 ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D ▲ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED
- SITE BOUNDARY (FENCE)
- ▨ RECHARGE BASIN
- ▤ LANDFILL AREA
- 81 LINE OF EQUAL POTENTIOMETRIC SURFACE ELEVATION IN FEET ABOVE MEAN SEA LEVEL (DASHED WHERE APPROXIMATE)
- DIRECTION OF HORIZONTAL COMPONENT OF GROUNDWATER FLOW
- 80.21 POTENTIOMETRIC HEAD IN FEET ABOVE MEAN SEA LEVEL
- TOB-DPW TOWN OF OYSTER BAY—DEPARTMENT OF PUBLIC WORKS


0 500 FT



EXPLANATION

- PK-101 ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D ▲ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED
- SITE BOUNDARY (FENCE)
- ▨ RECHARGE BASIN
- ▤ LANDFILL AREA
- 81 LINE OF EQUAL POTENTIOMETRIC SURFACE ELEVATION IN FEET ABOVE MEAN SEA LEVEL (DASHED WHERE APPROXIMATE)
- ← DIRECTION OF HORIZONTAL COMPONENT OF GROUNDWATER FLOW
- 80.79 POTENTIOMETRIC HEAD IN FEET ABOVE MEAN SEA LEVEL
- TOB-DPW TOWN OF OYSTER BAY—DEPARTMENT OF PUBLIC WORKS

0 500 FT



EXPLANATION

- PK-101 ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ⊙ ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ⊙ ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D ⊙ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 ⊙ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ⊙ EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ⊙ ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED
- SITE BOUNDARY (FENCE)
- ▨ RECHARGE BASIN
- ▤ LANDFILL AREA
- 81 LINE OF EQUAL POTENTIOMETRIC SURFACE ELEVATION IN FEET ABOVE MEAN SEA LEVEL (DASHED WHERE APPROXIMATE)
- ➔ DIRECTION OF HORIZONTAL COMPONENT OF GROUNDWATER FLOW
- 80.79 POTENTIOMETRIC HEAD IN FEET ABOVE MEAN SEA LEVEL
- TOB-DPW TOWN OF OYSTER BAY-DEPARTMENT OF PUBLIC WORKS

0 500 FT




DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING:
USE TO VERIFY FIGURE REPRODUCTION SCALE

| | |
|------------------------|--------------------|
| PROJECT NO.: NY0029008 | FILE NO: 1584 |
| DRAWING: IZ-1193 | PLOT SIZE: 1"=300' |
| DRAFTED BY: VC | DATE: 3/9/94 |
| CHECKED BY: SZ | DATE: |
| APPROVED BY: VC | DATE: |

POTENTIOMETRIC SURFACE OF THE INTERMEDIATE ZONE OF THE MAGOTHY AQUIFER ON NOVEMBER 24, 1993
SYOSSET LANDFILL, SYOSSET, NEW YORK

FIGURE
3-7



EXPLANATION

- PK-10I ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D ▲ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 W-4 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED
- SITE BOUNDARY (FENCE)
- RECHARGE BASIN
- LANDFILL AREA
- CM CHLOROMETHANE
- VC VINYL CHLORIDE
- 1,1-DCE 1,1 DICHLOROETHENE
- 1,1-DCA 1,1 DICHLOROETHANE
- CIS-1,2-DCE CIS 1,2 DICHLOROETHENE
- 1,1,1-TCA 1,1,1 TRICHLOROETHANE
- B BENZENE
- TCE TRICHLOROETHENE
- TOL TOLUENE
- PCE TETRACHLOROETHENE
- CB CHLOROBENZENE
- TCFM TRICHLOROFLUOROMETHANE
- 2-HEX 2-HEXANONE
- DCDFM DICHLORODIFLUOROMETHANE
- O-X ORTHO-XYLENE
- M/P-X META/PARA XYLENE
- NOT DETECTED
- J ESTIMATED VALUE
- / CONCENTRATIONS OF VOLATILE ORGANIC COMPOUNDS FOR NOVEMBER/DECEMBER SAMPLING ROUND IN MICROGRAMS PER LITER (ug/L)
- TOB-DPW TOWN OF OYSTER BAY-DEPARTMENT OF PUBLIC WORKS

0 500 FT



DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.
USE TO VERIFY FIGURE REPRODUCTION SCALE

| REV. NO. | DATE | DESCRIPTION | BY | APPR. |
|----------|------|-------------|----|-------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| | |
|--------------------------|-------------------|
| PROJECT NO: NY029008 | FILE NO: 1084 |
| DRAWING: VDC-SHAL | PLOT SIZE: 11x25" |
| DRAFTED BY: V. CARUNCHO | DATE: 3/10/94 |
| CHECKED BY: L. HENDRICKS | DATE: - |
| APPROVED BY: V. GLASSER | DATE: - |

CONCENTRATIONS OF VOLATILE ORGANIC COMPOUNDS DETECTED IN SITE MONITORING WELLS SCREENED IN THE SHALLOW ZONE OF THE MAGOTHY AQUIFER SECOND OPERABLE UNIT REMEDIAL INVESTIGATION SYOSSET LANDFILL, SYOSSET, NEW YORK

| REP-2 | | |
|-------------|--------|------|
| DCDFM | - / | 0.2J |
| VC | 0.8J / | 0.7J |
| 1,1-DCE | - / | 0.2J |
| 1,1-DCA | 6.3 / | 5.6 |
| CIS-1,2-DCE | 2.5 / | 1.4 |
| B | 0.5J / | - |
| TCE | 1.2 / | 0.9J |
| TOL | - / | 1.0 |
| PCE | 3.3 / | 1.5 |
| CB | 17 / | 5.3 |
| TOTAL | 31.6 / | 16.8 |

| RW-12I | | |
|-------------|---------|-------|
| VC | - / | 0.6J |
| 1,1-DCE | 13 / | 26 |
| 1,1-DCA | 11 / | 17 |
| CIS-1,2-DCE | 5.2 / | 5.7 |
| 1,1,1-TCA | 40 / | 75 |
| B | - / | 0.5J |
| TCE | 6.2 / | 9.8 |
| TOL | - / | 13 |
| PCE | 68 / | 110 |
| CB | 1.1J / | 0.9 |
| TCFM | - / | 1.2J |
| TOTAL | 144.5 / | 259.7 |


| REP-3 | | |
|-------------|-------|---------|
| 1,1-DCE | 15 | / 27 |
| 1,1-DCA | 13 | / 17 |
| CIS-1,2-DCE | 5.7 | / 5.9 |
| 1,1,1-TCA | 40 | / 75 |
| B | - | / 0.5J |
| TCE | 6.3 | / 9.9 |
| TOL | - | / 12 |
| PCE | 71 | / 110 |
| CB | 1.3J | / 10.9J |
| TCFM | - | / 1.2J |
| TOTAL | 152.3 | / 259.4 |

| SY-1D | | |
|-------------|------|--------|
| DCDFM | - | / 1.4J |
| VC | 1.6 | / 1.4J |
| 1,1-DCE | 0.1J | - |
| 1,1-DCA | 2.9 | / 2.4 |
| CIS-1,2-DCE | 6.4 | / 4.2 |
| CF | 9.1 | / 5.9 |
| B | 0.6J | / 0.5J |
| 1,2-DCA | - | / 1.7 |
| TCE | 1.3 | / 1.1 |
| PCE | 2.4 | / 1.7 |
| CB | 4.8 | / 3.7 |
| TOTAL | 29.2 | / 24 |

| REP-1 | | |
|-------------|-----------|-------------|
| | DCDFM | 1.6J / 2.7J |
| | 1,1-DCE | 1.3 / 1.5 |
| | 1,1-DCA | 10 / 13 |
| CIS-1,2-DCE | | 2.9 / 2.2 |
| | 1,1,1-TCA | 3.4 / 4.9 |
| | TCE | 3.0 / 4.0 |
| | TOL | 0.6J / 0.3J |
| | PCE | 19 / 23 |
| | TCFM | - / 0.9J |
| | TOTAL | 41.8 / 52.5 |

| SY-2D | | |
|-------------|---------|--------|
| DCDFM | - / | 0.2J |
| 1,1-DCE | 0.5J | / 0.7J |
| 1,1-DCA | 2.1 / | 3.6 |
| CIS-1,2-DCE | 0.2J / | 0.2J |
| 1,1,1-TCA | 0.7J / | 1.4 |
| TCE | 0.4J / | 0.7J |
| TOL | 0.2J / | - |
| PCE | 0.5J / | 0.5J |
| CB | 0.4J / | 0.6J |
| M/P-X | 0.08J / | - |
| TOTAL | 5.08 / | 7.9 |





0 500 FT



DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.
USE TO VERIFY FIGURE REPRODUCTION SCALE

| REV. NO. | DATE | DESCRIPTION | BY | APPR. |
|----------|------|-------------|----|-------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| | |
|--------------------------|--------------------|
| PROJECT NO.: NY028008 | FILE NO: 1084 |
| DRAWING: LEACH-S | PLOT SIZE: 1"=250' |
| DRAFTED BY: V. CARUNCHO | DATE: 3/10/94 |
| CHECKED BY: L. HENDRICKS | DATE: - |
| APPROVED BY: V. GLASSER | DATE: - |


CONCENTRATIONS OF LEACHATE INDICATOR PARAMETERS DETECTED IN SITE MONITORING WELLS SCREENED IN THE SHALLOW ZONE OF THE MAGOTHY AQUIFER.
SECOND OPERABLE UNIT REMEDIAL INVESTIGATION
SYOSSET LANDFILL, SYOSSET, NEW YORK

| SY-3DD | | | |
|------------|------|---|------|
| AMMONIA | - | / | - |
| ALKALINITY | 14.4 | / | 9.60 |
| CHLORIDE | 4.2 | / | 4.5 |
| HARDNESS | 7.6 | / | 6.6 |
| NITRATE | - | / | 0.32 |
| SULFATE | 1.8 | / | 11.9 |
| TDS | 44 | / | 54 |

| PK-10D | | | |
|------------|------|---|------|
| AMMONIA | - | / | - |
| ALKALINITY | 24.6 | / | 17.8 |
| CHLORIDE | 14.0 | / | 14.2 |
| HARDNESS | 12.2 | / | 12.2 |
| NITRATE | 0.90 | / | 0.90 |
| SULFATE | 15.6 | / | 11.5 |
| TDS | 87 | / | 85 |

| RB-11D | | | |
|------------|------|---|------|
| AMMONIA | - | / | - |
| ALKALINITY | 8.20 | / | 7.60 |
| CHLORIDE | 3.40 | / | - |
| HARDNESS | 3.60 | / | 4.4 |
| NITRATE | 0.24 | / | 0.62 |
| SULFATE | - | / | - |
| TDS | 17.0 | / | 51.0 |

| RW-12D | | | |
|------------|------|---|------|
| AMMONIA | - | / | 0.11 |
| ALKALINITY | 73.8 | / | 80.4 |
| CHLORIDE | 122 | / | 139 |
| HARDNESS | 132 | / | 144 |
| NITRATE | 1.09 | / | 0.10 |
| SULFATE | 31.7 | / | 54.3 |
| TDS | 320 | / | 511 |



EXPLANATION

- PK-10I ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D ▲ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- W-4 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED
- SITE BOUNDARY (FENCE)
- ▨ RECHARGE BASIN
- ▤ LANDFILL AREA
- TDS TOTAL DISSOLVED SOLIDS
- NOT DETECTED
- / CONCENTRATIONS FOR NOVEMBER/DECEMBER SAMPLING ROUND IN MICROGRAMS PER LITER (mg/L)
- TOB-DPW TOWN OF OYSTER BAY-DEPARTMENT OF PUBLIC WORKS

0 500 FT



DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING:
USE TO VERIFY FIGURE REPRODUCTION SCALE

| REV. NO. | DATE | DESCRIPTION | BY | APPR. |
|----------|------|-------------|----|-------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| | |
|--------------------------|--------------------|
| PROJECT NO.: NY029006 | FILE NO.: 1584 |
| DRAWING: LEACH-B | PLOT SIZE: 1"=250' |
| DRAFTED BY: V. CARUNCHIO | DATE: 3/10/94 |
| CHECKED BY: L. HENDRICKS | DATE: - |
| APPROVED BY: V. GLASSER | DATE: - |

CONCENTRATIONS OF LEACHATE INDICATOR PARAMETERS DETECTED IN SITE MONITORING WELLS SCREENED IN THE DEEP ZONE OF THE MAGOTHY AQUIFER
SECOND OPERABLE UNIT REMEDIAL INVESTIGATION
SYOSSET LANDFILL, SYOSSET, NEW YORK

SY-4

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ANTIMONY | 23.1 B | 38.3 B | 21.0 B | — |
| ARSENIC | 9.4 BJ | 5.2 B | 10.3 | 5.9 B |
| BARIUM | 129 B | 116 B | 128 B | 127 B |
| CHROMIUM | 7.8 B | — | 5.3 BJ | — |
| COPPER | 63.7 | — | 61.9 | — |
| IRON | 41,200 | 9,810 | 45,900 | 8,910 |
| LEAD | 24.3 | — | 65.4 J | — |
| NICKEL | — | — | 16.0 B | — |
| POTASSIUM | 27,800 | 26,500 | 27,600 | 27,700 |
| SODIUM | 117,000 | 118,000 | 115,000 | 112,000 |
| ZINC | 99.9 | 13.1 B | 147 J | 37.5 |

SY-8

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ANTIMONY | — | — | 25.5 B | — |
| BARIUM | 68.6 B | 74.4 B | 65.9 BJ | 82.9 B |
| CHROMIUM | — | — | — | 4.4 B |
| IRON | R | 2,540 | 2,450 | 2,480 |
| LEAD | 6.0 J | — | — | — |
| NICKEL | — | — | 16.8 B | — |
| POTASSIUM | 4,740 B | 5,110 | 5,420 | 5,790 |
| SODIUM | 26,800 | 29,000 | 29,300 J | 29,100 |
| ZINC | 1,840 J | 1,970 J | 1,900 | 1,940 |

EXPLANATION

- PK-101 ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D △ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 W-4 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED

SY-6

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| BARIUM | 59.6 B | 75.0 B | 91.6 B | 91.6 B |
| CADMIUM | — | 2.3 B | — | — |
| COPPER | 16.8 B | — | 38.5 | — |
| IRON | R | 399 | 22,200 | 173 |
| LEAD | 14.0 J | — | 21.5 J | — |
| POTASSIUM | 1,330 B | 1,640 B | 1,800 B | 1,660 B |
| SODIUM | 38,900 J | 49,100 J | 38,200 | 38,200 |
| ZINC | 347 J | 235 J | 611 J | 183 |

SY-7

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ANTIMONY | 27.8 B | 46.8 B | 34.4 B | 25.2 B |
| ARSENIC | 3.4 B | 1.2 B | 7.0 B | 1.7 B |
| BARIUM | 171 B | 146 B | 179 B | 179 B |
| BERYLLIUM | — | — | — | 1.5 B |
| CHROMIUM | 28.2 | — | 49.9 J | — |
| COPPER | 86.1 | 9.5 B | 134 | — |
| IRON | R | 77,800 | 181,000 | 71,200 |
| LEAD | 37.9 J | — | 21.9 J | — |
| MERCURY | 0.77 | — | 0.31 | — |
| NICKEL | 22.1 B | — | 69.6 | 14.1 B |
| POTASSIUM | 1,650 B | 1,660 B | 2,280 B | 1,940 B |
| SODIUM | 110,000 | 118,000 | 173,000 | 175,000 |
| THALLIUM | — | — | — | 1.8 BJ |
| ZINC | 529 J | 174 J | 389 J | 139 |


SY-9

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ARSENIC | 39.3 | 19.4 | 26.7 J | 19.1 |
| BARIUM | 144 B | 159 B | 155 BJ | 82.8B |
| CHROMIUM | 23.3 J | — | 24.7 | — |
| COPPER | R | R | 160 | — |
| IRON | 27,300 | 6,480 | 24,400 | 5,340 |
| LEAD | 58.8 | — | 41.8 | — |
| NICKEL | 22.2 B | — | 23.1 B | — |
| POTASSIUM | 3,120 B | 2,000 B | 3,550 B | 2,130 B |
| SODIUM | 25,900 J | 30,400 J | 27,600 J | 32,500 J |
| ZINC | 227 | 81.6 | 219 | 67.9 |

SY-1

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ARSENIC | 17.4 BJ | 18.5 | 23.9 J | 22.6 |
| BARIUM | 78.6 B | 86.6 B | 88.4 BJ | 102 B |
| CHROMIUM | 18.6 J | — | 18.7 | — |
| COPPER | 29.0 | 8.9 B | 9.5 B | — |
| IRON | 80,000 | 20,400 | 79,900 | 23,000 |
| LEAD | 13.1 | — | 9.5 J | — |
| NICKEL | 26.8 B | — | 11.2 B | 17.4 B |
| POTASSIUM | 5,090 | 4,490 B | 4,540 BJ | 4,750 B |
| SILVER | 2.8 B | — | — | — |
| SODIUM | 20,100 | 20,800 | 3,550 B | 23,800 |
| ZINC | 39.3 | 21.2 | R | 23.5 |

CERRO WIRE & CABLE COMPANY



SY-3

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ANTIMONY | 91.8 | — | 36.7 B | 36.7 B |
| ARSENIC | 41.4 J | 15.0 | 76.1 | 47.4 |
| BARIUM | 237 | 110 B | 213 | 186 B |
| CHROMIUM | 31.3 | — | 5.5 BJ | — |
| COPPER | 80.1 | — | 15.4 B | — |
| IRON | 295,000 | 2,550 | 70,100 | 7,900 |
| LEAD | 62.8 | — | 33.0 J | — |
| NICKEL | 24.2 B | — | — | — |
| POTASSIUM | 70,500 | 68,000 | 73,600 | 66,600 |
| SODIUM | 99,100 | 98,400 | 124,000 | 116,000 |
| ZINC | 181 | 16.5 B | 92.4 J | 33.0 |

PK-10S

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ARSENIC | 1.9 B | 1.1 B | 3.5 BJ | — |
| BARIUM | 38.5 B | 32.0 B | 36.3 BJ | 52.8 B |
| COPPER | 38.8 | — | 8.1 B | — |
| IRON | R | 682 | 5,380 | 694 |
| LEAD | 10.1 J | — | 6.2 | — |
| NICKEL | 25.0 B | 17.6 B | 17.5 B | 11.1 B |
| POTASSIUM | 1,010 B | 986 B | 1,900 B | 1,500 B |
| SODIUM | 19,400 | 20,900 | 20,500 | 20,900 |
| ZINC | 178 J | 165 J | 43.3 J | 53.8 J |

SY-2R

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| ANTIMONY | 36.4 B | — | 24.3 B | — |
| BARIUM | 64.2 B | 88.4 B | 50.3 B | 49.2 B |
| BERYLLIUM | 7.8 | 2.5 B | 1.4 B | 1.2 B |
| CADMIUM | — | — | — | 2.0 B |
| CHROMIUM | 16.2 | — | 3.7 BJ | — |
| COPPER | 24.5 B | — | — | — |
| IRON | 20,600 | 1,770 | 2,060 | 383 |
| LEAD | 128 | — | 11.1 J | 1.7 B |
| NICKEL | 91.1 | 21.8 B | 16.3 B | — |
| POTASSIUM | 18,700 | 18,200 | 19,800 | 18,200 |
| SODIUM | 239,000 | 232,000 | 227,000 | 204,000 |
| ZINC | 115 | 48.6 | 29.9 J | 29.7 |

RB-11S

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | SAMPLING ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | DECEMBER 1993 TOTAL | DISSOLVED |
| BARIUM | 8.6 B | 9.0 B | 8.1 B | 22.6 B |
| CADMIUM | 2.8 BJ | — | — | — |
| CHROMIUM | — | — | 8.6 B | — |
| COPPER | 13.9 B | — | — | — |
| IRON | 1130 | 175 | 1,270 | 114 |
| LEAD | 2.6 B | — | 3.7 | — |
| NICKEL | — | — | 18.2 B | — |
| POTASSIUM | 1,140 B | 790 B | 1,510 B | 1,510 B |
| SODIUM | 7,590 | 8,020 | 7,920 | 8,040 |
| ZINC | 30.4 | 28.2 | 53.1 | 33.1 |

0 500 FT

GERAGHTY & MILLER, INC.
Environmental Services

DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS
ONE INCH ON THE
ORIGINAL DRAWING:

USE TO VERIFY FIGURE
REPRODUCTION SCALE

| REV. NO. | DATE | DESCRIPTION | BY | APPR. |
|----------|------|-------------|----|-------|
| | | | | |
| | | | | |
| | | | | |

| | |
|-------------------------|----------------------|
| PROJECT NO.: NY0228-008 | FILE NO: 1584 |
| DRAWING: METAL-S | PLOT SIZE: 11" x 25" |
| DRAFTED BY: WH ODO | DATE: 12-1-95 |
| CHECKED BY: D SOTILE | DATE: 12-1-95 |
| APPROVED BY: M WOLFERT | DATE: 12-1-95 |

**CONCENTRATIONS OF METALS
DETECTED IN SITE MONITORING WELLS SCREENED IN THE
SHALLOW ZONE OF THE MAGOTHY AQUIFER
SECOND OPERABLE UNIT REMEDIAL INVESTIGATION**
SYOSSET LANDFILL, SYOSSET, NEW YORK

FIGURE
3-16

RW-121

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | REPLICATE ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | NOVEMBER 1993 TOTAL | DISSOLVED |
| ANTIMONY | — | 29.2 B | — | — |
| ARSENIC | — | 1.4 B | 1.5 B | 1.8 B |
| BARIUM | 46.9 B | 39.8 B | 54.0 B | 47.7 B |
| CADMIUM | — | — | 2.4 B | — |
| CHROMIUM | 6.8 B | — | 3.7 BJ | 5.5 B |
| IRON | R | — | 320 | R |
| LEAD | 4.5 J | — | 2.8 BJ | — |
| POTASSIUM | 8,100 J | 9,680 J | 10,300 | 9,670 |
| SODIUM | 53,500 J | 59,500 J | 60,800 | 57,800 |
| ZINC | 57.7 J | 83.2 J | 48.9 J | 43.7 |

EXPLANATION

- PK-101 ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D △ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 W-4 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED

SY-6D

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | REPLICATE ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | NOVEMBER 1993 TOTAL | DISSOLVED |
| ARSENIC | 1.2 BJ | — | — | — |
| BARIUM | 41.8 B | 52.4 B | 37.7 BJ | 44.6 B |
| CHROMIUM | 23.9 J | — | — | — |
| COPPER | R | R | 7.6 B | — |
| IRON | 3,280 | 961 | 985 | 939 |
| LEAD | 7.5 | — | — | — |
| NICKEL | 12.6 B | — | 14.3 B | — |
| POTASSIUM | 2,080 B | 676 B | 2,030 B | 2,210 B |
| SILVER | 3.9 B | — | — | — |
| SODIUM | 50,100 | 50,400 | 50,900 | 51,200 |
| ZINC | 52.4 | 55.3 | R | 20.8 |

SY-3D

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | REPLICATE ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | NOVEMBER 1993 TOTAL | DISSOLVED |
| ARSENIC | 94.7 J | 8.9 B | 102 | 2.5 B |
| BARIUM | 162 B | 101 B | 153 B | 112 B |
| CADMIUM | — | — | — | 2.4 B |
| CHROMIUM | 7.3 BJ | — | — | — |
| COPPER | 104 | 40.8 | 44.9 | 8.3 B |
| IRON | 34,700 | 1,810 | 23,300 | 728 |
| LEAD | 10.7 | — | 8.8 J | — |
| NICKEL | — | 17.8 B | 14.9 B | — |
| POTASSIUM | 131,000 | 132,000 | 142,000 | 132,000 |
| SODIUM | 194,000 | 198,000 | 211,000 | 196,000 |
| ZINC | 76.5 | 23.3 | 66.0 J | 37.2 |

PK-101

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | REPLICATE ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | NOVEMBER 1993 TOTAL | DISSOLVED |
| BARIUM | 54.8 B | 52.2 B | 65.4 BJ | 64.8 B |
| CHROMIUM | — | — | 3.7 B | — |
| COPPER | 9.9 B | 13.7 B | — | — |
| IRON | R | — | 474 | R |
| LEAD | 3.8 J | 2.6 BJ | 3.2 | — |
| NICKEL | — | — | 16.4 B | 15.0 B |
| POTASSIUM | 46,100 | 47,300 | 53,400 | 50,400 |
| SODIUM | 178,000 | 179,000 | 235,000 J | 220,000 |
| ZINC | 58.7 J | 63.0 J | 42.6 | 22.8 |

SY-2D


| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | REPLICATE ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | NOVEMBER 1993 TOTAL | DISSOLVED |
| BARIUM | 57.0 B | 57.8 B | 48.7 B | 37.6 B |
| CADMIUM | 2.8 BJ | — | — | 2.4 B |
| CHROMIUM | — | — | 6.4 BJ | — |
| COPPER | 12.6 B | — | — | — |
| IRON | 264 | — | R | — |
| LEAD | — | — | 1.8 BJ | — |
| POTASSIUM | 13,200 | 12,600 | 12,600 | 12,600 |
| SODIUM | 70,500 | 66,600 | 65,000 | 62,500 |
| ZINC | 11.5 B | 10.3 B | 29.1 J | 24.7 |

RB-111

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | REPLICATE ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | NOVEMBER 1993 TOTAL | DISSOLVED |
| BARIUM | 56.2 B | 39.7 B | 67.2 BJ | 71.7 B |
| CADMIUM | 2.0 BJ | — | — | — |
| CHROMIUM | 15.5 | — | — | — |
| COPPER | 15.1 B | — | — | — |
| IRON | 958 | 104 | 881 | — |
| LEAD | 4.9 | 3.2 | 4.2 | — |
| NICKEL | — | — | 21.8 B | 12.1 B |
| POTASSIUM | 1,320 B | 1,080 B | 1,620 B | 1,710 B |
| SODIUM | 17,400 | 18,600 | 18,500 | 18,800 |
| ZINC | 66.9 | 62.8 | 48.6 | 44.3 |

SY-1D

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | REPLICATE ROUND | |
|---------------------------------------|------------------------|-----------|------------------------|-----------|
| | NOVEMBER 1993 TOTAL | DISSOLVED | NOVEMBER 1993 TOTAL | DISSOLVED |
| BARIUM | 57.0 B | 56.6 B | 62.2 BJ | 69.2 B |
| IRON | 152 | — | — | — |
| NICKEL | — | — | — | 12.1 B |
| POTASSIUM | 10,600 | 10,600 | 10,700 | 11,000 |
| SODIUM | 180,000 | 179,000 | 192,000 J | 190,000 |
| ZINC | 11.9 B | 11.6 B | 14.8 B | 29.2 |



ug/L MICROGRAMS PER LITER

TOB-DPW TOWN OF OYSTER BAY-DEPARTMENT OF PUBLIC WORKS

0 500 FT



DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING
USE TO VERIFY FIGURE REPRODUCTION SCALE

| REV. NO. | DATE | DESCRIPTION | BY | APPR. |
|----------|------|-------------|----|-------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |



| | |
|-------------------------|--------------------|
| PROJECT NO.: NY0029.006 | FILE NO.: 1584 |
| DRAWING: METAL-1 | PLOT SIZE: 1"=250' |
| DRAFTED BY: WH CIO | DATE: 12-1-95 |
| CHECKED BY: D SOTILE | DATE: 12-1-95 |
| APPROVED BY: M WOLFERT | DATE: 12-1-95 |

CONCENTRATIONS OF METALS
DETECTED IN SITE MONITORING WELLS SCREENED IN THE
INTERMEDIATE ZONE OF THE MAGOTHY AQUIFER
SECOND OPERABLE UNIT REMEDIAL INVESTIGATION

SYOSSET LANDFILL, SYOSSET, NEW YORK

FIGURE

3-17



RW-12D

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | | |
|---------------------------------------|----------------|-----------|---------------|-----------|
| | NOVEMBER 1993 | | DECEMBER 1993 | |
| | TOTAL | DISSOLVED | TOTAL | DISSOLVED |
| BARIUM | 46.9 B | 18.3 B | 75.2 B | 49.8 B |
| CADMIUM | - | - | 2.4 B | - |
| CHROMIUM | 11.9 | 3.1 B | - | 3.0 BJ |
| COPPER | - | - | 7.0 B | - |
| IRON | R | - | 552 | - |
| LEAD | 7.1 J | 2.7 BJ | 7.1 J | - |
| POTASSIUM | 1,880 B | 2,040 B | 1,850 B | 1,850 B |
| SELENIUM | 8.4 BJ | 5.4 | 5.4 | 5.7 |
| SODIUM | 55,700 | 55,000 | 66,500 | 65,000 |
| ZINC | 77.4 J | 95.6 J | 85.6 J | 78.4 |

SY-3DD

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | | |
|---------------------------------------|----------------|-----------|---------------|-----------|
| | NOVEMBER 1993 | | DECEMBER 1993 | |
| | TOTAL | DISSOLVED | TOTAL | DISSOLVED |
| ANTIMONY | 25.0 B | - | - | - |
| BARIUM | - | - | 2.5 B | 11.3 B |
| CHROMIUM | - | - | 9.4 B | - |
| COPPER | R | R | 20.1 B | - |
| IRON | 1,030 | - | 564 | - |
| LEAD | 7.5 | - | 2.7 B | - |
| NICKEL | 14.6 B | - | 34.2 B | 16.4 B |
| POTASSIUM | 869 B | - | 823 B | 1,030 B |
| SILVER | 2.3 B | - | - | - |
| SODIUM | 7,530 | 5,780 | 4,760 B | 4,730 B |
| ZINC | 160 | 72.9 | R | 52.4 |

PK-10D

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | | |
|---------------------------------------|----------------|-----------|---------------|-----------|
| | NOVEMBER 1993 | | DECEMBER 1993 | |
| | TOTAL | DISSOLVED | TOTAL | DISSOLVED |
| ARSENIC | 9.7 B | 9.8 B | 6.3 B | 7.0 B |
| BARIUM | 3.0 B | 2.0 B | 4.2 B | 10.6 B |
| CADMIUM | - | - | 2.0 B | - |
| CHROMIUM | 9.4 B | 3.9 B | 3.5 BJ | 3.5 BJ |
| IRON | R | 112 | 179 | - |
| LEAD | 3.4 J | - | 1.7 BJ | - |
| POTASSIUM | - | 586 B | 853 B | 974 B |
| SELENIUM | - | - | - | 2.2 B |
| SODIUM | 22,900 | 24,600 | 15,900 | 16,600 |
| ZINC | 64.8 J | 51.3 J | 53.6 J | 42.1 |

RB-11D

| PARAMETER (Concentrations in ug/L) | SAMPLING ROUND | | | |
|---------------------------------------|----------------|-----------|---------------|-----------|
| | NOVEMBER 1993 | | DECEMBER 1993 | |
| | TOTAL | DISSOLVED | TOTAL | DISSOLVED |
| BARIUM | 9.4 B | 7.2 B | 6.9 B | 24.5 B |
| CHROMIUM | - | - | 9.8 B | - |
| COPPER | 13.9 B | - | - | - |
| IRON | 975 | - | 958 | - |
| LEAD | 4.6 | - | 3.0 | - |
| NICKEL | - | - | 17.8 B | 12.8 B |
| POTASSIUM | - | - | 787 B | 1,210 B |
| SODIUM | 4,280 B | 4,520 B | 4,220 B | 4,810 B |
| ZINC | 41.2 | 37.2 | R | R |

EXPLANATION

- PK-10I ⊕ OFF-SITE MONITORING WELL INSTALLED BY GERAGHTY & MILLER INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- SY-3 ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERW NORTHEAST
- SY-2R ● ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3D △ ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3 W-4 □ ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- SY-3DD ● EXPLORATORY BORING/DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC. FOR THE OU-2 REMEDIAL INVESTIGATION
- G-13 ● ON-SITE LANDFILL GAS MONITORING WELL
- CS-20 ⊙ OFF-SITE GAS MONITORING WELL, INSTALLED BY GERAGHTY & MILLER, INC. DURING THE OU-2 REMEDIAL INVESTIGATION
- * DESTROYED MONITORING WELL
- ** MONITORING WELL CAN NO LONGER BE SAMPLED DUE TO BEND IN WELL CASING
- *** MONITORING WELL COULD NOT BE LOCATED
- SITE BOUNDARY (FENCE)
- ▨ RECHARGE BASIN
- ▤ LANDFILL AREA
- NOT DETECTED
- B ANALYTE CONCENTRATION IS BETWEEN THE INSTRUMENT DETECTION LIMIT AND CONTRACT REQUIRED LIMIT
- J ESTIMATED VALUE
- R UNUSABLE VALUE
- ug/L MICROGRAMS PER LITER
- TOB-DPW TOWN OF OYSTER BAY-DEPARTMENT OF PUBLIC WORKS



DRAWING CONFIDENTIAL: THIS DRAWING AND ALL INFORMATION CONTAINED THEREON IS AND SHALL REMAIN THE PROPERTY OF GERAGHTY & MILLER, INC. AS AN INSTRUMENT OF PROFESSIONAL SERVICE. THIS INFORMATION SHALL NOT BE USED IN WHOLE OR IN PART WITHOUT THE FULL KNOWLEDGE AND PRIOR WRITTEN CONSENT OF GERAGHTY & MILLER, INC.

SCALE VERIFICATION
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING:
USE TO VERIFY FIGURE REPRODUCTION SCALE

| REV. NO. | DATE | DESCRIPTION | BY | APPR. |
|----------|------|-------------|----|-------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| | |
|------------------------|--------------------|
| PROJECT NO.: NY029008 | FILE NO: 1584 |
| DRAWING: METAL-D | PLOT SIZE: 11"x25" |
| DRAFTED BY: WH CIO | DATE: 12-1-95 |
| CHECKED BY: D SOTILE | DATE: 12-1-95 |
| APPROVED BY: M WOLFERT | DATE: 12-1-95 |

CONCENTRATIONS OF METALS
DETECTED IN SITE MONITORING WELLS SCREENED IN THE
DEEP ZONE OF THE MAGOTHY AQUIFER
SECOND OPERABLE UNIT REMEDIAL INVESTIGATION
SYOSSET LANDFILL, SYOSSET, NEW YORK

APPENDIX A

**JANUARY 20, 1993 LETTER TO
LOCKWOOD, KESSLER & BARTLETT, INC.
REGARDING PROPOSED SCREEN SETTINGS**



January 20, 1993

John P. Lekstutis, P.E.
Lockwood, Kessler & Bartlett
1 Aerial Way
Syosset, New York 11797

Subject: Syosset Landfill - Second Operable Unit Remedial Investigation

Dear Mr. Lekstutis:

Geraghty & Miller, Inc., is writing to propose screen settings for the remaining nine ground-water monitoring wells that will be installed for the subject investigation. The screen settings proposed in this letter were selected in accordance with the Work Plan for this investigation. As you know, the two exploratory borings (SY-3DD [on-site] and PK-10D [off-site]) were recently completed. Ground-water samples were collected at 20 foot intervals from both well borings and were analyzed for leachate indicator parameters (see attached tables). These data were used in conjunction with the lithologic profiles (from geophysical logging [natural gamma] and formation samples) to determine the respective screen settings for the wells that were installed in these two borings. The screen for Well SY-3DD was set at 530 to 540 feet below land surface and the screen for Well PK-10D was set at 489 to 499 feet below land surface. Based on the geologic logs and geophysical logs from both well borings, there are four low-permeability layers that were encountered at both boring locations which we interpret as being continuous. Assuming that the land surface elevations at both well locations are the same, which the topographic map indicates, the lithologic layers slope upward in a northerly direction. This is consistent with the regional hydrogeologic setting in which the bedrock surface and the overlying unconsolidated geologic units slope upward in a northerly direction. It is our opinion that this hydrogeologic setting explains why the bottom of the plume is situated at a higher elevation off-site than on-site even though there is a strong downward vertical hydraulic gradient.

Because of this situation, we recommend that the screens for the deep wells at the other two off-site locations be set at the same depth as off-site Well PK-10D (approximately 490 to 500 feet below land surface). The intermediate depth wells (off-site) should be set at a depth of about 360 feet because it was at this depth that the highest concentrations of leachate parameters were detected in Well Boring PK-10D. Because the highest concentrations of leachate parameters in the on-site Well Boring SY-3DD were detected at 218 feet below land surface, Geraghty & Miller recommends that existing Well SY-6D, which


is screened at a similar depth (195 to 205 feet below land surface), serve as the deep upgradient monitoring well. In this way, upgradient and downgradient water-quality data can be optimally compared. As described in the Work Plan, the shallow wells should be set at a depth of about 150 feet because this is the depth between the first sampling depth where ground water was defined as leachate in Well Boring PK-10D (160 feet) and the sampling depth just above that definition.

The drilling of the intermediate-depth well boring at the Town Park (PK-10I) is scheduled to begin next week. The final screen settings for the remaining eight wells should be determined in consultation with the United States Environmental Protection Agency (USEPA) based on the lithologic profiles from the deep wells at each drilling site. Geraghty & Miller recommends that we meet with the USEPA to discuss the screen settings proposed in this letter and to review the overall project objectives given the new information developed.


Please call us if you have any questions.

Sincerely,

GERAGHTY & MILLER, INC.



Vincent J. Glasser
Senior Scientist/Project Manager



Michael F. Wolfert
Vice President/Project Director

cc: R.W. Lenz, P.E.

VJG/MFW:bjm

NY029-04lets120.let

Table 1. Summary of Field Measurements of Leachate Parameters of Ground-Water Samples Collected During Drilling of Exploratory Boring PK-10, Syosset Landfill, Syosset, New York.

| Sample Depth (feet) | Date Sampled Action Level (a) | Primary Leachate Parameters | | | Secondary Leachate Parameters | | | |
|------------------------|-------------------------------------|-----------------------------|------------------------------|-------------------------|-----------------------------------|------------|------------------------|----------------------------------|
| | | Alkalinity mg/L 11 | Total Hardness mg/L 43 | Ammonia mg/L 0.12 | Conductivity (umhos/cm) 217 | pH 5.75 | Chloride mg/L 19 | Temperature (Celcius) 14.5 |
| PK-10D | | | | | | | | |
| 120 | 12/15/92 | (b) | (b) | (b) | (b) | (b) | (b) | (b) |
| 140 | 12/15/92 | 5.5 | 59 | <0.06 | 240 | 7.45 | 14 | 15 |
| 160 | 12/15/92 | 13 | 59 | <0.06 | 240 | 7.25 | 17 | 15 |
| 180 | 12/15/92 | 37 | 39 | <0.06 | 180 | 7.15 | 14 | 15 |
| 200 | 12/15/92 | 39 | 92 | <0.06 | 340 | 5.25 | 18 | 15 |
| 220 | 12/15/92 | (b) | (b) | (b) | (b) | (b) | (b) | (b) |
| 240 | 12/15/92 | 44 | 78 | <0.06 | 400 | 5.45 | 42 | 15 |
| 260 | 12/16/92 | (c) | (c) | (c) | (c) | (c) | (c) | 15 |
| 280 | 12/16/92 | 37 | 93 | 0.17 | 500 | 7.55 | 47 | 15 |
| 280(e) | 12/16/92 | 33.7 | 92.2 | 0.65 | NA | NA | 46.8 | NA |
| 300 | 12/16/92 | 18 | 63 | 0.08 | 300 | 7.10 | 26 | 15 |
| 300 (d) | 12/16/92 | 16 | 58 | 0.07 | 290 | 7.15 | 23 | 15 |
| 300(e) | 12/16/92 | 15 | 58.6 | 0.10 | NA | NA | 23.3 | NA |
| 320 | 12/16/92 | 66 | 47 | 6.2 | 750 | 7.65 | 68 | 15 |
| 340 | 12/16/92 | 250 | 220 | 19 | 1,670 | 7.45 | (e) | 15 |
| 360 | 12/17/92 | 370 | 310 | 24 | 2,000 | 7.55 | 360 | 15 |
| 380 | 12/18/92 | 220 | 278 | 19 | 2,100 | 7.90 | 439 | 15 |
| 400 | 12/18/92 | 150 | 210 | 9.9 | 1,600 | 7.70 | 350 | 15 |
| 420 | 12/21/92 | 46 | 120 | 8.6 | 720 | 7.15 | 140 | 15 |
| 440 | 12/21/92 | 6.6 | 75 | <0.06 | 400 | 6.25 | 76 | 15 |

Table 1. Summary of Field Measurements of Leachate Parameters of Ground-Water Samples Collected During Drilling of Exploratory Boring PK-10, Syosset Landfill, Syosset, New York.

| Sample Depth (feet) | Date Sampled Action Level (a) | Primary Leachate Parameters | | | Secondary Leachate Parameters | | | |
|------------------------|-------------------------------------|-----------------------------|------------------------------|-------------------------|-----------------------------------|------------|------------------------|----------------------------------|
| | | Alkalinity mg/L 11 | Total Hardness mg/L 43 | Ammonia mg/L 0.12 | Conductivity (umhos/cm) 217 | pH 5.75 | Chloride mg/L 19 | Temperature (Celsius) 14.5 |
| PK-10D | | | | | | | | |
| 460 | 12/22/92 | 6.8 | 160 | 0.08 | 920 | 7.10 | 160 | 15 |
| 479 | 12/28/92 | 6.1 | 7.6 | 0.07 | 50.6 | 6.80 | 11.2 | 15 |
| 479(e) | 12/28/92 | <1.0 | 62.2 | 0.09 | NA | NA | 7.53 | NA |
| 499 | 12/28/92 | 9.1 | 16 | 0.07 | 74 | 7.0 | 13 | 15 |
| 499(e) | 12/28/92 | 9.9 | 12.8 | 0.51 | NA | NA | 14.5 | NA |
| Hydrant Water | 12/17/92 | 31 | 13 | <0.06 | 160 | 8.20 | 8.7 | 15 |

(a) Based on statistical analysis of background water-quality data.

(b) Sample could not be collected due to the presence of a dry clay layer at the sampling depth.

(c) Sample was collected but almost all of it was particulate matter (clay particles).

(d) Field Replicate.

(e) Replicate sample analyzed by IEA, Inc., Monroe, Connecticut.

(f) Not enough sample collected for analyses.

mg/L Milligrams per liter.

umhos/cm Micromhos per centimeter.

Table 3. Summary of Field Measurements of Leachate Parameters of Ground-Water Samples Collected During Drilling of Exploratory Boring SY-3DD, Syosset Landfill, Syosset, New York.

| Sample Depth (feet) | Date Sampled Action Level (a) | Primary Leachate Parameters | | | Secondary Leachate Parameters | | | Temperature (Celsius) |
|------------------------|-------------------------------------|-----------------------------|------------------------|-----------------|-------------------------------|------|------------------|--------------------------|
| | | Alkalinity mg/L | Total Hardness mg/L | Ammonia mg/L | Conductivity (umhos/cm) | pH | Chloride mg/L | |
| | | 11 | 43 | 0.12 | 217 | 5.75 | 19 | |
| <u>Well SY-3DD</u> | | | | | | | | |
| 118 | 11/5/92 | (c) | 39 | 23 | 280 | 5.05 | 28 | 15 |
| 137 | 11/5/92 | 190 | 140 | 21 | 640 | 6.35 | 36 | 15 |
| 158 | 11/6/92 | 390 | 170 | 71 | 960 | 6.35 | 54 | 15 |
| 179 | 11/6/92 | 840 | 380 | 160 | 1,600 | 6.95 | 120 | 15 |
| 192 | 11/6/92 | 630 | 280 | 120 | 1,200 | 7.35 | 26 | 15 |
| 218 | 11/6/92 | 910 | 300 | 420 | 2,000 | 7.85 | 22 | 15 |
| 239 | 11/9/92 | 890 | 400 | 150 | 2,400 | 7.35 | 100 | 15 |
| 256 | 11/9/92 | 540 | 330 | 200 | 1,900 | 7.05 | 180 | 15 |
| 279 | 11/9/92 | 440 | 310 | 180 | 1,900 | 7.10 | 240 | 15 |
| 299 | 11/9/92 | 500 | 280 | 160 | 1,700 | 6.10 | 270 | 15 |
| 318 | 11/10/92 | 430 | 270 | 220 | 2,300 | 6.55 | 490 | 15 |
| 335 | 11/17/92 | 360 | 200 | (b) | 2,200 | 7.87 | 390 | 15 |
| 355 | 11/17/92 | 31 | 220 | (b) | 1,200 | 7.90 | 190 | 15 |
| 355 (d) | 11/17/92 | 31.7 | 211 | 11.4 | NA | NA | 200 | NA |
| 375 | 11/17/92 | 38 | (c) | (b) | 1,600 | 4.80 | (c) | 15 |
| 375 (d) | 11/17/92 | 41.6 | 231 | 19.1 | NA | NA | 271 | NA |
| 395 | 11/17/92 | 70 | 210 | (b) | 1,200 | 7.20 | 230 | 15 |
| 395 (d) | 11/17/92 | 76.4 | 174 | 21.0 | NA | NA | 222 | NA |

See page 2 for footnotes.

Table 3. Summary of Field Measurements of Leachate Parameters of Ground-Water Samples Collected During Drilling of Exploratory Boring SY-3DD, Syosset Landfill, Syosset, New York.

| Sample Depth (feet) | Date Sampled | Primary Leachate Parameters | | | Secondary Leachate Parameters | | | |
|----------------------------|------------------|-----------------------------|------------------------|-----------------|-------------------------------|------|------------------|--------------------------|
| | Action Level (a) | Alkalinity mg/L | Total Hardness mg/L | Ammonia mg/L | Conductivity (umhos/cm) | pH | Chloride mg/L | Temperature (Celsius) |
| | | 11 | 43 | 0.12 | 217 | 5.75 | 19 | 14.5 |
| <u>Well SY-3DD (Cont.)</u> | | | | | | | | |
| 417 | 11/18/92 | 48 | 250 | 5.0 | 1,500 | 7.80 | 270 | 15 |
| 437 | 11/18/92 | 52 | 240 | 4.0 | 1,200 | 7.70 | 220 | 15 |
| 457 | 11/18/92 | 80 | 240 | 2.4 | 1,100 | 7.70 | 180 | 15 |
| 480 | 11/25/92 | 66 | 180 | 2.6 | 920 | 7.70 | 150 | 15 |
| 500 | 11/30/92 | 15 | 23 | 0.41 | 56 | 7.40 | 15 | 15 |
| 520 | 12/1/92 | 9.7 | 9.0 | 0.29 | 58 | 7.20 | 4.9 | 15 |
| 520 (e) | 12/1/92 | 12 | 6.9 | <0.05 | NA | NA | 6 | NA |
| 520** | 12/1/92 | 10 | 8.1 | 0.16 | 57 | 7.20 | 4.8 | 15 |
| 540 | 12/1/92 | 13 | 12 | <0.06 | 52 | 6.80 | 5.2 | 15 |
| Hydrant Water | 11/6/92 | 39 | 47 | 30 | 200 | 4.90 | 16 | 15 |
| Hydrant Water | 12/1/92 | 45 | 33 | 0.14 | 180 | 8.70 | 15 | 15 |

mg/L Milligrams per liter.

umhos/cm Micromhos per centimeter.

(a) Based on statistical analysis of background water-quality data.

(b) Probe malfunction.

(c) Not enough sample collected for all analyses.

(d) Replicate sample analyzed by IEA, Inc., Monroe, Connecticut.

(e) Replicate sample analyzed by EcoTest Laboratories, Inc., North Babylon, New York.

** Field replicate.

NA Not analyzed.

APPENDIX B

**MARCH 11, 1993 LETTER TO
LOCKWOOD, KESSLER & BARTLETT, INC.
REGARDING COLLAPSE OF WELL BORING PK-10I**



March 11, 1993

VIA TELECOPIER

John P. Lekstutis, P.E.
Lockwood, Kessler, & Bartlett, Inc.
1 Aerial Way
Syosset, New York 11791

Subject: Second Operable Unit Remedial Investigation, Syosset Landfill, Syosset,
New York

Dear John:

Geraghty & Miller, Inc. has prepared this letter to provide Lockwood, Kessler, & Bartlett, Inc. (LKB) with recommendations to resolve problems encountered during the drilling of Well Boring PK-10I. As you are aware, the rapid loss of circulation of drilling mud at the 328-foot depth on Friday, February 26, 1992, led to the collapse of Well Boring PK-10I up to several feet below the bottom of the 10-inch diameter surface casing (approximately 138 feet below land surface). This loss of drilling mud is probably due to loose, unstable formation material created during the drilling of Well PK-10D, which is located about 12 feet away from Well Boring PK-10I. The formation instability was likely caused by the removal of sand heave inside the drill casings during drilling of PK-10D which resulted in more material being removed from the boring than the collective volume of the casings installed. This condition precludes completion of the intermediate depth well (PK-10I) at this location.

In order to expedite continuation and completion of the well installation program, Geraghty & Miller recommends that the shallow well, PK-10S, be installed in the collapsed PK-10I well boring. This shallow well will only have to be drilled an additional 12 feet below the existing (open) 10-inch diameter steel casing which is set at a depth of 138 feet. PK-10S is proposed to be installed in the following manner: the 4-inch diameter well should be set in a 6-inch diameter steel casing, which will be lowered inside the 10-inch diameter surface casing and driven to the completion depth (150 feet) using a cable tool rig. The well will be gravel-packed by adding the gravel in the annulus between the well casing and 6-inch diameter casing as the 6-inch diameter casing is pulled back. The gravel pack will extend to land surface inside the 10-inch diameter casing to allow for potential settling. To prevent the well from settling in the boring with the gravel pack, it will be centered and secured to the 10-inch diameter casing at land surface. A large well seal will be fabricated by Delta Well & Pump Company, Inc. (Delta) which will be slightly recessed inside the 10-inch diameter surface casing. A 2-inch diameter pipe nipple with a screw-on cap will be set in the well seal to allow for measuring the depth to the gravel pack and for adding additional gravel, as needed. After the gravel level has stabilized, a permanent bentonite seal will be emplaced above the gravel pack and extending to land surface. The well head will be completed by welding a flush mount, bolt-down manhole cover directly to the 10-inch diameter surface casing.


Delta proposes drilling a replacement PK-10I well boring at a new location about 100 feet south of the original location. Geraghty & Miller believes that the disturbed formation from the drilling of PK-10D is unlikely to be encountered at this distance, however, this cannot be known with certainty until this new boring is actually drilled. This well boring and well will be drilled and installed according to the Site Operations Plan (SOP) except for the surface casing. Delta's subcontractor, Catoh, Inc., who installed the two exploratory borings and the surface casings for the planned modified mud rotary borings, is no longer at the site (they demobilized in December 1992). Delta has therefore proposed installing the 10-inch diameter surface casing for Well PK-10I using a combination of the hollow-stem auger (auger) and cable tool drilling methods. The auger rig will use large diameter (12-inch inside diameter) auger flytes to drill to the maximum depth possible (approximately 50 to 60 feet), and the cable tool rig will be used to install the 10-inch diameter casing inside the augers and drive this casing to about 130 feet below land surface. Geraghty & Miller finds this method to be acceptable and recommends its use. The installation of the surface casing is expected to take about 3 or 4 days. The well boring will then be completed in the prescribed manner using the modified mud-rotary drilling method.

As part of their effort to expedite the drilling program, Delta plans on subcontracting another firm (United Well and Pump Corporation, Bohemia, New York) to do the cable tool work. The driller from this firm has not completed the 40-hour Occupational Safety and Health Administration (OSHA) training course, however, because the work will be undertaken in uncontaminated soil, Geraghty & Miller believes that the requirement for this training is not applicable to this specific activity. As such, Geraghty & Miller recommends that the U.S. Environmental Protection Agency (USEPA) be asked to waive the OSHA training requirements for this activity.


Please call us if you have any questions.

Sincerely,

GERAGHTY & MILLER, INC.



Vincent J. Glasser
Senior Scientist/Project Manager



Michael F. Wolfert
Vice President/Project Director

cc: R.W. Lenz, P.E.

VJG/MFW:bjm

NY029-0462a311.let

APPENDIX C
SAMPLE/CORE LOGS



SAMPLE/CORE LOG

BORING/WELL: SY3DD

PROJECT NO: NY02908

PAGE: 1 of 5

SITE
LOCATION: Syosset Landfill -
near Gordon DriveDRILLING
STARTED: 11/03/92DRILLING
COMPLETED: 12/01/92TOTAL DEPTH
DRILLED: 540HOLE
DIAMETER: 16/10/8/6 in.TYPE OF SAMPLE/
CORING DEVICE: CycloneLENGTH & DIAMETER
OF CORING DEVICE: --SAMPLING
INTERVAL: Continuous out of
CycloneLAND-SURFACE
ELEVATION: --{ } SURVEYED
{ } ESTIMATED DATUM: --DRILLING
FLUID USED: WaterDRILLING
METHOD: Barber (air rotary)DRILLING
CONTRACTOR: Catch

DRILLER: J. McAdden

HELPER: M. Jackowski

PREPARED BY: Sarah Zagaja

HAMMER WEIGHT: --

HAMMER DROP: --

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|----|------------------------|-----------------------------------|---|
| FROM | TO | | | |
| 0 | 3 | -- | -- | Top soil. |
| 3 | 8 | | | Sand, medium to coarse, and gravel, fine, some medium, brown, dry. |
| 8 | 14 | | | Sand, medium, some coarse, trace gravel, fine, brown, dry. |
| | 18 | | | Sand, medium, some coarse, and gravel, fine, some coarse, brown, dry. |
| 18 | 28 | | | Sand, medium to coarse, some gravel, fine, trace medium, brown, dry. |
| 28 | 34 | | | Sand, medium to coarse, some gravel, fine, trace medium, brown, dry. |
| 34 | 37 | | | Sand, medium, some coarse, trace gravel, fine, brown, dry. |
| 37 | 42 | | | Sand, medium, some coarse, trace gravel, fine, brown, dry. |
| 42 | 49 | | | Sand, medium, some fine, some coarse, trace gravel, fine, brown, dry. |
| 49 | 57 | | | Sand, medium, trace fine, some coarse, some gravel, fine, brown, dry. |
| 57 | 68 | | | Sand, medium, some fine, trace coarse, brown, dry. |
| 68 | 74 | | | Sand, medium, some fine, trace coarse, trace gravel, fine, brown, dry. |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|-----|------------------------|-----------------------------------|--|
| FROM | TO | | | |
| 74 | 77 | -- | -- | Sand, medium, some fine, some coarse, some gravel, fine, brown, dry. |
| 77 | 85 | | | Sand, medium to coarse, trace fine, trace gravel, fine, brown, dry. |
| 85 | 97 | | | Sand, medium to coarse, and gravel, fine to medium, brown, dry. |
| 97 | 110 | | | Gravel, fine to medium, some coarse, and sand, medium to coarse, brown. |
| 110 | 114 | | | Sand, medium to coarse, trace fine, some gravel, fine to medium, brown. |
| 114 | 117 | | | Sand, fine to medium, some coarse, trace fine gravel, light brown/grey. |
| 118 | 125 | | | Sand, fine to medium, some coarse, trace fine gravel, light brown/grey. |
| 125 | 137 | | | Sand, fine, micaceous, some silt, some clay, grey. |
| 137 | 147 | | | Sand, fine, some medium, trace clay, micaceous, grey. |
| 147 | 158 | | | Sand, fine to medium, trace clay, brown. |
| 158 | 170 | | | Sand, fine to medium, trace clay, brown. |
| 170 | 179 | | | Sand, fine to medium, trace clay, brown. |
| 179 | 188 | | | Sand, fine, some medium, micaceous, orange/ brown. |
| 188 | 197 | | | Sand, fine, trace medium, trace silt, micaceous, trace clay, orange/brown, some iron pyrite concretions are present. |
| 197 | 212 | | | Sand, fine, trace medium, some silt, trace clay, micaceous, orange/brown. |
| 212 | 218 | | | Sand, fine to medium, trace silt, micaceous, orange/brown. |
| 218 | 232 | | | Sand, fine to medium, trace silt, micaceous, orange/brown, some iron concretions. |

BORING/WELL: SY3DD

PREPARED BY: S. Zagaja

PAGE: 3 of 5

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|-----|------------------------|-----------------------------------|---|
| FROM | TO | | | |
| 232 | 239 | -- | -- | Sand, fine, trace medium, trace silt, some clay, micaceous. Sand is orange/brown. Clay is light grey. Probably in stringers. |
| 239 | 256 | | | Sand, fine, trace medium, trace silt, trace clay, some iron concentrations, orange/brown. |
| 239 | 256 | | | |
| 256 | 261 | | | Sand, fine, trace medium, some silt, trace clay, some iron concentrations, orange/brown. |
| 256 | 261 | | | |
| 261 | 278 | | | Sand, fine, trace silt, some clay-in lenses, sand is brown/orange, clay and silt are brown/grey. There was a substantial clay layer at approximately 261 feet. |
| 261 | 278 | | | |
| 278 | 282 | | | Sand, fine, some silt, trace clay, brown/grey. |
| 282 | 283 | | | Clay, grey, trace silt. |
| 283 | 299 | | | Sand, fine, some silt, some clay, in lenses, grey, micaceous. |
| 299 | 316 | | | Sand, fine, some medium, and silt, some clay, brown/ grey. |
| 299 | 316 | | | |
| 316 | 318 | | | Sand, fine to medium, greyish brown, with iron concretions. |
| 316 | 318 | | | |
| 318 | 325 | | | Sand, fine to medium, greyish brown, with iron concretions. |
| 318 | 325 | | | |
| 325 | 332 | | | Sand, fine, some silt, grey. |
| 332 | 335 | | | Sand, fine, and silt, brownish/grey |
| 335 | 344 | | | Sand, fine, and silt, light grey. |
| 344 | 348 | | | Sand, fine, some silt, brownish grey, some iron concretions. |
| 344 | 348 | | | |
| 348 | 355 | | | Sand, fine, some silt, trace clay, brownish grey. |
| 355 | 365 | | | Sand, fine, some silt, some clay, brownish grey, micaceous. |
| 355 | 365 | | | |
| 365 | 375 | | | Sand, fine, some medium, some silt, trace clay, light grey, micaceous. |
| 365 | 375 | | | |
| 375 | 380 | | | Sand, fine, some medium, some silt, trace clay, light grey, micaceous. |
| 375 | 380 | | | |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|-----|------------------------|-----------------------------------|---|
| FROM | TO | | | |
| 380 | 385 | -- | -- | Sand, fine, some medium, some silt, trace clay, light grey, micaceous, orange. |
| 385 | 395 | | | Sand, fine to medium, trace coarse, trace silt, trace clay, with iron concretions, orange/red, micaceous. |
| 395 | 410 | | | Sand, fine to medium, trace coarse, trace silt, trace clay, orange/red, micaceous, iron concretions. |
| 410 | 417 | | | Sand, fine, trace medium, some silt, orangeish brown, micaceous. |
| 417 | 427 | | | Sand, fine, trace medium, some silt, orangeish brown, micaceous. |
| 427 | 430 | | | Sand, fine, some medium, trace silt, micaceous, orangeish brown, with iron concretions. |
| 430 | 437 | | | Sand, fine, some medium, some silt, trace clay, brown, getting greyer with depth, micaceous, some iron concretions. |
| 437 | 457 | | | Sand, fine, trace medium, some silt, trace clay, grey-grading into brown with depth, micaceous. |
| 457 | 462 | | | Sand, fine, trace medium, trace coarse, some silt, brown, micaceous. |
| 462 | 470 | | | Sand, fine, trace medium, trace silt, light brown, micaceous. |
| 470 | 480 | | | Sand, fine, some medium, trace silt, light brown, micaceous. |
| 480 | 485 | | | Sand, fine, some medium, trace silt, dark grey with iron concretions. |
| 485 | 488 | | | Sand, fine, some medium, trace silt, light grey with iron concretions. |
| 488 | 493 | | | Clay and sand, fine, some silt, clay is in competent laminations, light grey. |
| 493 | 500 | | | Sand, fine, some silt, some clay in laminations, light grey to brown, some iron concretions. |
| 500 | 503 | | | Sand, fine, some silt, some clay in laminations, light grey to brown, some iron concretions. |

PREPARED BY: S. Zagaja

PAGE: 5 of 5

[illegible]

SAMPLE/CORE LOG

Syosset Landfill

BORING/WELL: PK-10D PROJECT NO: NY02908 PAGE: 1 of 5

SITE LOCATION: Park on Syosset Circle DRILLING STARTED: 10/28/92 DRILLING COMPLETED: 12/30/92

TOTAL DEPTH DRILLED: 500 ft. HOLE DIAMETER: 16/10/8 in. TYPE OF SAMPLE/CORING DEVICE: Cyclone

LENGTH & DIAMETER OF CORING DEVICE: -- SAMPLING INTERVAL: Continuous out of Cyclone

LAND-SURFACE ELEVATION: { } SURVEYED { } ESTIMATED DATUM: --

DRILLING FLUID USED: Water DRILLING METHOD: Barber (air rotary)

DRILLING CONTRACTOR: Catch DRILLER: J. McAdden HELPER: M. Jackowski

PREPARED BY: Sarah Zagaja HAMMER WEIGHT: -- HAMMER DROP: --

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|-----|------------------------|-----------------------------------|---|
| FROM | TO | | | |
| 0 | 5 | -- | -- | Top soil, sand and gravel, brown. |
| 5 | 10 | | | Sand, medium to coarse, some gravel, fine to medium, trace coarse, light brown, dry. |
| 10 | 16 | | | Gravel, fine to coarse, and sand, medium to coarse, light brown, dry. |
| 16 | 26 | | | Sand, medium to coarse, trace gravel, fine, light brown, dry. |
| 26 | 37 | | | Sand, medium to coarse, some gravel, fine to medium, light brown, dry. |
| 37 | 44 | | | Sand, medium to coarse, some gravel, fine to medium, light brown, dry. |
| 44 | 54 | | | Sand, medium to coarse, trace gravel, fine to medium, light brown, dry. |
| 54 | 58 | | | Sand, medium to coarse, and gravel, fine to medium, some coarse, light brown, dry. |
| 58 | 68 | | | Sand, medium to coarse, and gravel, fine to medium, some coarse, light brown, dry. |
| 68 | 76 | | | Sand, medium to coarse, some gravel, fine to medium, trace coarse, light brown, dry. |
| 76 | 96 | | | Sand, medium to coarse, some fine gravel, trace medium, light brown, dry. |
| 96 | 105 | | | Sand, medium to coarse, and gravel, fine, some medium, brown, dry. |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|-------|------------------------|-----------------------------------|---|
| FROM | TO | | | |
| 105 | 114 | -- | -- | Sand, coarse, some medium, and gravel, fine to medium, brown, dry. |
| 114 | 117 | | | Gravel, fine to medium, some coarse, trace fine cobbles, some sand, medium to coarse, brown, dry. |
| 117 | 119 | | | Sand, fine to medium, some silt, trace clay, brown/grey, moist. |
| 119 | 133 | | | Clay and sand, fine, some silt, slightly moist, light grey. |
| 133 | 137.5 | | | Sand, fine, some clay, some silt, some fine gravel, slightly moist, light grey. |
| 137.5 | 140 | | | Sand, fine, and clay, some silt, clay layers are light grey, sand and silt is light brown. Clay is micaceous. |
| 140 | 146 | | | Sand, fine to medium, some silt, trace clay, trace gravel, light brown to rusty brown. |
| 146 | 152 | | | Sand, fine to medium, some silt, trace gravel, fine to medium brown. |
| 152 | 160 | | | Sand, fine to medium, micaceous, brown. |
| 160 | 165 | | | Sand, fine to medium, micaceous, brown. |
| 165 | 172 | | | Sand, fine to medium, some silt, brown, micaceous. |
| 172 | 175 | | | Sand, fine to medium, some silt, brown, micaceous. |
| 175 | 180 | | | Sand, fine, some medium, trace silt, brown, micaceous. |
| 180 | 190 | | | Sand, fine, some medium, trace silt, brown, micaceous, with some iron concretions. |
| 190 | 197 | | | Sand, fine to medium, trace silt, brown, micaceous, with iron concretions. |
| 197 | 200 | | | Sand, fine, trace medium, some silt, some clay-in layers, light brown to light grey, micaceous, iron concretions. |
| 200 | 206 | | | Sand, fine, trace medium, some silt, some clay, sand is light brown, clay is grey, iron concretions abundant. |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|-----|------------------------|-----------------------------------|---|
| FROM | TO | | | |
| 206 | 211 | -- | -- | Sand, fine, some silt, trace clay, with concretions. |
| 211 | 220 | | | Clay, some silt, trace fine sand, sand and silt is light brown, clay is light grey to dark grey. Iron concretions abundant. |
| 220 | 228 | | | Silt, some clay, trace fine sand, light brown to light grey, micaceous, few iron concretions. |
| 228 | 233 | | | Silt, some clay, trace fine sand, light brown to light grey, micaceous, few iron concretions. |
| 233 | 240 | | | Sand, fine, and silt, trace clay, light brown, micaceous, abundant iron concretions. |
| 240 | 243 | | | Sand, fine, and silt, trace clay, light brown, micaceous, abundant iron concentrations. |
| 243 | 254 | | | Sand, fine, some medium, some silt, light brown. |
| 254 | 257 | | | Sand, fine, and clay, trace silt, rusty brown, iron concretions. |
| 257 | 260 | | | Clay, trace sand, fine, trace silt, light brown to grey, micaceous. |
| 260 | 263 | | | Clay, trace sand, fine, trace silt, light brown to grey, micaceous. |
| 263 | 272 | | | Sand, fine, and silt, rusty brown, iron concretions. |
| 272 | 280 | | | Sand, fine to medium, some silt, brown to rusty brown, some iron concretions. |
| 280 | 285 | | | Sand, fine to medium, trace silt, brown to rusty brown. |
| 285 | 295 | | | Sand, fine, some medium, some silt, brown. |
| 295 | 300 | | | Sand, medium, some fine, trace silt, light brown. |
| 300 | 315 | | | Sand, medium, some fine, trace silt, light brown. |
| 315 | 320 | | | Sand, fine, some medium, some silt, trace clay, light brown to grey, some iron concretions. |
| 320 | 326 | | | Sand, fine, some medium, some silt, trace clay, light brown to grey, some iron concretions. |
| 326 | 332 | | | Sand, fine, trace medium, and silt, trace clay, light grey, micaceous. |
| 2 | 336 | | | Sand, fine to medium, some silt, light grey/brown, micaceous. |

BORING/WELL: PK-10

PREPARED BY: S. Zagaja

PAGE: 4 of 5

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECOVERY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION |
|--|-----|--------------------------|-----------------------------------|--|
| FROM | TO | | | |
| 336 | 340 | -- | -- | Sand, fine, trace medium, some silt, trace clay, light grey, micaceous. |
| 340 | 345 | | | Sand, fine, and silt, light brownish/grey. |
| 345 | 354 | | | Sand, fine, some medium, some silt, light brown turning greyer with depth. |
| 354 | 360 | | | Sand, fine, some medium, some silt, grey. |
| 360 | 370 | | | Sand, fine, some medium, some silt, grey. |
| 370 | 376 | | | Sand, fine to medium, trace coarse, trace silt, light grey, some iron concretions. |
| 376 | 380 | | | Sand, medium, some fine, some coarse, trace silt, light grey/brown. |
| 380 | 385 | | | Sand, medium, some fine, some coarse, trace silt, light grey/brown. |
| 385 | 392 | | | Sand, medium, some fine, some coarse, trace silt, brown, micaceous. |
| 392 | 394 | | | Sand, medium, some fine, trace coarse, trace silt, brown, micaceous, grading to brownish red. |
| 394 | 400 | | | Sand, medium, trace fine, rusty brown, micaceous, some iron concretions. |
| 400 | 405 | | | Sand, medium, trace coarse, trace fine, brown, micaceous. |
| 405 | 416 | | | Sand, medium, trace coarse, trace fine, brown to dark brown. |
| 416 | 420 | | | Sand, fine, trace medium, some silt, light brown to grey, micaceous. |
| 420 | 428 | | | Sand, fine, trace medium, some silt, light brown to grey, micaceous. |
| 428 | 440 | | | Sand, fine, and silt, trace clay, micaceous, light grey. |
| 440 | 444 | | | Sand, fine, and silt, trace clay, micaceous, light grey. |
| 444 | 452 | | | Sand, medium, some fine, trace coarse, light brown, micaceous, iron concretions. |
| 452 | 460 | | | Sand, medium, and fine, some silt, light grey, micaceous. |

PAGE: 5 of 5

[illegible]

SAMPLE/CORE LOG

BORING/WELL: RB-11 PROJECT NO: NY0029008 LKB/Syosset Landfill PAGE: 1 of 4
 SITE Syosset Recharge Basin DRILLING DRILLING
 LOCATION: on Belmont Circle STARTED: 8/4/93 COMPLETED: 9/26/93
 TOTAL DEPTH HOLE TYPE OF SAMPLE/ Barber - cuttings
 DRILLED: 509 ft DIAMETER: 10/8 in CORING DEVICE: Mud/reverse - split-
 LENGTH & DIAMETER SAMPLING continuous/
 OF CORING DEVICE: 2 ft x 2 inches INTERVAL: every 20 ft
 LAND-SURFACE { } SURVEYED
 ELEVATION: { } ESTIMATED DATUM:
 DRILLING DRILLING
 FLUID USED: water/mud/water METHOD: Barber/mud rotary/reverse rotary
 DRILLING
 CONTRACTOR: Delta Well & Pump Co. DRILLER: John McAdden/
 Joe Guggino HELPER: Mark/Rich/Brian
 PREPARED BY: Sarah Zagaja/
 Mike Breault HAMMER WEIGHT: 175 HAMMER DROP: 24 inches

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION | DRILLING METHOD |
|--|----|------------------------|-----------------------------------|---|--------------------|
| FROM | TO | | | | |
| 0 | 5 | -- | -- | Top soil, dark brown, dry. | Barber |
| 5 | 13 | -- | -- | Sand, fine to coarse, and gravel, fine to coarse, light brown, dry. | Barber |
| 13 | 17 | -- | -- | Sand, fine to coarse, and gravel, fine to coarse, light brown, dry. | Barber |
| 17 | 26 | -- | -- | Sand, medium to coarse, some gravel, fine to medium, light brown, dry. | Barber |
| 26 | 33 | -- | -- | Gravel, fine to coarse, some sand, medium to coarse, light brown, dry. | Barber |
| 33 | 38 | -- | -- | Sand, medium to coarse, some gravel, fine to medium, trace coarse, light brown, dry. | Barber |
| 38 | 48 | -- | -- | Sand, medium to coarse, trace fine, some gravel, fine to medium, light brown, dry. | Barber |
| 48 | 54 | -- | -- | Sand, medium to coarse, trace gravel, fine, light brown. | Barber |
| 54 | 59 | -- | -- | Sand, medium to coarse, some fine, some gravel, fine to medium, light brown, dry. | Barber |
| 59 | 63 | -- | -- | Sand, medium, some fine, trace coarse, light brown, dry. | Barber |
| 63 | 75 | -- | -- | Sand, medium to coarse, trace fine, some gravel, fine to medium. | Barber |
| 75 | 86 | -- | -- | Sand, medium to coarse, some fine, trace gravel, fine, dry. | Barber |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION | DRILLING METHOD |
|--|-----|------------------------|-----------------------------------|--|--------------------|
| FROM | TO | | | | |
| 86 | 96 | -- | -- | Sand, fine to medium, light brown, slightly moist. | Barber |
| 96 | 106 | -- | -- | Sand, fine to medium, light brown, slightly moist. | Barber |
| 106 | 113 | -- | -- | Sand, fine to medium, trace clay, light grey to brown, moist. | Barber |
| 113 | 118 | -- | -- | Sand, fine, some clay, trace medium sand, trace silt, light brown to grey, clay is in stringers, moist. Magothy at approximately 114-115 ft bgs. | Barber |
| 139 | 141 | .5 | 16-21- 36-42 | Sand, fine, some silt, trace clay, thin layers (1/4" - 1/2") of light grey, rusty orange, and light brown, wet, poorly sorted, moderately compact. | Mud Rotary |
| 159 | 161 | 1 | 21-32- 39-46 | Sand, fine, some medium in top portion of spoon grading downward to sand, fine, some silt, some iron oxide aggregates, wet, moderately sorted, compact, brown, rusty brown, and light grey layers. | Mud Rotary |
| 179 | 181 | 2 | 27-37- 28-46 | Sand, fine, some silt (2" layers contain some clay), light brown to rusty brown, trace grey layers, wet, moderately compact. | Mud Rotary |
| 199 | 201 | .5 | 29-33- 38-47 | Sand, fine, trace medium, trace silt, light brown, with some grey and some rusty brown layers, wet, compact, moderately sorted. | Mud Rotary |
| 219 | 221 | .75 | 33-38- 44-42 | Sand, fine, trace silt, trace clay grading with depth to sand, fine, trace medium light grey to tan, minimal iron staining, wet, moderately sorted, compact. | Mud Rotary |
| 239 | 241 | 1 | 38-41- 46-51 | Sand, fine, trace silt, light grey with minimal iron stained layers, wet, poorly sorted, very compact, micaceous. | Mud Rotary |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION | DRILLING METHOD |
|--|-----|------------------------|-----------------------------------|---|--------------------|
| FROM | TO | | | | |
| 259 | 261 | 1 | 46-39- | Sand, fine, trace silt, light grey to | Mud Rotary |
| | | | 48-55 | light brown, wet, micaceous, minimal | |
| | | | | iron staining. | |
| 279 | 281 | 1.5 | 35-32- | Sand, fine, some silt with two 2-inch | Mud Rotary |
| | | | 46-49 | layers which contain some clay, light | |
| | | | | grey, micaceous, very compact, wet. | |
| 299 | 301 | .75 | 40-45- | Sand, medium, some fine, light greyish | Mud Rotary |
| | | | 47-56 | tan, some red layers, very compact, wet, | |
| | | | | poorly sorted. | |
| 319 | 321 | .5 | 35-38- | Clay, trace silt, trace fine sand, well | Mud Rotary |
| | | | 43-58 | sorted, bottom 1 inch is sand, medium, | |
| | | | | some fine, light greyish brown. Clay | |
| | | | | portion is extremely compact, contains | |
| | | | | fragments of lignite. | |
| 339 | 341 | 1 | 37-30- | Sand, fine, trace medium, trace silt, | Mud Rotary |
| | | | 35-46 | light grey, micaceous, compact. | |
| 359 | 361 | 1 | 33-39- | Sand, fine, some medium, light grey, | Mud Rotary |
| | | | 38-49 | micaceous, compact. | |
| 379 | 381 | .5 | 30-39- | Sand, medium, trace fine, micaceous, | Mud Rotary |
| | | | 48-56 | light grey, compact. | |
| 399 | 401 | 1 | 43-38- | Sand, medium, trace fine, greyish-pink, | Mud Rotary |
| | | | 41-52 | compact, poorly sorted. | |
| 419 | 421 | 2 | 35-23- | Clay, trace silt, light brownish grey, | Mud Rotary |
| | | | 28-26 | very competent, moist, slightly mottled. | |
| 439 | 441 | 1 | 40-32- | Sand, medium, some fine, trace coarse, | Mud Rotary |
| | | | 53-59 | poorly sorted, relatively loose, light | |
| | | | | grey, wet. | |
| 459 | 461 | .75 | 39-31- | Sand, medium and fine, light grey to tan, | Reverse Rotary |
| | | | 38-32 | poorly sorted, moderately loose, wet. | |
| | | | | *NOTE: From approximately 180 ft through | |
| | | | | 259 ft there were some clay layers. | |
| | | | | Apparently these layers were missed | |
| | | | | in the spoons. | |

PREPARED BY: S. Zagaja/
M. Breault

[illegible]

SAMPLE/CORE LOG

BORING/WELL: RW-12 PROJECT NO: NY0029008 LKB - Syosset Landfill PAGE: 1 of 4

SITE LOCATION: Roadway - off of Gordon Drive DRILLING STARTED: 8/25/93 DRILLING COMPLETED: 9/27/93

TOTAL DEPTH DRILLED: 500 HOLE DIAMETER: 21/10/8 inches TYPE OF SAMPLE/ CORING DEVICE: Auger/cable tool - cuttings
Mud rotary/reverse - split spoons
SAMPLING INTERVAL: See log

LENGTH & DIAMETER OF CORING DEVICE: 2 feet x 2 inches

LAND-SURFACE ELEVATION: { } SURVEYED { } ESTIMATED DATUM:

DRILLING FLUID USED: Water/mud/water DRILLING METHOD: H.S.A./cable tool/ mud rotary/reverse rotary

DRILLING CONTRACTOR: Delta Well & Pump Co. DRILLER: Joe Guggino HELPER: Rich

PREPARED BY: Sarah Zagaja & David Vines HAMMER WEIGHT: 175 HAMMER DROP: 24 inches

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION | DRILLING METHOD |
|--|----|------------------------|-----------------------------------|---|--------------------|
| FROM | TO | | | | |
| 0 | 3 | -- | -- | Topsoil, sand, medium to coarse and gravel, fine to coarse, some cobbles, many roots, dark brown, moist. | H.S.A. |
| 3 | 8 | -- | -- | Gravel, fine to coarse, some sand, medium to coarse, some cobbles, fine to coarse, poorly sorted, dry, medium brown. | H.S.A. |
| 8 | 20 | -- | -- | Gravel, fine to coarse, some sand, medium to coarse, some cobbles, fine to coarse, poorly sorted, dry, medium brown (some intervals seemed to have only trace sand). | H.S.A. |
| 20 | 28 | -- | -- | Sand, medium to coarse, some gravel, fine to medium, trace coarse, brown, poorly sorted, dry. | H.S.A. |
| 28 | 34 | -- | -- | Sand, medium to coarse, and gravel, fine to medium, trace coarse, brown, poorly sorted, dry. | H.S.A. |
| 34 | 48 | -- | -- | Sand, medium to coarse, trace fine, some gravel, fine to medium, dark brown, dry. | H.S.A. |
| 48 | 52 | -- | -- | Sand, medium to coarse, trace fine, some gravel, fine to medium, dark brown, dry. | H.S.A. |
| 52 | 61 | -- | -- | Gravel, fine, some medium, some sand, medium to coarse, brown, poorly sorted. | Cable Tool |
| | 65 | -- | -- | Sand, medium and coarse, some gravel, fine | Cable Tool |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION | DRILLING METHOD |
|--|-----|------------------------|-----------------------------------|--|--------------------|
| FROM | TO | | | | |
| | | | | to medium, little silt, poorly sorted, light brown. | |
| 72 | 76 | -- | -- | Sand, coarse, some medium, some gravel, fine, trace medium, brown, faint odor. HNU = 2 ppm. | Cable Tool |
| 78 | 83 | -- | -- | Sand, medium, some fine, some coarse, trace fine gravel, medium brown, poorly sorted, faint odor. HNU = 1 ppm. | Cable Tool |
| 83 | 85 | -- | -- | Sand, fine, little silt, some clay, light brown to grey, well sorted (clay is in thin layers). HNU = 1 ppm. | Cable Tool |
| 89 | 94 | -- | -- | Sand, fine, trace medium, little clay (in layers), little silt, well sorted, light brown to grey. HNU = 0 ppm. | Cable Tool |
| | 96 | -- | -- | Sand, fine, trace medium, little clay (in layers), little silt, well sorted, light brown to grey. HNU = 0 ppm. | Cable Tool |
| 96 | 105 | -- | -- | Sand, medium, some fine, some silt, trace clay, light brown, poorly sorted. HNU = 0 ppm. | Cable Tool |
| 119 | 121 | 1.0 | 21,26, 34,41 | Sand, fine, light brown to white, some silt, well sorted. OVA = 0.2 | Mud Rotary |
| 139 | 141 | 1.0 | 27,38, 34,35 | Sand, fine, some very fine, orange to white, trace silt, poorly sorted micaceous. OVA = 0.5 | Mud Rotary |
| 159 | 161 | 0.75 | 47,55, 78,83 | Sand, medium, some fine, trace silt, light brown to brown, moderately sorted, micaceous. OVA = 0.5 | Mud Rotary |
| 170 | 175 | -- | -- | Streaks of clay in cuttings, clumps of white and clumps of orange (separate) present. | Mud Rotary |
| 179 | 181 | 0.75 | 21,29, 34,36 | Sand, fine, some medium, light brown to brown, well sorted. HNU = 1 ppm | Mud Rotary |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION | DRILLING METHOD |
|--|-----|------------------------|-----------------------------------|--|--------------------|
| FROM | TO | | | | |
| 199 | 201 | 0.70 | 38,50 | Sand, fine, some very fine, light brown | Mud Rotary |
| | | | 44,49 | to orange brown, well sorted. | |
| | | | | OVA = 3.5 | |
| 219 | 221 | 1.75 | 31,24, | N.R. first time down - top 3 inches silty | Mud Rotary |
| | | | 13,29 | fine sand, whitish grey, - bottom | |
| | | | | 18 inches sand, fine, some very fine, | |
| | | | | some silt, tan/white to light grey, well | |
| | | | | sorted. OVA = 5.0 | |
| 239 | 241 | 0.45 | 63,49, | N.R. first attempt - silty sand, fine to | Mud Rotary |
| | | | 37,51 | very fine, tan and light grey, well | |
| | | | | sorted. OVA = 1.5 ppm; HNU = 0.4 | |
| 259 | 261 | 0.75 | 42,31, | Sand, fine, some very fine, and silt, | Mud Rotary |
| | | | 38,27 | shades of tan-brown, very compact and | |
| | | | | well sorted. | |
| 279 | 281 | 1.0 | 29,33, | Sand, fine, some medium, some silt, light | Mud Rotary |
| | | | 44,26 | brown to brown, well sorted. | |
| 299 | 301 | 1.5 | 37,26, | Sand, fine, some medium, some silt, light | Mud Rotary |
| | | | 43,50 | tan to orange brown, well sorted. | |
| 319 | 321 | 1.25 | 32,38, | Sand, fine, trace medium, some silt, tan | Mud Rotary |
| | | | 45,30 | to orange brown, well sorted. | |
| 339 | 341 | 0.5 | 35,33, | Sand, fine, some medium, trace coarse, | Mud Rotary |
| | | | 47,41 | light tanish to white, poorly sorted. | |
| 359 | 361 | 0.35 | 25,27, | Sand, medium, some coarse, some fine, tan | Mud Rotary |
| | | | 35,28 | to brown, some gravel, iron oxide, poorly | |
| | | | | sorted. | |
| 379 | 381 | 1.75 | 25,29, | Sand, fine to very fine, and silt, trace | Mud Rotary |
| | | | 39,42 | medium sand, light grey to tan, well | |
| | | | | sorted. | |
| 399 | 401 | 1.0 | 29,27, | Sand, fine to medium, some silt, light tan | Mud Rotary |
| | | | 39,32 | (almost white) to light brown, poorly | |
| | | | | sorted. | |
| 419 | 421 | 1.9 | 21,27, | Sand, fine to very fine, some silt, light | Mud Rotary |
| | | | 16,30 | grey to light brown, some iron oxide, | |

| SAMPLE DEPTH (FT BELOW LAND SURFACE) | | CORE RECVRY (FT) | BLOW COUNTS PER 6 INCHES | SAMPLE/CORE DESCRIPTION | DRILLING METHOD |
|--|-----|------------------------|-----------------------------------|--|--------------------|
| FROM | TO | | | | |
| | | | | well sorted. Last 3" very incompetent | |
| | | | | light grey clayey sand. | |
| 420 | 430 | | | White clay in cuttings. | Mud Rotary |
| 439 | 441 | 0.75 | 18,22, | Sand, fine to medium, some silt, trace | Mud Rotary |
| | | | 28,30 | gravel, light grey to tan, very well | |
| | | | | sorted, some iron oxide, white clay | |
| | | | | stringers present. | |
| 450 | 460 | | | Gravel, medium in cuttings. | Mud Rotary |
| 459 | 461 | 1.25 | 33,31, | Top 5 inches-clayey sand, white with fine | Mud Rotary |
| | | | 28,34 | sand - bottom 10 inches-sand, medium to | |
| | | | | fine, trace silt, light grey to tan, | |
| | | | | iron oxide staining, poorly sorted. | |
| 470 | 475 | | | Fine sand, iron oxide concretions, | Mud Rotary |
| | | | | clayey sand (light brown) and coarse | |
| | | | | gravel in cuttings. | |
| 475 | 485 | | | White clay then fine and very fine tan | Reverse Rotary |
| | | | | sand in cuttings. | |
| 484 | 486 | 0.5 | 25,32, | Sand, fine to medium, some coarse, little | Reverse Rotary |
| | | | 38,46 | silt, light tan; iron oxide present, | |
| | | | | very compact, poorly sorted. | |
| | | | | HNU = 0.5 ppm | |
| 484 | 494 | | | Some white clay stringers, some fine brown | Reverse Rotary |
| | | | | sand, and a lot of coarse gravel in | |
| | | | | cuttings. | |
| 494 | 496 | 1.25 | 56,49, | Sand, fine to coarse, some gravel, medium | Reverse Rotary |
| | | | 48,53 | to coarse, white/tan, trace clay | |
| | | | | stringers, white; iron oxide, very | |
| | | | | compact, poorly sorted. | |
| 495 | 500 | | | Cuttings have fine brown sand and medium | Reverse Rotary |
| | | | | to coarse gravel. | |
| | | | | | |
| | | | | | |

APPENDIX D

**STATISTICAL PROCEDURE USED
TO ESTABLISH TERMINATION CRITERIA**



APPENDIX D

STATISTICAL PROCEDURE USED TO ESTABLISH TERMINATION CRITERIA

The termination depths of the two exploratory borings (SY-3DD and PK-10D) were determined by using statistical methods to analyze water-quality data from public supply and monitoring wells near the Syosset Landfill. Initially, the termination criteria were statistically determined using background water-quality data obtained in accordance with the method specified in the Work Plan and Site Operations Plan. Action levels for each primary and secondary leachate parameter were calculated by adding two standard deviations (σ) to the average concentration (\bar{x}) calculated for each respective parameter ($\bar{x} + 2\sigma$). These data are presented in Table D-1. However, as the data in Table D-1 shows only a limited data set was obtained (15 to 47 data points per parameter) using the specified statistical method, and the upper confidence limits were, in Geraghty & Miller's opinion, too high to be indicative of background water-quality conditions. Therefore, additional water-quality data were obtained and two other statistical methods, which are more appropriate for the number of data points, were used to compute the action levels. These two equations were used to determine the 95 percent confidence limits about the median and average leachate indicator concentrations and are presented below.

Lower Limit

Upper Limit

$$\bar{x} - 1.96 \frac{\sigma}{\sqrt{n}} \leq \text{average} \leq \bar{x} + 1.96 \frac{\sigma}{\sqrt{n}}$$

$$X_{\frac{n+1}{2}} - 1.96 \frac{\sqrt{n}}{2} \leq \text{median} \leq X_{\frac{n+1}{2}} + 1.96 \frac{\sqrt{n}}{2}$$

\bar{x} = average concentration.

σ = standard deviation.

n = number of observations.

Lower limit about median/average interpolated ordered data set.

Upper limit about median/average interpolated ordered data set.

$\frac{X_{n+1}}{2}$ = the $\frac{X_{n+1}}{2}$ value of the ordered data.

The statistical data generated from these two equations, including the action levels used to determine the termination criteria, are summarized in Table D-2. As can be seen from Table D-2, the limits about the median and average are similar, and the upper limits about the average were selected as the action levels for each leachate parameter except ammonia. No action level was calculated for ammonia (primary indicator) using the selected equation because there were still too few data points for this particular parameter (This parameter was not an analyte for the water districts). Therefore, the action level was set at twice the detection limit of the ammonia meter used (0.12 milligrams per liter [mg/L]).

According to the Work Plan, each exploratory boring was to be terminated when the concentrations of the three primary leachate indicators were below their respective action levels in two consecutive samples. However, if only one of the primary indicators remained slightly above its action level in consecutive samples, then the action levels of the three secondary leachate indicator parameters were compared to field analytical results and the boring was terminated when one or more of the secondary action levels were not exceeded.

Table D-1. Preliminary Statistical Evaluation of Leachate Indicator Parameter Data for Wells Within a two-Mile Radius of the Syosset Landfill, Syosset, New York.

| Parameter | No. of Points | Average | Median | Standard Deviation (S.D.) | Confidence Limits About the Average | | Confidence Limits About the Median | | Action Levels (Average+2S.D.) |
|----------------------|---------------|---------|--------|---------------------------------|--|---------|---------------------------------------|-----------|----------------------------------|
| | | | | | (Lower) | (Upper) | l (Lower) | u (Upper) | |
| Alkalinity | 24 | 13.1 | 10.2 | 12.3 | 8.21 | 18.02 | 6.34 | 16 | 37.64 |
| Hardness | 24 | 48.6 | 47.0 | 20.8 | 40.24 | 56.92 | 32 | 60.2 | 90.28 |
| Chloride | 40 | 18.7 | 13.7 | 19.7 | 12.62 | 24.84 | 12.5 | 15.72 | 58.15 |
| Specific Conductance | 44 | 186.2 | 162.7 | 103.6 | 155.57 | 216.79 | 150 | 196 | 393.37 |
| pH | 47 | 5.6 | 5.7 | 0.5 | 5.46 | 5.75 | 5.5 | 5.8 | 6.62 |
| Temperature | 15 | 13.8 | 14.0 | 1.4 | 13.11 | 14.49 | 13 | 15 | 16.55 |

Table D-2. Final Statistical Evaluation of Leachate Indicator Parameter Data for Wells Within a two-Mile Radius of the Syosset Landfill, Syosset, New York.

| Parameter | No. of Points | Average | Median | Standard Deviation (S.D) | Confidence Limits About the Average | | Confidence Limits About the Median | | (Average+2S.D.) |
|----------------|---------------|---------|--------|--------------------------------|--|-------------|---------------------------------------|-----------|-----------------|
| | | | | | (Lower) | (Upper) (a) | l (Lower) | u (Upper) | |
| Alkalinity | 115 | 9.0 | 6.0 | 9.1 | 7.37 | 10.69 | 5.0 | 7.0 | 27.20 |
| Hardness | 115 | 38.8 | 33.0 | 23.1 | 34.58 | 43.03 | 30 | 39 | 85.08 |
| Chloride | 131 | 16.6 | 13.0 | 13.9 | 14.25 | 19.00 | 12 | 14.4 | 44.34 |
| Specific Cond. | 44 | 186.2 | 162.7 | 103.6 | 155.57 | 216.79 | 150 | 196 | 393.37 |
| pH | 47 | 5.6 | 5.7 | 0.5 | 5.48 | 5.75 | 5.5 | 5.8 | 6.62 |
| Temperature | 15 | 13.8 | 14.0 | 1.4 | 13.11 | 14.49 | 13 | 15 | 16.55 |




Shading represents the most appropriate limits based on the data set.

(a) Selected as action level.




APPENDIX E
GEOPHYSICAL LOGS



COMPANY: GERAGHTY AND MILLER
HOLE ID: SY3DD
LOCATION: SYOSSET
DATE: 12-2-92
TIME: 0120
OPERATOR: DM
COMMENT1: GAMMA UP
COMMENT2:



COMPANY: GERAGHTY AND MILLER
HOLE ID: PK-10DG2
LOCATION: SYOSSET
DATE: 12-29-92
TIME: 1100
OPERATOR: GE
COMMENT1: GAMMA UP
COMMENT2:



COMPANY: GERAGHTY AND MILLER

HOLE ID: RB-11

LOCATION: SYOSSET




DATE: 8-9-93

TIME: 1815




OPERATOR: GE

COMMENT1: GAMMA UP

COMMENT2:



COMPANY: GERAGHTY AND MILLER
HOLE ID: RB-11
LOCATION: SYOSSET
DATE: 8-9-93
TIME: 1815
OPERATOR: GE
COMMENT1: R-SP UP
COMMENT2:



COMPANY: GEMMERTY AND MILLER

HOLE ID: RW-12D

LOCATION: SYOSSET




DATE: 9-23-93

TIME: 1700

OPERATOR: GE



COMMENT1: GAMMA UP

COMMENT2:



COMPANY: GERAGHTY AND MILLER
HOLE ID: RW-12D
LOCATION: SYOSSET
DATE: 9-23-93
TIME: 1700
OPERATOR: GE
COMMENT1: R-SP UP
COMMENT2:

| | | |
|------|-----------|------|
| 1000 | RESD OHMS | 1500 |
| 750 | SPD MU | 1250 |




APPENDIX F

MONITORING WELL CONSTRUCTION LOGS



WELL CONSTRUCTION LOG (UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

*Depth Below Land Surface

Project LKB - Syosset Landfill Well SY3DD

Town/City Syosset

County Nassau State New York

Permit No. _____

Land-Surface Elevation _____ feet
and Datum _____
☐ Surveyed
☐ Estimated

Installation Date(s) 11/9/92 to 12/9/92

Drilling Method Barber (modified air rotary)

Drilling Contractor Catch

Drilling Fluid Air, water

Development Technique(s) and Date(s)

Compressed Air - January 1993

Final Turbidity = 7 NTUs

Fluid Loss During Drilling Approx. 12,000 gallons

Water Removed During Development 27,000 gallons

Static Depth to Water 111.2 feet below M.P.

Pumping Depth to Water not measured feet below M.P.

Pumping Duration _____ hours

Yield 25 gpm Date _____

Specific Capacity _____ gpm/ft

Well Purpose monitoring

Remarks Well was drilled with:

16-inch diameter steel casing 0-118 ft

10-inch diameter steel casing 0-318 ft

8-inch diameter steel casing 0-464 ft

6-inch diameter steel casing 0-540 ft


The 16, 10, and 8-inch casings were left in place.

The 6-inch was pulled back to 528 ft.

Prepared by Sarah Zagaja

WELL CONSTRUCTION LOG

(UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

*Depth Below Land Surface

LKB -
Project Syosset Landfill OU2 RI Well PK-10S
Town/City Syosset
County Nassau State NY
Permit No. --
Land-Surface Elevation
and Datum feet ☐ Surveyed
☐ Estimated
Installation Date(s) 3/24/93, 3/25/93
Drilling Method Barber* and Cable-Tool*
Drilling Contractor Delta
Drilling Fluid Water


Development Technique(s) and Date(s)
Submersible pump with backwashing
3/26/93, 3/29/93, 3/30/93

Fluid Loss During Drilling 2,000 gallons
Water Removed During Development 19,000 gallons
Static Depth to Water 110 feet below M.P.
Pumping Depth to Water 137 feet below M.P.
Pumping Duration 15 hours
Yield 40 gpm Date 3/30/93
Specific Capacity 1.5 gpm/ft
Well Purpose Monitoring

Remarks * 10-inch surface casing was installed to 137.5 ft by the barber rig (modified air rotary method) and the cable-tool rig was used to install the remainder of the borehole (to 153 ft). The 10-inch steel casing was left in place.
Turbidity (final) = 25 NTUs

Prepared by Sarah Zagaja

WELL CONSTRUCTION LOG (UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

*Depth Below Land Surface

Project LKB - Syosset Landfill Well PK-101

Town/City Syosset

County Nassau State New York

Permit No. --

Land-Surface Elevation

and Datum feet ☐ Surveyed

☐ Estimated

Installation Date(s) April 14, 1993

Drilling Method mud rotary/reverse rotary

Drilling Contractor Delta Well and Pump Co.

Drilling Fluid mud/water

Development Technique(s) and Date(s)

Compressed air w/surging - 4/22/93

Fluid Loss During Drilling approximately 500 gallons

Water Removed During Development 8,000 gallons

Static Depth to Water 106 feet below M.P.

Pumping Depth to Water feet below M.P.

Pumping Duration hours

Yield gpm Date

Specific Capacity gpm/ft


Well Purpose monitoring

Remarks *A 10-inch diameter steel surface casing,
installed to 128 ft below grade by the cable-tool
drilling method, was left in place. The borehole
was then drilled to 328 ft by the mud rotary drilling
method followed by the reverse rotary drilling
method which was used to drill to the final depth.

Prepared by Sarah Zagaja

WELL CONSTRUCTION LOG

(UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

*Depth Below Land Surface

Project LKB - Syosset Landfill Well PK-10D

Town/City Syosset

County Nassau State New York

Permit No. _____

Land-Surface Elevation _____

and Datum _____ feet ☐ Surveyed

☐ Estimated

Installation Date(s) 12/10/93 to 12/31/92

Drilling Method Barber (modified air rotary)

Drilling Contractor Catoh

Drilling Fluid air, water

Development Technique(s) and Date(s)

Compressed Air - January 7, 8

Final Turbidity = 25 NTUs

Fluid Loss During Drilling Approximately 8,000 gallons

Water Removed During Development 15,000 gallons

Static Depth to Water 116 + feet below M.P.

Pumping Depth to Water not measured feet below M.P.

Pumping Duration _____ hours

Yield 25-30 gpm Date _____

Specific Capacity _____ gpm/ft

Well Purpose monitoring

Remarks Well was drilled with:

16-inch diameter steel casing 0-118 ft

10-inch diameter steel casing 0-460 ft

8-inch diameter steel casing 0-500 ft


The 16-inch and 10-inch casings were left in place

and the 8-inch was pulled back to 484 ft.

Prepared by Sarah Zagaja

WELL CONSTRUCTION LOG

(UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

*Depth Below Land Surface

Project LKB/Syosset Landfill Well RB-11S

Town/City Syosset

County Suffolk State New York

Permit No. _____

Land-Surface Elevation _____

and Datum _____ feet ☐ Surveyed

☐ Estimated

Installation Date(s) August 26, 1993

Drilling Method Hollow-Stem Auger

Drilling Contractor Delta Well and Pump Co.

Drilling Fluid Water (to suppress heave)

Development Technique(s) and Date(s)

Submersible pump - 9/2/93

Fluid Loss During Drilling 1200 gallons

Water Removed During Development 2430 gallons

Static Depth to Water 109 feet below M.P.

Pumping Depth to Water * feet below M.P.

Pumping Duration 6.75 hours

Yield 6 gpm Date 9/2/93

Specific Capacity _____ gpm/ft

Well Purpose Monitoring


Remarks * Water depth indicator could not reach

the water table during pumping due to tangling

with the pump and hose.

Prepared by Sarah Zagaja

WELL CONSTRUCTION LOG (UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.


*Depth Below Land Surface

Project LKB/Syosset Landfill Well RB-111
Town/City Syosset
County Nassau State New York
Permit No. _____
Land-Surface Elevation _____
and Datum _____ feet ☐ Surveyed
☐ Estimated
Installation Date(s) August 19, 1993
Drilling Method Barber*/mud-reverse rotary
Drilling Contractor Delta Well & Pump Co.
Drilling Fluid mud/water
Development Technique(s) and Date(s)
Compressed air - 9/1/93
Fluid Loss During Drilling approximately 1,500 gallons
Water Removed During Development 6,000 gallons
Static Depth to Water 109 feet below M.P.
Pumping Depth to Water _____ feet below M.P.
Pumping Duration 2.5 hours
Yield 40 gpm Date _____
Specific Capacity _____ gpm/ft
Well Purpose Monitoring

Remarks *10-inch diameter steel casing was installed by the Barber Drilling Method to 139.5 ft.
The borehole was drilled to 329 ft by the mud rotary method and the final 30 ft was installed by the reverse rotary method.

Prepared by Sarah Zagaia

WELL CONSTRUCTION LOG (UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.


*Depth Below Land Surface

Project LKB/Syosset Landfill Well RB-11D
 Town/City Syosset, NY
 County Nassau State NY
 Permit No. _____
 Land-Surface Elevation _____ feet ☐ Surveyed ☐ Estimated
 Installation Date(s) 8/09/93
 Drilling Method direct mud rotary; reverse rotary only (water only)
 Drilling Contractor Delta Well and Pump
 Drilling Fluid 0-120 air, 120-473 mud, 473-509 water
 Development Technique(s) and Date(s)
Compressed air - 9/1/93
 Fluid Loss During Drilling approx. 2,000 gal water gallons
 Water Removed During Development 6,000 gallons
 Static Depth to Water 109 feet below M.P.
 Pumping Depth to Water _____ feet below M.P.
 Pumping Duration 1.5 hours
 Yield _____ gpm Date _____
 Specific Capacity _____ gpm/ft
 Well Purpose Monitoring

Remarks 6½ bags (100 lbs) of #1 sand
8 5-gal buckets of 00-sand
39 100-lb bags of volclay grout
 * A 10-inch diameter steel surface casing was installed by the Barber Drilling Method to 119.5 ft. The mud rotary method was used to install the borehole to 473 ft followed by the reverse rotary method to the final depth.
 Prepared by Michael Breault/Sarah Zagaja

WELL CONSTRUCTION LOG

(UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

*Depth Below Land Surface

Project LKB/Syosset Landfill Well RW-12I

Town/City Syosset

County Nassau State New York

Permit No. _____

Land-Surface Elevation

and Datum _____ feet

☐ Surveyed

☐ Estimated

Installation Date(s) 10/6, 10/7, 1993

Drilling Method H.S.A./Cable Tool/Mud Rotary/Reverse Water

Drilling Contractor Delta Well & Pump Company, Inc.

Drilling Fluid mud, water (hydrant)

Development Technique(s) and Date(s)

Submersible pump - 10/14/93

Fluid Loss During Drilling 1,800 gallons

Water Removed During Development 7,000 gallons

Static Depth to Water 119.24 feet below M.P.

Pumping Depth to Water ** feet below M.P.

Pumping Duration 1.5 hours

Yield _____ gpm

Date 10/14/93

Specific Capacity _____ gpm/ft

Well Purpose Monitoring


Remarks * 10-inch surface casing was installed to 107 ft by the hollow-stem auger and cable-tool drilling methods. The borehole was then advanced by the mud rotary method followed by the reverse rotary method for the final 30-ft.

** Water depth indicator could not reach the water table during pumping due to tangling with the pump and hose. Turbidity final 0.56 NTUs.

Prepared by David Vines



WELL CONSTRUCTION LOG (UNCONSOLIDATED)



Measuring Point is
Top of Well Casing
Unless Otherwise Noted.

*Depth Below Land Surface

Project LKB - Syosset Landfill Well RW-12D
Town/City Syosset
County Nassau State New York
Permit No. _____
Land-Surface Elevation _____
and Datum _____ feet ☐ Surveyed ☐ Estimated
Installation Date(s) 9/13, 9/24, 9/27/93
Drilling Method H.S.A./cable tool/mud rotary/reverse rotary
Drilling Contractor Delta Well & Pump
Drilling Fluid mud; water (potable hydrant)

Development Technique(s) and Date(s)
Submersible pump - 10/15/93

Fluid Loss During Drilling 2,100 gallons
Water Removed During Development 7,000 gallons
Static Depth to Water 118.36 feet below M.P.
Pumping Depth to Water ** feet below M.P.
Pumping Duration 1.5 hours
Yield _____ gpm Date 10/15/93
Specific Capacity _____ gpm/ft
Well Purpose Monitoring

Remarks 11 bags sand (#1)
30 gallons of 00 sand
* 10-inch diameter black steel surface casing was installed to 105 ft by the hollow-stem auger and cable-tool drilling methods. The borehole was then advanced by the mud rotary method followed by the reverse rotary method for the final 30 ft.
** Water depth indicator could not reach the water table during pumping due to tangling with the pump and hose
Final turbidity = 24.7 NTUs.

Prepared by David Vines

APPENDIX G

**ANALYTICAL RESULTS OF DEVELOPMENT WATER
FROM MONITORING WELL PK-10D**



377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777 • FAX (516) 422-5770

LAB NO. C930140/1

01/15/93

Geraghty & Miller, Incorporated
125 East Bethpage Road
Plainview, NY 11803

ATTN: Vincent Glasser

SOURCE OF SAMPLE: Syosset, Project No. NY02908

COLLECTED BY: Client DATE COL'D: 01/12/93 RECEIVED: 01/12/93

SAMPLE: Wastewater sample, PK-10D-Dev, 1300

ANALYTICAL PARAMETERS

| | | |
|-----------------------|------|----|
| Chloromethane | ug/L | <1 |
| Bromomethane | ug/L | <1 |
| Dichlorodifluomethane | ug/L | <2 |
| Vinyl Chloride | ug/L | <1 |
| Chloroethane | ug/L | <1 |
| Methylene Chloride | ug/L | <1 |
| Trichlorofluomethane | ug/L | <2 |
| 1,1 Dichloroethene | ug/L | <1 |
| 1,1 Dichloroethane | ug/L | <1 |
| 1,2 Dichloroethene | ug/L | <1 |
| Chloroform | ug/L | <1 |
| 1,2 Dichloroethane | ug/L | <1 |
| 111 Trichloroethane | ug/L | <1 |
| Carbon Tetrachloride | ug/L | <1 |
| Bromodichloromethane | ug/L | <1 |
| 1,2 Dichloropropane | ug/L | <1 |
| t 13 Dichloropropene | ug/L | <2 |
| Trichloroethylene | ug/L | <1 |
| Chlorodibromomethane | ug/L | <1 |
| 112 Trichloroethane | ug/L | <2 |
| c 13 Dichloropropene | ug/L | <2 |
| 2chloroethvinylether | ug/L | <2 |
| Bromoform | ug/L | <2 |
| 1122Tetrachloroethan | ug/L | <2 |
| Tetrachloroethene | ug/L | <1 |

ANALYTICAL PARAMETERS

| | | |
|----------------------|------|-------|
| Chlorobenzene | ug/L | <1 |
| 1,3 Dichlorobenzene | ug/L | <2 |
| 1,2 Dichlorobenzene | ug/L | <2 |
| 1,4 Dichlorobenzene | ug/L | <2 |
| Benzene | ug/L | <1 |
| Toluene | ug/L | <2 |
| Ethyl Benzene | ug/L | <1 |
| m Xylene | ug/L | <2 |
| o+p Xylene | ug/L | <4 |
| Ammonia as N | mg/L | <0.05 |
| Chloride as Cl | mg/L | 15 |
| Alkalinity tot CaCo3 | mg/L | 16 |
| Hardness as CaCO3 | mg/L | 7.4 |

CC:

REMARKS:

DIRECTOR 

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777 • FAX (516) 422-5770

LAB NO. C930140/2

01/15/93

Geraghty & Miller, Incorporated
125 East Bethpage Road
Plainview, NY 11803

ATTN: Vincent Glasser

SOURCE OF SAMPLE: Syosset, Project No. NY02908

COLLECTED BY: Client DATE COL'D: 01/12/93 RECEIVED: 01/12/93

SAMPLE: Wastewater sample, TB011293

ANALYTICAL PARAMETERS

| | | |
|-----------------------|------|----|
| Chloromethane | ug/L | <1 |
| Bromomethane | ug/L | <1 |
| Dichlorodifluomethane | ug/L | <2 |
| Vinyl Chloride | ug/L | <1 |
| Chloroethane | ug/L | <1 |
| Methylene Chloride | ug/L | <1 |
| Trichlorofluomethane | ug/L | <2 |
| 1,1 Dichloroethene | ug/L | <1 |
| 1,1 Dichloroethane | ug/L | <1 |
| 1,2 Dichloroethene | ug/L | <1 |
| Chloroform | ug/L | <1 |
| 1,2 Dichloroethane | ug/L | <1 |
| 111 Trichloroethane | ug/L | <1 |
| Carbon Tetrachloride | ug/L | <1 |
| Bromodichloromethane | ug/L | <1 |
| 1,2 Dichloropropane | ug/L | <1 |
| 1,3 Dichloropropene | ug/L | <2 |
| Trichloroethylene | ug/L | <1 |
| Chlorodibromomethane | ug/L | <1 |
| 112 Trichloroethane | ug/L | <2 |
| 1,3 Dichloropropene | ug/L | <2 |
| 2chloroethvinylether | ug/L | <2 |
| Bromoform | ug/L | <2 |
| 1122Tetrachloroethan | ug/L | <2 |
| Tetrachloroethene | ug/L | <1 |

ANALYTICAL PARAMETERS

| | | |
|---------------------|------|----|
| Chlorobenzene | ug/L | <1 |
| 1,3 Dichlorobenzene | ug/L | <2 |
| 1,2 Dichlorobenzene | ug/L | <2 |
| 1,4 Dichlorobenzene | ug/L | <2 |
| Benzene | ug/L | <1 |
| Toluene | ug/L | <2 |
| Ethyl Benzene | ug/L | <1 |
| m Xylene | ug/L | <2 |
| o+p Xylene | ug/L | <4 |

CC:

REMARKS:

DIRECTOR _____


APPENDIX H

WATER SAMPLING LOGS/CHAIN-OF-CUSTODY FORMS



FIRST GROUNDWATER SAMPLING ROUND

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. S4-1 Coded/
Replicate No. MS/MSD

Date 11/3/93

Weather overcast 40's Time Sampling
Began 1336

Time Sampling
Completed 1530

EVACUATION DATA

Description of Measuring Point (MP) TOC.

Height of MP Above/Below Land Surface 0.15' MP Elevation 194.52

Total Sounded Depth of Well Below MP 134.32 Water-Level Elevation 81.16

Held _____ Depth to Water Below MP 113.36 Diameter of Casing 2"

Wet _____ Water Column in Well 20.96 Gallons Pumped/Bailed
Prior to Sampling 11 gal.

Gallons per Foot 0.16

Gallons in Well 3.35

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 2" sub. pump Q=1 gpm T=11 min

SAMPLING DATA/FIELD PARAMETERS

Color black/colorless/colorless Odor yes/none/none Appearance v. turbid/clear/clear Temperature 16/16/16

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 280/275/260 pH 6.30/6.10/6.05

Sampling Method and Material Teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see LOC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel DV, LTH

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill, NY0029008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SY-1D Coded/Replicate No. _____

Date 11/4/93

Weather sunny SDS Time Sampling Began 940

Time Sampling Completed 1015

EVACUATION DATA

Description of Measuring Point (MP) MP on PVC cap

Height of MP Above Land Surface 2.31 MP Elevation 197.36

Total Sounded Depth of Well Below MP 192.00 Water-Level Elevation 81.39

Held _____ Depth to Water Below MP 15.97 Diameter of Casing 4"

Wet _____ Water Column in Well 76.03 Gallons Pumped/Bailed Prior to Sampling 149 gal.

on: 940
off: 1002

Gallons per Foot 0.65
Gallons in Well 49.42

Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method perm. sub. pump Q=7 gpm T=22 min

SAMPLING DATA/FIELD PARAMETERS

Color orange/colorless/colorless Odor -/-/- Appearance turbid/st. turbid/clear Temperature 15.5/17/17 at 10C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 1100/1100/1100 pH 5.85/5.75/5.8

Sampling Method and Material 3/4" teflon bailer w/ leader (voc's) Tap discharge (other parameters)

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See COL</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel SV, GH

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008 Page _____ of _____
 Site Location Syosset, NY
 Site/Well No. SU-2R Coded/Replicate No. _____ Date 11.2.93
 Weather Sunny 50's Time Sampling Began 1310 Time Sampling Completed 1450

EVACUATION DATA

Description of Measuring Point (MP) MP on top of PVC casing
 Height of MP (Above/Below) Land Surface 1.95 MP Elevation 187.48
 Total Sounded Depth of Well Below MP 150.00 Water-Level Elevation 81.31
 Held _____ Depth to Water Below MP 106.17 Diameter of Casing 4"
 Wet _____ Water Column in Well 43.83 Gallons Pumped/Bailed Prior to Sampling 86 gal.
 on: 1:31
 off: 2:29
 Gallons per Foot 0.65
 Gallons in Well 28.49 Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method perm. sub. pump Q = 1.5 gpm T = 58 min

SAMPLING DATA/FIELD PARAMETERS

yellow tint
 Color /colorless/clear Odor slight/slight/slight Appearance turbid/clear/clear Temperature 14/15/14 °F/°C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 1050/1150/1100 pH 5.4/5.3/5.35

Sampling Method and Material 3/4" teflon bailer w/ leader (vocs) sample spigot for others

| Constituents Sampled | Container Description From Lab <u>X</u> or G&M _____ | Preservative |
|----------------------|---|--------------|
| <u>See WCL</u> | | |
| | | |
| | | |

Remarks _____

Sampling Personnel GW/DV/LH

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill/NY0029008 Page 1 of 1
 Site Location Syosset, New York
 Site/Well No. SY-2D Coded/Replicate No. _____ Date 11/2/93
 Weather Sunny 50's Time Sampling Began 1455 Time Sampling Completed 1600

EVACUATION DATA

Description of Measuring Point (MP) TOC
 Height of MP Above/Below Land Surface 2.18 MP Elevation 186.57
 Total Sounded Depth of Well Below MP 215.00 Water-Level Elevation 80.96
 Held _____ Depth to Water Below MP 105.61 Diameter of Casing 3"
 Wet _____ Water Column in Well 109.39 Gallons Pumped/Bailed Prior to Sampling 122 gal
 Gallons per Foot 0.37
 Gallons in Well 40.48 Sampling Pump Intake Setting (feet below land surface) _____
 Evacuation Method sub. pump Q = 4 gpm T = 3/min

SAMPLING DATA/FIELD PARAMETERS

Color colorless/colorless/colorless Odor none/none/none Appearance clear/clear/clear Temperature 15.5/17/17 90C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 1000/470/475 pH 6.15/6.50/6.50
 Sampling Method and Material teflon bailer

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see LOC</u> | | |
| | | |
| | | |

Remarks _____
 Sampling Personnel GW/BN/LH

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill / NY0029.008 Page 1 of 1
 Site Location Syosset, NY
 Site/Well No. SY-3 Coded/Replicate No. _____ Date 11.2.93
 Weather SDS sunny Time Sampling Began 945 Time Sampling Completed 1210

EVACUATION DATA

Description of Measuring Point (MP) TOC
 Height of MP Above/Below Land Surface 0.50 MP Elevation 191.38
 Total Sounded Depth of Well Below MP 145.28 Water-Level Elevation 81.35
 Held _____ Depth to Water Below MP 110.03 Diameter of Casing 2"
 Wet _____ Water Column in Well 35.25 Gallons Pumped/Bailed Prior to Sampling 17 gal.
 Gallons per Foot 0.16
 Gallons in Well 5.64 Sampling Pump Intake Setting (feet below land surface) _____
 Evacuation Method Teflon bailer w/ leader

SAMPLING DATA/FIELD PARAMETERS

Color black/black/black Odor present/present/present Appearance very turbid/very turbid/very turbid Temperature 10/12/16.5/16 °F/°C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance umhos/cm 900/920/1300/1310 pH 6.8/6.8/6.8/6.8

Sampling Method and Material Teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|---|--------------|
| <u>See COC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel EW/DV/UT

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill / NY0029.008

Page _____ of _____

Site Location Syosset, NY

Site/Well No. SU-3D Coded/Replicate No. _____

Date 11/2/93

Weather Sunny 50's Time Sampling Began 800

Time Sampling Completed 930

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation 194.74

Total Sounded Depth of Well Below MP 197.35 Water-Level Elevation 80.69

Held _____ Depth to Water Below MP 114.05 Diameter of Casing 3"

Wet _____ Water Column in Well 83.30 Gallons Pumped/Bailed Prior to Sampling 93 gal

on: 8:21
off: 8:45

Gallons per Foot 0.37

Gallons in Well 30.82

Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method 2" sub. pump Q=4 gpm T=24 min

SAMPLING DATA/FIELD PARAMETERS

Color yellow/yellow/yellow Odor slight/light/light Appearance sl. sl. sl. Temperature 16/17/17 10C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance 2400/2400/2300 pH 6.8/6.8/7.0

Sampling Method and Material teflon bailer w/ teflon leader

Constituents Sampled

Container Description
From Lab X or G&M _____

Preservative

See LOC

Remarks _____

Sampling Personnel * Field blank done before this well *

GW 18V/4H

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill / NY0029.08

Page 1 of 1

Site Location Syosset NY

Site/Well No. SY-3DD Coded/Replicate No. _____

Date 11/1/93

Weather overcast 40's Time Sampling Began 1335

Time Sampling Completed 1520

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 541.83 Water-Level Elevation _____

Held _____ Depth to Water Below MP 113.99 Diameter of Casing 2"

Wet _____ Water Column in Well 427.84 Gallons Pumped/Bailed Prior to Sampling 206 gal.

on: 145
off: 2:37
Gallons per Foot 0.16
Gallons in Well 68.45 Sampling Pump Intake Setting (feet below land surface) ~15D

Evacuation Method 2" sub. pump Q=4 gpm T=52 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear Odor none/none/none Appearance clear/clear/clear Temperature 15/15/4 ROC

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 181.8/133 pH 5.6/5.8/5.9

Sampling Method and Material Teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|---|--------------|
| <u>See COC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks *field blank done prior to SY/3DD and after SY-9

Sampling Personnel _____

| WELL CASING VOLUMES | | | | | |
|---------------------|---------------|---------------|---------------|-----------|--|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 | |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 | |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY 0029.008 Page 1 of 1
 Site Location Syosset, NY
 Site/Well No. SY-4 Coded/Replicate No. _____ Date 11-2-93
 Weather clear 45° Time Sampling Began 8:40 Time Sampling Completed 1205

EVACUATION DATA

Description of Measuring Point (MP) TDC
 Height of MP Above Land Surface 0.20 MP Elevation 193.32
 Total Sounded Depth of Well Below MP 150.00 Water-Level Elevation 81.87
 Held _____ Depth to Water Below MP 111.45 Diameter of Casing 2"
 Wet _____ Water Column in Well 38.55 Gallons Pumped/Bailed Prior to Sampling 19 gal
 Gallons per Foot 0.16
 Gallons in Well 6.17 Sampling Pump Intake Setting (feet below land surface) _____
 Evacuation Method teflon bailer

SAMPLING DATA/FIELD PARAMETERS

Color black/brown/brown Odor slight/slight Appearance turbid/turbid/turbid Temperature 15/15/15.5 °C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance umhos/cm 1250/1300/1250 pH 7.1/6.45/6.56

Sampling Method and Material teflon bailer

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See COL</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel GW/DV/LH

| WELL CASING VOLUMES | | | | | |
|---------------------|---------------|---------------|---------------|-----------|--|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 | |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 | |

WATER SAMPLING LOG

Project/No. Syosset Landfill / NY 0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SU-6

Coded/
Replicate No. _____

Date 11/1/93 ^{attempted} 11/5/93 ^{done}

Weather overcast

Time Sampling Began 800

Time Sampling Completed 1300

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface 0.10 MP Elevation 185.85

Total Sounded Depth of Well Below MP 138.00 Water-Level Elevation 81.53

Held _____ Depth to Water Below MP 104.32 Diameter of Casing 2"

Wet _____ Water Column in Well 33.68 Gallons Pumped/Bailed Prior to Sampling 17 gal.

Gallons per Foot 0.16

Gallons in Well 5.39 Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method disposable bailer

SAMPLING DATA/FIELD PARAMETERS

Color black/brown/lt. brown/lt. brown Odor 1-1-1- Appearance turbid/turbid/turbid/sl. turbid Temperature 15.5/15/15/15 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 85/300/375/370 pH 8.25/6.63/6.24/6.27

Sampling Method and Material 3/4" teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <u>X</u> or G&M _____ | Preservative |
|----------------------|---|--------------|
| <u>See COL</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel SV, BW, LH

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY 0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SY-6D

Coded/
Replicate No. _____

Date 11/1/93

Weather overcast SD's

Time Sampling
Began 0830

Time Sampling
Completed 1125

EVACUATION DATA

Description of Measuring Point (MP) TOC (mp)

Height of MP ~~Above~~/Below Land Surface 0.30 MP Elevation 185.60

Total Sounded Depth of Well Below MP 205.00 Water-Level Elevation 81.55

Held _____ Depth to Water Below MP 104.05 Diameter of Casing 4"

Wet _____ Water Column in Well 100.95 Gallons Pumped/Bailed
Prior to Sampling 197 gal.

Gallons per Foot 0.65

Gallons in Well 65.62

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method permanent submersible pump Q=8gpm T=27 min.

SAMPLING DATA/FIELD PARAMETERS

Color black/grey/clear Odor yes/yes/yes Appearance v. turbid/turbid/sl. turbid Temperature 13/15/15 °C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 415/500/390 pH 5.70/5.4/5.50

Sampling Method and Material 3/4" teflon bailer w/ leader (voc) Tap Discharge others

Constituents Sampled

Container Description
From Lab X or G&M _____

Preservative

see OLC

Remarks _____

Sampling Personnel GW/BR/LH

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" | = 0.06 | 2" | = 0.16 | 3" | = 0.37 | 4" | = 0.65 |
|----------|--------|--------|--------|--------|--------|--------|----|--------|
| | 1-1/2" | = 0.09 | 2-1/2" | = 0.26 | 3-1/2" | = 0.50 | 6" | = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. S4-7 Coded/
Replicate No. _____

Date 11-4-93

Weather sunny SO's Time Sampling
Began 1530

Time Sampling
Completed 1610

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above Land Surface 0.25 MP Elevation 199.63

Total Sounded Depth of Well Below MP 139.40 Water-Level Elevation 83.92

Held _____ Depth to Water Below MP 115.71 Diameter of Casing 2"

Wet _____ Water Column in Well 23.69 Gallons Pumped/Bailed
Prior to Sampling 12 gal

Gallons per Foot 0.16

Gallons in Well 3.80 Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 2" PVC Bailer

SAMPLING DATA/FIELD PARAMETERS

Color black/black/black Odor yes/yes/yes Appearance turbid/turbid/turbid Temperature 15/15.5/15.5 °C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 650/1200/1150 pH 5.90/6.00/5.95

Sampling Method and Material 3/4" teflon bailer w/teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see LOC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel * field blank done before sampling *
GW/DV/LH

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SL-B Coded/Replicate No. _____

Date 11.4.93

Weather 55° sunny Time Sampling Began 1030

Time Sampling Completed 1100

EVACUATION DATA

Description of Measuring Point (MP) MP on PVC casing

Height of MP Above Land Surface 2.25 MP Elevation 195.84

Total Sounded Depth of Well Below MP 137.00 Water-Level Elevation 81.79

Held _____ Depth to Water Below MP 114.05 Diameter of Casing 4"

Wet _____ Water Column in Well 22.95 Gallons Pumped/Bailed Prior to Sampling 45 gallons

on: 1040

Gallons per Foot 0.65

off: 10:47

Gallons in Well 14.92

Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method perm. sub pump Q = 7 gpm T = 7 min

SAMPLING DATA/FIELD PARAMETERS

Color colorless Odor present/yes/yes Appearance clear/clear/clear Temperature 16/16/16 70°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance 290/300/295 umhos/cm pH 5.55/5.50/5.55

Sampling Method and Material teflon bailer w/ leader

Constituents Sampled

Container Description From Lab X or G&M _____

Preservative

See LOC

Remarks _____

Sampling Personnel DL, LH

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" | 2" | 3" | 4" |
|----------|--------|--------|--------|--------|
| | = 0.06 | = 0.16 | = 0.37 | = 0.65 |
| | = 0.09 | = 0.26 | = 0.50 | = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008 Page 1 of 1
 Site Location Syosset, NY
 Site/Well No. SY-9 Coded/Replicate No. _____ Date 11/1/93
 Weather overcast SI Time Sampling Began 800 Time Sampling Completed 935

EVACUATION DATA

Description of Measuring Point (MP) TOL
 Height of MP Above/Below Land Surface 0.70 MP Elevation 199.41
 Total Sounded Depth of Well Below MP 118.60 Water-Level Elevation 82.64
 Held _____ Depth to Water Below MP 116.77 Diameter of Casing 4"
 Wet _____ Water Column in Well 1.83 Gallons Pumped/Bailed Prior to Sampling 4gal
 Gallons per Foot 0.65
 Gallons in Well 1.19 Sampling Pump Intake Setting (feet below land surface) _____
 Evacuation Method Teflon bailer w/ Teflon leader

SAMPLING DATA/FIELD PARAMETERS

Color grey/black Odor strong/strong/strong Appearance turbid/turbid/turbid Temperature 13.5/14/14 90C
 Other (specific ion; OVA; HNU; etc.) OVA: below back round

Specific Conductance umhos/cm 310/410/420 pH 5.70/5.8/6

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <u>X</u> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See COL</u> | | |
| | | |
| | | |

Remarks _____

Sampling Personnel DV, BW, LTH

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. 1KB / Syosset Landfill NY0029.008

Page 1 of 1

Site Location Syosset, New York

Site/Well No. PK 101 Coded/
Replicate No. Rep 2

Date 11.4.93

Weather clear 55° Time Sampling
Began 1:15

Time Sampling
Completed 2:25

EVACUATION DATA

Description of Measuring Point (MP) TDC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 362.12 Water-Level Elevation _____

Held _____ Depth to Water Below MP 107.80 Diameter of Casing 4"

Wet _____ Water Column in Well 254.32 Gallons Pumped/Bailed
Prior to Sampling 496 gallons

Gallons per Foot 0.65

Gallons in Well 165.31

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 4" sub. pump Q=12 gpm T= 42 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear/clear Odor none/none/none/none Appearance clear/clear/clear/clear Temperature 51.4/51.4/51.4 51.4

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance,
umhos/cm 1450/1600/1700/1500 pH 6.15/6.15/6.21/6.36

Sampling Method and Material Teflon bailer w/ teflon leader

Constituents Sampled

Container Description
From Lab X or G&M _____

Preservative

See COT

Remarks _____

Sampling Personnel GW, DM

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008

Page 1 of 1

Site Location Syosset, New York

Site/Well No. PK-10D Coded/
Replicate No. MS/MSD

Date 11.4.93

Weather sunny 40 Time Sampling
Began 801

Time Sampling
Completed 1122

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 499.13 Water-Level Elevation _____

Held _____ Depth to Water Below MP 108.41 Diameter of Casing 4"

Wet _____ Water Column in Well 390.72 Gallons Pumped/Bailed
Prior to Sampling 762 gallons

on: 9:01
off: 10:00

Gallons per Foot 0.65 Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 4" sub. pump Q=13gpm T=59 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/yellowish/clar Odor none/none/none Appearance slightly sl. turbid/sl. turbid Temperature 13.5/13/13.5 @ 10C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 125/125/105/105 pH 5.8/5.82/5.5/5.5

Sampling Method and Material Teflon bailer w/ teflon leader

Constituents Sampled _____ Container Description
From Lab X or G&M _____ Preservative _____

Remarks *field blank taken after sampling 10D*

Sampling Personnel GW/DV/LH

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
|----------|---------------|---------------|---------------|-----------|
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. RB-115 Coded/
Replicate No. _____

Date 11.3.94

Weather Overcast 40 Time Sampling
Began 155

Time Sampling
Completed 2:15

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 144.50 Water-Level Elevation _____

Held _____ Depth to Water Below MP 109.12 Diameter of Casing 4"

Wet _____ Water Column in Well 35.38 Gallons Pumped/Bailed
Prior to Sampling 69 gal.

Gallons per Foot 0.65

Gallons in Well 23.00

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 4" sub. pump Q = 12 gpm T = 6 min

SAMPLING DATA/FIELD PARAMETERS

Color yellow/yellow/slight/slight
pink/pink/tint/tint Odor none/none/none/none Appearance turbid/moderately/slightly/slightly
turbid/turbid/turbid/turbid Temperature 14/14/14/14 °C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 75/65/65/65 pH 5.6/5.4/5.4/5.42

Sampling Method and Material Teflon bailer w/ teflon leader

Constituents Sampled

Container Description
From Lab X or G&M _____

Preservative

See LOC

Remarks _____

Sampling Personnel LH, GW, DV

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
|----------|---------------|---------------|---------------|-----------|
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY 0029.008

Page _____ of _____

Site Location Syosset, NY

Site/Well No. RB-11I ^{Coded} Replicate No. Rep 1

Date 11/3/93

Weather overcast 40° Time Sampling Began 1015

Time Sampling Completed 1145

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 358.06 Water-Level Elevation _____

Held _____ Depth to Water Below MP 110.38 Diameter of Casing 4"

Wet _____ Water Column in Well 247.68 Gallons Pumped/Bailed Prior to Sampling 483 gal.

Gallons per Foot 0.65

Gallons in Well 160.99 Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method 4" submersible pump @ 12 gpm T = 41 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear Odor none/none/none Appearance clear/clear/clear Temperature 13/12/12 ^{°C}

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance 230/225/225 umhos/cm pH 5.4/4.79/4.78

Sampling Method and Material teflon bailer w/ leader

| Constituents Sampled | Container Description From Lab <u>A</u> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see COC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel SW/DV/LH

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008 Page 1 of 1
 Site Location Syosset, NY
 Site/Well No. RB-11D Coded/
 Replicate No. _____ Date 11.3.93
 Weather overcast SAs Time Sampling
 Began 800 Time Sampling
 Completed 1010

EVACUATION DATA

Description of Measuring Point (MP) TOP of PVC casing
 Height of MP Above/Below Land Surface _____ MP Elevation _____
 Total Sounded Depth of Well Below MP 503.50 Water-Level Elevation _____
 Held _____ Depth to Water Below MP 111.97 Diameter of Casing 4"
 Wet _____ Water Column in Well 391.53 Gallons Pumped/Bailed
 Prior to Sampling 764 gal.
 on: 826 Gallons per Foot 0.65
 off: 930 Gallons in Well 254.50 Sampling Pump Intake Setting
 (feet below land surface) _____
 Evacuation Method 4" sub. pump Q = 12 gpm T = 64 min

SAMPLING DATA/FIELD PARAMETERS

Color colorless colorless colorless Odor none/none/none Appearance clear/clear/clear Temperature 13/12.5/13 °F/°C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 15/15/15 pH 5.10/5.3/5.7

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See COL</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks *COM split samples on this well
 Sampling Personnel DV, GW, LH

| GAL./FT. | WELL CASING VOLUMES | | | |
|----------|---------------------|---------------|---------------|-----------|
| | 1-1/4" | 2" | 3" | 4" |
| | = 0.06 | = 0.16 | = 0.37 | = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029008 Page 1 of 6
 Site Location Syosset, NY
 Site/Well No. RW-12 I Coded/Replicate No. Rep 3 Date 11.5.93
 Weather rain 40's Time Sampling Began 1030 Time Sampling Completed 1210

EVACUATION DATA

Description of Measuring Point (MP) TOP of PVC casing
 Height of MP Above/Below Land Surface _____ MP Elevation _____
 Total Sounded Depth of Well Below MP 361.07 Water-Level Elevation _____
 Held _____ Depth to Water Below MP 117.84 Diameter of Casing 4"
 Wet _____ Water Column in Well 243.23 Gallons Pumped/Bailed Prior to Sampling 475 gal
 Gallons per Foot 0.65
 Gallons in Well 158.10 Sampling Pump Intake Setting (feet below land surface) _____

on: 1030
off: 1142

Evacuation Method 4" sub. pump @ 9 gpm ± 52 min

SAMPLING DATA/FIELD PARAMETERS
 Color colorless yellow tint colorless colorless Odor NONE Appearance clear turbid clear clear Temperature 15.5/15.5/15 97/100
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance umhos/cm 500/500/500/500 pH 6.35/6.2/6.2/6.4

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|---|--------------|
| <u>See AL</u> | | |
| | | |
| | | |

Remarks * field blank taken before sampling 12I + after RW-12 D *
 Sampling Personnel LH, DV, GW

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Land fill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. RW-12D Coded/
Replicate No. _____

Date 11.5.93

Weather rainy 60's Time Sampling
Began 800

Time Sampling
Completed 1045

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 500.74 Water-Level Elevation _____

Held _____ Depth to Water Below MP 117.98 Diameter of Casing 4"

Wet _____ Water Column in Well 382.76 Gallons Pumped/Bailed
Prior to Sampling 747 gallons

Gallons per Foot 0.65

Gallons in Well 248.80

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 4" sub. pump Q = 12 gpm T = 63 min

SAMPLING DATA/FIELD PARAMETERS

Color colorless Odor none Appearance clear Temperature 15/15/14/15 °C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance 420/400/425/440 umhos/cm pH 5.9/5.7/5.7/5.7

Sampling Method and Material Teflon bailer w/ Teflon leader

Constituents Sampled

Container Description
From Lab ☒ or G&M _____

Preservative

See LOC

Remarks *field blank done after sampling 12D and before 12E

Sampling Personnel LH, SW, DV

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" | 2" | 3" | 4" |
|----------|--------|--------|--------|--------|
| | = 0.06 | = 0.16 | = 0.37 | = 0.65 |
| | = 0.09 | = 0.26 | = 0.50 | = 1.47 |

Laboratory Task Order No. 06161

CHAIN-OF-CUSTODY RECORD

Page 1 of 1

Project Number 418/Sydney Landfill N1/002908

Project Location Syosset, New York

Laboratory TLA Labs Inc.

Sampler(s)/Affiliation G. Williams

Handicks

Date/Time

| SAMPLE IDENTITY | Code | Sampled | Lab ID |
|-----------------|------|---------|--------|
|-----------------|------|---------|--------|

Sampled

Lab ID:

SAMPLE BOTTLE / CONTAINER DESCRIPTION

[illegible]

Sample Code: L = Liquid; S = Solid; A = Air

Total No. of Bottles/
Containers

3

Relinquished by: Willie G. Gandy

Organization: Leighton + Miller, Inc.

Received by:

Organization:

Date 11 29 1932

5:07 pm

Seal Intact?
Yes No N/A

Relinquished by:

Organization:

Received by:

Organization:

Date / / Time :

Seal Intact?
Yes No N/A

Special Instructions/Remarks:

* Dissolved Metals filtered in the field through $0.45 \mu\text{m}$ filters *

Delivery Method:

☐ In Person

☐ Common Carrier

☐ Lab Courier☐ Other

GR4 Form 00 100

SPECIFY

SPECIFY

Sampler(s)/Affiliation G. Williams, D. McGregor
L. Hendricks

Sample Code: L = Liquid; S = Solid; A = Air

Total No. of Bottles/
Containers

55

Date 11/30/93 Time _____

Seal Intact? Yes No N/A

Date 1/1/ Time 11:00

Seal Intact?
Yes No N/A

☐ Common Carrier

☐ Lab Courier☐ Other _____

Project Number Siyaset Landfill NY0029008

Project Location Syosset, NY

Laboratory TEA, Labs Inc.

Sampler(s)/Affiliation P. M. C. G. C. R.

G. Williams

Date/Time

| SAMPLE IDENTITY | Code | Date/Time Sampled | Lab ID |
|-----------------|------|-------------------|--------|
|-----------------|------|-------------------|--------|

SAMPLE BOTTLE / CONTAINER DESCRIPTION

[illegible]

Sample Code: L = Liquid; S = Solid; A = Air

Total No. of Bottles/
Containers

Relinquished by: Paul M. Gagnier
Received by: _____

Organization: Berkowitz & Miller
Organization: _____

Date 12/1/93 Time 6:15pm

Seal Intact?
Yes No N/A

Relinquished by: _____
Received by: _____

Organization: _____
Organization: _____

Date 1/1 Time 11:11

Seal Intact?
Yes No N/A

Special Instructions/Remarks:

Dissolved Metals filtered through 0.45 μ m filter

Delivery Method:

☐ In Person☒ Common Carrier

Fed Ex

☐ Lab Courier☐ Other

Project Number Syosset Landfill NY0029008

Project Location Syosset, NY

Laboratory IEH, Labs Inc.

Sampler(s)/Affiliation D. McGregor

A Williams

| SAMPLE IDENTITY | Code | Date/Time Sampled | Lab ID |
|-----------------|------|----------------------|--------|
|-----------------|------|----------------------|--------|

SAMPLE BOTTLE / CONTAINER DESCRIPTION

| | | | | | | | TOTAL |
|---------------------------|---|---------|---|---|---|---|-------|
| FB 12-1-93 | L | 12-1-93 | 1 | 1 | | 3 | 5 |
| PK-105 | L | 12-1-93 | 1 | 1 | 1 | 3 | 7 |
| SU-8 | L | 12-1-93 | 1 | 1 | 1 | 3 | 7 |
| SU-10 | L | 12-1-93 | 1 | 1 | 1 | 3 | 7 |
| TB 12-1-93 | L | 12-1-93 | | | | 3 | 3 |
| PK-10 I | L | | | | | 3 | 3 |
| Rep-2 | L | | | | | 3 | 3 |
| PK-10K | L | | | | | 3 | 3 |
| PK-10D ^{initial} | L | | | | | 3 | 3 |
| PK-10D ^{natural} | L | V | | | | 3 | 3 |

Sample Code: L = Liquid; S = Solid; A = Air

Total No. of Bottles/
Containers

44

Relinquished by: Paul M. Lopez

Organization: Geoghegan & Miller

Date 12/1/93 Time 6:15 pm

Seal Intact?
Yes No N/A

Received by: _____

Organization: University of California, Los Angeles

Date / / Time : :

Seal Intact?
Yes No N/A

Relinquished by: _____

Organization: _____

Received by: _____

Organization: _____

Special Instructions/Remarks:

Dissolved metals filtered through a 0.45 μm filter

Delivery Method:

☐ In Person☒ Common Carrier

Fed
SPECIFY

☐ Lab Courier☐ Other

SPECIFY

SECOND GROUNDWATER SAMPLING ROUND

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029,008

Page 1 of 1

Site Location Syosset, New York

Site/Well No. SY-1

Coded/
Replicate No. MS/MSD

Date 11/30/93

Weather clear, 40's

Time Sampling
Began 2:20

Time Sampling
Completed 4:20

EVACUATION DATA

Description of Measuring Point (MP) T.O.C.

Height of MP Above/Below Land Surface 0.15 MP Elevation 194.52

Total Sounded Depth of Well Below MP 134.30 Water-Level Elevation 81.03

Held _____ Depth to Water Below MP 113.49 Diameter of Casing 2"

Wet _____ Water Column in Well 20.81 Gallons Pumped/Bailed Prior to Sampling 10 gallons

Gallons per Foot 0.16

Gallons in Well 3.33

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 2" sub. pump Q=1 gpm T=10 min

SAMPLING DATA/FIELD PARAMETERS

Color green tint / clear / clear / clear Odor present / present / light / slight Appearance mostly turbid / clear / clear / clear Temperature 14/15/15.5/16/16 47°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 270/270/260/260/260 pH 6.6/6.1/5.9/5.9/6.0

Sampling Method and Material Teflon bailer w/ teflon leader

Constituents Sampled _____ Container Description From Lab X or G&M _____ Preservative _____

see C.O.C.

Remarks _____

Sampling Personnel G.W./L.H.

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
|----------|---------------|---------------|---------------|-----------|
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.08

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SY-1D Coded/
Replicate No. _____

Date 12/1/93

Weather Overcast 35° Time Sampling
Began 4:10

Time Sampling
Completed 5:01

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface 2.31 MP Elevation 197.36

Total Sounded Depth of Well Below MP 192.00 Water-Level Elevation 81.28

Held _____ Depth to Water Below MP 116.08 Diameter of Casing 4"

Wet _____ Water Column in Well 75.92 Gallons Pumped/Bailed
Prior to Sampling 148.04

on: 4:15 Gallons per Foot 0.65

off: 4:45 Gallons in Well 49.34

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method dedicated sub. pump Q=5 gpm T=30 min.

SAMPLING DATA/FIELD PARAMETERS

Color none / same / same / same Odor slight / slight / slight / slight Appearance sl. turbid / sl. turbid / sl. turbid / sl. turbid Temperature 16/16/17/17 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance 105 / 105 / 105 / 105 umhos/cm pH 5.9 / 5.8 / 5.8 / 5.8

Sampling Method and Material _____

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See COC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel G.W. / D.M.C.

| GAL./FT. | WELL CASING VOLUMES | | | |
|----------|---------------------|--------|--------|--------|
| | 1-1/4" | 2" | 3" | 4" |
| | = 0.06 | = 0.16 | = 0.37 | = 0.65 |
| | 1-1/2" | 2-1/2" | 3-1/2" | 6" |
| | = 0.09 | = 0.26 | = 0.50 | = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029,008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SU-2R Coded/
Replicate No. _____

Date 12.3.93

Weather clear 40's Time Sampling
Began 10:25

Time Sampling
Completed 11:30

EVACUATION DATA

Description of Measuring Point (MP) T.O.C.

Height of MP Above/Below Land Surface 1.95 MP Elevation 187.48

Total Sounded Depth of Well Below MP 150.00 Water-Level Elevation 81.25

Held _____ Depth to Water Below MP 106.23 Diameter of Casing 4"

Wet _____ Water Column in Well 43.77 Gallons Pumped/Bailed
Prior to Sampling 85.35

Gallons per Foot 0.65

Gallons in Well 28.45 Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method dedicated 4" sub pump Q=2gpm T=43 min. well surging

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear Odor none/none/none Appearance clear/clear/clear Temperature 15/15/15 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance,
umhos/cm 900/1100/1100 pH 5.2/5.2/5.2

Sampling Method and Material _____

| Constituents Sampled | Container Description From Lab _____ or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See LOC</u> | | |
| | | |
| | | |

Remarks _____

Sampling Personnel GW, D.McG.

| WELL CASING VOLUMES | | | | | |
|---------------------|---------------|---------------|---------------|-----------|--|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 | |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 | |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SY-3 Coded/Replicate No. _____

Date 12.3.93

Weather clear 45 Time Sampling Began 3:20

Time Sampling Completed 5:05

EVACUATION DATA

Description of Measuring Point (MP) TLC

Height of MP Above/Below Land Surface 0.50 MP Elevation 191.38

Total Sounded Depth of Well Below MP 145.20 Water-Level Elevation 81.25

Held _____ Depth to Water Below MP 110.13 Diameter of Casing 2"

Wet _____ Water Column in Well 35.07 Gallons Pumped/Bailed Prior to Sampling 16.83

Gallons per Foot 0.16

Gallons in Well 5.61 Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method Teflon bailer w/ teflon leader

SAMPLING DATA/FIELD PARAMETERS

Color greenish/greenish/grey/grey Odor slight/slight/slight/slight Appearance dark bl. turbid/turbid/sl. turbid Temperature 17.5/17.5/17.5/2.5 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 1150/1100/1400/1400 pH 7.0/6.9/6.8/6.8

Sampling Method and Material Teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See C.O.C.</u> | | |
| _____ | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel G.W. DMCB.

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.08 Page _____ of _____
 Site Location Syosset, NY
 Site/Well No. SU-3D Coded/ Replicate No. _____ Date 12.3.93
 Weather overcast 45° Time Sampling Began 2:20 Time Sampling Completed 3:15

EVACUATION DATA

Description of Measuring Point (MP) TOC
 Height of MP Above/Below Land Surface _____ MP Elevation 194.74
 Total Sounded Depth of Well Below MP 197.35 Water-Level Elevation 80.62
 Held _____ Depth to Water Below MP 114.12 Diameter of Casing 3"
 Wet _____ Water Column in Well 83.23 Gallons Pumped/Bailed Prior to Sampling 92.38
 on: 2:31
 off: 3:01
 Gallons per Foot 0.37
 Gallons in Well 30.79 Sampling Pump Intake Setting (feet below land surface) _____
 Evacuation Method 2" sub pump Q=3 gpm T=31 min

SAMPLING DATA/FIELD PARAMETERS

Color green/green light light light light Odor light light light light Appearance clear clear clear clear Temperature 9/20/19 90C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 2550/2600/2600/2600 pH 7.0/6.9/7.0/7.1

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see COC</u> | | |

Remarks * field blank taken before SU-3D was sampled

Sampling Personnel GW, DMCG

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.007

Page _____ of _____

Site Location Syosset, NY

Site/Well No. S4-3 DD

Coded/
Replicate No. _____

Date 11/29/93

Weather clear, 40's

Time Sampling
Began 2:15

Time Sampling
Completed 4:10

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 541.77 Water-Level Elevation _____

Held _____ Depth to Water Below MP 113.97 Diameter of Casing 2"

Wet _____ Water Column in Well 427.80 Gallons Pumped/Bailed
Prior to Sampling 205 gallons

Gallons per Foot 0.16

Gallons in Well 68.45

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 2" sub. pump Q = 3 gpm T = 69 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear/clear Odor none/none/none/none Appearance clear/clear/clear/clear Temperature 19/10/15/15/15 at 70C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 28/20/20/20 pH 5.7/5.8/5.8/5.8

Sampling Method and Material Teflon bailer w/ teflon leader

Constituents Sampled

Container Description
From Lab ☒ or G&M _____

Preservative

see COC

Remarks _____

Sampling Personnel LH BW

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
|----------|---------------|---------------|---------------|-----------|
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. SY-4

Coded/
Replicate No. _____

Date 12-3-93

Weather cloudy 45°

Time Sampling
Began 7:50

Time Sampling
Completed 10:10

EVACUATION DATA

Description of Measuring Point (MP) _____

Height of MP Above/Below Land Surface 0.20

MP Elevation 193.32

Total Sounded Depth of Well Below MP 150.55

Water-Level Elevation 81.71

Held _____ Depth to Water Below MP 111.61

Diameter of Casing 2"

Wet _____ Water Column in Well 38.94

Gallons Pumped/Bailed
Prior to Sampling 18.60 gal

Gallons per Foot 0.16

Gallons in Well 6.20

Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method teflon bailer w/ teflon leader

SAMPLING DATA/FIELD PARAMETERS

Color dk grey / bk grey / lt. grey / light brown Odor moderate / moderate / moderate / moderate Appearance turbid / turbid / turbid / turbid Temperature 5/15/15/15 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 1100/1150/1150/1100 pH 7.5/7.1/7.0/7.0

Sampling Method and Material Teflon bailer w/ teflon leader

Constituents Sampled _____ Container Description
From Lab ☒ or G&M _____ Preservative _____

See CA _____

Remarks _____

Sampling Personnel GW, DMC

WELL CASING VOLUMES

| | | | | |
|----------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008

Page _____ of _____

Site Location Syosset, NY

Site/Well No. SY-6 Coded/Replicate No. _____

Date 12.2.93

Weather overcast 40S Time Sampling Began 10:10

Time Sampling Completed 12:15

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface 0.10 MP Elevation 185.85

Total Sounded Depth of Well Below MP 138.00 Water-Level Elevation 81.36

Held _____ Depth to Water Below MP 104.49 Diameter of Casing 2"

Wet _____ Water Column in Well 33.51 Gallons Pumped/Bailed Prior to Sampling 16.08

Gallons per Foot 0.16

Gallons in Well 5.36 Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method disp. bailer Q = - T = -

SAMPLING DATA/FIELD PARAMETERS

Color brown/brown/brown/brown tint/tint Odor slight/slight/light/light Appearance turbid/turbid/sl. turbid/sl. turbid Temperature 14/14/14.5/14 47°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance umhos/cm 285/350/360/360 pH 7.35/6.95/6.7/6.65/6.65

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|---|--------------|
| <u>see COC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel GW, DMCG

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY002908

Page 1 of 1

Site Location Syosset, NY

Site/Well No. Sy-6D Coded/
Replicate No. _____

Date 11-29-93

Weather clear SDS Time Sampling
Began 11:00

Time Sampling
Completed 1:15

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface 0.30 MP Elevation 185.00

Total Sounded Depth of Well Below MP 205.00 Water-Level Elevation 81.12

Held _____ Depth to Water Below MP 104.48 Diameter of Casing 4"

Wet _____ Water Column in Well 100.52 Gallons Pumped/Bailed
Prior to Sampling 196 gal.

Gallons per Foot 0.65

Gallons in Well 65.30 Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method perm. pump Q=5gpm T=40min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear/clear Odor slight/slight/slight/slight Appearance clear/clear/clear/clear Temperature 15.5/15.5/16.0 91.0C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 275/310/355/355 pH 6.1/5.9/5.7/5.7

Sampling Method and Material _____

Constituents Sampled _____ Container Description
From Lab X or G&M _____ Preservative _____

see TOC

Remarks * field blank ^{taken} prior to sampling Sy-6D

Sampling Personnel _____

| GAL./FT. | WELL CASING VOLUMES | | | |
|----------|---------------------|--------|--------|--------|
| | 1-1/4" | 2" | 3" | 4" |
| | = 0.06 | = 0.16 | = 0.37 | = 0.65 |
| | 1-1/2" | 2-1/2" | 3-1/2" | 6" |
| | = 0.09 | = 0.26 | = 0.50 | = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008 Page 1 of 1
 Site Location Syosset, NY
 Site/Well No. SY-7 Coded/
 Replicate No. _____ Date 12.2.93
 Weather Overcast 40's Time Sampling
 Began 2:30 Time Sampling
 Completed 4:00

EVACUATION DATA

Description of Measuring Point (MP) TDC
 Height of MP Above/Below Land Surface 0.25 MP Elevation 199.63
 Total Sounded Depth of Well Below MP 127.49 Water-Level Elevation 84 -
 Held _____ Depth to Water Below MP 115.63 Diameter of Casing 2"
 Wet _____ Water Column in Well 11.86 Gallons Pumped/Bailed
 Prior to Sampling 5.69
 Gallons per Foot 0.16
 Gallons in Well 1.89 Sampling Pump Intake Setting
 (feet below land surface) _____
 Evacuation Method 1" PVC bailer

SAMPLING DATA/FIELD PARAMETERS

Color black/black/black Odor Slight/Slight/Slight Appearance turbid/turbid/turbid Temperature 15/15/15.5 °F/°C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
 umhos/cm 1250/1300/1300 pH 6.1/6.1/6.2
 Sampling Method and Material 3/4" teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See COL</u> | | |
| | | |
| | | |

Remarks _____
 Sampling Personnel GW/ D. McG

| GAL./FT. | WELL CASING VOLUMES | | | |
|----------|---------------------|---------------|---------------|-----------|
| | 1-1/4" | 2" | 3" | 4" |
| | = 0.06 | = 0.16 | = 0.37 | = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. S4-8 Coded/
Replicate No. _____

Date 12.1.93

Weather overcast 50 Time Sampling
Began 3:05

Time Sampling
Completed 4:06

EVACUATION DATA

Description of Measuring Point (MP) MP on PVC Cap

Height of MP Above/Below Land Surface 2.25 MP Elevation 195.84

Total Sounded Depth of Well Below MP 137.00 Water-Level Elevation 81.67

Held _____ Depth to Water Below MP 114.17 Diameter of Casing 4"

Wet _____ Water Column in Well 22.83 Gallons Pumped/Bailed
Prior to Sampling 44.49

on: 3:16 Gallons per Foot 0.65
off: 3:23 Gallons in Well 14.83 Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method ded. sub. pump Q = 7 gpm T = 7 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear Odor slight/light/light Appearance clear/clear/clear Temperature 5/15/15 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 295/295/295 pH 5.6/5.6/5.6

Sampling Method and Material sample spigot except for VOC (teflon bailer)

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See CEC</u> | | |
| | | |
| | | |

Remarks _____

Sampling Personnel GW DMCG

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008

Page _____ of _____

Site Location Syosset, NY

Site/Well No. SY-9 Coded/Replicate No. _____

Date 11/29/93

Weather clear, 40's Time Sampling Began 9:30

Time Sampling Completed 10:40

EVACUATION DATA

Description of Measuring Point (MP) T.O.C.

Height of MP Above/Below Land Surface 0.70 MP Elevation 199.41

Total Sounded Depth of Well Below MP 118.50 Water-Level Elevation 82.41

Held _____ Depth to Water Below MP 117.00 Diameter of Casing 4"

Wet _____ Water Column in Well 1.50 Gallons Pumped/Bailed Prior to Sampling 3 gallons

Gallons per Foot 0.65

Gallons in Well 0.975

Sampling Pump Intake Setting (feet below land surface) _____

Evacuation Method Teflon bailer w/ teflon leader

SAMPLING DATA/FIELD PARAMETERS

Color grey/grey/grey Odor strong/moderate/moderate Appearance ruibid/turbid/turbid Temperature 15.5/15/15/15 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance umhos/cm 365/385/370/370 pH 5.8/5.8/5.7/5.7

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see COC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel GW, LH

| WELL CASING VOLUMES | | | |
|---------------------|---------------|---------------|---------------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 |
| | | | 4" = 0.65 |
| | | | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008 Page _____ of _____
 Site Location Syosset, NY
 Site/Well No. PK-105 Coded/
 Replicate No. _____ Date 12.1.93
 Weather Sunny 40 Time Sampling
 Began 9:30 Time Sampling
 Completed 12:05

EVACUATION DATA

Description of Measuring Point (MP) TDC
 Height of MP Above/Below Land Surface _____ MP Elevation _____
 Total Sounded Depth of Well Below MP 149.90 Water-Level Elevation _____
 Held _____ Depth to Water Below MP 108.49 Diameter of Casing 4"
 Wet _____ Water Column in Well 41.41 Gallons Pumped/Bailed
 Prior to Sampling 135 gal.
 on: 10:45 Gallons per Foot 0.65
 off: 11:15 Gallons in Well 26.90 Sampling Pump Intake Setting
 (feet below land surface) 123 ft. bmp
 Evacuation Method 4" sub. pump Q = 4.5 gpm T = 20 min

SAMPLING DATA/FIELD PARAMETERS

yellowish/yellowish/yellomish/yellowish
 Color none/none/none/none Odor cloudy/cloudy/cloudy/cloudy Appearance 13/13/13/13 Temperature 13/13/13/13 °F/°C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
 umhos/cm 185/190/188/187 pH 5.7/5.8/5.9/5.9

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <input checked="" type="checkbox"/> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See LOC</u> | | |
| | | |
| | | |

Remarks _____

Sampling Personnel GW, DMCF

| WELL CASING VOLUMES | | | | | |
|---------------------|---------------|---------------|---------------|-----------|--|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 | |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 | |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008 Page _____ of _____
 Site Location Syosset, NY
 Site/Well No. PK-10I Coded/Replicate No. Rep-2 Date 12.1.93
 Weather Clear SD's Time Sampling Began 12:15 Time Sampling Completed 1:45

EVACUATION DATA

Description of Measuring Point (MP) TOL
 Height of MP Above/Below Land Surface _____ MP Elevation _____
 Total Sounded Depth of Well Below MP 362.19 Water-Level Elevation _____
 Held _____ Depth to Water Below MP 107.87 Diameter of Casing 4"
 Wet _____ Water Column in Well 254.32 Gallons Pumped/Bailed Prior to Sampling 495 gal.
 on: 12:31 Gallons per Foot 0.65
 off: 1:12 Gallons in Well 165.30 Sampling Pump Intake Setting (feet below land surface) _____
 Evacuation Method 4" sub. pump Q=12 T=41

SAMPLING DATA/FIELD PARAMETERS
 Color clear/clear/clear Odor slight/slight/slight Appearance bubbly/clear/clear/clear Temperature 14/15/15/14.5
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance umhos/cm 1500/1500/1600/1550 pH 6.5/6.5/6.6/6.6

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <u>X</u> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See LOC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks * field blank taken after PK10S before PK 10I
 Sampling Personnel GW, DMCB

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. PK-10D Coded/
Replicate No. MS/MSD

Date 12.1.93

Weather sunny 40's Time Sampling
Began 8am

Time Sampling
Completed 11.15

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 499.68 Water-Level Elevation _____

Held _____ Depth to Water Below MP 108.38 Diameter of Casing 4"

Wet _____ Water Column in Well 391.30 Gallons Pumped/Bailed
Prior to Sampling 960

on: 8:55
off: 10:15

Gallons per Foot 0.65 120 dned in 5 min

Gallons in Well 25.43 Sampling Pump Intake Setting
(feet below land surface) set at 135

Evacuation Method 4" sub. pump $Q = 129 \text{ gpm}$ $T = 63 \text{ min}$

SAMPLING DATA/FIELD PARAMETERS

Color colorless/colorless/colorless/colorless Odor none/none/none/none Appearance slightly cloudy Temperature 13/12/12/12.5 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 92/112/90/85 pH 6.0/6.3/6.1/6.1

Sampling Method and Material _____

| Constituents Sampled | Container Description From Lab <u>X</u> or G&M _____ | Preservative |
|----------------------|---|--------------|
| <u>See COC</u> | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

Remarks _____

Sampling Personnel GW, DMCG

| WELL CASING VOLUMES | | | |
|---------------------|---------------|---------------|---------------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 |
| | | | 4" = 0.65 |
| | | | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill/NY0029.008 Page 1 of 1
 Site Location Syosset, NY
 Site/Well No. RB-115 Coded/Replicate No. _____ Date 11/30/93
 Weather 40's clear Time Sampling Began 10:30 Time Sampling Completed 3:00

EVACUATION DATA

Description of Measuring Point (MP) TOC
 Height of MP Above/Below Land Surface _____ MP Elevation _____
 Total Sounded Depth of Well Below MP 144.49 Water-Level Elevation _____
 Held _____ Depth to Water Below MP 109.38 Diameter of Casing 4"
 Wet _____ Water Column in Well 35.11 Gallons Pumped/Bailed Prior to Sampling 69 gal.
 on: 1:56 Gallons per Foot 0.65 Sampling Pump Intake Setting (feet below land surface) _____
 off: 2:06 Gallons in Well 22.82
 Evacuation Method 4" submersible pump Q=7 gpm T=10 min

SAMPLING DATA/FIELD PARAMETERS

Color orange/none/none/none Odor none/none/none/none Appearance v. turbid 7.5"/1" Temperature 14/14/14/14 °F/°C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance, umhos/cm 58/57/55/56 pH 5.16/5.23/5.27/5.25

Sampling Method and Material teflon bailer w/teflon leader

| Constituents Sampled | Container Description From Lab <u>X</u> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see lab</u> | | |
| | | |
| | | |
| | | |

Remarks _____
 Sampling Personnel GW, DMCG

| WELL CASING VOLUMES | | | | | |
|---------------------|---------------|---------------|---------------|-----------|--|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 | |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 | |

WATER SAMPLING LOG

Project/No. Syosset Land fill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. RB-11I Coded/
Replicate No. Rep-1

Date 11.30.93

Weather Clear 40 Time Sampling
Began 8:00

Time Sampling
Completed 12:00

EVACUATION DATA

Description of Measuring Point (MP) TOC

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 358.07 Water-Level Elevation _____

Held _____ Depth to Water Below MP 110.45 Diameter of Casing 4"

Wet _____ Water Column in Well 247.62 Gallons Pumped/Bailed
Prior to Sampling 483 gallons

on: 10:18
off: 11:19

Gallons per Foot 0.65

Gallons in Well 160.95 Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 4" sub. pump Q = 8 gpm T = 61 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear Odor none/none/none Appearance clear/clear/clear Temperature 10.5/11/10/10 °F/°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 210/210/208/210 pH 5.0/5.2/5.2/5.2

Sampling Method and Material Teflon bailer w/ teflon leader

Constituents Sampled _____ Container Description
From Lab ☒ or G&M _____ Preservative _____

See COC

Remarks * field blank taken b/f sampling

Sampling Personnel LH, DMcb, GW

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
|----------|---------------|---------------|---------------|-----------|
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset Landfill NY/0029.008 Page _____ of _____
 Site Location Syosset, NY
 Site/Well No. RB-11D Coded/
 Replicate No. _____ Date 11.30.93
 Weather clear 40's Time Sampling
 Began 7:15 Completed 10:15

EVACUATION DATA

Description of Measuring Point (MP) TDL
 Height of MP Above/Below Land Surface _____ MP Elevation _____
 Total Sounded Depth of Well Below MP 503.49 Water-Level Elevation _____
 Held _____ Depth to Water Below MP 110.95 Diameter of Casing 4"
 Wet _____ Water Column in Well 392.54 Gallons Pumped/Bailed
 Prior to Sampling 766 gal.
 on: 8:24 Gallons per Foot 0.65 Sampling Pump Intake Setting
 off: 9:26 Gallons in Well 255.15 (feet below land surface) _____
 Evacuation Method 4" sub. pump Q = 12 gpm T = 64 min

SAMPLING DATA/FIELD PARAMETERS

Color clear/clear/clear/clear Odor none/none/none/none Appearance clear/clear/clear/clear Temperature 11.5/10/10/11 100
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
 umhos/cm 15/15/15/15 pH 6.4/5.1/5.2/5.2

Sampling Method and Material _____

| Constituents Sampled | Container Description From Lab _____ or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>see COC</u> | | |
| | | |
| | | |

Remarks _____

Sampling Personnel LH, DMCG, GW

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY 0028 0029.08 Page 1 of 1
 Site Location Syosset, NY
 Site/Well No. RW-12I Coded/Replicate No. Rep-3 Date 12.2.93
 Weather overcast 40 Time Sampling Began 8:15 Time Sampling Completed 12:30

EVACUATION DATA

Description of Measuring Point (MP) TOL
 Height of MP Above/Below Land Surface _____ MP Elevation _____
 Total Sounded Depth of Well Below MP 360.34 Water-Level Elevation _____
 Held _____ Depth to Water Below MP 117.87 Diameter of Casing _____
 Wet _____ Water Column in Well 242.47 Gallons Pumped/Bailed Prior to Sampling 472.81
 on: 10:55 Gallons per Foot 0.65
 off: 11:44 Gallons in Well 157.60 Sampling Pump Intake Setting (feet below land surface) _____
 Evacuation Method 4" sub. pump @ 10 gpm T= 49 min

SAMPLING DATA/FIELD PARAMETERS

Color colorless colorless colorless colorless Odor none none none none Appearance sl. turbid sl. turbid sl. turbid sl. turbid Temperature 13/13/13/13 70C
 Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance umhos/cm 500/505/500/500 pH 6.3/6.3/6.4/6.3

Sampling Method and Material teflon bailer w/ teflon leader

| Constituents Sampled | Container Description From Lab <u>X</u> or G&M _____ | Preservative |
|----------------------|--|--------------|
| <u>See TOL</u> | | |
| | | |
| | | |
| | | |

Remarks _____

Sampling Personnel BW, D. MCB

| WELL CASING VOLUMES | | | | |
|---------------------|---------------|---------------|---------------|-----------|
| GAL./FT. | 1-1/4" = 0.06 | 2" = 0.16 | 3" = 0.37 | 4" = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

WATER SAMPLING LOG

Project/No. Syosset landfill NY0029.008

Page 1 of 1

Site Location Syosset, NY

Site/Well No. RW 12D

Coded/
Replicate No. _____

Date 12.2.93

Weather overcast 40

Time Sampling
Began 8:15

Time Sampling
Completed 10:50

EVACUATION DATA

Description of Measuring Point (MP) TDL

Height of MP Above/Below Land Surface _____ MP Elevation _____

Total Sounded Depth of Well Below MP 501.24 Water-Level Elevation _____

Held _____ Depth to Water Below MP 118.02 Diameter of Casing _____

Wet _____ Water Column in Well 383.22 Gallons Pumped/Bailed
Prior to Sampling 747.27

on: 921

Gallons per Foot 0.65

off: 1026

Gallons in Well 249.09 Sampling Pump Intake Setting
(feet below land surface) _____

Evacuation Method 4" sub. pump Q=12gpm T=65min

SAMPLING DATA/FIELD PARAMETERS

Color ~~color less~~ ~~color less~~ ~~color less~~ ~~color less~~ Odor none/none/none/none Appearance clear/clear/clear/clear Temperature 3/13/14/13 67°C

Other (specific ion; OVA; HNU; etc.) _____

Specific Conductance
umhos/cm 468/405/410/415 pH 5.6/5.7/5.6/5.7

Sampling Method and Material (teflon bailer w/teflon leader)

Constituents Sampled

Container Description
From Lab X or G&M _____

Preservative

See COL

Remarks _____

Sampling Personnel GW, DMCG

WELL CASING VOLUMES

| GAL./FT. | 1-1/4" | 2" | 3" | 4" |
|----------|---------------|---------------|---------------|-----------|
| | = 0.06 | = 0.16 | = 0.37 | = 0.65 |
| | 1-1/2" = 0.09 | 2-1/2" = 0.26 | 3-1/2" = 0.50 | 6" = 1.47 |

Project Number L19/Sycset Landfill M10271003

Project Location ENOSSET, New York

Laboratory IEA Labs Inc.

Sampler(s)/Affiliation D. Vines, G. Williams
L. Hendricks

| SAMPLE IDENTITY | Code | Date/Time Sampled | Lab ID |
|-----------------|------|----------------------|--------|
|-----------------|------|----------------------|--------|

SAMPLE BOTTLE / CONTAINER DESCRIPTION

[illegible]

Sample Code: L = Liquid; S = Solid; A = Air

Total No. of Bottles/
Containers**FBI**

Relinquished by: [Signature]
Received by: [Signature]

Organization: Geraghty & Miller
Organization:

Date 11/1/83 Time 1530

Seal Intact?
Yes No N/A

Relinquished by: _____
Received by: _____

Organization: _____
Organization: _____

Date 1/1/1 Time 1:00

Seal Intact?
Yes No N/A

Special Instructions/Remarks:

- * Dissolved metals filtered in field through 0.45 μm filters

Delivery Method: ☐ In Person ☒ Common Carrier Federal Express

☐ Lab Courier ☐ Other

Project Number LEB/455et landfill NY0029008

Project Location: Syosset, New York

Laboratory TEA lab Inc.

Sampler(s)/Affiliation L. Products, D. Vines
G. Williams

| SAMPLE IDENTITY | Code | Date/Time Sampled | Lab ID |
|-----------------|------|----------------------|--------|
|-----------------|------|----------------------|--------|

SAMPLE BOTTLE / CONTAINER DESCRIPTION

[illegible]

Sample Code: L = Liquid; S = Solid; A = Air

| Date | Description | Total No. of Bottles/ Containers |
|------|-------------|-------------------------------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Relinquished by: Michael J. Indict
Received by: [Signature]

Organization: Geraghty + Miller, Inc
Organization: _____

Date 11/3/93 Time 1645

Seal Intact?
Yes No N/A

Relinquished by:

Organization:

Date 11/11/11 Time 11:11

Seal Intact?
Yes No N/A

Received by:

Organization:

Date 11/11/11 Time 11:11

Seal Intact?
Yes No N/A

Special Instructions/Remarks:

ALL METALS were field filter through 0.45 microns filters.

Delivery Method: ☐ In Person ☒ Common Carrier CC F-X

☐ Lab Courier ☐ Other

Project Number LEB 54854 Layhill NY 0029008

Project Location Syosset, New York

Laboratory IEA Labs, Inc.

Sampler(s)/Affiliation D. Vines, B. Williams
L. Hendricks

| SAMPLE IDENTITY | Code | Date/Time Sampled | Lab ID |
|-----------------|------|----------------------|--------|
|-----------------|------|----------------------|--------|

SAMPLE BOTTLE / CONTAINER DESCRIPTION

[illegible]

Sample Code: ~~L = Liquid; S = Solid; A = Air~~

Total No. of Bottles/
Containers

5

Relinquished by: Joan F. [Signature]
Received by: _____

Organization: Gerachty & mind
Organization: _____

Date 11/4/93 Time 1830

Seal Intact?
(Yes) No N/A

Relinquished by: _____
Received by: _____

Organization: _____
Organization: _____

Date 1/1 Time 1:10

Seal Intact?
Yes No N/A

Special Instructions/Remarks:

* Please use this sample for our matrix spike/matrix spike duplicate
* Distilled water, Cost filtered through 0.45 μ m filters

Delivery Method: ☐ In Person ☒ Common Carrier Federal Express ☐ Lab Courier ☐ Other _____

Project Number L113/Syosset Landfill NY002903

Project Location GYOSSET, New York

Laboratory TEA Labs, Inc.

Sampler(s)/Affiliation D. Vinas; O. Williams
L. Hendricks

| SAMPLE IDENTITY | Code | Date/Time Sampled | Lab ID |
|-----------------|------|----------------------|--------|
|-----------------|------|----------------------|--------|

SAMPLE BOTTLE / CONTAINER DESCRIPTION

[illegible]

Sample Code: L = Liquid, S = Solid, A = Air

Total No. of Bottles/
Containers

13

Relinquished by: [Signature]
Received by: _____

Organization: Geraghty & Miller
Organization: _____

Date 11/14/93 Time 1830

Seal Intact?
Yes No N/A

Relinquished by: _____
Received by: _____

Organization: _____
Organization: _____

Date / / Time : :

Seal Intact?
Yes No N/A

Special Instructions/Remarks:

Delivery Method: ☐ In Person

☒ Common Carrier Federal Express
SPECIES

☐ Lab Courier☐ Other

Project Number LEB/HUSA Landfill Number 2908

Project Location Sydney, N.Y.

Laboratory IEA Labs, Inc

Sampler(s)/Affiliation L. Hadricks, D. Vines
G. Williams

| SAMPLE IDENTITY | Code | Date/Time Sampled | Lab ID |
|-----------------|------|----------------------|--------|
|-----------------|------|----------------------|--------|

SAMPLE BOTTLE / CONTAINER DESCRIPTION

[illegible]

Sample Code: L = Liquid; S = Solid; A = Air

**Total No. of Bottles/
Containers**

36

Relinquished by: Yvonne C. Hendricks
Received by: Yvonne C. Hendricks

Organization: Geraghty: Miller, Inc
Organization: _____

Date 11/5/93 Time 1500

Seal Intact?
(Yes) No N/A

Relinquished by: _____
Received by: _____

Organization:
Organization:

Date / / Time : :

Seal Intact?
Yes | No | N/A

Special Instructions/Remarks:

* Dissolved Metals were filtered through 0.45 μm filters

Delivery Method: ☐ In Person

☐ Common Carrier

Federal Express

☐ Lab Courier☐ Other

APPENDIX J

GAS WELL CONSTRUCTION LOGS



SUBJECT: GAS MONITORING WELLS
PROJECT: LKB- Syosset Landfill
CLIENT/PROJECT NO: NY0029008

BY: J. Ziegler DATE: 9/30/93
CHKD: DATE:
REV: DATE:


PAGE

1

SHEET

1

CS-20



NOTE: Each well was secured with an 8-inch diameter, flush-mounted steel man hole and cover, cemented in place.

SUBJECT: GAS MONITORING WELLS
PROJECT: LKB- Syosset Landfill
CLIENT/PROJECT NO: NY0029008

BY: J. Ziegler DATE: 9/30/93
CHKD: DATE:
REV: DATE:


PAGE

1

SHEET

1

CS-21



NOTE: Each well was secured with an 8-inch diameter, flush-mounted steel man hole and cover, cemented in place.

SUBJECT: GAS MONITORING WELLS
PROJECT: LKB- Syosset Landfill
CLIENT/PROJECT NO: NY0029008

BY: S. Ziegler DATE: 9/30/93
CHKD: DATE:
REV: DATE:


PAGE

1

SHEET

1

CS-22



NOTE: Each well was secured with an 8-inch diameter, flush-mounted steel man hole and cover, cemented in place.

APPENDIX K

**MEMORANDUM FROM LOCKWOOD, KESSLER & BARTLETT, INC.
REGARDING THE INSTALLATION AND MONITORING
OF ON-SITE SUBSURFACE GAS MONITORING WELLS
AS PART OF THE FIRST OPERABLE UNIT
REMEDIAL DESIGN PROGRAM**



APPENDIX K
ON-SITE SUBSURFACE GAS MONITORING

PERFORMED BY
LOCKWOOD, KESSLER & BARTLETT, INC.
AS PART OF THE
FIRST OPERABLE UNIT
REMEDIAL DESIGN FOR THE SYOSSET LANDFILL

PURPOSE

The Syosset Landfill Second Operable Unit (OU2) Remedial Investigation (RI) Work Plan called for the installation of five new on-site gas monitoring cluster wells along the site's northeastern property line. These wells were installed and monitored during the First Operable Unit (OU1) Remedial Design Program. The following paragraphs discuss the monitoring well installation, well construction, gas monitoring protocols and sampling results.

GAS WELL INSTALLATION AND CONSTRUCTION

The five on-site gas monitoring cluster wells (CW-4 through CW-8), having monitoring depths of 15 and 35 feet below grade, were installed as part of the soil boring program for the OU1 Remedial Design in accordance with the requirements of the OU1 Remedial Design Work Plan (LKB, 1991). The wells were installed from September 16-21, 1992 by Soil Mechanics Drilling Corp. under the supervision of LKB and Malcolm Pirnie (USEPA oversight consultant for the OU1 Remedial Design).

The cluster well locations are shown on Figure K-1. Cluster well CW-4 was installed along the property line adjacent to the homes at the northern end of Abby Lane. Wells CW-5 and CW-6 were located at the property line in the vicinity of the South Grove Elementary School Building and the South Grove School Annex, respectively. Wells CW-7 and CW-8 were installed at the property line near the homes on Colony Lane and adjacent to existing gas monitoring wells G-14 and G-13, respectively. Locating wells CW-7 and CW-8 in this manner provided well clusters consisting of three wells each at those two locations with monitoring depths of 5', 10' and 35'. The installation of these five cluster wells along the northeastern property line supplemented the three existing cluster wells (CW-1, 2 and 3) located in the vicinity of the site's gas venting trench. Cluster wells CW-1, 2 and 3 have monitoring depths of 6', 11' and 35' each. These eight cluster wells provide gas monitoring points throughout the site's northeastern boundary.

Cluster wells CW-4 through CW-8 were constructed by using the hollow stem auger method to drill a 10-inch diameter borehole to a depth of 35 feet. Two 2-inch diameter PVC monitoring wells were installed within each borehole at depths of 15 and 35 feet below grade. Each monitoring well contained a five foot length of PVC well screen. The annular space around each

screen length was filled with gravel packing and the wells were separated with a two foot deep section of bentonite slurry. The remaining borehole annulus was filled with backfill material. The well head assembly consisted of a PVC cap, reducer fitting and a 1/2 inch diameter PVC ball valve as shown on Figure K-1. The wells were completed at grade with a flush mount frame and cover set in two feet of concrete centered around each cluster well.

The OU2 RI Work Plan called for monitoring the five additional cluster wells along with existing well CW-2 on two occasions of falling barometric pressure. Following the first sampling round conducted on January 21, 1993, the Town requested permission from the USEPA to install three additional five foot deep monitoring wells at cluster well locations CW-4, 5 and 6 to provide additional information at shallow depths. The Town received USEPA approval to install the wells on August 23, 1993 and the wells were installed by LKB on October 22, 1993. The wells were constructed similar to the proposed off-site gas monitoring wells. LKB drilled an eight inch borehole using a gas powered, hand held auger supplemented by a manual sand auger. A five foot deep, 1 inch diameter PVC gas monitoring well was installed in the borehole. Each well contained a screen length of four feet. The borehole annulus around the screen was backfilled with gravel packing material with a bentonite slurry seal above the screened zone extending to the land surface. The wells were completed approximately three feet above grade with a PVC cap.

GAS MONITORING PROTOCOLS

Wells CW-2, 4, 5, 6, 7, and 8 were sampled for TCL-VOCs and methane on January 21, 1993 and December 3, 1993 by LKB. VOC samples were obtained following the protocols in the OU1 Remedial Design Work Plan using laboratory traps and sampling pumps to collect 250 ml sample volumes. QA/QC procedures outlined in the OU1 Remedial Design Work Plan were followed, including performing one duplicate sample during each monitoring event. The individual TCL-VOCs were analyzed by EcoTest, Inc. using a gas chromatograph. The second round of VOC samples was rejected due to laboratory contamination of the sampling apparatus. The second round was repeated on April 15, 1994. The samples are currently being analyzed by the laboratory. Methane was also monitored at each cluster well using a combustible gas indicator.

SAMPLING RESULTS

The results of the first round of gas monitoring at the on-site cluster wells are summarized in Table K-1. Since there are no current air quality standards for VOC's in ambient air, the sampling results were compared to the current New York State (NYS) Air Guide 1 Annual Guideline Concentrations (AGC) for ambient air. In general, TCL-VOCs were not detected or detected in low concentrations (below the AGC) on-site with the following exceptions. Methylene Chloride was found in several of the cluster wells at concentrations ranging from 12 to 100 ug/m³. However, this compound was also found in the field blank at 24 ug/m³ and is known as a common laboratory contaminant. Chloroform was found in wells CW-2 (6' & 35'), CW-4 (15' & 35'), and CW-7 (15') at concentrations from 24 to 52 ug/m³. Tetrachloroethene was detected in wells CW-4 (15' & 35') and CW-7 (35') at concentrations between 10 and 68 ug/m³.

Chlorobenzene was found in wells CW-4 (15' & 35') and CW-5 (35') at concentrations between 48 and >200 ug/m³ (exceeded the upper quantification limit). The upper quantification limit was exceeded because the sample trap became saturated with the compound before the fixed volume of sample (250 ml) was fully collected. This problem was rectified by the laboratory during the second round of samples, however the data collected in that round was rejected due to laboratory contamination of the sampling apparatus. The upper quantification limit above the respective AGC levels was also exceeded for other compounds including chloromethane (CW-5, 35'); carbon disulfide (CW-5, 35'); vinyl acetate (CW-4, 35'; CW-5, 35'); m+p xylene (CW-4, 35'; CW-5, 35'); total xylenes (CW-4, 35'; CW-5, 35'; CW-8, 35'; CW-8, 35' DUP). For some other compounds detected, the AGC value was greater than the upper quantification limit. Therefore, excursion of the guideline value is unable to be determined.

Methane was detected in only four of the eighteen wells sampled, ranging in concentrations from 1.4 % in well CW-8 (35') to 10.0 % in wells CW-4 (35') and CW-5 (35').


TABLE K-1
SYOSSET LANDFILL
CLUSTER WELL GAS SAMPLING RESULTS - 1/21/93

| COMPOUND | WELL NUMBER AND RESULTS (UG/M3) | | | | | | | | | | | | | | | | GUIDELINES | | |
|------------------------|---------------------------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|--------------|---------------|---------------|--------------|---------------|---------------|-----------------|----------------|------------------------|--------|
| | CW-2 (6') | CW-2 (11') | CW-2 (35') | CW-4 (15') | CW-4 (35') | CW-5 (15') | CW-5 (35') | CW-6 (15') | CW-6 (35') | G-14 (5') | CW-7 (15') | CW-7 (35') | G-13 (5') | CW-8 (15') | CW-8 (35') | CW-8 35' DUP | FIELD BLANK | NYS Air Guide 1 SGC | AGC |
| Chloromethane | - | - | - | - | - | - | >200 | - | 16 | - | - | - | 72 | 68 | - | 36 | - | 22,000 | 770 |
| Bromomethane | - | - | - | - | - | - | - | - | - | - | 12 | - | - | - | - | - | - | 4,524 (I) | 45 (I) |
| Vinyl Chloride | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Chloroethane | - | - | - | 20 | - | - | - | - | - | - | - | - | - | - | - | - | - | 630,000 | 63,000 |
| Methylene Chloride | 60 | - | 100 | 56 | 12 | 76 | 44 | 80 | 12 | 76 | 76 | 40 | - | 76 | 36 | 72 | 24 | 41,000 | 27 |
| Acetone | - | - | - | >200 | - | - | - | - | - | - | - | - | 80 | 68 | >200 | >200 | - | 140,000 | 14,000 |
| Carbon Disulfide | - | - | - | - | - | - | >200 | - | - | - | - | - | - | - | - | - | - | 710 | 7 |
| 1,1 Dichloroethene | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1,1 Dichloroethane | - | - | - | - | 20 | - | 12 | - | - | - | - | - | - | - | - | - | - | 190,000 | 500 |
| 1,2 Dichloroethene | - | - | - | - | 16 | - | - | - | - | - | - | - | - | - | - | - | - | 190,000 | 1,900 |
| Chloroform | 28 | - | 28 | 24 | 52 | 20 | 12 | 16 | - | 20 | 40 | - | - | - | - | - | - | 980 | 23 |
| 1,2 Dichloroethane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 2-Butanone | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 111 Trichloroethane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 110 | 120 | - | 140,000 | 300 |
| Carbon Tetrachloride | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Vinyl Acetate | - | - | - | - | >200 | - | >200 | - | - | - | - | - | - | - | - | - | - | - | - |
| Bromodichloromethane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 8,333 (I) | 83 (I) |
| 1,2 Dichloropropane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1,3 Dichloropropane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Trichloroethylene | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Chlorodibromomethane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 112 Trichloroethane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1,3 Dichloropropane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Bromoform | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 2-Hexanone | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 4-Methyl-2-Pentanone | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 40 | 20 | - | 48,000 | 480 |
| 1122 Tetrachloroethane | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Tetrachloroethene | - | - | - | 68 | 10 | - | - | - | - | - | - | 10 | - | - | - | - | - | 81,000 | 0.075 |
| Chlorobenzene | - | - | - | 48 | >200 | - | >200 | - | - | - | - | - | - | - | - | - | - | 11,000 | 20 |
| Benzene | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Toluene | - | - | - | 28 | 76 | - | >200 | - | - | - | - | - | - | - | 80 | 60 | - | 89,000 | 2,000 |
| Ethyl Benzene | - | - | - | 190 | >200 | - | >200 | - | - | - | - | - | - | - | 60 | 60 | - | 100,000 | 1,000 |
| Styrene | - | - | - | >200 | >200 | - | >200 | - | - | - | - | - | - | - | 180 | 200 | - | 51,000 | 510 |
| o Xylene | - | - | - | - | >200 | - | >200 | - | - | - | - | - | - | - | >200 | >200 | - | 100,000 | 700 |
| m + p Xylene | 40 | - | - | 170 | >400 | - | >400 | - | - | - | 32 | - | 10 | - | 120 | 110 | - | 100,000 | 300 |
| Xylene | 40 | - | - | 170 | >600 | - | >600 | - | - | - | 32 | - | 10 | - | >300 | >300 | - | 100,000 | 300 |

| | | | | | | | | | | | | | | | | | |
|-----------------|---|---|---|-----|------|---|------|---|---|---|---|---|---|---|-----|-----|---|
| Methane (% gas) | - | - | - | 4.5 | 10.0 | - | 10.0 | - | - | - | - | - | - | - | 1.4 | 1.4 | - |
|-----------------|---|---|---|-----|------|---|------|---|---|---|---|---|---|---|-----|-----|---|

- = Not Detected
(I) = Assumed Interim Value

SGC = Short-term Guideline Concentrations
AGC = Annual Guideline Concentrations



| | | | | | |
|--|---|---|---|--|-------------------|
| PREPARED BY LOCKWOOD, KESSLER & BARTLETT, INC. <small>CONSULTING ENGINEERS SINCE 1889 SYOSSET, NEW YORK</small> | CLIENT TOWN OF OYSTER BAY DEPARTMENT OF PUBLIC WORKS SYOSSET, NEW YORK | PROJECT TITLE SYOSSET LANDFILL SECOND OPERABLE UNIT REMEDIAL INVESTIGATION | TITLE ON-SITE LANDFILL GAS CLUSTER WELL LOCATIONS | DESIGN BY TH DRAWN BY GC CHECKED BY TH DATE JUNE 1991 SCALE 1"=200' | FIGURE K-1 |
|--|---|---|---|--|-------------------|





FIGURE K-2

TYPICAL LANDFILL GAS CLUSTER WELL



APPENDIX L
**BACKGROUND INFORMATION TEXT
AND RELATED TABLES AND FIGURES
FROM OU-1 RI REPORT**



REMEDIAL INVESTIGATION REPORT
SYOSSET LANDFILL
SYOSSET, NEW YORK

1.0 INTRODUCTION

Geraghty & Miller, Inc. was retained by the firm of Lockwood, Kessler & Bartlett, Inc. (LKB) under contract to the Town of Oyster Bay to participate in a Remedial Investigation/Feasibility Study (RI/FS) for the Syosset municipal landfill site. LKB provided overall project management and will continue to provide engineering expertise necessary to complete the RI/FS process. This document constitutes the Interim RI Report. The RI was performed in accordance with the protocols and methodologies detailed in the Site Operations Plan (SOP, August 1986), which was approved by the U.S. Environmental Protection Agency (USEPA). The SOP was developed and prepared in accordance with the work plan for the Interim RI to ensure that the RI would be completed in a manner consistent with the National Contingency Plan (NCP).

The RI was conducted to complete data gaps from previous investigations (Table 1) in relation to the hydrogeology, water quality, and potential subsurface gas migration in order to determine the extent of on-site environmental impacts and the potential need for an off-site investigation. The previous investigations referred to in Table 1 were performed by various agencies and/or consultants to address specific issues associated with the site. The ERM-Northeast (ERM) report (1983) was the principal source of background data used to develop the RI work plan and the SOP. The monitoring wells installed during the ERM study were judged to be suitable for water-level and water-quality monitoring purposes based on observations made in the field and the drilling methodologies described in the ERM report. Therefore, these wells were used as monitoring points during the Interim RI. Further, the water-quality data from the ERM report were subjected to the verification process as described in the SOP, and these data were used to develop the RI work plan as described above.

2.0 SITE DESCRIPTION AND HISTORY

The Syosset Landfill is located in central Nassau County in the Town of Oyster Bay, Syosset, New York. The site is roughly rectangular in shape and encompasses approximately 35 acres. The offices and facilities of the Town of Oyster Bay Department of Public Works (TOB-DPW) are located adjacent (east) to the landfill and occupy approximately 18 acres; to-

gether the landfill and the adjacent facilities total approximately 53 acres. Currently the Town of Oyster Bay (TOB) controls access to the site which is fenced in. Topographically, the site is relatively flat and at similar elevation to the surrounding area. The site is characterized by basically a barren landscape with some clumps of trees. This is discussed in greater detail in Section 2.5. As illustrated in Figure 1, the site is bounded by the Long Island Expressway and Miller Road to the southeast, Cerro Wire & Cable Corporation to the southwest, and the Long Island Railroad to the northwest. A residential area and the South Grove Elementary School border the site to the northeast. The entire landfill area is enclosed by a 6-ft high cyclone fence.

There are two recharge basins owned by Nassau County which border the site to the northeast and north and are illustrated on figures provided in the Interim RI report. Nassau County recharge basin RB-284 (0.63 acres) borders the site to the northeast and Nassau County storm-water basin SWB-571 (0.23 acres) borders the site to the north. Both basins collect storm water runoff from the neighboring residential area where the water either evaporates or recharges to the underlying Magothy aquifer.

2.1 Well Inventory

During the Interim RI, a well inventory was performed to determine the locations of public supply wells (pumping and nonpumping) within a 3-mile radius of the site. Industrial wells were also included in the inventory for the area within a 1-mile radius of the site. The 1 mile distance was selected for industrial wells to account for major withdrawals that may affect ground-water flow patterns in the vicinity of the site. The 3-mile distance was selected for public supply wells to ensure all wells being used for consumptive purposes were accounted for within a distance beyond that which could be impacted by a potential leachate plume.

Data collected for this survey were obtained from well records and maps at the New York State Department of Environmental Conservation (NYSDEC) offices in Stony Brook, New York. A summary of data for the public supply and industrial wells is provided in Tables 2 and 3, respectively, and the locations of these wells are shown on Figure 2. The pumpage data (1986), reported in Tables 2 and 3, were the most recent data available in the NYSDEC files. Data on domestic or other users of ground water in the vicinity of the site are not provided because they do not exist; the entire area is serviced by local water districts (Jericho, Hicksville, and Plainview).

2.1.1 Public Supply Wells

As can be seen in Figure 2, although there are four public supply wells within a 1-mile radius of the site (Wells N4133, N4246, N6190, and N6191), none of these wells are currently in service (Table 2). Well N4133 was sealed in 1982 reportedly as a result of odor problems.

According to the Jericho Water District, Well N4246 was disconnected from the water supply system and will likely be sealed as a result of the recent detection of volatile organic compounds (VOCs) in this well (Edwards, pers. comm. 1988). With respect to volatile organic compounds (VOCs) detected in the public supply well N4246, it is unlikely that this well has been impacted by the landfill. This well is located approximately 0.5 miles west of the site, thus conditions at this location are not consistent with conditions at the landfill, given the conclusions presented in this report. According to a representative of the Hicksville water district (Woodwell, pers. comm. 1988), Wells N6190 and N6191 are used only during periods of peak demand, although, as indicated in Table 2, there was no reported pumpage from these wells in 1986.

As seen in Figure 2, there are eight public supply wells (excluding Well N4133) located within 3 miles of the site in the general direction of ground-water flow (northeast)(see Section 4.1.1). The closest of these public supply wells (Wells N198 and N199) are located approximately 2 miles to the northeast. These two wells are screened in a deeper part of the Magothy aquifer (540 to 620 ft below land surface) and are still in service, according to the Jericho Water District (Edwards, pers. comm. 1988).

Public Supply Well N570, the next closest well, is located approximately 0.4 miles northeast of Well N198 and N199. The remaining five public supply wells, located in the northeast quadrant of the map, are either approximately 3 miles from the site and/or are due north or east of the site.

2.1.2 Industrial Wells

According to data obtained from the NYSDEC files, 14 industrial wells (pumping more than 45 gallons per minute [gpm]) are located within 1 mile of the site. The locations of these wells are shown on Figure 2. These wells are screened in the Magothy aquifer at depths ranging from 120 to 440 ft below land surface and are reportedly used for general industrial, air conditioning, or fire protection purposes. Only one of the 14 industrial wells (Well N3838)

is reportedly used for domestic purposes. This well is not located downgradient of the site; rather it is located approximately 0.2 miles west (upgradient) of the landfill. Only three of these wells have withdrawals reported to the NYSDEC in 1986. All owners of private wells are required to report their total pumpage on an annual basis for each well with a flow rate greater than 45 gpm. Two of the wells (N3569 and N6741) with pumpage reported to the NYSDEC are located on Cerro Wire & Cable Corporation's (Cerro) property, adjacent to the site, and are reportedly used for industrial purposes. In 1986, the withdrawal of ground water from Wells N3569 and N6741 was 53 and 115 million gallons, respectively; however, these two wells apparently are no longer in service since Cerro reportedly closed for business in the latter part of 1986. A third well, owned by Reckson Associates (N9842), reported 85 million gallons withdrawn from the Magothy aquifer in 1986; this well is located approximately 0.4 miles northwest of the site.

2.2 Waste Disposal

The Syosset Landfill reportedly began practicing refuse disposal in 1933 and continued until 1967. The only data available on waste characterization are provided in the ERM Northeast Report (1983). According to this report, the waste types accepted included the following: commercial, industrial, residential, demolition, agricultural, sludge, and ash. From 1967 until its close in 1975, the site accepted only scavenger cesspool waste, which was processed at the treatment facility located near the defunct incinerator building, and industrial waste.

Interviews with sanitation department personnel who were involved with the site's daily activities during its period of operation, and a review of aerial photographs of the site have been the sole sources of information on landfill practices. The site was excavated into two cells to depths of approximately 60 to 90 ft below land surface (see Sections 3.2 and 4.3). Segregation of wastes appears to have been limited to scavenger cesspool waste which was treated at the facility mentioned above, and tires which were disposed of along the fence in the vicinity of Well SY-4, as indicated by aerial photographs. Buried combustible fill materials were reportedly ignited and allowed to burn in portions of the landfill.

2.3 Climatology

Long Island has a modified continental climate, resulting from the combined influence of prevailing westerly winds and the proximity to the Atlantic Ocean. Most weather conditions

approach from the continental land mass from the west because of prevailing westerly winds. The climate is relatively humid, with air temperature extremes modified by the Atlantic Ocean and, to a lesser extent, by Long Island Sound. Graphs of air temperature in Garden City, New York, located approximately 8 miles from the study area, indicate that the lowest mean monthly air temperature is 31.4°F (January), and the highest is 74.9°F (July) (Isbister 1966).

The highest temperature recorded at LaGuardia Airport in northern Nassau County was 107°F in July 1966 and the lowest temperature was -3°F in January 1985. Average monthly wind speeds vary from 10.4 miles per hour (mph) in July and August to 14.1 mph in March with the wind speed averaging 12.3 mph for the year. The average wind direction is from the northwest or west-northwest from November through April and from the south from June through September. The average wind direction in March is from the northeast and in October from the southwest with an average wind direction from the south for the year (National Oceanic and Atmospheric Administration 1988).

2.3.1 Precipitation

Precipitation in Nassau County averages 42 inches per year, as determined from 30 years of records collected by the National Weather Service. The annual precipitation recorded in Manhasset, New York from 1938 to 1978 reached a maximum of 64.70 inches in 1975 and a minimum of 22.73 inches in 1965; the long-term average annual precipitation from 1938 to 1978 is 41.95 inches. Mean monthly precipitation in Manhasset ranges from a low of 2.68 inches in June to a high of 4.09 inches in August (Kilburn & Krulikas 1987). At LaGuardia Airport, there is an average of 20 to 25 thunderstorms per year (National Oceanic and Atmospheric Administration 1988).

2.3.2 Evapotranspiration

Evapotranspiration (evaporation and transpiration) in the Upton, New York area of Suffolk County ranges from 15 inches per year in areas where vegetation is thin to approximately 30 inches per year near streams and swamps. In this study area, the average annual evapotranspiration ranges from 22 to 26 inches per year (Isbister 1966).

2.3.3 Recharge

The water-table aquifer (Magothy) is recharged by precipitation which moves downward through the unsaturated zone until it reaches the water table. Precipitation at the site averages 42 inches per year, but as discussed earlier in this report, approximately one-half is lost by evapotranspiration. At the site runoff is considered negligible due to the relatively flat topography, the permeable surface conditions (sparse vegetation and sandy soil), and the absence of surface drainage (ditches, streams, etc.) (Isbister 1966). The remaining precipitation recharges the ground-water reservoir.

No permanent surface-water bodies exist on-site except for a small, isolated, shallow body of water southeast of the defunct incinerator building which mainly drains adjacent pavement and on-site roadways. Given the size of this pond, the area being drained, and the depth to ground water (greater than 100 ft), it would not be possible to isolate the potential impact of this pond from the overall impact of the landfill. This contention is supported by hydrogeologic and water-quality data in the Interim RI report. Drainage for the rest of the site is accomplished mainly by infiltration of precipitation into the subsurface. In the event overland flow (runoff) occurs, this water would only be in contact with the clean cover soil at the site and drained to the recharge basins located north and northeast of the site.

Infiltration rates of ground water are relatively high at the site, which is situated on an outwash plain where loamy soil is underlain by permeable sand and gravel deposits. A few miles north of the site is the Ronkonkoma terminal moraine where infiltration is impeded by extensive deposits of clay and till near the surface.

Infiltration and recharge vary considerably according to the season. Although precipitation is relatively evenly distributed throughout the year, net recharge is highest during winter and early spring when plant activity is at a minimum. During the summer and fall, growing plants utilize most of the precipitation and little, if any, recharge occurs. Runoff is probably also higher in the winter during the relatively brief periods when the ground is frozen (Isbister 1966).

The site is situated in an area defined by the Federal Emergency Management Agency as Zone C, an area of minimal flooding.

2.4 Soils and Vadose Zone

The native soils at the site were removed during its use as a sand and gravel pit. After its use as a landfill, the site was covered with a nearly flat layer of clean, sandy fill which forms the surface soil. This layer is recognized by the soil survey of Nassau County as being an Udorthent soil which consists of deep, excessively drained acid soils typically used at sanitary landfills. Usually, the surface is capped with a loamy veneer to encourage plant growth for stabilization. Udorthent soils are generally loose to firm, yellowish brown or pale brown loamy sand or sand.

2.5 Ecology

The site is located in a highly developed residential and industrial area which is not known to contain ecologically significant habitat. Surrounding land uses include industrial and commercial facilities to the south and west, Town of Oyster Bay Highway Yard to the east, and single-family homes to the north.

Most of the site is completely barren and with the remaining area consisting of sparse to moderately dense groupings of various hardwood trees, shrubs, and ground cover. Dominating tree species appear to be Black Locusts (4- to 8-inch diameter), Common Elder (2- to 6-inch diameter), and Chokecherry (2- to 6-inch diameter). Several varieties of broadleaf weeds, ivy, hawthorns, sumac, and various grasses make up the sparse understory along the perimeter of the property. There was no evidence of significant or protected plant species on or adjacent to the property.

There are no wetlands on or adjacent to the site. However, a low area that is on the northerly side of the site supports the growth of Giant Reed, a common freshwater wetland species. The occurrence of this species is most likely due to the infrequent ponding caused during storm conditions.

The site offers minimal wildlife habitat and does not represent a significant environment. Since residential communities and commercial businesses surround the site, species that are sensitive to human activities, such as the red fox, are not common to this location. A variety of small mammals, such as the cotton-tail rabbit, gray squirrel, rats and mice, field birds and song birds are common inhabitants. Endangered or threatened wildlife

species are not known to inhabit the subject site. The site does not contain habitat such as streams, ponds, or wetlands that might attract migratory bird species.

2.6 Geology

The Syosset Landfill is located on Long Island, New York within the glaciated part of the Atlantic Coastal Plain physiographic province. Hydrogeologic investigations on Long Island and within the vicinity of the Town of Oyster Bay have been conducted by the United States Geological Survey (USGS) (Isbister 1966; Franke and Cohen 1972). These studies generally agree on the geologic description of the deposits underlying the site. The Syosset Landfill is underlain by more than 1,000 ft of unconsolidated deposits of sand, silt, gravel, and clay which rest unconformably on the bedrock surface. The bedrock is Precambrian in age and consists of crystalline metamorphic and igneous rock (schist, gneiss, and granite). The bedrock surface has a fairly constant slope of approximately 80 ft per mile (1.5 percent) and dips in a southeasterly direction (Isbister 1966). The unconsolidated deposits overlying the bedrock surface have an even gentler slope of 60 ft per mile (Isbister 1966).

The bedrock surface is directly overlain by Late Cretaceous deposits known as the Raritan Formation, which consists of two units or members: the Lloyd Sand Member (Lloyd aquifer) and the clay member (Raritan Clay). Beneath the site, the Lloyd Sand is approximately 240 ft thick and rests unconformably on the bedrock surface; the Raritan Clay is a major regional confining unit which is approximately 160 ft thick and overlies the Lloyd Sand (Isbister 1966).

The Magothy Formation, which is also a late Cretaceous deposit, lies unconformably on the Raritan Formation (i.e., Raritan Clay) and is approximately 540 ft thick beneath the site. The Magothy is a regional formation occurring throughout most of Long Island, except locally near the North Shore where erosion has removed parts or all traces of the Magothy and/or Raritan.

The deposits of the Magothy Formation, which are characterized by their light color and fine-grained texture, consist chiefly of interbedded lenses of sand, sandy clay, with varying amounts of silt. The primary mineral of the sandy beds is quartz (angular to subangular) with varying amounts of clay minerals, chert, muscovite, and a small percentage of dark, heavy minerals such as lignite and pyrite. Iron oxide is also found locally abundant.

Although a general value of porosity is frequently assumed to be 30 percent by investigators, Isbister (1966) reports laboratory results from 32 to 41 percent.

Directly above the Magothy Formation lies the Pleistocene outwash deposits known as the Upper Glacial Formation (Upper Glacial aquifer); these deposits are characterized chiefly by stratified coarse sand and gravel. The surface of the Upper Glacial Formation on which the site is situated is known as outwash plain.

2.7 Regional Hydrogeology

Of the three unconsolidated geologic formations underlying the site (Upper Glacial, Magothy, and Raritan), only two are saturated: the Magothy Formation and the Raritan Formation. The Upper Glacial Formation is completely unsaturated in the vicinity of the site. The saturated portion of the Magothy Formation (Magothy aquifer) is the principal source of water for public and industrial use, therefore, most of the hydrogeological discussion will focus on this aquifer. The Lloyd Sand Member of the Raritan Formation is completely saturated (Lloyd aquifer) and is separated (confined) from the Magothy by the Raritan Clay (also saturated), which is a regional aquitard that is approximately 160 ft thick (see Section 2.6). Thus, although the Lloyd aquifer is used for water supply, this aquifer was not investigated because of its depth (approximately 760 ft beneath the site) and the presence of the Raritan Clay (160 ft thick).

2.7.1 Upper Glacial Formation

The Upper Glacial Formation is primarily composed of coarse sand and gravel deposited during the Pleistocene age, which ended approximately 15,000 years ago. These deposits were largely removed from the site due to the excavation (sand and gravel mining) of this material and subsequent filling during its use as a municipal landfill (1933 to 1975). A detailed discussion of the extent of the landfilling is presented in Section 3.2 (Landfill Dimension Study).

Prior to the mining of the sand and gravel deposits, the Upper Glacial Formation was approximately 60 to 100 ft in depth under the site. Unexcavated portions of this formation are found toward the boundaries of the site and beneath the landfill. The permeability of this formation is generally greater than the Magothy, and it serves as the principal source of precipitation recharge to the Magothy. In areas located in the vicinity of (but beyond) the lim-

its of the site where the Upper Glacial Formation is partially saturated, it is known as the Upper Glacial aquifer. The Upper Glacial aquifer and the underlying Magothy aquifer, are generally considered to be a single hydrogeologic unit as they are directly connected hydraulically (i.e., there is no continuous confining unit [aquitard] between the two aquifers).

2.7.2 Magothy Aquifer

The saturated portion of the Magothy Formation (Magothy aquifer) extends from the water-table surface (which occurs at approximately 100 to 115 ft below land surface) to the Raritan Clay. As stated previously, the Magothy aquifer is composed of fine-grained sediments: Interbedded sequences of sand with sandy clay, silt, and clay are prevalent through the unit. In the study area, the Magothy is directly (hydraulically) connected to the overlying Upper Glacial Formation area as no continuous confining beds (aquitards) are present. The Magothy aquifer is separated from the Lloyd aquifer by the Raritan Clay, a regional, continuous aquitard, which limits the ground-water flow between the two ground-water systems.

As a result of the heterogeneous nature of the Magothy aquifer, the water-transmitting properties can vary widely. Although the horizontal hydraulic conductivity in the Magothy aquifer in the vicinity of the site is reported to be approximately 400 gallons per day per square foot (gpd/ft²) (McClymonds and Franke 1972), considerable variation is known to occur throughout this formation.

3.0 METHODOLOGY

In this section, the methodologies employed for the tasks in the Interim RI are reviewed. These methods were described in detail in the SOP. Deviations or changes from the SOP protocols are discussed in the appropriate sections.

3.1 On-Site Ground-Water Study

The On-Site Ground-Water Investigation was designed to expand the existing on-site monitoring well network. This network consisted of seven shallow monitoring wells installed during a previous ground-water investigation by ERM (1983) during which leachate impacts to ground water beneath the site had been identified. As discussed in Section 1.0, the on-site wells previously installed under the supervision of ERM were judged to be suitable for

Table 1. Site Studies for the Syosset Landfill.

| Report | Author/Organization | Date | Content |
|--|--|-------------------------------|---|
| Vent Trench Monitoring | Town of Oyster Bay-DPW | 1981 | Continuous monitoring for methane in vent trench (no report submitted). |
| Methane Survey of the Syosset Landfill | Town of Oyster Bay-DPW | March 15 to April 3, 1981 | Gas samples collected for methane analysis from temporary monitoring points arranged in a grid pattern. |
| "Landfill Gas Migration" | Malcolm Pirnie, Inc. for the Syosset Central School District | June 1982 | Report presents the findings of the Syosset Landfill and the Syosset Central School property studies. Methane has been found, but not other gases. Reports by NCDH and others are appended to this report. |
| Methane Survey of the Syosset Landfill | Town of Oyster Bay-DPW | January 3 to February 1, 1983 | Gas samples collected for methane analysis from temporary monitoring points arranged in a grid pattern. |
| "Investigation of Landfill Impact on Ground-Water Quality" | ERM-Northeast for the Nassau County Dept. of Health (NCDH) | Jan. 1983 | Report on study of ground-water conditions at the Syosset Landfill. The investigation included the installation of seven on-site monitoring wells. The report concluded that ground-water quality was being impacted by landfill leachate. Elevated heavy metal concentrations are present in the leachate. |
| "Preliminary Remedial Action Master Plan (RAMP) for the Syosset Landfill." | C.C. Johnson, Inc./ CDM for the USEPA | May 1983 | RAMP report summarizes the previous work done at the Syosset Landfill and forms the basis for the RI/FS. |

Table 1: Site Studies for the Syosset Landfill.

| Report | Author/Organization | Date | Content |
|--|---|-------------------|--|
| "Capping and Closure of the Syosset Landfill" | Sidney B. Bowne and Son | Dec. 1983 | Conceptual design of cap and gas control measures. Includes data on five borings installed through the landfill. |
| Landfill Migration Study - Updating Supplement | Malcolm Pirnie, Inc. for the Syosset Central School District | Dec. 1983 | Review of data and issues on the Syosset Landfill since 1982 report. The report includes testing for non-methane compounds and evaluation of the gas intercept trench. |
| "Draft Environmental Impact Statement (DEIS) for the Proposed Construction of a 1500 Car Commuter Parking Facility at Landia (Syosset)" | Nassau County Planning Dept. | April 1984 | The DEIS summarizes previous work done at the site and assesses potential environmental impacts of the proposed Landia station. |
| Water-Quality Data (unpublished) | Nassau County | Continuous | NCDH has collected samples from nearby supply wells and the on-site ERM wells. |

2. Summary of Data for Public Supply Wells Located Within 3 Miles of the Syosset Landfill,
Syosset, New York.

| Well | Water District | 1986 Pumpage (thousands of gallons) | Pump Capacity (gallons per minute) | Formation | Screen Interval (feet below land surface) | Distance from Center of the Site (miles) |
|---------|----------------|--|---------------------------------------|-----------|--|---|
| N0149 | Hicksville | 0 | 616 | Magothy | 131-151 | 1.8 |
| N0150 | Hicksville | 0 | 540 | Magothy | 122-142 | 1.8 |
| N0198 | Jericho | 321,172 | 1,100 | Magothy | 566-616 | 1.8 |
| N0199 | Jericho | 289,231 | 1,120 | Magothy | 544-600 | 1.9 |
| N0570 | Jericho | 277,837 | 1,000 | Magothy | ? | 2.2 |
| N2072 | Hicksville | 0 | 750 | Magothy | 138-159.25 | 1.6 |
| N3878 | Hicksville | 53,947 | 1,200 | Magothy | 375-428 | 2.4 |
| N3953 | Hicksville | 0 | 1,200 | Magothy | 169-213 | 2.4 |
| | | | | | 370.75-418.75 | |
| N4095 | Plainview | 284,203 | 1,200 | Magothy | 440-490 | 2.9 |
| N4096 | Plainview | 55,580 | 1,200 | Magothy | 444-495 | 2.9 |
| N4097 | Plainview | 68,662 | 1,200 | Magothy | 413-463 | 1.9 |
| N4133 | Jericho | 0 | 1,000 | Magothy | 400-450 | 0.19 * |
| N4245 | Jericho | 369,887 | 1,194 | Magothy | 525-565 | 1.4 |
| N4246 a | Jericho | 0 | 1,140 | Magothy | 403-453 | 0.48 * |
| N6076 | Plainview | 81,885 | 1,200 | Magothy | 191.83-253.25 | 1.9 |
| N6077 | Plainview | 141,283 | 400 | Magothy | 398-459.58 | 1.9 |
| N6092 | Jericho | 252,585 | 1,200 | Magothy | 561-631 | 2.9 |
| N6093 | Jericho | 90,524 | 1,200 | Magothy | 546-606 | 2.9 |
| N6190 b | Hicksville | 0 | 1,200 | Magothy | 550-600 | 0.77 * |
| N6191 b | Hicksville | 0 | 1,200 | Magothy | 390-451 | 0.80 * |
| N6192 | Hicksville | 53,505 | 1,400 | Magothy | 575.16-626.58 | 3.0 |
| N6193 | Hicksville | 0 | 1,400 | Magothy | 396.33-456.41 | 2.94 |
| N6580 | Plainview | 306,029 | 1,200 | Magothy | 418.75-495.75 | 2.1 |
| N6651 | Jericho | 355,344 | 1,200 | Magothy | 560-610 | 1.3 |
| N7030 | Jericho | 114,101 | 1,230 | Magothy | 480-530 | 2.8 |

Data obtained from the NYSDEC offices, SUNY at Stony Brook, New York.

* Measured from the nearest boundary of the landfill.

a Well is reportedly no longer in service due to detection of volatile organic compounds and water main break.

b Well is reportedly used on a part-time basis during periods of high demand.

-- Data not available.

GERAGHTY & MILLER, INC.

Table 2. Summary of Data for Public Supply Wells Located Within 3 Miles of the Syosset Landfill,
Syosset, New York.

| Well | Water District | 1986 Pumpage (thousands of gallons) | Pump Capacity (gallons per minute) | Formation | Screen Interval (feet below land surface) | Distance from Center of the Site (miles) |
|--------|----------------|--|---------------------------------------|-----------|---|---|
| N7526 | Plainview | 61,967 | 1,280 | Magothy | 570-585.5 600.75-611.16 621.19-641.63 661.83-687.75 687.75-690.75 | 2.68 |
| N7562 | Hicksville | 372,653 | 1,400 | Magothy | 458-519 | 1.7 |
| N7772 | Jericho | 221,156 | 1,220 | Magothy | 502.75-562.75 | 2.8 |
| N7773 | Jericho | 161,543 | 1,180 | Magothy | 416.08-476.08 | 2.8 |
| N7781 | Jericho | 317,129 | 1,240 | Magothy | 394-454 | 1.5 |
| N8043 | Jericho | 432,549 | 1,200 | Magothy | 515-688.42 | 1.9 |
| N8249 | Hicksville | 206,378 | 1,400 | Magothy | 299.66-389.58 | 1.7 |
| N8355 | Jericho | 100,463 | 1,200 | Magothy | 520-570 | 1.3 |
| N8778 | Hicksville | 87,657 | 1,400 | Magothy | 529-590 | 2.6 |
| N8779 | Hicksville | 221,640 | 1,400 | Magothy | 524.25-585 | 2.7 |
| N9180 | Hicksville | 346,533 | 1,400 | Magothy | 545-576 598-630 | 2.9 |
| N9463 | Hicksville | 285,657 | 1,200 | Magothy | 560-595 603-638 | 2.5 |
| N9488 | Hicksville | 136,251 | 1,380 | Magothy | 515-575 | 1.6 |
| N10208 | Hicksville | 130,848 | 1,750 | Magothy | 572-624 634-644 | 2.7 |
| N10555 | Hicksville | 0 | -- | Magothy | 608-693 | 2.4 |


Data obtained from the NYSDEC offices, SUNY at Stony Brook, New York.

- * Measured from the nearest boundary of the landfill.
- a Well is reportedly no longer in service due to detection of volatile organic compounds and water main break.
- b Well is reportedly used on a part-time basis during periods of high demand.
- Data not available.


Table 3. Summary of Data for Industrial Wells Located Within 1 Mile of Syosset Landfill, Syosset, New York.

| Well | Owner | 1986 Pumpage (thousands of gallons) | Pump Capacity (gallons per minute) | Formation | Screen Interval (feet below land surface) | Distance from the nearest Boundary of the Syosset Landfill (miles) | Reported Use |
|-------|-------------------------------|--|--|-----------|--|--|------------------|
| N3569 | Cerro Wire & Cable Corp. | 53,353 | 1,000 | Magothy | 353-402 | 0.08 | General |
| N3834 | Geo Spohrer | * | 4 | Magothy | 189-193 | 0.53 | Shop |
| N3838 | Fairchild Camera & Instrument | * | 50 | Magothy | 153-163 | 0.31 | Domestic |
| N3850 | Fairchild Camera & Instrument | * | 750 | Magothy | 400-440 | 0.25 | Fire Protection |
| N3860 | Fairchild Camera & Instrument | * | 750 | Magothy | 400-440 | 0.31 | Fire Protection |
| N3874 | Fairchild Camera & Instrument | * | 300 | Magothy | 310-330 | 0.26 | Industrial |
| N5354 | Geo Spohrer | * | 16 | Magothy | 259-264 | 0.45 | Bathroom |
| N5901 | Certified Redi-Mix Co., Inc. | * | 45 | Magothy | 137-148 | 0.72 | Concrete Mixing |
| N6531 | Riverside Plastics Corp. | * | 40 | Magothy | 114-119 | 0.65 | Air Conditioning |
| N6741 | Cerro Wire & Cable Corp. | 115,303 | 1,000 | Magothy | 374-424 | 0.11 | General |
| N7052 | Syosset Hospital | * | 330 | Magothy | 223-253 | 0.68 | Air Conditioning |
| N8436 | Riverside Plastics Corp. | * | 300 | Magothy | 159-179 | 0.84 | * |
| N8517 | Great Atlantic Realty Co. | * | 130 | Magothy | 248-273 | 0.78 | Cooling |
| N9842 | Reckson Associates | 85,302 | 350 | Magothy | 262-297 | 0.36 | * |

Data obtained from the NYSDEC offices, SUNY at Stony Brook, New York.
Wells included in this table have withdrawals greater than 45 gallons per minute.
* Data not reported to the NYSDEC.



**LOCATIONS OF PUBLIC SUPPLY WELLS WITHIN
A 3-MILE RADIUS AND INDUSTRIAL WELLS WITHIN
A 1-MILE RADIUS OF THE SYOSSET LANDFILL,
SYOSSET, NEW YORK**



0 200 FT
SCALE

EXPLANATION

- SY-3 ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF ERM-NORTHEAST
- SY-2R ON-SITE SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- △ SY-3D ON-SITE DEEP MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- B-3/W-4 ON-SITE LANDFILL DIMENSION STUDY SOIL BORING/SHALLOW MONITORING WELL INSTALLED UNDER THE SUPERVISION OF GERAGHTY & MILLER, INC.
- 79.5 LINE OF EQUAL POTENTIOMETRIC SURFACE ELEVATION IN FEET ABOVE MEAN SEA LEVEL (DASHED WHERE INFERRED)
- ← DIRECTION OF HORIZONTAL COMPONENT OF GROUND-WATER FLOW

SOURCE: LOCKWOOD, KESSLER & BARTLETT, INC.
SYOSSET, NEW YORK

POTENTIOMETRIC SURFACE OF THE SHALLOW ZONE (51 TO 71 ft msl) OF THE
MAGOTHY AQUIFER ON OCTOBER 27, 1988, Syosset Landfill, Syosset, New York

APPENDIX M

REGIONAL BACKGROUND GROUNDWATER QUALITY



APPENDIX M

REGIONAL BACKGROUND GROUNDWATER QUALITY

Groundwater is the sole source of drinking water on Long Island (Nassau and Suffolk Counties). As such, maintaining high quality drinking water is important. When volatile organic compounds, tetrachloroethylene (PCE) and trichloroethylene (TCE), were detected in supply wells in the southeastern part of Nassau County in 1975, the Nassau County Department of Health (NCDH) launched a series of investigations to evaluate regional groundwater quality conditions. One of these studies (Dvirka and Bartilucci Consulting Engineers 1986) was a preliminary investigation of five areas of aquifer segments contaminated with VOCs (New Cassel, Garden City Park, West Hicksville, New Hyde Park, and North Hicksville). During this study, a total of 96 wells were sampled, which included 18 public supply wells. Most of these wells are screened in the Upper Glacial aquifer but many are screened in the Magothy aquifer. VOC contamination was found in all five study areas, and this contamination was characterized as being widespread in three of these areas.

The probable source of the VOC contamination in four of the five study areas was identified as industrial areas near the LIRR tracks. A similar industrial area is present directly adjacent (west) to the LIRR tracks that also border the Syosset Landfill. In the Dvirka and Bartilucci study, the VOC contamination was found at highest concentrations, and most frequently, in the Upper Glacial aquifer, but VOCs were also observed deep in the Magothy (more than 500 feet below land surface). In the New Cassel Study Area, 17 of the 35 wells sampled had concentrations of VOCs exceeding the then current New York State guidelines for organic compounds in drinking water. The principal VOCs detected (i.e. at highest concentrations and frequencies) were 1,1,1-trichloroethane (TCA), PCE, and TCE. In the Garden City Park Study Area, nine of the 17 wells sampled had VOC concentrations exceeding the New York state guidelines with PCE and TCE as the principal VOCs. One well screened in the upper part of the Magothy Formation had total VOC concentrations of approximately 200 ug/L.

Included in the Dvirka and Bartilucci report is a discussion of regional groundwater quality and VOC contamination is described as fairly widespread in Nassau County and considered a major threat



to the water supply. VOC data collected between 1976 and 1984 from 434 public supply wells and 437 monitoring wells screening the Upper Glacial, Magothy and Llyod aquifers were obtained by NCDH and included in a table in the Dvirka and Bartilucci report. This table has been reproduced by Geraghty & Miller and is included as Table A-1 (attached). According to this data, of the 434 public supply wells sampled for VOCs, 21 percent had concentrations of up to 10 ug/L, 8 percent had concentrations from 10 ug/L to 50 ug/L, and 3 percent had concentrations greater than 50 ug/L. Of the 437 monitoring wells sampled, 28 percent contained VOC concentrations of up to 10 ug/L, 19 percent contained VOCs at concentrations from 10 ug/L to 50 ug/L, and 18 percent contained VOC concentrations over 50 ug/L.

It was stated in the Dvirka and Bartilucci report "In addition to industrial and commercial waste disposal, an extensive investigation into the uses of toxic household products determined that unsewered residential areas may also be a significant source of organic contamination (i.e., VOCs) of groundwater." The residential area downgradient of the Syosset Landfill is a residential area that was recently sewered about 15 years ago after the landfill closed (Viscardi, pers. comm. 1994). According to the Town of Oyster Bay, the average population density of Syosset is 3,766 people per square mile, or 5.88 people per acre (Rufrano, pers. comm. 1994). The actual population density in the residential development downgradient of the landfill is likely more than 10 people per acre because there is virtually no open space and, based on site visits, the houses are built on quarter-acre lot sizes or less. Therefore, assuming conservatively that there are three houses per acre and four persons residing in each house, then the population density calculates to 12 people per acre.

Five areas of different land use on Long Island located near the regional groundwater divide (long-term sewered suburban, recently sewered suburban, unsewered suburban, agricultural, and undeveloped) were the subject of a recent U.S. Geological Survey (USGS) study to statistically relate shallow contaminant distribution to land use (Leamond and Haefner, et. al 1992). Fourteen of the 19 wells sampled in the recently sewered area (defined in the report as having had sewer hookup beginning about 1980 or approximately 14 years ago) were found to contain VOCs. VOC detections occurred with the highest frequency in the recently sewered study area. The most commonly detected



VOCs were TCA, TCE, and PCE with total concentrations ranging from 2 ug/L to more than 12,000 ug/L. In five of these wells, VOCs were detected at concentrations above 29 ug/L.

Another USGS paper (Cain, Helsel, and Ragone 1989) also evaluates the degradation of regional groundwater quality (especially VOCs) as a result of human activities. Data from studies in six different states, including one on Long Island, New York, were used in the evaluation. All the studies were designed to quantitatively relate human activities, expressed as land use, to regional groundwater quality. For the Long Island study, water-quality data from 903 wells screened in the Upper Glacial aquifer were evaluated. The most commonly detected VOCs were TCA (24 percent of wells sampled), PCE (20 percent of wells sampled), TCE (18 percent of wells sampled), chloroform (9 percent of wells sampled) and 1,2-dichloroethylene (5 percent of wells sampled). In commercial or industrial areas, TCE, TCA, and PCE were detected in about 40 percent of wells sampled, while in medium to high-density residential areas, 20 to 40 of the wells sampled contained these VOCs. By using a simple linear regression, the percentage of occurrence of two of the more commonly detected VOCs (TCA and TCE) in the groundwater in the Long Island study were related to population density.

This relationship is graphically represented in Figure A-1 and clearly demonstrates a direct correspondence between the two parameters (i.e., as population density increase so does the frequency of detection of VOCs). For example, Figure A-1 shows that with a population density equivalent to Syosset (approximately 12 people per acre) TCA and TCE would be expected to be detected in approximately 50 percent of any group of wells sampled in this area.

In yet another NCDH study, from 1977 to 1986, 46 public supply wells were restricted from use because individual VOCs had been detected above the 1977 New York State Department of Health guideline of 50 ug/L (NCDH 1988). Most of these wells are located in an east-west band across central Nassau County, close to the regional groundwater divide (Proceedings 1993).

In summary, the Syosset Landfill is located adjacent to an industrial area near the LIRR tracks and also adjacent to a recently sewerred, densely populated residential area, which is close to the regional groundwater divide in central Nassau County. The investigations cited above were conducted in a



setting strikingly similar to Syosset Landfill and the results indicate a similar range in VOC concentrations as those detected at the landfill. Thus, the documented regional degradation of groundwater provides strong supporting evidence that the VOC contamination detected in the Syosset Landfill study area is consistent with the findings of these studies.

G:\PROJECT\LOCKESBA\NY0029.099\REPORTS\ATACHMTM.DOC



Table M-1. Summary of VOC Data Collected From Public Supply Wells and Monitoring Wells in Nassau County (1976 TO 1984).

| | Number of Wells Tested | Percentage of Wells with no Detected VOCs | Percentage of Wells with VOC Concentrations of Less than 10 ug/L for any Single VOC | Percentage of Wells with VOC Concentrations from 10 to 50 ug/L for any Single VOC | Percentage of Wells with VOC Concentrations Greater than 50 ug/L for any Single VOC |
|---------------------------------|------------------------------|---|---|---|---|
| <u>Public Supply Wells</u> | | | | | |
| Upper Glacial Aquifer | 43 | 53 | 30 | 7 | 9 |
| Magothy Aquifer | 348 | 69 | 20 | 9 | 2 |
| Lloyd Aquifer | 43 | 79 | 19 | 2 | 0 |
| Subtotal | 434 | 69 | 21 | 8 | 3 |
| <u>Monitoring Wells</u> | | | | | |
| Upper Glacial Aquifer | 283 | 29 | 31 | 24 | 15 |
| Magothy Aquifer | 142 | 44 | 22 | 11 | 23 |
| Lloyd Aquifer | 12 | 83 | 17 | 0 | 0 |
| Subtotal | 437 | 36 | 28 | 19 | 18 |
| <u>Aquifer Composite Totals</u> | | | | | |
| Upper Glacial Aquifer | 326 | 33 | 31 | 22 | 14 |
| Magothy Aquifer | 490 | 62 | 20 | 10 | 8 |
| Lloyd Aquifer | 55 | 80 | 18 | 2 | 0 |
| TOTAL | 871 | 52 | 24 | 14 | 10 |

VOCs: Volatile organic compounds.

Note: Percentage of wells with respective VOC concentrations was based on the maximum level of any single VOC which was detected in the last sample collected from each well.
This includes all wells (including abandoned wells) that were sampled for VOCs and benzene, toluene, and xylenes since 1976.

Source: Dvirka and Bartilucci Consulting Engineers (1986) and Nassau County Department of Health.

G:\PROJECT\LOCKESBA\NY0029\REPORTS\TABLEM-1.TAB



REFERENCES

- Cain, D., D.R. Helsel, and S.E. Ragone. 1989. Preliminary Evaluations of Regional Groundwater Quality in Relation to Land Use. Ground-Water vol. 27, no. 2, pp. 230 - 244.
- Dvirka and Bartilucci Consulting Engineers. 1986. Investigation of Contaminated Aquifer Segments, Nassau County, New York. Nassau County Department of Health, June 1986.
- Leamond, C.E., R.J. Haefner, et al. 1992. Ground-Water Quality in Five Areas of Differing Land Use in Nassau and Suffolk Counties, Long Island, New York, 1987 - 1988. U.S. Geological Survey Open File Report 91 - 180, 67 pp.
- Nassau County Department of Health. 1988. Assessment of Groundwater Contamination by a Broad Spectrum of Organic Chemicals and Heavy Metals, Nassau County 1980 - 1986. January 1988.
- Proceedings. 1993. Proceedings of the Conference on Water Quality on Long Island. State University of New York at Stonybrook. January 26, 1993.
- Rufrano, R. 1994. Town of Oyster Bay, Department of Public Information. Telephone Conversation with N.H. Benowitz, Geraghty & Miller, Inc., September 29, 1994.
- Viscardi, M. 1994. Nassau County Department of Public Works, Division of Sanitation. Telephone Conversation with V.J. Glasser, Geraghty & Miller, Inc., September 26, 1994.



APPENDIX N

CORRECTION FACTORS USED FOR GAMMA LOGS



APPENDIX N

CORRECTION FACTORS USED FOR GAMMA LOGS

During the OU-2 RI, two deep well borings (SY-3DD and PK-10D) were drilled by the air-rotary (Barber) method using steel casing. Due to the frictional resistance of drilling these borings to a depth of over 500 feet, several different casing diameters (16-inch, 10-inch, 8-inch, and 6-inch) were required to reach the termination depths of these two well borings. These casings are telescoped within each other with all the casing sizes present in the interval from land surface to the termination depth of the largest casing size (16-inch diameter). When the final depth of each boring was reached (540 feet for Well Boring SY-3DD and 500 feet for PK-10D), only the smallest casing size remained (6-inch diameter casing for Well Boring SY-3DD and 8-inch diameter casing for Well Boring PK-10D). Each well boring was then logged by the natural gamma method using an EG&G Mount Sopris Model II logging system. Mount Sopris, Inc., the manufacturer of the logging system, is owned by Colog, Inc. (Colog), and both companies are located in Golden, Colorado.

According to Colog, steel casing dampens the gamma log response in direct proportion to the wall thickness of the casing. Borehole diameter also dampens the gamma log response (in direct proportion to the diameter), but to a much lesser degree. Adjustments are not routinely made to correct for either casing or borehole diameter interferences, especially when these factors are constant for the depth of the borehole. However, because these factors were not constant due to the telescoped casings, a correction factor was developed for the casing interferences. A correction factor was not used for the borehole diameter because, as noted above, the dampening effect on the gamma log response is not significant for this parameter. According to Colog, computer models have been run by Mount Sopris to quantify correction factors for gamma logs run inside of steel casings of varying thicknesses. Colog informed Geraghty & Miller that computer modeling has also been performed by Mount Sopris to determine correction factors for telescoped casings, and if the telescoped casings are close in diameter (i.e., with less than 2-inches of annular space), then they can be regarded as a single casing. Thus, the composite thickness, which is equivalent to the sum of the thicknesses of each individual casing, was then used to obtain the corresponding correction factor from the attached graph (Figure E-1). A summary of the factors that were used for each interval of telescoped steel casing to correct the gamma logs run in Well Borings SY-3DD and PK-10D is presented in Table E-1. Once the correction factor was determined, it was used as a multiplication factor for the gamma radiation count



rate to calculate the adjusted natural gamma log response depicted on Figures 3-1 and 3-2 in the OU-2 RI report.

No correction factor was provided for the depth interval of each well boring that included the 16-inch diameter casing because the annular space between this casing and the next smaller diameter casing (10-inch) is too large (i.e., 4 inches). An annular space of this size causes too many attenuations because the gamma waves cannot penetrate the inner casing (10-inch) properly after penetrating the outer casing (16-inch) and travelling through the annular space. Because the 16-inch diameter casing was used to case off the rather coarse and homogeneous deposits of the Upper Glacial aquifer, the missing data from this zone was not an important factor in preparing hydrogeologic cross sections.

G:\PROJECT\LOCKESBANY0029.099\REPORTS\ATCHMTN.DOC



Table N-1. Correction Factors Used for Well Casing Interferences for Gamma Logs of Well Borings SY-3DD and PK-10D.

| Well Boring Number | Depth Interval (ft bls) | Casings Present per Depth Interval (diameter in inches) | Composite Casing Thickness ^(a) (inches) | Correction Factor |
|--------------------|-------------------------|---|--|-------------------|
| SY-3DD | 0 - 118 | 6, 8, 10, 16 | 1.342 | (b) |
| | 118 - 318 | 6, 8, 10 | 0.967 | 3.52 |
| | 318 - 462 | 6, 8 | 0.602 | 2.50 |
| | 462 - 540 | 6 | 0.280 | 1.62 |
| PK-10D | 0 - 118 | 8, 10, 16 | 1.062 | (b) |
| | 118 - 460 | 8, 10 | 0.687 | 2.75 |
| | 460 - 500 | 8 | 0.322 | 1.74 |

ft bls Feet below land surface.

- (a) According to the firm that drilled the well borings, Delta Well and Pump Company, Inc., the thickness of the 16-inch diameter casing, 10-inch diameter casing, 8-inch diameter casing, and 6-inch diameter casing are 0.375 inches, 0.365 inches, 0.322 inches and 0.280 inches, respectively.
- (b) No correction factor was provided for the depth interval that included the 16-inch diameter casing in each well boring because the annular space between this casing and the next smaller diameter casing (10-inch) is too large. An annular space of this size causes too many attenuations because the gamma waves cannot penetrate the inner casing (10-inch) properly after penetrating the outer casing (16-inch) and travelling through the annular space.

G:\PROJECT\LOCKESBA\NY0029.099\REPORTS\TABLEN-1.TAB



APPENDIX 0

JULY 13, 1995 INDUSTRIAL AREA SURVEY MEMO



MEMORANDUM

TO: John Lekstutis, P.E. - Lockwood, Kessler & Bartlett, Inc. (LKB)
FROM: Michael Wolfert - Geraghty & Miller, Inc. *MW*
DATE: July 13, 1995
SUBJECT: Industrial Area Survey Adjacent to the Syosset Landfill, Syosset, New York

An historical record search of the 300 Michael Drive property and vicinity has been completed. This search was carried out to determine whether potential sources of the volatile organic compounds found in Well RW-12I exist in the vicinity of the Syosset Landfill. In order to obtain mapped information, a street address had to be specified and, therefore, 300 Michael Drive was selected as the approximate center of our search area. The historical record search consisted of the following specific elements: a review of historical aerial photographs, a review of the New York State Department of Environmental Conservation (NYSDEC) spill log, an environmental regulatory database search, a review of building department documents to identify past owners of properties within a 1/2-mile radius of the target area, a review of Syosset Fire Department records, a review of Sanborn Fire Insurance maps, a site reconnaissance to document current operations within a 1/2-mile radius of the target area, review of information gathered from the Nassau County Department of Public Works concerning waste discharges prior to the installation of the municipal sewer system, and review of data obtained from Freedom of Information Law (FOILs) letters sent to the Nassau County Department of Health. The results of the historical record search are discussed below (see Appendix C for a location map showing some of the properties discussed in this memo).

Aerial Photographs

Aerial photographs of the Michael Drive property taken in 1950, 1957, 1962, 1964, 1966, 1969, 1972, 1978, 1984, 1988, and 1992 were reviewed at the Office of Lockwood, Kessler, and Bartlett, Inc. The 1950 photograph showed no development of the property. The 1957 and 1962 photographs showed slight development of the property. The area becomes more densely developed in



the 1964 and 1988 photographs, with the two lagoons associated with the Cerro Wire property observable to the west side of the Town of Oyster Bay animal shelter. The 1992 aerial photograph shows the property as it exists today.

NYSDEC Spill Log

The NYSDEC began keeping records of spills occurring at properties throughout New York State in 1978. A review of the NYSDEC spill log (through 1993) revealed no reported spills on the Michael Drive property; however, eight spills in the vicinity of the property were contained in the spill log. According to the information contained in the spill log, five of the spills have been closed out (indicating that they were addressed and/or remediated to the satisfaction of the NYSDEC). Those five spills each involved no more than 5 gallons of Number 2 fuel oil which spilled on land. Three spills are still considered active. The three active spills involved a 25-gallon spill of heating oil, a 5-gallon spill of heating oil, and a 5-gallon spill of waste oil. All spills were on land surface. A copy of the NYSDEC spill log is attached to this memo (Appendix A).

Environmental Database Search

Environmental Data Resources, Inc. (EDR) of Southport, Connecticut was contracted to obtain federal and state regulatory databases consistent with the site assessment guidelines established by the American Society of Testing and Materials (ASTM). The environmental regulatory databases searched include the National Priorities List, USEPA Hazardous Waste Treatment, Storage, and Disposal facility list, New York State Inactive Hazardous Waste site list, CERCLIS list, Leaking Underground Storage Tank list, Registered Underground Storage Tank list, USEPA Large and Small Quantity Hazardous Waste Generators list. The Michael Drive property does not appear on any of the lists, nor do any adjoining properties. While not an adjoining property to Michael Drive, the Fairchild (now Loral) site on Robbins Lane is on the CERCLIS list. One adjoining property (Cerro Wire and Cable Company) was formerly listed as a Class 2 inactive hazardous waste disposal site by the NYSDEC. A Class 2 site is defined as posing a significant threat to the public or environment. During



the past 5 years, the property has been investigated and has undergone remediation. According to the January 1994 Quarterly Status Report of Inactive Hazardous Waste Sites, prepared by the NYSDEC, the status of the Cerro Wire and Cable Company property has been downgraded to a Class 4 site. A Class 4 site is one which has been properly closed, but requires continued management. A copy of the regulatory database list is attached to this memo (Appendix B).

Building Department Review

Records on file with the Town of Oyster Bay Building Department were reviewed to determine current/past ownership of properties located within a 1/2-mile radius of the target property (see attached location sketch [Appendix C]). A list of the past owners of the properties has been developed and is attached (Appendix D). The current tenants of the 26 commercial/industrial parcels of property shown in the location sketch are listed in Table 1 (Appendix E). No records of environmental impact concerning the Michael Drive property or adjacent properties were found at the Building Department. Attached to this memo are copies of Building Department Certificates of Occupancy and a 50-year Chain-of-Title for the 300 Michael Drive property (Appendix F).

As part of the Building Department review, Geraghty & Miller obtained tax map identification numbers for all of the properties identified in the 1/2-mile radius search. With the tax map numbers, Geraghty & Miller was able to determine past ownership (title) of each property going back as much as 40 years. Based on the results of the title search, several properties in the search radius were at one time or another owned by such entities as the U.S. Navy, Metallurgical Processing Corp., Fairchild Instrument Corp., and Great Eastern Printing Co. In addition, at one time a large portion of the radius area was used as an airport (Hicksville Airport). Because of the potential uses of these properties (based on their record of ownership), Geraghty & Miller submitted FOIL requests to the Nassau County Health Department (NCHD) to obtain available records for these properties. These properties are highlighted on the attached location sketch (Appendix C). A discussion of the findings of the FOIL requests is provided later under the section Freedom of Information Law.



Syosset Fire Department

Geraghty & Miller interviewed Mr. Robert Swanson of the Syosset Fire Department to investigate known spills along the Long Island Railroad tracks. Mr. Swanson has worked for the Syosset Fire Department for 30 years and currently holds the position of Fire District Supervisor. According to Mr. Swanson, no chemical spills have occurred on the section of the Long Island Railroad tracks that traverse the target area, i.e. the 1.5-mile stretch of track extending between Jericho Turnpike and Robbins Lane.

Sanborn Fire Insurance Maps

Sanborn Geotechnical Mapping Company found no maps on record for the Michael Drive property or vicinity. Sanborn maps are generally more available for urban areas than suburban areas. The lack of maps for the Michael Drive area indicates they have not mapped the area and bears no relation to existence or absence of environmental problems.

Site Reconnaissance

Geraghty & Miller documented current business operations within a 1/2-mile radius of the target property to the extent amenable to visual confirmation. During the site reconnaissance, numerous unlabelled drums were observed stored outside the building occupied by Ademco at the end of Oak Drive (see map in Appendix C for Oak Drive location). The contents of the drums are unknown as is the purpose of chemical usage by Ademco. No visible evidence of drum spillage or leakage was observed.

Municipal Sewer System

To determine when the area was first connected to the municipal sewer system, Geraghty & Miller contacted Mr. J. Viscardi at the Nassau County Department of Public Works. According to Mr.



Viscardi, in general, the area around Michael Drive and Eileen Way was connected to the municipal sewer system during the years 1987 and 1988. Therefore, discharges that currently enter the municipal system from this area could have been discharged directly into area soils via on-site septic systems and leaching pools prior to 1987/88.

Nassau County Department of Public Works

In an attempt to investigate potential discharges prior to the installation of municipal sewers, Geraghty & Miller contacted the office of Mr. Maurice Osman of the Nassau County Department of Public Works Sewer Division. Mr. Osman is the person who would have knowledge concerning this issue. On Monday, May 8, 1995, Mr. Osman was contacted by telephone. According to Mr. Osman, only one property in the Michael Drive or Eileen Way area has a historical record of non-compliance with regard to chemical usage and disposal. The property is located at 300 Michael Drive (approximately at the center of our search radius). The property is currently owned by Ruser Realty and used by Caligor Hospital Supply Company and New Breed Corporation Integrated Logistical Services. These two operators are operating in compliance with NCDPW. However, during the 1970's when the property was operated by Lyn-Pac Cardboard, Great American Container, and Columbia Container, waste disposal was a constant area of non-compliance.

According to Mr. Osman, on-site operations involved the manufacturing and printing of cardboard boxes. Chemicals used on-site during those operations involved inks, dyes, paints, prewashes, thinners, proof wash and rinses, lubricating oils, and solvents. According to Mr. Osman, the site operators reportedly used a hold and haul method of waste disposal. When the area was connected to the sewer system, the operators applied to discharge their waste to the sewer, but the NCDPW refused to accept their waste unless it was pretreated. According to Mr. Osman, the operators never implemented a pre-treatment system and continued with the hold and haul method until they ceased operation on the site some time in the 1980s.



According to Mr. Osman, whenever he inspected the property, there were typically housekeeping issues of non-compliance such as outside chemical storage and soil staining in the area where chemicals were stored. We are currently attempting to obtain analytical data on this property from Mr. Osman.

Freedom of Information Law

As a result of our FOIL requests (Bureau of Environmental Management and Bureau of Environmental Engineering files), we visited the NCHD on May 16, 1995. Review of the NCHD records revealed the following:

- Metallurgical Processing Corp., 180 Michael Drive, Syosset.
 - Metallurgical Processing Corp. conducted a heat treating and plating operation on-site. Cd, Cr, Cu, Fe, Ni, Zn, Chlorine, Cyanide, Fluorides, Sulfides, and Tin were utilized in the processes conducted on-site and were analyzed for in discharge. There was no information on file in reference to any other chemicals being utilized on-site.
 - April 16, 1979 NYSDEC deleted the SPDES permit for Metallurgical Processing because they were no longer discharging to the sewers.
 - September 20, 1978 Plating operation terminated & equipment and chemicals to be moved to S.Plainfield, NJ.
 - August 16, 1978 NCHD noted chemical water on floors, plant grounds in poor condition, and carboys (large containers of liquid) of acid stored in open drums containing waste sludge and drums were beginning to leak.
 - Discharge flow rates & chemical analysis data from 1973 to 1978.
 - Business closed from November 1976 to October 1977 and June 1978 to December 1978 (reason for closing not indicated).
 - April 17, 1975 SPDES permit issued NY0076244 for discharge to sewer. There was no information in the file in reference to the where the water was discharged prior to this permit.
 - 1-21-75 and 1-16-78 NYSDEC Inspection form reported that treatment facility was in poor condition and sloppy housekeeping.
 - September 13, 1967 Storm water and cooling water is going to be disposed of by 4 existing leaching pools when the waste treatment facility is constructed. Not clear if treated wastewater was also to be discharged to leaching pools.



- Emro Dry Cleaners, 235 Robbins Lane, Syosset.
 - A 275-gallon aboveground outdoor fuel oil tank was registered and approximately 100-gallons (average quantity) of Tetrachloroethene (Perchloroethylene), which is stored inside the building, was also registered with the Nassau County Department of Health on July 9, 1990.
 - There was no information on file in reference to when Tetrachloroethene (Perchloroethylene) was initially stored on-site.
- Pax Surface Chemical, Inc., 235A Robbins Lane, Syosset.
 - Chemical Storage area within building. The following chemicals and their average quantity were registered with the Nassau County Department of Health on August 17, 1992: D-Tarnich 1364, 25-gallons; Paxstrip 530, 25-gallons; Paxtique 1401, 10-gallons; Paxtique 1420, 20-gallons; Paxbrite 408, 150-gallons; Chemseal 330, 5-gallons; Chemmax 836, 220-gallons; Anionic Surfactant 4, 40-gallons; Ethylenediamine, 40-gallons; Sulfuric Acid, 10-gallons; Ammonium Hydroxide, 30-gallons; Acetic Acid, 10-gallons; Phosphoric Acid, 10-gallons; Nitric Acid, 25-gallons; Hydrogen Peroxide (33%), 4-gallons; and Hydroxyacetic Acid, 20-gallons.
 - There was no information on file in reference to when the chemicals were initially stored on-site.
- Space Machine Corp., 233-5 Robbins Lane, Syosset.
 - Space Machine Corp. performs metal machining operations and utilizes VOCs for cleaning fluid in their normal operations.
 - May 20, 1986 cleanup accomplished (soil excavated and disposed), but adjacent sites may be contaminated. Groundwater not investigated.
 - January 21, 1986 soil collected from three soil borings drilled in front of the rear entrance to the building as part of a Remedial Investigation. Concentrations of 1,1-DCA, 1,1,1-TCA, PCE, and toluene were detected at levels of 2700, 250000, 2300, and 12000 parts per billion (ppb), respectively.
 - April 22, 1985 NCHD sampled soil behind building and discovered high concentrations of 1,1-DCA, 1,1,1-TCA, Toluene, and PCE, at 380000, 67000, 14000, and 9700 ppb respectively. Other solvents and vocs were detected.
 - Company utilized 1,1,1-TCA as a degreaser. There was no information on file in reference to when chemical was initially stored on-site.
 - Contamination was detected at 21 feet below grade at 10 ppb for 1,1,1-TCA.



- Spiegel Associates, 225 Robbins Lane, Syosset.
 - On January 7, 1987, soil removed and 1,1-DCA, 1,2-DCE, 1,1,1-TCA, PCE, methylene chloride and benzene were detected in the base of the excavation at 16, 10, 28, 5, 120, and 31 ppb respectively.
 - Spiegel Associates property was an unoccupied warehouse facility. There is no evidence that Spiegel caused the contamination as per a letter from the Nassau County Department of Health dated June 11, 1986.
- LKB, 1 Aerial Way, Syosset.
 - A 3000-gallon fuel oil UST was registered on 6/29/92 and removed on 7/16/92; no contamination noted.
- Bertan Associates, Inc., 3 Aerial Way, Syosset.
 - Bertan Associates, Inc. is an electronics company manufacturing high voltage power supplies. Utilized Chlorothane, Chlorothene, MEK, and TCE to clean the component parts. A maximum of 30-gallons of waste Chloroethene was produced per month on-site as documented to the Nassau County Department of Health on August 23, 1983. This waste was collected by Atlas Assoc. The average quantity on hand of MEK and TCE was 5-gallons and 30-gallons respectively as per a document dated February 15, 1977.
 - There was no other information on file in reference to chemical storage or waste disposal practices.
- Great Eastern Printing Co., Inc., 7 Aerial Way Syosset.
 - Hooked up to sewer in 1981.
 - Utilized photographic developers, fixers, etc.
- Centroid Inc., 3 Aerial Way, Syosset.
 - The following chemicals and average quantities stored indoors were registered with the Nassau County Department of Health in January 1987: Freon, 50-gallons; 1,1,1-TCA, 50-gallons; MEK, 50-gallons; Methylene Chloride, 50-gallons; waste Freon, 50-gallons; waste TCA, 50-gallons; waste MEK, 5-gallons; and waste Methylene Chloride, 50-gallons. The waste is reportedly picked up by Chemical Pollution Control.
 - Manufactured electronic components. There was no information on file in reference to when chemical was initially stored on-site.



- PMI Motors, 5 Aerial Way, Syosset.
 - PMI Motors manufactures electric motors on-site.
 - In 1977, information on the following chemicals and average annual usage was given to the Nassau County Department of Health: Methylene Chloride, 1320-gallons and 1,1,1-TCA, 250-gallons. These chemicals were used as degreasers and cleaners. The drums of these waste solvents were taken to Photocircuits in Glen Cove for disposal.
 - There was no information on file in reference to when chemicals were initially stored on-site.
- Chemo, 7 Aerial Way, Syosset.
 - 1977 Chemicals used on-site Isopar, fixers, developers, Solvent 10-20, and Toluol.
- Loral Fairchild Systems, 300 Robbins Lane, Syosset.
 - Numerous chemicals used on-site.
 - Processed waste water re-routed to NC Sewers in September 1979. Prior to that it was put into a recharge basin.
 - SPDES permit March 1975.

Review of the NCHD Bureau of Environmental Engineering records for:

- Kliegl Bros. Universal Electrical Stage Lighting Co., Inc. 5 Aerial Way, Syosset.
 - Air emission permit for on-site emissions.
- Great Eastern Printing Co., Inc., 7 Aerial Way Syosset.
 - NYSDEC Process Exhaust or Ventilation System form for printing presser and folding machines.
- PMI Motors, 5 Aerial Way, Syosset.
 - 1984 Application for a spray booth.
 - 1978 Air permit for facing lathes.

Additional information gained from this file search is contained in Appendix G. Data on each property is separated from the next property by colored sheets of paper.



FINDINGS AND CONCLUSIONS

1. Analysis of groundwater samples collected from Monitoring Well RW-12I in November and December 1993 indicated total volatile organic compound (VOC) concentration ranging from 144.5 to 259.7 parts per billion (including replicates). Of this total, tetrachloroethene (PCE) made up nearly half of the total and 1,1,1-trichloroethane (1,1,1-TCA) was the compound with the next highest concentration.
2. Review of the information contained in this memo and attached appendices (especially Appendix G) indicates that the following sites have used, are using, or have had discharges of PCE and/or 1,1,1-TCA:
 - Emro Dry Cleaners - store PCE onsite.
235 Robbins Lane, Syosset
 - Space Machine Corp. - had discharge(s) of 1,1,1-TCA and PCE based on soil analytical results.
233-5 Robbins Lane, Syosset
 - Spiegel Associates - had discharge(s) of 1,1,1-TCA based on soil analytical results.
225 Robbins Lane, Syosset
 - Centroid - used 1,1,1-TCA onsite.
3 Aerial Way, Syosset
 - PMI Motors - used 1,1,1-TCA onsite.
5 Aerial Way, Syosset
3. All the above locations are currently generally hydraulically upgradient of the Syosset Landfill and Monitoring Well RW-12I and they would also have been upgradient when Public Supply Well N4223 (located north of Syosset Landfill) was in operation.
4. In general, except as specifically noted elsewhere in this memo, the industrial area around the Syosset Landfill was not sewered until the 1980s and, therefore, wastewater discharges prior to this time would have likely gone directly to the subsurface via septic system leaching fields, cesspools, and dry wells. Moreover, Dvirka and Bartilucci Consulting Engineers, Inc. (1986) studied five areas of aquifer segments contaminated with VOCs (New Cassel, Garden City Park, West Hicksville, New Hyde Park, and North Hicksville). The probable source of the VOC contamination in four of the five study areas was identified as industrial areas near the LIRR tracks. A similar area is present directly adjacent (west) to the LIRR tracks that also border the Syosset Landfill. In the Dvirka and Bartilucci study, the VOC contamination was found at highest concentrations, and most frequently, in the Upper Glacial aquifer, but VOCs



were also observed deep in the Magothy (more than 500 feet below land surface). The principal VOCs detected (i.e., at highest concentrations and frequencies) were 1,1,1-trichloroethane (TCA), PCE, and TCE. Included in the Dvirka and Bartilucci report is a discussion of regional groundwater quality and VOC contamination is described as fairly widespread in Nassau County and considered a major threat to the water supply. It was stated in the Dvirka and Bartilucci report, "In addition to industrial and commercial waste disposal, an extensive investigation into the uses of toxic household products determined that unsewered residential areas may also be a significant source of organic contamination (i.e., VOCs) of groundwater."

5. Based on the above, it appears that one or more of the above facilities could have contributed to the elevated levels of VOCs in Well RW-12I.
6. Although less is known regarding details of 300 Michael Drive as compared to the five properties mentioned above, based on the descriptions of site activities at 300 Michael Drive discussed above and its proximity to Syosset Landfill and Well Cluster RW-12, this property should also be considered as a potential source of the elevated levels of VOCs in Well RW-12I.
7. Geraghty & Miller contacted Adam Shisgal from the Bureau of Water Supply Protection of the Nassau County Health Department in reference to two properties. The Centroid Inc. file in Bureau of Water Supply Protection contained three letters dated September 7, 1988, September 9, 1988, and September 12, 1988 which discussed that Centroid Inc. was connected to the public sewers on April 25, 1984 by Orchard Sewer Corporation. The other file (Auto Collision, 233A Robbins Lane) could not be located, but Mr. Shisgal stated that this file contained the sewer connection date of November 14, 1983 and an inspection on July 20, 1990. Additional information has been requested from Mr. Osman on 300 Michael Drive. An addendum to this memo will be prepared if additional information is obtained.





g:\project\Lockesba\NY0029.001\corres\LKB628.mem



DWG 13 JUL 95
 PROJECT NO.: NY0029008
 HARD FILE: 1584
 DRAWING: F. J. WNR
 CHECKED: M. WOLFERT
 APPROVED: M. WOLFERT
 DRAFTER: W. CIO



PRIOR OWNER/TENANT

-  HICKSVILLE AIRPORT
PRIOR TO 1959
-  METALURGICAL PROCESSING
CORP. 1969-1979
-  U.S. NAVY
1948-1962
-  FAIRCHILD CAMERA AND
INSTRUMENT CORP.
1967-1970

 APPROXIMATE DIRECTION OF
HORIZONTAL GROUNDWATER
MOVEMENT (1993)

Approximate Location
of Well Cluster RW-12

CURRENT
OWNER/TENANT

Centroid
 PMI Motors
 Emro Dry Cleaners
 Space Machine Corp.
 Spiegel Associates

300 Michael Drive

Cerro

**SYOSSET
LANDFILL**

NOTE:
 DRAWING NOT TO SCALE.
 ALL LOCATIONS AND CONFIGURATIONS
 ARE APPROXIMATE.



**GERAGHTY
& MILLER, INC.**
Environmental Services
 A Heldemilj Company

**PROPERTY OWNERS/TENANTS
 IN THE VICINITY
 OF THE SYOSSET LANDFILL**

FIGURE

Geraghty & Miller, Inc.
Spill Log Table

PAG
DATE: 10
TIME: 11

| Spill # | Location | Spill Type | Qty. (Gals) | Cause | Affected Area | Status |
|------------------|---|------------|-------------|--------------|------------------------|--------|
| 12/06/93 9310823 | NY Savings Bank 200 OAK DRIVE SYOSSET | Waste Oil | 5.00 | Housekeeping | On Land | A |
| 11/28/90 9009675 | Vector Vacuum 60 OAK DRIVE SYOSSET | | 0.00 | Human Error | Groundwater/water body | C |
| 01/19/88 8708913 | Stomins O.I. 70 GREAT OAK DRIVE MANHASSET | # 2 Fuel | 3.00 | Human Error | Groundwater/water body | C |
| 09/14/87 8704943 | UPA Technology 60 OAK DRIVE SYOSSET | # 2 Fuel | 0.00 | Tank failure | Groundwater/water body | C |

4 Spills Listed

Search Criteria: Region: 1 Nassau

Location(s): Oak Drive

11/9/93 9304646 Roadway Express
140 Gordon Drive 25 gal land A human error

9/03/90 9006350 UNK 5 Aerialway Deliberate on land A

11/10/90 8909745 APA 7 " " Diesel 5 gal. unknown on land C

2/16/89 8808962 LKD 1 " " #2 tank overfill Land C

EDR Environmental
Data
Resources, Inc.

Creators of Toxicheck®

**The EDR-Radius Map / Plus™
Report**

**Syosset Project
Michael Dr.
Town of Oyster Bay, NY 11791**

Inquiry Number: 056852.1r

September 28, 1994

***The Source
For Environmental
Risk Management
Data***

3530 Post Road
Southport, Connecticut 06490

Nationwide Customer Service

Telephone: 1-800-352-0050
Facsimilie: 1-800-231-6802

THE EDR-RADIUS MAP™

The EDR-Radius Map™ is a screening tool which maps sites with potential or existing environmental liabilities. Specified government databases are searched in accordance with the ASTM Standard (E 1527) or custom specifications provided by the user.

The EDR-Radius Map™ includes the following three maps:

Topographic Map:

- displays a two mile radius around the target property
- displays the United States Geological Survey (USGS) topographic contours and selected road features (i.e., major street names, and hydrographic data)

Overview Map:

- displays a one-mile (ASTM Standard) or customer specified radius around the target property
- includes major geographic attributes available in EDR's computer mapping system (i.e., street names, available hydrography)

Detail Map:

- displays a quarter-mile radius or customer specified radius around the target property and provides the user with a close-up view
- includes all geographic attributes available in EDR's computer mapping system (i.e., street names, address ranges)
- helps the user locate "orphan" sites, those sites with insufficient address information such that they can only be identified as within the zip code, city, or county of the target property

Please call EDR's Nationwide Customer Service at
1-800-352-0050 (8am - 8pm EST)
with questions or comments about your report.

Thank you for your business!

Disclaimer

EDR makes no representation or warranty regarding the accuracy, quality or completeness of any data provided by governmental or other entity used by EDR in the preparation of its reports. The customer shall take full responsibility for the use of EDR reports. **No warranty of merchantability or of fitness for particular purpose, expressed or implied, shall apply and EDR specifically disclaims the making of any such warranties.** In no event shall EDR be liable to anyone for special, incidental, consequential or exemplary damages.

GOVERNMENT RECORDS SEARCHED / DATA CURRENCY TRACKING

To maintain currency of the following federal and state databases, EDR contacts the appropriate governmental agency on a monthly or quarterly basis, as required.

Elapsed ASTM days: Provides confirmation that this EDR report meets or exceeds the 90-day updating requirement of the ASTM standard.

FEDERAL ASTM RECORDS:

CERCLIS: Comprehensive Environmental Response, Compensation, and Liability Information System

Source: EPA/NTIS

Telephone: 703-416-0702

CERCLIS: Comprehensive Environmental Response, Compensation and Liability Information System; Source: United States Environmental Protection Agency (USEPA). CERCLIS contains information on sites identified by the USEPA as abandoned, inactive or uncontrolled hazardous waste sites which may require cleanup.

Date of Government Version: 06/30/94

Date Made Active at EDR: 09/20/94

Date of Data Arrival at EDR: 07/19/94

Elapsed ASTM days: 63

ERNS: Emergency Response Notification System

Source: EPA

Telephone: 202-260-2342

ERNS: Emergency Response Notification System; Source: USEPA and the National Response Center of the US Coast Guard. ERNS records and stores information on reported releases of oil and hazardous substances.

Date of Government Version: 12/31/93

Date Made Active at EDR: 05/25/94

Date of Data Arrival at EDR: 04/11/94

Elapsed ASTM days: 44

NPL: National Priority List

Source: EPA

Telephone: 703-603-9027

NPL: National Priorities List (Superfund); Source: USEPA. The NPL is a subset of CERCLIS and identifies over 1,200 sites for priority cleanup under the Superfund Program.

Date of Government Version: 01/10/94

Date Made Active at EDR: 03/09/94

Date of Data Arrival at EDR: 01/26/94

Elapsed ASTM days: 42

RCRIS: Resource Conservation and Recovery Information System

Source: EPA/NTIS

Telephone: 202-260-3393

RCRIS: Resource Conservation and Recovery Information System; Source: USEPA. RCRIS includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA).

Date of Government Version: 03/31/94

Date Made Active at EDR: 07/20/94

Date of Data Arrival at EDR: 04/26/94

Elapsed ASTM days: 85

FEDERAL NON-ASTM RECORDS:

FINDS: Facility Index System

Source: EPA/NTIS

Telephone: 800-908-2493

FINDS: Facility Index System; Source: USEPA. FINDS contains both facility information and "pointers" to other sources that contain more detail. These include: RCRIS, PCS (Permit Compliance System), AIRS (Aerometric Information Retrieval System), FATES (FIFRA [Federal Insecticide Fungicide Rodenticide Act] and TSCA Enforcement System, FTTS (FIFRA/TSCA Tracking System)), CERCLIS, DOCKET (Enforcement Docket used to manage and track information on civil judicial enforcement cases for all environmental statutes), FURS (Federal Underground Injection Control), FRDS (Federal Reporting Data System), SIA (Surface Impoundments), CICIS (TSCA Chemicals in Commerce Information System), PADS, RCRA-J (medical waste transporters/disposers), TRIS and TSCA.

Date of Government Version: 09/14/93

Date of Next Scheduled Update: 10/17/94

PADS: PCB Activity Database System

Source: EPA

Telephone: 202-260-3992

PADS: PCB Activity Database; Source: USEPA. PADS identifies generators, transporters, commercial storers and/or brokers and disposers of PCB's who are required to notify the EPA of such activities.

Date of Government Version: 01/17/94

Date of Next Scheduled Update: 09/19/94

RAATS: RCRA Administrative Action Tracking System

Source: EPA

Telephone: 202-260-2810

RAATS: RCRA Administration Action Tracking System; Source: USEPA. RAATS contains records based on enforcement actions issued under RCRA pertaining to major violators and includes administrative and civil actions brought by the EPA.

Date of Government Version: 04/06/94

Date of Next Scheduled Update: 11/07/94

TRIS: Toxic Chemical Release Inventory System

Source: EPA/NTIS

Telephone: 202-260-2320

TRIS: Toxic Release Inventory System; Source: USEPA. TRIS identifies facilities which release toxic chemicals to the air, water and land in reportable quantities under SARA Title III Section 313.

Date of Government Version: 12/31/91

Date of Next Scheduled Update: 10/03/94

TSCA: Toxic Substances Control Act

Source: EPA/NTIS

Telephone: 202-260-1444

TSCA: Toxic Substances Control Act; Source: USEPA. TSCA identifies manufacturers and importers of chemical substances included on the TSCA Chemical Substance Inventory list. It includes data on the production volume of these substances by plant site. USEPA has no current plan to update and/or re-issue this database.

Date of Government Version: 05/15/86

Date of Next Scheduled Update: 09/19/94

HMIRS: Hazardous Materials Information Reporting System

Source: U.S. Department of Transportation

Telephone: 202-366-4555

HMIRS: Hazardous Materials Incident Report System; Source: United States Department of Transportation (DOT). HMIRS contains hazardous material spill incidents reported to DOT.

Date of Government Version: 06/30/93

Date of Next Scheduled Update: 12/06/94

NPL LIENS: Federal Superfund Liens

Source: EPA

Telephone: 202-260-3733

NPL LIENS: Federal Superfund Liens; Source: USEPA. Under the authority granted the USEPA by the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) of 1980, the USEPA has the authority to file liens against real property in order to recover remedial action expenditures or when the property owner receives notification of potential liability. USEPA compiles a listing if filed notices of Superfund Liens.

Date of Government Version: 10/15/91

Date of Next Scheduled Update: 11/27/94

STATE OF NEW YORK ASTM RECORDS:

LUST: Spills Information Database

Source: Department of Environmental Conservation
Telephone: 518-457-2462

LUST: Leaking Underground Storage Tank Incident Reports. LUST records contain an inventory of reported leaking underground storage tank incidents. Not all states maintain these records, and the information stored varies by state.

Date of Government Version: 06/15/94
Date Made Active at EDR: 07/05/94

Date of Data Arrival at EDR: 06/22/94
Elapsed ASTM days: 13

SHWS: Inactive Hazardous Waste Disposal Sites in New York State

Source: Department of Environmental Conservation
Telephone: 518-457-0747

SHWS: State Hazardous Waste Sites. State hazardous waste site records are the states' equivalent to CERCLIS. These sites may or may not already be listed on the federal CERCLIS list. Priority sites planned for cleanup using state funds (state equivalent of Superfund) are identified along with sites where cleanup will be paid for by potentially responsible parties. Available information varies by state.

Date of Government Version: 04/30/93
Date Made Active at EDR: 09/17/93

Date of Data Arrival at EDR: 07/08/93
Elapsed ASTM days: 71

SWF/LS: Facility Register

Source: Department of Environmental Conservation
Telephone: 518-457-7336

SWF/LS: Solid Waste Facilities/Landfill Sites. SWF/LS type records typically contain an inventory of solid waste disposal facilities or landfills in a particular state. Depending on the state, these may be active or inactive facilities or open dumps that failed to meet RCRA Section 2004 criteria for solid waste landfills or disposal sites.

Date of Government Version: 03/01/94
Date Made Active at EDR: 04/20/94

Date of Data Arrival at EDR: 04/04/94
Elapsed ASTM days: 16

UST: Petroleum Bulk Storage (PBS, CBS, MOSF) Database

Source: Department of Environmental Conservation
Telephone: 518-457-4351

UST: Registered Underground Storage Tanks. UST's are regulated under Subtitle I of the Resource Conservation and Recovery Act (RCRA) and must be registered with the state department responsible for administering the UST program. Information in NEDIS varies by state program.

Date of Government Version: 06/27/94
Date Made Active at EDR: 08/17/94

Date of Data Arrival at EDR: 06/30/94
Elapsed ASTM days: 48

Historical and Other Database(s)

Former Manufactured Gas (Coal Gas) Sites: The existence and location of Coal Gas sites is provided exclusively to EDR by Real Property Scan, Inc. ©Copyright 1993 Real Property Scan, Inc.

Disclaimer Provided by Real Property Scan, Inc.

The information contained in this report has predominantly been obtained from publicly available sources produced by entities other than Real Property Scan. While reasonable steps have been taken to insure the accuracy of this report, Real Property Scan does not guarantee the accuracy of this report. Any liability on the part of Real Property Scan is strictly limited to a refund of the amount paid. No claim is made for the actual existence of toxins at any site. This report does not constitute a legal opinion.

MANUFACTURED GAS PLANT (Coal Gas) SITES

Prior to the widespread use of natural gas, combustible gas manufactured from coke, coal and oil served as the major fuel for urban heating, cooking and lighting in the U.S. for over 100 years. Beginning in 1816, manufactured gas or "town gas" was produced at thousands of plant sites throughout the United States. Pipeline distribution of natural gas during the 1950s rapidly replaced manufactured gas as the major gaseous fuel. As a result, manufactured gas production gradually came to an end through the 1950s and 1960s.

Along with the production of large volumes of gas, manufactured gas plants also yielded large quantities of by-products during their operation, including complex mixtures of coal tars, sludges, oils and other chemicals. Coal tar was the principal by-product from the gasification process. Although some of the coal tars were refined into a variety of marketable products, substantial volumes remained unused and were considered as waste. Coal tar and other waste products from the gasification plants were frequently disposed on the plant site in unlined pits or in some cases injected underground through injection wells. These practices have left behind subsurface coal tar contamination at many former manufactured gas plant (MGP) sites.


Coal tar is the waste of primary concern at MGP sites. Coal tars are relatively dense, viscous liquid mixtures. The composition of coal tar varies but is usually a mixture of the following:

- Polycyclic aromatic hydrocarbons (PAH), such as benzo-pyrene, naphthalene, anthracene, acenaphthene and phenanthrene.
- Phenolic compounds, including phenol and methylphenols.
- Light aromatic compounds, such as benzene, toluene and xylenes.
- Miscellaneous organics, such as dibenzofuran.
- Small quantities of inorganic chemicals, such as iron, lead, copper, zinc, various sulfides, cyanides and nitrates.

Coal tar is somewhat heavier than water and tends to migrate vertically downward in the subsurface until it encounters a stratum that it cannot permeate. There it resides in an immobile state or spreads slowly. It can then serve as a continuous source of groundwater contamination in that PAH and other constituent compounds are slowly solubilized. Coal tars in the subsurface at MGP sites have persisted for decades because they are sparingly soluble, resistant to biodegradation and they move slowly through porous media. The problem of coal tars in the subsurface at old MPG sites represents a significant part of the general problem of subsurface contamination with dense organic liquids in the United States.

The residue from former MGP sites often contains significant amounts of hazardous substances which can cause contamination of both soil and groundwater. A number of these sites are already included on EPA's CERCLIS list and the hazardous waste site lists of many states. Individual site cleanup costs have been estimated in the million dollar plus range.

The information included in EDR's "Former Manufactured Gas Plant Site" Database is provided under exclusive license by Real Property Scan, Inc. The information in this report has predominantly been obtained from publicly available sources produced by entities other than Real Property Scan. While reasonable steps have been taken to insure the accuracy of this report, Real Property Scan does not guarantee the accuracy of this report. Any liability on the part of Real Property Scan is strictly limited to a refund of the amount paid. No claim is made for the actual existence of toxins on any site. This report does not constitute a legal opinion.




- ★ - Indicates TARGET PROPERTY.
- ▲ - Indicates environmental elements at elevations higher than or equal to the target property.
- ◆ - Indicates environmental elements at elevations lower than the target property.
- ▲ - Coal Gasification Sites (if requested)

National Priority List Sites

TARGET PROPERTY: Syosset Project
 ADDRESS: Michael Dr.
 CITY/STATE/ZIP: Town of Oyster Bay NY 11791
 LAT/LONG: 40.8000 / 73.5155


CUSTOMER: Geraghty & Miller, Inc.
 CONTACT: Bill Holubowich
 INQUIRY #: 056852.1r
 DATE: September 27, 1994

TOPOGRAPHIC MAP - 056852.1r - Geraghty & Miller, Inc.



Source: US Geological Survey 1-Degree Digital Elevation Model
Compiled 09/15/92


- Major Roads
- Contour lines (25 foot interval unless otherwise shown)
- Waterways
- Indicates closest well in quadrant to target property.



TARGET PROPERTY: Syosset Project
ADDRESS: Michael Dr.
CITY/STATE/ZIP: Town of Oyster Bay NY 11791
LAT/LONG: 40.8000 / 73.5155

CUSTOMER: Geraghty & Miller, Inc.
CONTACT: Bill Holubowich
INQUIRY #: 056852.1r
DATE: September 27, 1994

DETAIL MAP - 056852.1r - Geraghty & Miller, Inc.



- ★ - Indicates TARGET PROPERTY.
- ▲ - Indicates environmental elements at elevations higher than or equal to the target property.
- ◆ - Indicates environmental elements at elevations lower than the target property.
- ▲ - Coal Gasification Sites (if requested)
- - National Priority List Sites

0 1/8 1/4
Miles

TARGET PROPERTY: Syosset Project
 ADDRESS: Michael Dr.
 CITY/STATE/ZIP: Town of Oyster Bay NY 11791
 LAT/LONG: 40.8000 / 73.5155

CUSTOMER: Geraghty & Miller, Inc.
 CONTACT: Bill Holubowich
 INQUIRY #: 056852.1r
 DATE: September 27, 1994

MAP FINDINGS SUMMARY SHOWING
ALL SITES

| <u>Database</u> | <u>Target Property</u> | <u>Search Distance (Miles)</u> | <u>< 1/8</u> | <u>1/8 - 1/4</u> | <u>1/4 - 1/2</u> | <u>1/2 - 1</u> | <u>> 1</u> | <u>Total Plotted</u> |
|----------------------|----------------------------|--|-----------------|------------------|------------------|----------------|---------------|--------------------------|
| NPL | | 1.000 | 0 | 0 | 1 | 0 | NR | 1 |
| RCRIS-TSD | | 1.000 | 0 | 0 | 0 | 0 | NR | 0 |
| State Haz. Waste | | 1.000 | 0 | 0 | 0 | 0 | NR | 0 |
| CERCLIS | | 0.500 | 0 | 1 | 1 | NR | NR | 2 |
| State Landfill | | 0.500 | 0 | 0 | 0 | NR | NR | 0 |
| LUST | | 0.500 | 0 | 0 | 5 | NR | NR | 5 |
| UST | | 0.125 | 0 | NR | NR | NR | NR | 0 |
| RAATS | TP | | NR | NR | NR | NR | NR | 0 |
| RCRIS Sm. Quan. Gen. | | 0.125 | 0 | NR | NR | NR | NR | 0 |
| RCRIS Lg. Quan. Gen. | | 0.125 | 0 | NR | NR | NR | NR | 0 |
| HMIRS | TP | | NR | NR | NR | NR | NR | 0 |
| PADS | TP | | NR | NR | NR | NR | NR | 0 |
| ERNS | TP | | NR | NR | NR | NR | NR | 0 |
| FINDS | TP | | NR | NR | NR | NR | NR | 0 |
| TRIS | TP | | NR | NR | NR | NR | NR | 0 |
| NPL Liens | TP | | NR | NR | NR | NR | NR | 0 |
| TSCA | TP | | NR | NR | NR | NR | NR | 0 |
| Coal Gas | | 1.000 | 0 | 0 | 0 | 0 | NR | 0 |

TP = Target Property

NR = Not Requested at this Search Distance

* Sites may be listed in more than one database

MAP FINDINGS SUMMARY SHOWING
ONLY SITES HIGHER THAN OR THE SAME ALTITUDE AS TP

| <u>Database</u> | <u>Target Property</u> | <u>Search Distance (Miles)</u> | <u>< 1/8</u> | <u>1/8 - 1/4</u> | <u>1/4 - 1/2</u> | <u>1/2 - 1</u> | <u>> 1</u> | <u>Total Plotted</u> |
|----------------------|----------------------------|--|-----------------|------------------|------------------|----------------|---------------|--------------------------|
| NPL | | 1.000 | 0 | 0 | 1 | 0 | NR | 1 |
| RCRIS-TSD | | 1.000 | 0 | 0 | 0 | 0 | NR | 0 |
| State Haz. Waste | | 1.000 | 0 | 0 | 0 | 0 | NR | 0 |
| CERCLIS | | 0.500 | 0 | 1 | 1 | NR | NR | 2 |
| State Landfill | | 0.500 | 0 | 0 | 0 | NR | NR | 0 |
| LUST | | 0.500 | 0 | 0 | 5 | NR | NR | 5 |
| UST | | 0.125 | 0 | NR | NR | NR | NR | 0 |
| RAATS | TP | | NR | NR | NR | NR | NR | 0 |
| RCRIS Sm. Quan. Gen. | | 0.125 | 0 | NR | NR | NR | NR | 0 |
| RCRIS Lg. Quan. Gen. | | 0.125 | 0 | NR | NR | NR | NR | 0 |
| HMIRS | TP | | NR | NR | NR | NR | NR | 0 |
| PADS | TP | | NR | NR | NR | NR | NR | 0 |
| ERNS | TP | | NR | NR | NR | NR | NR | 0 |
| FINDS | TP | | NR | NR | NR | NR | NR | 0 |
| TRIS | TP | | NR | NR | NR | NR | NR | 0 |
| NPL Liens | TP | | NR | NR | NR | NR | NR | 0 |
| TSCA | TP | | NR | NR | NR | NR | NR | 0 |
| Coal Gas | | 1.000 | 0 | 0 | 0 | 0 | NR | 0 |

TP = Target Property

NR = Not Requested at this Search Distance

* Sites may be listed in more than one database

MAP FINDINGS

Map ID
Direction
Distance
Altitude

Site

Database(s)

EDR ID Number
EPA ID Number

Coal Gas Site Search: No site was found in a search of Real Property Scan's ENVIROHAZ database.

1
South
1/8-1/4
Higher

FAIRCHILD INSTRUMENT CORP
300 ROBBINS LANE
SYOSSET, NY 11791

CERCLIS
FINDS

1000354423
NYD980754709

CERCLIS Classification Data:

Site Incident Category: Not reported

Federal Facility: NO

Ownership Status: OTHER

NPL Status: NOT ON NPL

EPA Notes: Not reported

CERCLIS Assessment History:

Assessment: DISCOVERY

Completed: 10/01/80

Assessment: PRELIMINARY ASSESSMENT

Completed: 09/22/87

CERCLIS Site Status:

EPA has conducted a preliminary assessment on this site and has determined that no further action is necessary and no hazard was identified

CERCLIS Alias Names: Not Reported

Other Pertinent Environmental Activity Identified at Site:

facility has active water discharge permits

2
SSE
1/4-1/2
Higher

NYS DOT
500 ROBBINS LANE
SYOSSET, NY 11791

LUST

S100177072
N/A

LUST:

Facility ID: 9105514

Spill Date: 19910521

First notified: CENTRAL OFFICE

Material class: PETROLEUM

Material spilled: 5

Release QTY: 0.00 GALLONS

Water body affected: Not reported

Origin: NON-COMMINST

Resource affected: GROUNDWATER

Notifier: TANK TESTER

Basin of spill: 1700

Project ID: 0

Cleaner: SPILLER

Date cleaned: Not reported

Initiated clean up: Not reported

Close date: Not reported

Last inspection: Not reported

Investigator: T/T/F

PBS #: 0

UST Trust Fund: T

Status: Not reported

Penalty: NO PENALTY

Quantity recovered: 0.00

Cause: TANK TEST FAILURE (BULK STORE, PRO.)

Emergency response: IT WAS NOT TAKEN

Facility status: ACTIVE SPILL (ON GOING)

3
West
1/4-1/2
Higher

LOCKWOOD,KESSLER,BARTLETT
1 AERIAL WAY
SYOSSET, NY 11791

LUST

S100147542
N/A

MAP FINDINGS

Map ID
Direction
Distance
Altitude

Site

Database(s)

EDR ID Number
EPA ID Number

LOCKWOOD,KESSLER,BARTLETT (Continued)

S100147542

LUST:

| | | | |
|----------------------|--|-----------------|--------------|
| Facility ID: | 8808962 | Spill Date: | 19890216 |
| First notified: | REGIONAL OFFICE | Material class: | PETROLEUM |
| Material spilled: | 2 | Release QTY: | 0.00 GALLONS |
| Water body affected: | Not reported | Origin: | COMMINDUST |
| Resource affected: | ON LAND | Notifier: | OTHER |
| Basin of spill: | 1700 | Project ID: | 0 |
| Cleaner: | SPILLER | Date cleaned: | 19890316 |
| Initiated clean up: | Not reported | Close date: | 19890316 |
| Last inspection: | Not reported | Investigator: | MIRZA |
| PBS #: | 0 | UST Trust Fund: | F |
| Status: | MEANS ITS BEEN RESOLVED | Penalty: | NO PENALTY |
| Quantity recovered: | 0.00 | | |
| Cause: | TANK OVERFILL | | |
| Emergency response: | IT WAS NOT TAKEN | | |
| Facility status: | COMPLETED SPILL (SPILL IS CLEANED UP AND ALL PAPERWORK IS COMPLETED) | | |

4
SE
1/4-1/2
Higher

SYOSSET LF
150 MILLER PLACE
OYSTER BAY, NY 11791

CERCLIS
FINDS
NPL
1000386366
NYD000511360

CERCLIS Classification Data:

| | | | |
|-------------------------|---|-------------------|----------------------------|
| Site Incident Category: | LANDFILL | Federal Facility: | NO |
| Ownership Status: | OTHER | NPL Status: | CURRENTLY ON THE FINAL NPL |
| EPA Notes: | TWN OF OYSTER BAY SUSPENDED WASTE DISPL OPERNS AT LF AFTER WTR POLLUTN DETECTD. HI CONCETRNS OF HEAVY METALS IN INDUSTLSLUDGES BEING DEPOSITD & IN DISCHGD WASTES FR SCAVENGER PLT OPERNS. VOC'S IN 2 PRIVT WELLS. CNTY'S PRIMARY GW BECHG AREA | | |

CERCLIS Assessment History:

| | | | |
|-------------|---------------------------|------------|----------|
| Assessment: | HAZARD RANKING DETERMINED | Completed: | 12/01/82 |
| Assessment: | SCREENING SITE INSPECTION | Completed: | 12/01/82 |
| Assessment: | DISCOVERY | Completed: | 11/01/79 |
| Assessment: | PRELIMINARY ASSESSMENT | Completed: | 11/01/79 |
| Assessment: | FINAL LISTING ON NPL | Completed: | 09/08/83 |
| Assessment: | PROPOSAL TO NPL | Completed: | 12/30/82 |

CERCLIS Site Status:

This site is currently under investigation by the government to assess the extent of further action

CERCLIS Alias Name(s):

SYOSSET LANDFILL

MAP FINDINGS

Map ID
Direction
Distance
Altitude

Site

Database(s)

EDR ID Number
EPA ID Number

SYOSSET LF (Continued)

1000386366

NPL:

| | |
|------------------------------------|--|
| ID: | 02NY029 |
| Date Listed: | 9/08/83 (FINAL) |
| EPA/ID: | NYD000511360 |
| Haz. Rank Score: | 54.27 |
| Status: | LISTED ON NPL |
| Rank: | 122 |
| Group: | 3 |
| Ownership: | Municipal |
| Permit: | None |
| Site Activities: | Landfill, Municipal |
| Site Activities: | Landfill, Comm./Indus. |
| Site Condition: | Contam. Drinking Water |
| Site Condition: | Direct Contact |
| Site Condition: | Contam. Ground Water |
| Waste Type: | Metals |
| Waste Type: | Solvents |
| Waste Form: | Not reported |
| Contaminant: | Media Affected: |
| 1,1,2-TRICHLOROETHYLENE (TCE) | Ground Water |
| TETRACHLOROETHENE | Ground Water |
| 1,1,1-TRICHLOROETHANE | Ground Water |
| ARSENIC | Ground Water |
| CADMIUM (CD) | Ground Water |
| CHROMIUM AND COMPOUNDS, NOS (CR) | Ground Water |
| LEAD (PB) | Ground Water |
| Distance to nearest Population: | Not reported |
| Population within a 1 Mile Radius: | More than 10,000 People |
| Vertical Distance to Aquifer: | Not reported |
| Ground Water Use: | Not Used as Drinking Water, Alternative Source Available |
| Distance to nearest Surface Water: | Not reported |

Other Pertinent Environmental Activity Identified at Site:

civil judicial and administrative enforcement cases against facility

(For more information on this site, call your EDR Customer Service Rep.)

5
NNW
1/4-1/2
Higher

LILCO
200 MICHAEL DRIVE
SYOSSET, NY 11791

LUST

S100664637
N/A

MAP FINDINGS

Map ID
Direction
Distance
Altitude

Site

Database(s)

EDR ID Number
EPA ID Number

LILCO (Continued)

S100664637

LUST:

| | | | |
|----------------------|--|-----------------|-------------------|
| Facility ID: | 9203818 | Spill Date: | 19920701 |
| First notified: | ANSWERING SERVICE | Material class: | PETROLEUM |
| Material spilled: | 8 | Release QTY: | 1.00 GALLONS |
| Water body affected: | Not reported | Origin: | COMMINDUST |
| Resource affected: | ON LAND | Notifier: | RESPONSIBLE PARTY |
| Basin of spill: | 1700 | Project ID: | 0 |
| Cleaner: | SPILLER | Date cleaned: | 19920702 |
| Initiated clean up: | Not reported | Close date: | 19920702 |
| Last inspection: | Not reported | Investigator: | NONE |
| PBS #: | 0 | UST Trust Fund: | F |
| Status: | MEANS ITS BEEN RESOLVED | Penalty: | NO PENALTY |
| Quantity recovered: | 0.00 | | |
| Cause: | OTHER | | |
| Emergency response: | IT WAS NOT TAKEN | | |
| Facility status: | COMPLETED SPILL (SPILL IS CLEANED UP AND ALL PAPERWORK IS COMPLETED) | | |

A6
West
1/4-1/2
Higher

CUSHMAN & WAKEFIELD
200 ROBBINS LANE
JERICHO, NY 11753

LUST

S100147735
N/A

LUST:

| | | | |
|----------------------|--|-----------------|--------------|
| Facility ID: | 8902489 | Spill Date: | 19890609 |
| First notified: | REGIONAL OFFICE | Material class: | PETROLEUM |
| Material spilled: | 2 | Release QTY: | 0.00 GALLONS |
| Water body affected: | Not reported | Origin: | NON-COMMINST |
| Resource affected: | GROUNDWATER | Notifier: | TANK TESTER |
| Basin of spill: | 1700 | Project ID: | 0 |
| Cleaner: | SPILLER | Date cleaned: | 19910529 |
| Initiated clean up: | Not reported | Close date: | 19910529 |
| Last inspection: | Not reported | Investigator: | LEUNG |
| PBS #: | 0 | UST Trust Fund: | F |
| Status: | MEANS ITS BEEN RESOLVED | Penalty: | NO PENALTY |
| Quantity recovered: | 0.00 | | |
| Cause: | TANK TEST FAILURE (BULK STORE. PRO.) | | |
| Emergency response: | IT WAS NOT TAKEN | | |
| Facility status: | COMPLETED SPILL (SPILL IS CLEANED UP AND ALL PAPERWORK IS COMPLETED) | | |

| | | | |
|----------------------|--|-----------------|--------------|
| Facility ID: | 8902490 | Spill Date: | 19890609 |
| First notified: | REGIONAL OFFICE | Material class: | PETROLEUM |
| Material spilled: | 2 | Release QTY: | 0.00 GALLONS |
| Water body affected: | Not reported | Origin: | NON-COMMINST |
| Resource affected: | GROUNDWATER | Notifier: | TANK TESTER |
| Basin of spill: | 1700 | Project ID: | 0 |
| Cleaner: | SPILLER | Date cleaned: | 19890802 |
| Initiated clean up: | Not reported | Close date: | 19890802 |
| Last inspection: | Not reported | Investigator: | LEUNG |
| PBS #: | 0 | UST Trust Fund: | F |
| Status: | MEANS ITS BEEN RESOLVED | Penalty: | NO PENALTY |
| Quantity recovered: | 0.00 | | |
| Cause: | TANK TEST FAILURE (BULK STORE. PRO.) | | |
| Emergency response: | IT WAS NOT TAKEN | | |
| Facility status: | COMPLETED SPILL (SPILL IS CLEANED UP AND ALL PAPERWORK IS COMPLETED) | | |

MAP FINDINGS

Map ID
Direction
Distance
Altitude

Site

Database(s)

EDR ID Number
EPA ID Number

CUSHMAN & WAKEFIELD (Continued)

S100147735

| | | | |
|----------------------|--|-----------------|--------------|
| Facility ID: | 8902774 | Spill Date: | 19890616 |
| First notified: | REGIONAL OFFICE | Material class: | PETROLEUM |
| Material spilled: | 2 | Release QTY: | 0.00 GALLONS |
| Water body affected: | Not reported | Origin: | COMMINDUST |
| Resource affected: | GROUNDWATER | Notifier: | TANK TESTER |
| Basin of spill: | 1700 | Project ID: | 0 |
| Cleaner: | SPILLER | Date cleaned: | 19890831 |
| Initiated clean up: | Not reported | Close date: | 19890831 |
| Last inspection: | Not reported | Investigator: | LEUNG |
| PBS #: | 0 | UST Trust Fund: | F |
| Status: | MEANS ITS BEEN RESOLVED | Penalty: | NO PENALTY |
| Quantity recovered: | 0.00 | | |
| Cause: | TANK TEST FAILURE (BULK STORE. PRO.) | | |
| Emergency response: | IT WAS NOT TAKEN | | |
| Facility status: | COMPLETED SPILL (SPILL IS CLEANED UP AND ALL PAPERWORK IS COMPLETED) | | |

A7
West
1/4-1/2
Higher

BURGER KING DISTRIBUTION SERVICES
200 ROBBINS LN
JERICHO, NY 11753

FINDS
LUST
RCRIS-LQG

1000233802
NYD986898955

RCRIS:

Owner: BURGER KING DISTRIBUTION SERVICES
(212) 555-1212

| Waste | Quantity | Info Source |
|-------|--------------|--------------|
| D001 | Not reported | Notification |

LUST:

| | | | |
|----------------------|--|-----------------|--------------|
| Facility ID: | 8909592 | Spill Date: | 19891227 |
| First notified: | REGIONAL OFFICE | Material class: | PETROLEUM |
| Material spilled: | 5 | Release QTY: | 0.00 GALLONS |
| Water body affected: | Not reported | Origin: | COMMINDUST |
| Resource affected: | ON LAND | Notifier: | DEC |
| Basin of spill: | 1700 | Project ID: | 0 |
| Cleaner: | SPILLER | Date cleaned: | 19900625 |
| Initiated clean up: | Not reported | Close date: | 19900625 |
| Last inspection: | Not reported | Investigator: | MANCILLA |
| PBS #: | 0 | UST Trust Fund: | F |
| Status: | MEANS ITS BEEN RESOLVED | Penalty: | NO PENALTY |
| Quantity recovered: | 0.00 | | |
| Cause: | OTHER | | |
| Emergency response: | IT WAS NOT TAKEN | | |
| Facility status: | COMPLETED SPILL (SPILL IS CLEANED UP AND ALL PAPERWORK IS COMPLETED) | | |

ORPHAN SUMMARY

| City | EDR ID | Site Name | Site Address | Zip | Database(s) | Reason |
|---------------|------------|---------------------------------|-----------------------------|-------|------------------|--------|
| JERICO | S100782037 | SHELL S/S | 417 NORTH BROADWAY | 11753 | LUST | 7 |
| JERICO | S100148377 | JERICO FIRE DISTRICT | NORTH BROADWAY | 11753 | LUST | 7 |
| JERICO | S100149311 | JERICO F.D | NORTH BROADWAY | 11753 | LUST | 7 |
| JERICO | S100149172 | JERICO ASSOC. | 366 NORTH BROADWAY | 11753 | LUST | 3 |
| JERICO | S100177503 | SHELL SERVICE STATION | 417 NORTH BROADWAY | 11753 | LUST | 7 |
| JERICO | U001853058 | WELL #22 | NYS RT 106 | 11791 | UST | 1 |
| JERICO | S100149274 | JERICH SCHOOL | OLD CEDAR SWAMP ROAD | 11753 | LUST | 2 |
| MUTTONTOWN | U000725176 | WELL SITE #29 AND #30 | OFF NYS RT 106 | 11791 | UST | 1 |
| NASSAU COUNTY | S100443774 | HEMPSTEAD (OCEANSIDE) (T) | | | SWF/LF | 7 |
| NASSAU COUNTY | S100443775 | NORTH HEMPSTEAD T.S. | | | SWF/LF | 7 |
| NASSAU COUNTY | S100295909 | GLEN COVE T.S. | | | SWF/LF | 7 |
| NASSAU COUNTY | S100295906 | BETHPAGE LF ENERGY ASSOC | | | SWF/LF | 7 |
| NASSAU COUNTY | S100443773 | ENERGY TACTICS OCEANSIDE | | | SWF/LF | 7 |
| NASSAU COUNTY | S100116307 | VALLEY STREAM T.S. | | | SWF/LF | 7 |
| NASSAU COUNTY | S100116309 | ROCKVILLE CENTER T.S. | | | SWF/LF | 7 |
| NASSAU COUNTY | S100116312 | OYSTER BAY T.S. | | | SWF/LF | 7 |
| NASSAU COUNTY | S100546641 | GREAT NECK T.S. (V) | | | SWF/LF | 7 |
| SYOSSET | 1000694470 | SHELL OIL CO | RTE 25A OVER BURKE ST | 11791 | FINDS, RCRIS-LQG | 1 |
| SYOSSET | S100168404 | EXXON | 250 EILEEN ST | 11791 | LUST | 7 |
| SYOSSET | 1000833524 | SYOSSET COMPLEX | 80 W JERICO TNPK | 11791 | RCRIS-SQG | 1 |
| SYOSSET | 1000555591 | SYOSSET MEDICAL BUILDING | 175 JERICO TNPK | 11791 | RCRIS-SQG, FINDS | 1 |
| SYOSSET | 1000446597 | OYSTER BAY TOWN OF SYOSSET PARK | JERICO TNPK | 11791 | RCRIS-SQG, FINDS | 1 |
| SYOSSET | U001855196 | MEADOWBROOK FORD/SYOSSET | 271 JERICO TNPK. | 11791 | UST | 1 |
| SYOSSET | U001855122 | SYOSSET THEATRE | 7500 JERICO TNPK. | 11791 | UST | 1 |
| SYOSSET | U001854917 | SYOSSET EXXON | 573 JERICO TKURNPIKE | 11791 | UST | 7 |
| SYOSSET | U001445587 | SYOSSET COMMUNITY HOSP. | 221 JERICO TNPK. | 11791 | UST | 1 |
| SYOSSET | S100149465 | FAIRHAVEN APTS | JERICO TURNPIKE / RT 135 | 11791 | LUST | 5 |
| SYOSSET | S100171387 | UNK | JERICO TPKE/RTE 135 | 11791 | LUST | 5 |
| SYOSSET | S100521014 | SYOSSET LANDFILL | MILLER PLACE / ROBBINS LANE | 11791 | SHWS | 6 |
| SYOSSET | S100172745 | NYS DOT | NYS DOT HIGHWAY GARAGE | 11791 | LUST | 1 |
| SYOSSET | U001855046 | SYOSSET HIGH SCHOOL | SOUTHWOODS ROAD | 11791 | UST | 3 |
| SYOSSET | U001446321 | SYOSSET C.S.D. BUS GARAGE | WOODBURY ROAD | 11791 | UST | 3 |
| SYOSSET | 1000547877 | SYOSSET S H S | SO WOODS RD | 11791 | FINDS | 7 |
| SYOSSET | S100878967 | SYOSSET SCHOOL DISTRICT | WOODS ROAD | 11791 | LUST | 7 |

Reason Codes:

1 = No matching street name
2 = No matching address range

3 = Multiple matching addresses / street intersections
4 = First street name in intersection not found

5 = Second street name in intersection not found
6 = Named streets do not intersect

7 = Other

EPA Waste Codes Addendum

| Code | Description |
|------|--|
| D001 | IGNITABLE HAZARDOUS WASTES ARE THOSE WASTES WHICH HAVE A FLASHPOINT OF LESS THAN 140 DEGREES FAHRENHEIT AS DETERMINED BY A PENSKEY-MARTENS CLOSED CUP FLASH POINT TESTER. ANOTHER METHOD OF DETERMINING THE FLASH POINT OF A WASTE IS TO REVIEW THE MATERIAL SAFETY DATA SHEET, WHICH CAN BE OBTAINED FROM THE MANUFACTURER OR DISTRIBUTOR OF THE MATERIAL. LACQUER THINNER IS AN EXAMPLE OF A COMMONLY USED SOLVENT WHICH WOULD BE CONSIDERED AS IGNITABLE HAZARDOUS WASTE. |

**GEOCHECK VERSION 1.1
SUMMARY**

HYDROGEOLOGICAL INFORMATION

| <u>WELL QUADRANT</u> | <u>DISTANCE FROM TP</u> | <u>LITHOLOGY</u> | <u>DEPTH TO WATER TABLE</u> |
|--------------------------|-----------------------------|------------------|---------------------------------|
| Northern | 1/2 - 1 Mile | Sand | 144 ft. |
| Eastern | >2 Miles | Sand | 103 ft. |
| Southern | 1 - 2 Miles | Sand | 94 ft. |
| Western | >2 Miles | Sand | 61 ft. |

AREA RADON INFORMATION

NASSAU COUNTY, NY

Living Area

| | |
|-------------------|-------------|
| Average Activity: | 0.640 pCi/L |
| % <4 pCi/L: | 98% |
| % 4-20 pCi/L: | 2% |
| % >20 pCi/L: | 0% |

Basement Area

| | |
|-------------------|-------------|
| Average Activity: | 1.100 pCi/L |
| % <4 pCi/L: | 98% |
| % 4-20 pCi/L: | 2% |
| % >20 pCi/L: | 0% |

GEOCHECK VERSION 1.1
HYDROGEOLOGICAL INFORMATION
Well Closest to Target Property (Northern Quadrant)

BASIC WELL DATA

| | | | |
|-----------------------|--|----------------------|--------------|
| Site ID: | 404820073312101 | Distance from TP: | 1/2 - 1 Mile |
| Site Type: | Single well, other than collector or Ranney type | | |
| Year Constructed: | Not Reported | County: | Nassau |
| Altitude: | 228.00 ft. | State: | New York |
| Well Depth: | 185.00 ft. | Topographic Setting: | Undulating |
| Depth to Water Table: | 144.00 ft. | Prim. Use of Site: | Observation |
| Date Measured: | 01011943 | Prim. Use of Water: | Unused |

LITHOLOGIC DATA

| | |
|---------------------|---------------------------|
| Lithologic Unit: | Mesozoic-Cretaceous-Upper |
| Lithology of Unit: | Sand |
| Lithology Modifier: | FINE GRAINED |

WATER LEVEL VARIABILITY

Not Reported

GEOCHECK VERSION 1.1
HYDROGEOLOGICAL INFORMATION

Well Closest to Target Property (Eastern Quadrant)

BASIC WELL DATA

| | | | |
|-----------------------|--|----------------------|-------------|
| Site ID: | 404704073264201 | Distance from TP: | >2 Miles |
| Site Type: | Single well, other than collector or Ranney type | | |
| Year Constructed: | Not Reported | County: | Nassau |
| Altitude: | 185.00 ft. | State: | New York |
| Well Depth: | 185.00 ft. | Topographic Setting: | Valley flat |
| Depth to Water Table: | 103.00 ft. | Prim. Use of Site: | Observation |
| Date Measured: | 05011940 | Prim. Use of Water: | Unused |

LITHOLOGIC DATA

| | |
|---------------------|---------------------------|
| Lithologic Unit: | Mesozoic-Cretaceous-Upper |
| Lithology of Unit: | Sand |
| Lithology Modifier: | Not Reported |

WATER LEVEL VARIABILITY

Not Reported

GEOCHECK VERSION 1.1
HYDROGEOLOGICAL INFORMATION
Well Closest to Target Property (Southern Quadrant)

BASIC WELL DATA

| | | | |
|-----------------------|--|----------------------|---------------------|
| Site ID: | 404707073305301 | Distance from TP: | 1 - 2 Miles |
| Site Type: | Single well, other than collector or Ranney type | | |
| Year Constructed: | 1958 | County: | Nassau |
| Altitude: | 175.00 ft. | State: | New York |
| Well Depth: | 605.00 ft. | Topographic Setting: | Flat surface |
| Depth to Water Table: | 94.00 ft. | Prim. Use of Site: | Withdrawal of water |
| Date Measured: | 01011958 | Prim. Use of Water: | Public supply |

LITHOLOGIC DATA

| | |
|---------------------|---------------------------|
| Lithologic Unit: | Mesozoic-Cretaceous-Upper |
| Lithology of Unit: | Sand |
| Lithology Modifier: | COARSE GRAINED |

WATER LEVEL VARIABILITY

Not Reported

GEOCHECK VERSION 1.1
HYDROGEOLOGICAL INFORMATION

Well Closest to Target Property (Western Quadrant)

BASIC WELL DATA

| | | | |
|-----------------------|--|----------------------|---------------------|
| Site ID: | 404628073342001 | Distance from TP: | >2 Miles |
| Site Type: | Single well, other than collector or Ranney type | | |
| Year Constructed: | 1935 | County: | Nassau |
| Altitude: | 142.00 ft. | State: | New York |
| Well Depth: | 501.00 ft. | Topographic Setting: | Flat surface |
| Depth to Water Table: | 61.00 ft. | Prim. Use of Site: | Withdrawal of water |
| Date Measured: | 05011935 | Prim. Use of Water: | Public supply |

LITHOLOGIC DATA

| | |
|---------------------|---------------------------|
| Lithologic Unit: | Mesozoic-Cretaceous-Upper |
| Lithology of Unit: | Sand |
| Lithology Modifier: | COARSE GRAINED |

WATER LEVEL VARIABILITY

Not Reported

**Federal
EDR-Site Report**

SYOSSET LF
150 MILLER PLACE
OYSTER BAY, NY 11791

EDR-ID: 1000386366

Site Report Summary:

- Is this site on the Federal CERCLIS list as an abandoned, inactive or uncontrolled hazardous waste site ?..... Yes
- Is this site a Federal SUPERFUND site ?..... Yes
- Is this site on the Federal RCRA list as a generator of hazardous wastes ?..... No
- Is this site on the Federal RCRA list as a facility that treats, stores or disposes of hazardous wastes ?..... No
- Is this site on the Federal TRIS list as having released toxic chemicals to the environment ?..... No
- Is this site on the Federal FINDS list ?..... Yes
- Is this site on the Federal TSCA list as an importer and/or manufacturer of toxic chemicals ?..... No

Federal EDR-Site Report

... Continued ...

NPL Record:

This site is classified as a federal SUPERFUND site or is proposed for inclusion on the SUPERFUND list. This record was last updated by the government on: 01/10/1994

Site Name: Syosset Landfill
150 MILLER PLACE
Oyster Bay, NY 11791

Status: Listed on the NPL

Date Listed: 9/08/83

NPL-ID: 02NY029

EPA-ID: NYD000511360

NPL Rank / Group: 122 / 3

Haz Rank Score: 54.27 [0.00 Least Severe - 100.00 Most Severe]

Site Ownership: Municipal

Site Permits: None

Site Activities: Landfill, Municipal
Landfill, Comm./Indus.

Site Condition: Contam. Drinking Water
Direct Contact
Contam. Ground Water

Waste Type: Metals
Solvents

Waste Form: NOT REPORTED

Contaminant

1,1,2-TRICHLOROETHYLENE [TCE]
TETRACHLOROETHENE
1,1,1-TRICHLOROETHANE
ARSENIC
CADMIUM [CD]
CHROMIUM AND COMPOUNDS, NOS [CR]
LEAD [PB]

Media Affected

Ground Water
Ground Water
Ground Water
Ground Water
Ground Water
Ground Water

Population Proximity Data

Distance to nearest Population: NOT REPORTED
Population within a 1 Mile Radius: More than 10,000 People

Ground Water Data

Vertical Distance to Aquifer: NOT REPORTED
Ground Water Use: Not Used as Drinking Water, Alternative Source Available
Distance to nearest Surface Water: NOT REPORTED

Federal EDR-Site Report

... Continued ...

CERCLIS Record:

This site is listed in the Federal CERCLIS database as having an abandoned, inactive or uncontrolled hazardous waste site. This record was last updated by the government on: 03/29/94

CERCLIS Name: SYOSSET LF
150 MILLER PLACE
OYSTER BAY, NY 11791
NASSAU County

EPA-ID: NYD000511360

Classification: Landfill

Ownership Status: Other than Federal, State, District, County, Municipality, Indian Lands,
Mixed Ownership or Private

NPL Status: Currently on the Superfund (NPL) List

Site Status: This site is currently under investigation by the government to assess
the extent of further action.

EPA Notes: TWN OF OYSTER BAY SUSPENDED WASTE DISPL OPERNS AT LF AFTER WTR POLLUTN
DETECTD. HI CONCETRNS OF HEAVY METALS IN INDUSTLSLUDGES BEING DEPOSITD
& IN DISCHGD WASTES FR SCAVENGER PLT OPERNS. VOC'S IN 2 PRIVT WELLS. CNTY'S
PRIMARY GW BECHG AREA

| Site Assessment History: | Start | Completion |
|---|--------------|------------|
| DISCOVERY Primary Responsibility: EPA- fund financed | NOT REPORTED | 11-01-79A |
| PRELIMINARY ASSESSMENT Primary Responsibility: EPA- fund financed | NOT REPORTED | 11-01-79A |
| SCREENING SITE INSPECTION Primary Responsibility: EPA- fund financed | 11-01-79A | 12-01-82A |
| HAZARD RANKING DETERMINED Primary Responsibility: EPA- fund financed | NOT REPORTED | 12-01-82A |
| FINAL LISTING ON NPL Primary Responsibility: EPA- fund financed | NOT REPORTED | 09-08-83A |
| PROPOSAL TO NPL Primary Responsibility: EPA- fund financed | NOT REPORTED | 12-30-82A |

[A - Actual, P - Planned]

This site is also known under one or more aliases as follows:

SYOSSET LANDFILL
TOWN OF OYSTER BAY MILLER PL
SYOSSET, NY 11791

Federal EDR-Site Report

... Continued ...

FINDS Record:

This site is listed in the Federal FINDS database. Please note that the FINDS database may contain government records which are included in your particular report and may reference an out-of-date record formally associated with the site. The government last updated this specific record on: 10/05/90

FINDS Name: SYOSSET LF
150 MILLER PLACE
SYOSSET, NY 11791

EPA-ID: NYD000511360

Latitude: 404802

Longitude: 0733047

Owner Type: NOT REPORTED

Operator Type: NOT REPORTED

Sic Code: NOT REPORTED

EPA Records Indicate Facility Is Listed In:

COMPREHENSIVE ENVIRONMENTAL
RESPONSE, COMPENSATION AND
LIABILITY INFORMATION SYSTEM
[CERCLIS]

Facility ID: NYD000511360

GOVERNING LEGISLATION: COMPREHENSIVE ENVIRONMENTAL
RESPONSE, COMPENSATION AND
LIABILITY ACT [SUPERFUND].

THIS LEGISLATION COVERS: POTENTIALLY UNCONTROLLED
HAZARDOUS WASTE SITES,
SUPERFUND SITES.

IMPLEMENTING THE LEGISLATION IS THE RESPONSIBILITY OF EPA'S:
OFFICE OF EMERGENCY AND

ENFORCEMENT DOCKET SYSTEM
[DOCKET]

Facility ID: 02-90-0182

GOVERNING LEGISLATION: ALL ENVIRONMENTAL STATUTES.

THIS LEGISLATION COVERS: FACILITIES WITH CIVIL JUDICIAL
AND ADMINISTRATIVE ENFORCEMENT
CASES.

IMPLEMENTING THE LEGISLATION IS THE RESPONSIBILITY OF EPA'S:
OFFICE OF ENFORCEMENT AND

CHAIN OF TITLE**Section: 15****Block: G****Lot: 16**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|---|-------------|
| County of Nassau | Board of Coop. Education Services of Nassau County | 1/31/89 |
| Central School District #2 | County of Nassau | 12/30/63 |
| Town of Oyster Bay & U.S. of A (Dept. of Navy) | Central School District #2 | 6/15/62 |
| U.S. of A (Dept. of Navy) Reconstruction Finance Corp. | U.S. of A (Dept. of Navy) | 5/1/48 |

Section: 15**Block: G****Lot: 32**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|------------------------|-------------------------|-------------|
| Renwil Machine Corp. | 136 Oak Drive Assoc.'s. | 5/4/84 |
| W.H. Instrument, Inc. | Renwil Machine Corp. | 4/12/84 |
| Harry A. Trautmann Jr. | W.H. Instrument, Inc. | 11/14/74 |
| William Luxenberg | Harry A. Trautmann Jr. | 7/9/69 |
| Harry A. Trautmann Jr. | William Luxenberg | 4/15/60 |
| Robina S. Watson | Harry A. Trautmann Jr. | 9/16/55 |
| Albert A Lewis Exec. | Robina S. Watson | 9/2/49 |

Section: 15**Block: G****Lot: 33**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|------------------------|------------------------|-------------|
| Catherine C. Trautmann | The Pay-O-Matic Corp. | 2/28/84 |
| Octah Realty, Inc. | Catherine C. Trautmann | 3/17/64 |
| Robina S. Watson | Octah Realty, Inc. | 9/16/55 |
| Albert A. Lewis Exec. | Robina S. Watson | 9/2/49 |

Section: 15**Block: G****Lot: 34**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|---|-------------|
| Nassau County Industrial Development Agency | Joseph Silveri | 1/17/89 |
| Joseph Silveri | Nassau County Industrial Development Agency | 10/4/85 |
| Beltran Associates, Inc. | Joseph Silveri | 5/13/85 |
| Ray Contracting Co., Inc. | Beltran Associates, Inc. | 1/5/79 |
| 44 Maple Realty Corp. | Dorant, Inc. | 6/2/75 |
| William Luxenberg | 44 Maple Realty Corp. | 7/9/69 |
| Harry A. Trautmann Jr. | William Luxenberg | 7/9/69 |
| Robina S. Watson | Harry A. Trautmann Jr. | 9/16/55 |
| Albert A. Lewis Exec. | Robina S. Watson | 9/2/49 |

Section: 15**Block: G****Lot: 109**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---------------------------|---|-------------|
| Beltran Associates | Joseph Silveri | 5/13/85 |
| Joseph Silveri | Nassau County Industrial Development Agency | 10/4/84 |
| Revnil Machine Corp. | 136 Oak Dr. Assoc.'s | 5/4/84 |
| W.H. Instrument Inc. | Revnil Machine Corp. | 4/12/84 |
| Ray Contracting Co., Inc. | Bellrini Associates, Inc. | 1/5/79 |
| Free Realty Holding Corp. | Alarm Device Mfg. Co. | 9/21/78 |
| 44 Maple Realty Corp. | Dorant, Inc. | 6/2/75 |
| Harry A. Trautmann Jr. | W.H. Instrument Inc. | 11/14/74 |
| William Luxenberg | 44 Maple Realty Corp. | 7/9/69 |
| Harry A. Trautmann Jr. | William Luxenberg | 7/9/69 |
| William Luxenberg | Harry Luxenberg | 7/9/69 |

Lot 109 continued:

| | | |
|--|-------------------------------------|----------|
| Octah Realty Inc. | Catherine c. Trautmann | 3/17/64 |
| Axinn & Mascioli, Inc. | Free Realty Holding Corp. | 8/23/63 |
| Donald E. Axinn & Frank X. Mascioli | Axinn & Mascioli, Inc. | 1/30/63 |
| Pal-Pel Corp. | Donald E. Axinn & Frank X. Mascioli | 1/23/63 |
| Ced-Gro Realty Corp. | Pal-Pel Corp. | 1/18/60 |
| Herman E. Lauman | Ced-Gro Realty Corp. | 7/23/57 |
| Robina S. Watson | Harry A. Trautmann Jr. | 9/16/55 |
| Robina S. Watson | Octah Realty, Inc. | 9/16/55 |
| Est. Harold C. Lewis Exec. | H.E. Lauman | 11/18/52 |
| Albert A. Lewis Exec. | Robin S. Watson | 9/2/49 |

Section: 15**Block: G****Lot: 211**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--|-------------------------------------|-------------|
| Free Realty Holding Corp. | Alarm Device Mfg. Co. | 9/21/78 |
| Axinn & Mascioli, Inc. | Free Realty Holding Corp. | 8/23/63 |
| Donald E. Axinn & Frank X. Mascioli | Axinn & Mascioli, Inc. | 1/30/63 |
| Pal-Pel Corp. | Donald E. Axinn & Frank X. Mascioli | 1/23/63 |
| Ced-Gro Realty Corp. | Pal-Pel Corp. | 1/18/60 |
| Herman E. Lauman | Ced-Gro Realty Corp. | 7/23/57 |
| Est. Harold C. Lewis Exec's | H.E. Lauman | 11/18/52 |

Section: 15**Block: 41****Lot: 19**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|----------------------------|----------------------|-------------|
| Neil Posillico | Frank & Tony Toscano | 8/12/94 |
| 4 Bros. Mason Supply, Inc. | Neil Posillico etal | 2/14/84 |

Lot 19 continued:

| | | |
|-------------------------------------|----------------------------------|----------|
| Erasmus J. Tafaro | 4 Bros. Mason Supply, Inc. | 1/23/70 |
| Carl Johnson | Erasmus J. Tafaro | 11/14/63 |
| William Drost & Magnus Burfeindt | Carl Johnson | 5/5/59 |
| John C. & Hanni Schulz | William Drost & Magnus Burfeindt | 3/9/56 |
| Arthur M. Ragazzino | John C. & Hanni Schulz | 3/22/55 |
| Harold & Anna Wahne | Arthur M. Ragazzino | 8/6/50 |
| Lewis Development Co., Inc. | Harold & Anna Wahne | 11/26/48 |

Section: 15**Block: 41****Lot: 20**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--|--|-------------|
| Terence Cullen | Aaron Sokol | 1/23/95 |
| Lambda Holdings Inc. | Aaron Sokol & Terence Cullen | 10/22/93 |
| Veeco Instruments Inc., FCA Veeco Inst. Acquisition Corp. | Lambda Electronics Inc. | 3/15/91 |
| UPA Technology Inc. | Veeco Inst. Acquisition Corp. | 1/18/90 |
| Nassau County Industrial Development Agency | UPA Technology, Inc. | 12/19/86 |
| UPA Technology Inc. | Nassau County Industrial Development Agency | 6/24/82 |
| Sidney & Phyllis Lierber | UPA Technology Inc. | 6/29/81 |
| Rego Crescent Corp. | UPA Technology Inc. | 8/28/78 |
| Joseph Harris | Nassau County | 6/29/50 |
| County of Nassau | Joseph Harris | 10/14/49 |
| County of Nassau x Tres | County of Nassau | 4/21/49 |
| Reconstruction Finance Corp. | U.S. of A. (Dept. of Navy) | 5/1/48 |

Section: 15**Block: 157****Lot: 19**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|----------------------------|----------------------------|-------------|
| Aerial Way Corp. | Lockbart Realty Corp. | 2/1/62 |
| Ellis Chingos | Aerial Way Corp. | 11/20/56 |
| Murray Manufacturing Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Manufacturing Corp. | 4/17/51 |

Section: 15**Block: 157****Lot: 21**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|----------------------------|---|-------------|
| 3 Aerial Way Corp. | Gerald I. Starr | 7/5/72 |
| Morris Back | 3 Aerial Way Corp. | 6/30/72 |
| Nathan T. Sedley | Morris Back | 1/2/66 |
| Nathan T. Sedley | Morris Back as Trustee: Thomas-Leeds Inc. Profit Sharing Plan | 7/21/64 |
| Morris Back | Nathan T. Sedley | 7/24/61 |
| Ellis Chingos | Nathan T. Sedley & Morris Back | 3/30/61 |
| Murray Manufacturing Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Manufacturing Corp. | 4/17/51 |

Section: 15**Block: 157****Lot: 23**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|-------------------------------------|-------------------------------------|-------------|
| Rone Realty Corp. | Aerial Way Associates | 1/31/78 |
| Bank of NY as Trustee | Rone Realty Corp. | 1/31/78 |
| Fairchild Camera & Instrument Corp. | 14th & 34rd Corp. | 5/13/70 |
| Aerial Way Associates | Fairchild Camera & Instrument Corp. | 1/31/67 |
| Ellis Chingos | Aerial Way Associates | 8/12/58 |

Lot 23 continued:

| | | |
|----------------------------|----------------------------|---------|
| Murray Manufacturing Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Manufacturing Corp. | 4/17/51 |

Section: 15**Block: 157****Lot: 27**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--|--|-------------|
| Michael Forte | Pittway Corp. | 11/18/68 |
| Michael Forte | County of Nassau | 5/21/68 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15**Block: 157****Lot: 32**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---------------------------------|---|-------------|
| N.S. Realty Co. | 17 Aerial Way Assoc.'s | 8/3/79 |
| Chingos Associates | N.S. Realty Co. | 4/6/78 |
| John Chingos Construction Corp. | Chingos Associates | 4/18/74 |
| Chingos Associates | John Chingos Construction Corp. | 4/5/74 |
| Morris Back | Chingos Associates | 2/26/73 |
| Nathan T. Sedley | Morris Back | 1/2/66 |
| Nathan T. Sedley | Morris Back as Trustee Thomas-Leeds Co., Inc. Profit Sharing Plan | 7/21/64 |
| Nathan T. Sedley | Morris Back | 2/7/64 |
| Ellis Chingos | Nathan T. Sedley & Morris Bank | 3/30/61 |
| Murray Mfg. Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Mfg. Corp. | 4/17/51 |

Section: 15

Block: 157

Lot: 41

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|--|-------------|
| Michael Forte | Pittway Corp. | 11/18/68 |
| Foreal Homes Inc. | Michael Forte | 9/20/61 |
| Michael Forte | Foreal Homes Inc. | 9/20/61 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15

Block: 157

Lot: 42

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|--|-------------|
| Lee Blatt & Herman Kagan | Lee Blatt | 2/13/86 |
| Bogart Development Co. | Lee Blatt & Herman Kagan | 1/10/86 |
| Jessie Rothman | 175 Eileen Development Co. | 2/31/70 |
| 175 Eileen Development Corp. | 175 Eileen Development Co. | 3/17/69 |
| Michael Forte | 175 Eileen Development Co. | 3/17/69 |
| Michael Forte | County of Nassau | 5/21/68 |
| Foreal Homes, Inc. | Michael Forte | 12/28/66 |
| Michael Forte | Foreal Homes, Inc. | 12/28/66 |
| Foreal Homes, Inc. | Michael Forte | 3/28/61 |
| Michael Forte | Foreal Homes, Inc. | 3/28/61 |
| Michael Forte | Ruser Realty Corp. | 5/9/60 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15**Block: 157****Lot: 44**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|--|-------------|
| Metallurgical Processing Corp. | Pittway Corp. | 2/5/79 |
| Port Realty Co. | Metallurgical Processing Corp. | 4/9/69 |
| 180 Michael Drive Corp. | Port Realty Co. | 6/10/68 |
| Port Realty Co. | 180 Michael Drive Corp. | 6/10/68 |
| Michael Forte | Port Realty Co. | 2/7/66 |
| Arthur M. Rogozzino | Horm. Holding Co., Inc. | 6/22/60 |
| Michael Forte | Ruser Realty Corp. | 5/9/60 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15**Block: 157****Lot: 45**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|--|-------------|
| Taxco Holding Corp. | Alarm Device Mfg., Co. | 4/9/80 |
| Foreal Homes. Inc. | Taxco Holding Corp. | 4/6/79 |
| Formia Const. Co., Inc. | Foreal Homes. Inc. | 4/5/79 |
| Gail Gillman | Formia Const. Co., Inc. | 9/1/70 |
| Michael Forte | Foreal Homes. Inc. | 8/1/67 |
| Arthur M. Rogozzino | Hormi Holding Co., Inc. | 8/1/67 |
| Michael Forte | Ruser Realty Corp. | 5/9/60 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15**Block: 157****Lot: 46**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--|---------------------------------|-------------|
| Paul & Charlse Serwitz & Edith Rubinstein | Ruser Realty Co. | 12/12/91 |
| Dupont Associates Inc. | Paul Serwitz | 8/1/83 |
| Newport Assoc. Inc. | Dupont Associates, Inc. | 1/6/75 |
| Sol & Irving Goldman | Newport Associates Inc. | 10/26/72 |
| Chase Manhattan Bank as Trustee | Sol & Irving Goldman | 6/16/72 |
| Ruser Realty Corp. | Chase Manhattan Bank as Trustee | 2/1/63 |
| Michael Forte | Ruser Realty Corp. | 5/9/60 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin | 4/1/55 |

Section: 15**Block: 157****Lot: 49**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|--|-------------|
| Kirby Builders Inc. | Setre Corp. | 11/2/87 |
| Taxco Holding Corp. | Kirby Builders Inc. | 12/15/83 |
| Michael Forte | Taxco Holding Corp. | 4/6/79 |
| Michael Forte | Foreal Homes. Inc. | 1/10/69 |
| Foreal Homes. Inc. | Michael Forte | 1/10/69 |
| Arthur M. Rogozzino | Hormi Holding Co., Inc. | 6/22/60 |
| Michael Forte | Ruser Realty Corp. | 5/9/60 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15**Block: 157****Lot: 51**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--|--|-------------|
| Metallurgical Processing Corp. | Pittway Corp. | 2/5/79 |
| Port Realty Co. | Metallurgical Processing Corp. | 4/9/69 |
| Foreal Homes, Inc. | Michael Forte | 1/10/69 |
| Michael Forte | Foreal Homes, Inc. | 1/10/69 |
| 180 Michael Dr. Corp. | Port Realty Co. | 6/10/68 |
| Suburbia Federal & Savings and Loan Associate | 180 Michael Dr. Corp. | 6/7/68 |
| Arthur M. Rogozzino | Hormi Holding Co. Inc. | 6/22/60 |
| Michael Forte | Ruser Realty Corp. | 5/9/60 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15**Block: 157****Lot: 52**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--|--|-------------|
| Metallurgical Processing Corp. | Pittway Corp. | 2/5/79 |
| Port Realty Co. | Metallurgical Processing Corp. | 4/9/69 |
| 180 Michael Dr. Corp. | Port Realty Co. | 6/10/68 |
| Suburbia Federal & Savings and Loan Associate | 180 Michael Dr. Corp. | 6/7/68 |
| Arthur M. Rogozzino | Hormi Holding Co. Inc. | 6/22/60 |
| Michael Forte | Ruser Realty Corp. | 5/9/60 |
| Herman M. Seldin & Paul R. Silverstein | Michael Forte | 10/24/55 |
| Bank of NY etc. | Herman M. Seldin & Paul R. Silverstein | 4/1/55 |

Section: 15**Block: 157****Lot: 60**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|------------------------------|--------------------------------|-------------|
| Loral Corp. | Loral Fairchild Corp. | 6/25/90 |
| Fairchild Weston System Inc. | Loral Corp. | 6/12/90 |
| Ellis Chingos | Fairchild Camera & Inst. Corp. | 11/18/76 |
| Murray Mfg. Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Mfg. Corp. | 4/17/51 |

Section: 15**Block: 157****Lot: 61**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|-------------------------------|-------------------------------------|-------------|
| Loral Corp. | Loral Fairchild Corp. | 6/25/90 |
| Fairchild Weston Systems Inc. | Loral Corp. | 6/12/90 |
| Fairchild Semiconductor Corp. | Fairchild Weston Systems Inc. | 9/25/87 |
| Charles J. Mascioli | Fairchild Camera & Instrument Corp. | 11/18/76 |
| Joseph Mascioli | Charles J. Mascioli | 5/29/75 |
| Charles J. Mascioli | Joseph Mascioli | 11/28/72 |
| Wilmar Construction Corp. | Charles Mascioli | 8/28/67 |
| Charles Mascioli | Wilmar Construction Corp. | 8/25/67 |

Section: 15**Block: 161****Lot: 7**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|----------------------------|---------------------------------------|-------------|
| Dennis J. Driscoll | Tuck-Leou Associates | 8/2/84 |
| Est. Michael B. Driscoll | Dennis Driscoll | 6/11/84 |
| Great Eastern Printing Co. | Florence & Dennis Driscoll as Trustee | 6/8/84 |
| Ellis Chingos | Great Eastern Printing Co., Inc. | 1/5/71 |

Lot 7 continued:

| | | |
|-------------------------|-------------------|---------|
| Murray Mfg. Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Mfg. Corp. | 4/17/51 |

Section: 15**Block: 161****Lot: 8**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--------------------------------|--------------------------------|-------------|
| Rone Realty Corp. | Aerial Way Associates | 1/31/78 |
| Bank of NY as Trustee | Rone Realty Corp. | 1/31/78 |
| Fairchild Camera & Inst. Corp. | 14th & 3rd. Corp. | 5/13/70 |
| Aerial Way Associates | Fairchild Camera & Inst. Corp. | 1/31/67 |
| Ellis Chingos | Aerial Way Assoc.'s | 8/12/58 |
| Murray Mfg. Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Mfg. Corp. | 4/17/51 |

Section: 15**Block: 161****Lot: 9**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---------------------------------|---------------------------------|-------------|
| Daniel H. Frank | 6 Aerial Way Realty Corp. | 10/20/89 |
| Abandaco Inc. | Daniel H. Frank | 12/29/87 |
| Hidden Harbor Land Ltd. | Abandaco, Inc. | 7/15/87 |
| Seymour Lowell & Robert Belskey | Hidden Harbor Lands Ltd. | 12/13/86 |
| Chingos Associates | Seymour Lowell & Robert Belskey | 11/17/78 |
| John Chingos Construction Corp. | Chingos Associates | 9/27/68 |
| Ellis & John Chingos | John Chingos Construction Corp. | 8/16/68 |
| Ellis Chingos | Chingos Associates | 6/28/68 |
| Murray Mfg. Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Mfg. Corp. | 4/17/51 |

Section: 15**Block: 161****Lot: 40**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---------------------------------|---------------------------------|-------------|
| Daniel H. Frank | 6 Aerial Way Realty Corp. | 10/20/89 |
| Abandac, Inc. | Daniel H. Frank | 12/29/87 |
| Hidden Harbor Land Ltd. | Abandac, Inc. | 7/15/77 |
| Seymour Lowell & Robert Belsky | Hidden Harbor Land Ltd. | 12/3/86 |
| Chingos Associates | Seymour Lowell & Robert Belskey | 11/17/78 |
| John Chingos Construction Corp. | Chingos Associates | 9/27/68 |
| Ellis & John Chingos | John Chingos Construction Corp. | 8/16/68 |
| Ellis Chingos | Chingos Associates | 6/28/68 |
| Ellis Chingos | County of Nassau | 2/6/55 |
| Murray Mfg. Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Mfg. Corp. | 4/17/51 |

Section: 15**Block: 161****Lot: 41**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|-------------------------|-------------------|-------------|
| Ellis Chingos | County of Nassau | 2/6/55 |
| Murray Mfg. Corp. | Ellis Chingos | 3/31/54 |
| Hicksville Airpark Inc. | Murray Mfg. Corp. | 4/17/51 |

Section: 15**Block: 204****Lot: 14**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--------------------------------|----------------------------------|-------------|
| Terminal Industrial Park, Inc. | County of Nassau | 3/7/78 |
| Joseph Gluckman etal. | Terminal Industrial Park, Inc. | 5/15/61 |
| Nicholas A. Piccione | Gay Lore Development Comp., Inc. | 1/3/61 |

Section: 15**Block: 204****Lot: 17**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|----------------------------------|-------------|
| Terminal Industrial Park, Inc. | Gordon Nassau Realty Corp. | 3/7/86 |
| Joseph Gluckman etal. | Terminal Industrial Park, Inc. | 5/15/61 |
| Nicholas A. Piccione | Gay Lore Development Comp., Inc. | 1/3/61 |
| Joseph Gluckman & Nicholas A. Piccione | Terminal Industrial Park, Inc. | 5/16/60 |

Section: 15**Block: 204****Lot: 19**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|--------------------------------|------------------------------------|-------------|
| Terminal Industrial Park, Inc. | Gordon Floral Realty Corp. | 12/18/90 |
| Joseph Gluckman etal | Terminal Industrial Park, Inc. | 5/15/61 |
| Nicholas A. Piccioine | Gay Lore Development Company, Inc. | 1/3/61 |

Section: 15**Block: 204****Lot: 20**

| <u>Grantor</u> | <u>Grantee</u> | <u>Date</u> |
|---|------------------------------------|-------------|
| Joseph Gluckman etal. | Terminal Industrial Park, Inc. | 5/15/61 |
| Nicholas A. Piccione | Gay Lore Development Company, Inc. | 1/3/61 |
| Joseph Gluckman & Nicholas A. Piccione | Terminal Industrial Park, Inc. | 5/16/60 |

Table 1. Current Property Tenants.

1. Cerro Wire, former wire manufacturer.
2. Unsigned building, currently vacant.
3. Great Eastern Printing, 7 Aerial Way, printing company.
4. Universal Electric State Lighting, 5 Aerial Way, operations unknown;
U.S. Geological Survey, 5 Aerial Way
5. Centroid Inc., 3 Aerial Way, unknown operations.
6. LKB, Inc., 1 Aerial Way, engineering consultants.
7. Caligor Hospital Supply Company, 300 Michael Dr., sales and possible assembly of
hospital supplies.

New Breed Corp. Integrated Logistical Services, 300 Michael Dr.
8. Same as above.
9. Same as above.
10. Tristate Consumer Insurance Corp., 175 Eileen Way, insurance sales.
11. National Learning Corp., 212 Michael Dr., publishing operation.
12. Nissan Auto Parts, 200 Michael Drive, auto parts storage and sales operations.
13. Ademco, Inc., 176-178 Michael Drive, manufacture and sales of alarm systems.
14. First Alert, Inc., 172 Michael Drive, smoke alarm sales operation.
15. Same as above.
16. Office building, 160 Oak Dr.
17. Office Building, undetermined address on Oak Dr.
18. Johnson Construction, undetermined address on Oak Drive.
19. Empty structure, undetermined address on Oak Dr.

Table 1. Current Property Tenants.

20. Ademco, Inc., undetermined address on Oak Drive, manufacture and sales of alarm systems.
21. Roadway, Inc., 140 Gordon Dr., storage and possible maintenance of tractor trailers.
22. Office building, 80 Gordon Dr.
23. Office building, undetermined address on Gordon Dr.
24. Residential houses.
25. Residential houses.
26. Town of Oyster Bay Highway Maintenance Department.
Town of Oyster Bay Animal Shelter.
27. Residential houses.

VALTECH RESEARCH, INC.

820 Hempstead Turnpike • Franklin Square, New York 11010

(516) 358-9400

Fax (516) 358-5050

CERTIFICATE OF OCCUPANCY REPORT

TITLE NUMBER: GMES-NY0029008

DATE: 02/28/94

PREMISES: 300 MICHAEL DRIVE, SYOSSET

TAX CLASS: 710.14

MUNICIPALITY: TOWN OF OYSTER BAY

COUNTY: NASSAU

SECT: 15 BLK: 157 LOT(s): 46

THE FOLLOWING INFORMATION IS ON FILE WITH THE DEPARTMENT OF BUILDINGS:

- CO# 13654 01/17/61 PERMIT# A15025 05/09/60
242' X 457' INDUSTRIAL BUILDING
- CO# 30546 06/24/69 PERMIT# C9614 06/28/58
371' X 150' ADDITION
- CO# 50053 03/06/80 PERMIT# C1055 01/20/66
RECONSTRUCTED & ENCLOSED EXISTING
LOADING PLATFORM
- CO# A23111 01/04/91 PERMIT# L16330, L15005
REBUILT BOILER ROOM & DAMAGED WALL
- CO# A27554 10/02/92 PERMIT# L22236 03/29/91
INTERIOR ALTERATIONS
- OPEN PERMIT# L10323 03/31/89 (EXPIRED)
INTERIOR ALTERATIONS



Certificate of Occupancy

Town of Oyster Bay Department of Planning and Development
Division of Building, 74 Andrey Avenue, Oyster Bay, New York 11771

No. 12755

10/02/92

Property Owner Information:

Lin Pac Inc. 655A Selig Drive SW Atlanta Georgia 30336 404-691-1048

Property Information: Section: 15 Block: 157

Lot(s): 46

Zone: SD
H 14

Located on: Side of Feet of
South Michael Drive 331 South Eileen Way

Post Office
Syosset

Address: 300 Michael Drive Syosset

| | | | | | | | | | |
|----------|---------------|----------|-------------|------------|------|--------------|------|-------|---------|
| Appl No. | Bldg Per. No. | Date | Receipt No. | Z.B.A. No. | Date | Town Brd No. | Date | CA No | Elec No |
| 0853 | L22236 | 03/29/91 | H52169 | | | | | G9297 | N143998 |

Work Completed

L22236 - Interior Alterations

This certifies that the above construction conforms with the approved plans and Codes of the Town of Oyster Bay and the New York State Fire Prevention and Building Code.

TOBDPD Certificate of Occupancy - SBL Copy

Salvatore B. Puccio  Initials
Commissioner, Department of Planning and Development

| | | | |
|----|---|----|--------------------------------------|
| 4 | H.V.A.C. Drawings | 36 | Town Attorney Approval |
| 5 | Additional Permits (see comments) | 37 | N.C. Home Improvement License |
| 6 | Expired Building Permits | 38 | Workers Compensation Certificate |
| 7 | Building Permit Renewals | 39 | N.Y.S. Energy Conservation Code |
| 8 | Electrical Certificate of Approval | 40 | Certified Check |
| 9 | Plumbing Permit Application | 41 | Site Plan Approval |
| 10 | Plumbing Inspection | 42 | Elevation Certificate of Compliance |
| 11 | Plumbing Certificate of Approval | 43 | Concrete Certification |
| 12 | Sewer Certificate of Approval | 44 | Stack Certification |
| 13 | Compost Approval | 45 | Performance Bond |
| 14 | Final Inspection | 46 | N.Y.S. Dept. of Agriculture Approval |
| 15 | Final Survey | 47 | Filing Fee \$ |
| 16 | Read Waiver Affidavit | 48 | Final Fee \$ |
| | Homeowner <input type="checkbox"/> Builder <input type="checkbox"/> | 49 | Town Board Resolution Compliance |
| 17 | Park Fee | 50 | Z.B.A. Compliance |
| 18 | Final Supervisor Affidavit | 51 | Other |
| 19 | Trust Certification | | |
| 20 | Disclosure Affidavit | | |
| 21 | Board of Health Approval | | |
| 22 | X-Ray Approval | | |
| 23 | Fire Marshal Approval | | |
| 24 | Fire Sprinkler Test Approval | | |
| 25 | Flame Spread Certification | | |
| | Floor <input type="checkbox"/> Wall <input type="checkbox"/> Ceiling <input type="checkbox"/> Carpet <input type="checkbox"/> | | |
| 26 | Public Assembly License Approval | | |
| 27 | Multiple Residence Certificate Approval | | |
| 28 | T.O.B. Public Lighting Approval | | |
| 29 | T.O.B. Eng. and Design Approval | | |
| 30 | T.O.B. Park Dept. Approval | | |
| 31 | T.O.B. Environmental | | |
| 32 | T.O.B. Highway Approvals | | |

Comments:

I hereby approve the issuance of a Certificate of Occupancy.

Lyne R. Ponce C.T.I.

10/2/92

DP/CT/JP/fa

CERTIFICATE OF OCCUPANCY

No. A 23111

TOWN OF OYSTER BAY
DEPARTMENT OF PLANNING & DEVELOPMENT
DIVISION OF BUILDING

TOWN HALL, AUDREY AVENUE
OYSTER BAY, N.Y. 11771

ISSUED TO OWNER

NAME

STREET ADDRESS

POST OFFICE

FOR BUILDING LOCATED ON THE TAX

MAP OF THE TOWN OF OYSTER BAY IN

SECTION

BLOCK

LOTS

15

157

46

Clark Surgical Corp.

300 Michael Drive, P.O. #737-

Syosset, NY 11791

BUILDING PERMIT No.

APPLICATION No.

RECEIPT No.

PERMIT DATE

APPEAL BOARD No.

DATE 1/4/91

L16330, L15005

3707

H38802, H35041

1/5/90, 4/4/90

Zone

H

This CERTIFIES that the Building located at South side of Michael Drive, 331' South of Eileen Way, Syosset, NY

was constructed substantially in accordance with the plans filed for the above Building Permit and to all requirements of The Building Zone Ordinance and The Building Code of the Town of Oyster Bay and the occupancy is limited to the following use: Class L16330 - Rebuild boiler room, 41.67'x29.83'.

L15005 - Rebuild damaged wall.

SHOULD THE OCCUPANCY CHANGE FROM THE ABOVE LIMITATION OF USE, APPLICATION MUST BE MADE FOR NEW CERTIFICATE.

PLUMBING APPROVAL No.

UNDERWRITERS CERTIFICATE

N.B.F.U. No. H159253

Richard S. Blank
DEPARTMENT OF PLANNING & DEVELOPMENT
DIVISION OF BUILDING

Plumbing C.A. _____

Sewer C.A. _____

Final Survey _____

Lumber Affidavit _____

Highway Division Approval _____

Public Lighting Approval _____

Engineering & Drainage Approval _____

Certified Check Submitted _____

Health Department Approval _____

Park Fees Paid _____

Final Supervision Affidavit _____

Board of Appeals Compliance _____

Assembly License Approval _____



2. The 2000 Census New Construction

CERTIFICATE OF OCCUPANCY

No.

50053

TOWN OF OYSTER BAY
DEPARTMENT OF PLANNING & DEVELOPMENT
DIVISION OF BUILDING
TOWN HALL, AUDREY AVENUE
OYSTER BAY, N.Y. 11771

ISSUED TO OWNER

NAME

Columbia Corrugated Containers Corp.

STREET ADDRESS

300 Michael Drive

POST OFFICE

Syosset, New York

FOR BUILDING LOCATED ON THE TAX

MAP OF THE TOWN OF OYSTER BAY IN

SECTION 15 BLOCK 157 LOTS 46

DATE 3/6/80

BUILDING PERMIT No. C 1055

APPLICATION No. 376

RECEIPT No. 100,000

PERMIT DATE 1/20/66

APPEAL BOARD No.

Zone H

This CERTIFIES that the Building located at south end of Michael Drive, 331' south of Eileen Way, Syosset, New York, was constructed substantially in accordance with the plans filed for the above Building Permit and to all requirements of The Building Zone Ordinance and The Building Code of the Town of Oyster Bay and the occupancy is limited to the following use: Class

Reconstructed and enclosed existing loading platform

SHOULD THE OCCUPANCY CHANGE FROM THE ABOVE LIMITATION OF USE, APPLICATION MUST BE MADE FOR NEW CERTIFICATE.

PLUMBING APPROVAL No. None

UNDERWRITERS CERTIFICATE

N.B.F.U. No. 826474

DEPARTMENT OF PLANNING & DEVELOPMENT
DIVISION OF BUILDING

Thomas D. Sutton,
87 Henry St.,
Roosevelt, L.I. 11575

Carlton E. Alward
STATE SUPERINTENDENT

Per. 3

This certificate must not be altered in any manner; return to the office of the Board if incorrect. Inspectors may be identified by their credentials.

022
6781

CERTIFICATE OF OCCUPANCY

No. 30546

TOWN OF OYSTER BAY
DEPARTMENT OF ENGINEERING AND BUILDING
TOWN HALL, AUDREY AVENUE

QOYSTER BAY, N. Y.

ISSUED TO OWNER

Columbia Corrugated Container Corp.

DATE **June 24, 1969**

NAME

300 Midwood Drive

BUILDING PERMIT No.

C9810

STREET ADDRESS

SPOONER, New York

CESSPOOL PERMIT No.

POST OFFICE:

PLUMBING PERMIT NO.

FOR BUILDING LOCATED ON THE TAX

OIL BURNER PERMIT

MAP OF THE TOWN OF OYSTER BAY IN

APPEAL BOARD No

SECTION BLOCK ROLLERS

7-10123-54

CERTIFIES that the Building located at _____

was constructed substantially in accordance with the plans filed for the above Building Permit and to all requirements of The Building Zone Ordinance and The Building Code of the Town of Oyster Bay and the occupancy is limited to the following use: CLASS C-1-A-1-00 ADULTS TO CHURCH

Industrial Building - type 3 const. G.C. Classification

2000-2001 Data

SHOULD THE OCCUPANCY CHANGE FROM THE ABOVE LIMITATION OF USE, APPLICATION MUST BE
MADE FOR NEW CERTIFICATE

TOWN OF OYSTER BAY DEPARTMENT OF ENGINEERING & BUILDING

UNDERWATERS CERTIFICATE

N.B.F.U. No. N728232

Burner Permit No..... Cesspool Permit No.....

Electrical Certificate No. 111 (hereto attached)

Signed

Address

No Certificate of Occupancy will be issued unless Application is complete *and the fee is paid.* See reverse side. All payments by check or money order, payable to Town of Oyster Bay Building Department.

top soil. 1/2" of top

Lumber

Highway

Final Survey

PIF A15025

c/o 1/17/61

App. 6022
Receipt 6781

CERTIFICATE OF OCCUPANCY

No.

13654

TOWN OF OYSTER BAY BUILDING DEPARTMENT
OYSTER BAY, NASSAU COUNTY, N. Y.

ISSUED TO OWNER

NAME

STREET ADDRESS

POST OFFICE

FOR BUILDING LOCATED ON THE TAX

MAP OF THE TOWN OF OYSTER BAY IN

SECTION

BLOCK

LOTS

DATE

BUILDING PERMIT No.

CESSPOOL PERMIT No.

PLUMBING PERMIT No.

OIL BURNER PERMIT No.

APPEAL BOARD No.

SCHOOL DIST.

Zone

This CERTIFIES that the Building located at

south end of Michael Drive
south of Elson Way, Syosset, N. Y.

was constructed substantially in accordance with the plans filed for the above Building Permit and to all requirements of The Building Zone Ordinance and The Building Code of the Town of Oyster Bay and the occupancy is limited to the following use: **157 x 312 Industrial Building**

NOTE: PLACES OF PUBLIC ASSEMBLY MUST HAVE AN ADDITIONAL CERTIFICATE OF COMPLIANCE, RENEWED YEARLY.

SHOULD THE OCCUPANCY CHANGE FROM THE ABOVE LIMITATION OF USE, APPLICATION MUST BE MADE FOR NEW CERTIFICATE.

UNDERWRITERS CERTIFICATE
N.B.F.U. No.

TOWN OF OYSTER BAY BUILDING DEPARTMENT

[illegible]

FRANKLIN RESEARCH, INC.

820 Hempstead Turnpike • Franklin Square, New York 11010

(516) 358-9400

Fax (516) 358-5050

50 YEAR DEED AND LEASE CHAIN

MARCH 9, 1994

GMES-NY0029008

RE: 300 MICHAEL DRIVE, SYOSSET

SECTION: 15 BLOCK: 157 LOT(S): 46

OWNER: RUSER REALTY TAX CLASS: 710.14

DEED

GRANTOR- PAUL SERWITZ, CHARLES SERWITZ, EDITH RUBINSTEIN & RUSER
REALTY CO.

GRANTEE- RUSER REALTY CO.

DATED- 12/12/91 RECORDED 05/05/92 LIBER-10182 PAGE 480

DEED

GRANTOR- DUPONT ASSOCIATES, INC.

GRANTEE- PAUL SERWITZ, CHARLES SERWITZ, EDITH RUBINSTEIN & RUSER
REALTY CO.

DATED- 08/01/83 RECORDED 08/31/83 LIBER-9498 PAGE 24

ASSIGNMENT OF LEASE

GRANTOR- GREAT AMERICAN - CORRUGATED CONTAINER CORP.

GRANTEE- LIMPAC CORRUGATED CONTAINER CORP.

DATED- 03/31/80 RECORDED 04/08/80 LIBER-9262 PAGE 385

SUB-LEASE

GRANTOR- GREAT AMERICAN - CORRUGATED CONTAINER CORP.

GRANTEE- LIMPAC CORRUGATED CONTAINER CORP.

DATED- 03/31/80 RECORDED 04/08/80 LIBER-9263 PAGE 378

LEASE

GRANTOR- RUSER REALTY CORP.

GRANTEE- COLUMBIA CORRUGATED CONTAINER CORP.

DATED- 05/01/76 RECORDED 04/08/80 LIBER-9263 PAGE 374

ASSIGNMENT OF LEASE

GRANTOR- RUSER REALTY CORP.

GRANTEE- PAUL SERWITZ, CHARLES SERWITZ, EDITH RUBINSTEIN & RUSER
REALTY CO.

DATED- 05/28/66 RECORDED 04/08/80 LIBER- 9263 PAGE 362

TECH RESEARCH, INC.

820 Hempstead Turnpike • Franklin Square, New York 11010

(516) 358-9400

Fax (516) 358-5050

PAGE 2

ASSIGNMENT OF SUB-LEASE

GRANTOR- PAUL SERWITZ, CHARLES SERWITZ, EDITH RUBINSTEIN & RUSER
REALTY CO.

GRANTEE- RUSER REALTY CO.

DATED- 05/08/66 RECORDED 04/08/80 LIBER-9263 PAGE 368

DEED

GRANTOR- NEWPORT ASSOCIATES, INC.

GRANTEE- DUPONT ASSOCIATES, INC.

DATED- 01/06/75 RECORDED 05/19/75 LIBER-8801 PAGE 60

DEED

GRANTOR- SOL GOLDMAN, IRVING GOLDMAN

GRANTEE- NEWPORT ASSOCIATES

DATED- 10/26/72 RECORDED 11/01/72 LIBER-8460 PAGE 389

DEED (CORRECTION DEED)

GRANTOR- CHASE MANHATTAN BANK

GRANTEE- SOL GOLDMAN, IRVING GOLDMAN

DATED- 10/25/72 RECORDED 11/01/72 LIBER-8460 PAGE 383

DEED

GRANTOR- CHASE MANHATTAN BANK

GRANTEE- SOL GOLDMAN, IRVING GOLDMAN

DATED- 06/16/72 RECORDED 06/23/72 LIBER-8399 PAGE 207

DEED

GRANTOR- CHASE MANHATTAN BANK

GRANTEE- CHASE MANHATTAN BANK

DATED- 04/23/69 RECORDED 07/18/69 LIBER-8010 PAGE 147

DEED

GRANTOR- CHASE MANHATTAN BANK

GRANTEE- CHASE MANHATTAN BANK

DATED- 06/01/64 RECORDED 06/18/64 LIBER-7284 PAGE 413

LEASE

GRANTOR- GEORGIA-PACIFIC CORP.

GRANTEE- RUSER REALTY CORP.

DATED- 02/28/63 RECORDED 02/13/64 LIBER-7250 PAGE 417

LEASE

GRANTOR- CHASE MANHATTAN BANK

GRANTEE- GEORGIA-PACIFIC CORP.

DATED- 02/28/63 RECORDED 02/13/64 LIBER-7250 PAGE 422

TECH RESEARCH, INC.

820 Hempstead Turnpike • Franklin Square, New York 11010

(516) 358-9400

Fax (516) 358-5050

PAGE 3

DEED

GRANTOR- RUSER REALTY CORP.

GRANTEE- CHASE MANHATTAN BANK

DATED- 02/01/63 RECORDED 02/06/63 LIBER-7125 PAGE 177

NOTE: FORMERLY KNOWN AS SEC: 15 BLOCK: G LOT: 44

DEED

GRANTOR- MICHAEL FORTE

GRANTEE- RUSER REALTY CO.

DATED- 05/09/60 RECORDED 05/12/60 LIBER-6703 PAGE 495

NOTE: FORMERLY KNOWN AS PART OF LOT 35 & 42

DEED

GRANTOR- ARTHUR RAGOZZINO

GRANTEE- MICHAEL FORTE

DATED- 11/17/55 RECORDED 11/28/55 LIBER-5922 PAGE 322

NOTE: LOT 35 FORMERLY KNOWN AS LOT 2

LOT 42 FORMERLY KNOWN AS LOT 3

CHAIN FOR LOT 2

DEED

GRANTOR- GLADYS ANGELINI

GRANTEE- ARTHUR RAGOZZINO

DATED- 09/01/55 RECORDED 09/09/55 LIBER-5871 PAGE 327

DEED

GRANTOR- ARTHUR SEGRET

GRANTEE- ARTHUR RAGOZZINO

DATED- 09/01/55 RECORDED 09/09/55 LIBER-5871 PAGE 325

DEED

GRANTOR- ANNA NASO

GRANTEE- ARTHUR RAGOZZINO

DATED- 09/07/55 RECORDED 09/09/55 LIBER-5871 PAGE 335

DEED

GRANTOR- AMELIA BOLL

GRANTEE- ARTHUR RAGOZZINO

DATED- 09/07/55 RECORDED 09/09/55 LIBER-5871 PAGE 333

DEED

GRANTOR- ELEANOR METZ

GRANTEE- ARTHUR RAGOZZINO

PAGE 4

DEED

GRANTOR-MARY ROGERS

GRANTEE- ARTHUR RAGOZZINO

DATED- 09/07/55 RECORDED 09/09/55 LIBER-5871 PAGE 329

DEED

GRANTOR- FRANK DI NARDO, MARIA DI NARDO

GRANTEE- ARTHUR RAGOZZINO

DATED- 10/14/36 RECORDED 11/08/37 LIBER-1955 PAGE 331

DEED

GRANTOR- JOSEPH SEGRETO

GRANTEE- FRANK DI NARDO

DATED- 08/01/32 RECORDED 08/13/37 LIBER-1694 PAGE 333

NOTE: CHAIN FOR LOT 3

LEASE

GRANTOR- MICHAEL FORTE

GRANTEE- DANEGA STORES CORP.

DATED- 02/05/59 RECORDED 02/09/59 LIBER-6497 PAGE 147

LEASE

GRANTOR- MICHAEL FORTE

GRANTEE- ELSIN ELECTRONICS CORP.

DATED- 08/13/58 RECORDED 09/16/58 LIBER-6429 PAGE 381

DEED

GRANTOR- HERMON SELDIN, PAUL SILVERSTEIN

GRANTEE- MICHAEL FORTE

DATED- 10/24/55 RECORDED 11/04/55 LIBER-5909 PAGE 551

DEED

GRANTOR- BANK OF NEW YORK, AS EXECUTOR

GRANTEE- HERMON SELDIN, PAUL SILVERSTEIN

DATED- 04/01/55 RECORDED 04/15/55 LIBER-5770 PAGE 339

DEED

GRANTOR- NEW YORK TRUST CO., AS EXECUTOR

GRANTEE- CATHERINE HOFFMAN, WILLIAM WICKHAN

DATED- 04/30/40 RECORDED 05/02/40 LIBER-2213 PAGE 539

SOIL SAMPLING AND ANALYSIS
RESULTS AND DISCUSSION

SPECIAL PROPERTY

SYNOPSIS

James Philip Anderson

RESEARCH ...

SOIL SAMPLING
ANALYSIS RESULTS AND DISCUSSION
SPIEGEL PROPERTY
SYOSSET, NEW YORK

| | <u>Page No.</u> |
|-----------------------------------|-----------------|
| I. Introduction | 1 |
| II. Remediation Field Work | 1 |
| III. Soil Sampling Results | 1 |
| IV. Laboratory Results Discussion | 3 |
| V. Conclusion | 4 |

Appendix A - Laboratory Results and Chain of Custody
Documents

Appendix B - Toxicity Characteristic Leaching Procedure
and Regulated Chemical List

I. Introduction

On January 7, 1987, a remedial soil clean up was completed at the Spiegel Property, 225 Robbins Lane, Syosset, NY, as requested by the Nassau County Health Department. Approximately 20 cubic yards of soil was removed from the site and was fully manifested as per New York State Department of Environmental Conservation requirements.

The events of the field work completed for the remediation were documented in the "Engineering Report for Remedial Soil Clean Up at Spiegel Property, Syosset, New York, January 1987," completed by Fanning, Phillips and Molnar.

II. Remediation Field Work

During the remedial field work, which required the excavation of the soil, a Foxboro Century Gas Chromotograph was utilized to survey the excavation for the presence of organic vapors. Only three areas within the excavation reported a slight response by Gas Chromotograph and they were sampled (refer to Figure 1). The results of these soil samples are shown in Table 1 and in Appendix A.

III. Soil Sample Laboratory Results

Soil samples were obtained from the base of the 2' deep excavation at the three locations shown in Figure 1. Samples were collected in 40 ml vials with screw on teflon caps and were immediately preserved on ice. Chain of Custody documents were




FIGURE 1 LOCATION OF SOIL EXCAVATION, OVA RESPONSE & SOIL SAMPLING

completed and are enclosed in Appendix A. Samples were analyzed for the presence of volatile organic carbon compounds and Benzene, Toluene and Xylene compounds.

Positive results for soil sample 1 reported 120 ppb Methylene Chloride, 12 ppb of 111 Trichloroethane, 5 ppb of Tetrachloroethene, and 21 ppb of Benzene. No other parameters were detected. Soil sample 2 reported 18 ppb of Methylene Chloride, 28 ppb of 111 Trichloroethane and 31 ppb of Benzene. No other parameters were detected. Soil sample 3 reported 16 ppb of 11 Dichloroethane, 10 ppb of 1 2 Dichloroethene, 7 ppb of 111 Trichloroethane and 23 ppb of Benzene. No other parameters were detected.

Results of the sediment analysis will be compared to the EPA Toxicity Characteristic Leaching Procedure (TCLP) as documented in the EPA federal Register, Volume 51, No. 9. The TCLP replaces EP Toxicity Test and is intended to identify whether a waste is hazardous and whether it will leach hazardous substances. It was promulgated into law November 7, 1986.

IV. Lab Results Discussion

The TCLP's scope and application, as discussed in the Federal Register, was designated to determine the mobility of both organic and inorganic contaminants present in liquid, solid and multiphasic waste. Appendix B encloses the list of the chemicals that is regulated and their regulatory levels to be compared to after the TCLP test had been completed. It is noted that the analysis completed for the soil samples at the site are a total analysis result.

Of the compounds detected in the soil (Methylene Chloride, 111 Trichloroethane, Tetrachloroethene, Benzene, 11 Dichloroethane and 1 2 Dichloroethene), regulatory levels were listed for all the compounds except 11 Dichloroethane and 1 2 Dichloroethene. The two previously mentioned compounds were only detected in soil sample 3 and at the low levels of 16 and 10 ppb respectively. All the other compounds detected were well below the listed regulatory level at each of the sampling locations.

V. Conclusions

Total laboratory analysis for Volatile Organic Carbon Compounds and Benzene, Toluene and Xylene Compounds within the soil samples obtained from the base of the excavation has shown the contaminants present are at levels well below the regulatory levels as proposed by the Toxicity Characteristic Leaching Procedure (TCLP). Two compounds not regulated by the TCLP procedure were found at only one location and at low levels respectively (26 ppb total VOC). The TCLP procedure was designated to determine the mobility of contaminants present in solid, liquid and multiphasic wastes. The contaminant levels detected within the soil samples are well below the regulatory levels as established for these organic compounds.

TABLE 1 - SOIL ANALYSIS

All results are in parts per billion (ug/Kg)

| PARAMETER | SAMPLE LOCATION | | | TCLP ACTION LEVEL(ppb) |
|-----------------------|-----------------|----|----|------------------------|
| | 1 | 2 | 3 | |
| Vinyl Chloride | <1 | <1 | <1 | 50 |
| Freon 113 | <1 | <1 | <1 | - |
| Methylene Chloride | 120 | 18 | <2 | 1,400 |
| 11 Dichloroethane | <2 | <2 | 16 | - |
| 12 Dichloroethene | <2 | <2 | 10 | - |
| Chloroform | <1 | <1 | <1 | 70 |
| 111 Trichloroethane ✓ | 12 | 28 | 7 | 30,000 |
| Carbon Tetrachloride | <1 | <1 | <1 | 70 |
| 12 Dichloroethane | <2 | <2 | <2 | 400 |
| Trichloroethylene | <1 | <1 | <1 | 70 |
| 12 Dichloropropane | <2 | <2 | <2 | - |
| Bromodichloromethane | <1 | <1 | <1 | - |
| Tetrachloroethene | <5 | <1 | <1 | 100 |
| Chlorodibromomethane | <1 | <1 | <1 | - |
| Bromoform | <2 | <2 | <2 | - |
| Benzene | 21 | 31 | 23 | 70 |
| Toluene | <2 | <2 | <2 | 14,400 |
| Ethyl Benzene | <1 | <1 | <1 | - |
| m Xylene | <2 | <2 | <2 | - |
| o+p Xylene | <4 | <4 | <4 | - |
| m Dichlorobenzene | <2 | <2 | <2 | - |
| o Dichlorobenzene | <2 | <2 | <2 | 4,300 |
| p Dichlorobenzene | <2 | <2 | <2 | 10,800 |
| | 53 | 77 | | |

Note: - indicates no regulatory level established.

NASSAU COUNTY DEPARTMENT OF HEALTH
240 Old Country Road - Mineola, New York 11501

To : Roy N. Cacciatore, Commissioner
Department of Commerce & Industry


Date: June 11, 1986

From : Department of Health

Subject : Contamination of Soil on Property owned by Jerry Spiegel Associates
on Robbins Lane, Syosset (Section 15, Block 161, Lot 28)
Next to 233-5 Robbins Lane

During cleanup of contaminated site adjacent to the above referenced one, it was discovered that the contamination extended to the Jerry Spiegel owned property; specifically on a driveway between the two sites. The contaminant is 1,1,1 trichloroethane, a solvent cleaner used by many industries in the county.

The Spiegel site is the location of a presently unoccupied warehouse facility. There is no evidence that Spiegel caused the contamination. Also, we cannot prove the adjacent facility caused it. Consequently, we must direct the present owners to clean up. Recent correspondence to Spiegel is attached for your information. Intercession by your Department with Jerry Spiegel Associates to encourage voluntary compliance might be helpful.


Francis V. Pader, P.E., M.C.E.
Deputy Commissioner

FVP:LS:rc

REMEDIAL INVESTIGATION

at

Space Machines Corp.
233-5 Robbins Lane
Syosset, N.Y.

Prepared by:

Lockwood, Kessler & Bartlett, Inc.
Consulting Engineers
One Aerial Way
Syosset, NY 11791

February 1986

PROJECT STAFF

Ivan Pouschine, Jr.
Lockwood, Kessler & Bartlett, Inc.
Project Manager
Sr. Environmental Engineer

Rose Pelino
Lockwood, Kessler & Bartlett, Inc.
Project Engineer
Civil Engineer

TABLE OF CONTENTS

| | |
|-------------|--|
| Section I | Executive Summary |
| Section II | Events Leading to this Investigation |
| Section III | Background Information |
| | 3.1 Location and Description of Site |
| | 3.2 Hydrogeologic Setting |
| Section IV | Scope of Work |
| Section V | Site Assessment |
| Section VI | Remedial Alternatives and Associated Costs |
| References | |
| Appendices | |
| | Formation Data |
| | Soil Quality Data |

LIST OF FIGURES

| <u>Figure Number</u> | <u>Title</u> | <u>Follows Page</u> |
|--------------------------|-------------------|---------------------|
| 1-1 | Site Location Map | 1-1 |
| 3-1 | Site Plan | 3-1 |

LIST OF TABLES

| <u>Table Number</u> | | <u>Follows Page</u> |
|-------------------------|---------------------------------|---------------------|
| 4-1 | List of Analytical Parameters | 4-1 |
| 5-1 | Soil Quality Data | 5-1 |
| 6-1 | Cost of Recommended Remediation | 6-3 |

SECTION I

EXECUTIVE SUMMARY

Space Machines Corporation (SMC), located at 233-5 Robbins Lane Syosset, N.Y., as shown in Figure 1-1, performs metal machining operations on laths and similar equipment and utilizes volatile organic cleaning fluids in its normal operations. According to SMC, waste fluids are presently discarded into appropriate barrels, located on the premises, and periodically hauled away for disposal. During a routine survey by the Nassau County Department of Health (NCDH), an area of discolored soil was noted outside the rear entrance to the Space Machine facility. Subsequent testing indicated that the soil contained elevated levels of volatile organic compounds and an immediate clean-up was requested by NCDH. Clean-up was performed by Space Machines Corp. (SMC) soon after, but the Health Department was not notified and did not observe the removal activity. As a result, NCDH further requested that a remedial investigation be undertaken to determine the extent of contamination in the remaining soil.

Lockwood, Kessler & Bartlett, Inc., Consulting Engineers of Syosset, were retained by the owner of the building at 233 Robbins Lane, K.L.W.R.L. Co., to perform the investigation. The investigation included the drilling of soil borings and the collection and analyses of soil samples for the




FIGURE 1-1
SITE LOCATION MAP

presence of contaminants. Results of the boring and testing program indicate that an area approximately 20 feet by 5 feet, located outside the rear door to the SMC premises, is contaminated with halogenated and non-halogenated volatile organic compounds.

Considering these results, it is recommended that the contaminated soils be removed and replaced with clean fill. This will involve the excavation of earth and the hauling away of the excavated material by a licensed hauler to an approved hazardous waste landfill. It is also recommended that during excavation, the remaining soil be tested in the field using a TIP or OVA meter to ascertain that contaminated soils are removed to the extent feasible. After replacement of the excavated earth with clean fill, it is further recommended that the remaining unpaved areas of the site, in the immediate vicinity of SMC, be paved. A cost estimate for the recommended remedial activities is provided in the report.

SECTION II

EVENTS LEADING TO THIS INVESTIGATION

During the course of a routine survey by the Nassau County Department of Health (NCDH) on November 29, 1984, an area of discolored soil was noted outside the rear entrance to Space Machines Corporation (SMC). On April 22, 1985, representatives of NCDH sampled this soil. The sample was analyzed by the NCDH laboratories and found to be contaminated with the following chemicals:

| <u>Contaminant</u> | <u>Concentration (ppb)</u> |
|-----------------------|----------------------------|
| 1,1-Dichloroethane | 380,000 |
| 1,1,1-Trichloroethane | 67,000 |
| Trichloroethylene | 570 |
| 1,1,2-Trichloroethane | 160 |
| Benzene | 9,700 |
| Toluene | 14,000 |
| Ethylbenzene | 1,100 |
| Xylene | 5,000 |

These results, and the required subsequent procedures, were communicated to the owners of the building housing SMC (K.L.W.R.L. Company) in a letter dated September 11, 1985, from Stanley Juczak, Director, Bureau of Land Resources Management, NCDH. The letter requested an immediate clean-up of the visibly contaminated soil and its removal and proper disposal by an industrial waste transporter registered with the New York State

Department of Environmental Conservation (NYSDEC). K.L.W.R.L. Company requested SMC to comply with all NCDH demands and SMC removed about half a foot of soil and disposed of it in a dumpster which was hauled away. In place of the removed soil, SMC had concrete placed along the rear wall of their premises to the roadway forming a sidewalk outside their rear entrance.

Although the NCDH demanded to be notified by SMC prior to any site clean-up activity, they were not notified. As a result, NCDH requested that a remedial investigation be conducted to determine if any contaminated soil remained at the site. In response to a letter from Lawrence Sama of NCDH dated October 24, 1985, K.L.W.R.L. agreed to retain the services of a Professional Engineering firm to prepare and submit a Plan of Investigation to the NCDH. Lockwood, Kessler & Bartlett, Inc. were retained by K.L.W.R.L. and a Plan of Investigation was submitted to NCDH on December 10, 1985. The Plan was approved by NCDH and the investigation was subsequently undertaken on January 21, 1986.

SECTION III

BACKGROUND INFORMATION

3.1 Location and Description of Site


Space Machines Corp. is a tenant in a one story industrial building at 233 Robbins Lane, Syosset, Nassau County (Figure 3-1). Other occupants of 233 include Capgo Limousine Service, Action Automotive, Jomark Color, Robbins Lane Collision and Roger Printing Co., as shown in Figure 3-1.

The main (front) entrance to SMC is located in the southeast portion of the building. The rear entrance, where the discolored soil was discovered by NCDH, is located in the northwest portion of the premises.

Other facilities in the immediate vicinity of 233 Robbins Lane include Ultimate Precision to the northeast (a fabricator of sheet metal), Roger Printing Co. and some retail facilities to the southeast. The retail facilities include Looking Good Fashions, Liberty International Jewelers and Creative Plastercraft.

3.2 Hydrogeologic Setting

SMC is located in an area of Long Island that is underlain by four hydrogeologic units known generally as the Upper Glacial Formation, the Magothy Formation, and the Raritan Clay and Lloyd Sand Members of the Raritan Formation. The units rest on a southeasterly dipping bedrock surface.



ROBBINS LANE

FIGURE 3-1

SITE PLAN

UKB

The Upper Glacial Formation consists chiefly of sand and gravel deposits locally interbedded with clay and silt lenses. The Magothy Formation is composed of interbedded gray, buff and white fine sand and clayey sand and black gray, white, buff and red clay. Gravelly zones are common near the bottom of the formation but are rare in the upper part. The Raritan Clay consists chiefly of gray, red, white and blue clay and silty clay and lenses of sand and gravel. The Lloyd Sand is a stratified deposit comprising discontinuous layers of sand, gravel, sandy clay, silt and clay (Isbister, 1966).

The groundwater table occurs at the site in the Magothy Formation, at approximately 100-110 feet below land surface, or 80-90 feet above sea level (Kilburn et al, 1985). The water bearing stratum within the Magothy Formation is commonly referred to as the Magothy Aquifer. The Lloyd Sand, which underlies the Magothy Formation, is a water bearing formation. The Raritan Clay functions hydraulically as a confining unit separating the Magothy Formation from the Lloyd Sand.

The direction of the horizontal component of groundwater flow at the site is generally from the south-southwest to north-northeast, toward Long Island Sound (Kilburn et al, 1985). The vertical component of groundwater flow occurs from the water table downward into underlying formations. Areas of Long Island in which vertical groundwater flow predominates have been classified as Deep Flow Recharge Zones (Long Island Regional Planning Board, 1978). Regional hydrogeologic zone mapping indicates that the project site is situated within Hydrogeologic Zone No. 1, a deep flow

recharge zone. Deep flow areas are of special environmental importance because they replenish the waters in the deep aquifers which are the principal long-term source of Long Island's drinking water.

The closest public water supplies to 233-5 Robbins Lane include Magothy wells of the Jericho Water District (JWD) and the Hicksville Water District (HWD). Near the intersection of Jericho Turnpike and Tobie Lane, approximately 3500 feet west of the SMC site, is JWD well N6691. Located approximately 5500 feet southwest of the site are JWD wells N9245 and N7781 located at Jericho Turnpike and Merry Lane, and East Norwich Road and Cedar Swamp Road, respectively. JWD well N8355 is located approximately 5000 feet northwest of the site near Kirby's Lane. The Hicksville well located in the vicinity of the site is N8355. It is situated near Miller Place at Ingram Drive and is 6000 feet south of SMC.

There are no surface water bodies on the site or in the vicinity of the site.

SECTION IV

SCOPE OF WORK

Three borings were drilled on January 21, 1986 by Soil Mechanics of Seaford, N.Y., at the locations indicated on Figure 3-1. Boring No. 2 was located in front of the rear entrance to SMC approximately 3 1/2 feet from the door. Boring Nos. 1 and 3 were similarly drilled 3 to 3 1/2 feet from the building wall and located about 9 feet to the northeast and southwest, respectively, of Boring No. 2.

Core samples were taken at the existing ground surface and obtained continuously for the depth of drilling. After ten feet, samples were collected at five foot intervals. Sampling was done by use of a standard 2-inch O.D. split spoon sampler having a minimum barrel length of 18 inches. Specimens from each split spoon were placed in airtight glass jars. Samples selected for laboratory analysis were placed in 40-ml glass vials with Teflon faced, rubber lined, caps.

Core samples were examined in the field for discoloration and for the presence of odors from volatile organic compounds. Certain samples were selected for laboratory analysis for the contaminants listed in Table 4-1. Analyses were performed by Ecotest Laboratories, Inc. of North Babylon, in accordance with EPA Manual No. SW 846, Test Methods for Evaluating Solid Waste, Method Nos. 8010 and 8020. Formation data obtained during drilling were recorded in the field by the consultant. These data are provided in the Appendix of this report.

TABLE 4-1

List of Analytical Parameters

Vinyl Chloride
Freon 113
Methylene Chloride
1,1 Dichloroethane
1,2 Dichloroethene
Chloroform
1,1,1 Trichloroethane
Carbon Tetrachloride
1,2 Dichloropropane
Trichloroethylene
1,2 Dichloropropane
Bromodichloromethane
Tetrachloroethene
Chlorodibromomethane
Bromoform
Benzene
Toluene
Ethyl Benzene
m Xylene
o+p Xylene
m Dichlorobenzene
o Dichlorobenzene
p Dichlorobenzene

Final depth of borings were decided in the field based on visual observations and detection of odor. Estimated drilling depths were set forth in the Work Plan. Borings Nos. 1, 2 and 3 were to be drilled to 8, 40 and 8 feet below grade, respectively. Boring No. 1 (located as shown in Figure 3-1) was drilled to 8 feet and a sample collected from 3-4 feet below grade. Boring No. 2 was drilled to 42 feet. Samples were collected at 2-3 feet, 4-5 feet, 7-8 feet, and 21-22 feet below grade, respectively. Representatives of NCDH, present during the drilling, also collected samples from this boring including one at a depth of 16 feet. Boring No. 3 was drilled to 10 feet. Three samples were collected, at 2-3 feet, 4-5 feet, and 8-9 feet below grade. Similarly, samples were collected by NCDH from this boring.

SECTION V

SITE ASSESSMENT

This section presents a review of the results of the soil quality data from the field investigation. The data on soils are presented in the Appendix of this report.

Only one sample was collected from Boring No. 1 for laboratory analysis. Field data obtained during drilling did not indicate the presence of contaminants in the soil. Boring No. 1 was drilled to a depth of 8 feet and a soil sample was collected at the mid point, at a depth of 3-4 feet. The laboratory data (Table 5-1) show that halogenated and non-halogenated organic compounds are generally not present in the soil sample from Boring No. 1 with the exception of one compound present at a concentration just above detection. These results indicate that the soil in the vicinity of Boring No. 1 has not been affected by activities of SMC.

Four soil samples were collected from Boring No. 2 for laboratory analyses. These samples were collected at 2-3 feet, 4-5 feet, 7-8 feet and 20-21 feet below grade. The analytical data indicates that chlorinated compounds are present in the ground at this location to a depth of approximately 8 feet and possibly a few feet deeper, but no further than 16 feet below grade (Table 5-1).

TABLE 5-1

SOIL QUALITY DATA*

| | | B O R I N G N U M B E R | | | | | | | | | |
|-----------------------|-------|-------------------------|---------|---------|-----|-----|----|-----|-----|-----|------|
| | | 1 | 2 | | | | | 3 | | | |
| | | D E P T H (I N F E E T) | | | | | | | | | |
| | | 3-4 | 2-3 | | 4-5 | 7-8 | 20 | 2-3 | | 4-5 | 9-10 |
| ANALYTICAL PARAMETERS | | | | | | | | | | | |
| Vinyl Chloride | ug/kg | | | | | | | | | | |
| Freon 113 | ug/kg | | | | | | | | | | |
| Methylene Chloride | ug/kg | | | | | | | | | | |
| 1,1 Dichloroethane | ug/kg | | 1,500 | 2,700 | | | | 240 | 28 | | |
| 1,2 Dichloroethene | ug/kg | | | | | | | | | | |
| Chloroform | ug/kg | | | | | | | 7 | 14 | | |
| 1,1,1 Trichloroethane | ug/kg | 21 | 250,000 | 120,000 | 150 | 10 | | 590 | 190 | | |
| Carbon Tetrachloride | ug/kg | | 67 | | | | | | | | |
| 1,2 Dichloropropane | ug/kg | | 980 | 220 | | | | 69 | 93 | | |
| Trichloroethylene | ug/kg | | | | | | | | | | |
| 1,2 Dichloropropane | ug/kg | | | | | | | | | | |
| Bromodichloromethane | ug/kg | | | | | | | | | | |
| Tetrachloroethene | ug/kg | | 2,300 | 1,300 | | | | 840 | 500 | | |
| Chlorodibromomethane | ug/kg | | 800 | 250 | | | | | | | |
| Bromoform | ug/kg | | | | | | | | | | |
| Benzene | ug/kg | | | | | | | | | | |
| Toluene | ug/kg | | 12,000 | 590 | 11 | | | 520 | 250 | 15 | |
| Ethyl Benzene | ug/kg | | | | | | | | | | |
| m Xylene | ug/kg | | | | | | | | | | |
| o+p Xylene | ug/kg | | | | | | | 260 | 130 | | |
| m Dichlorobenzene | ug/kg | | | | | | | | | | |
| o Dichlorobenzene | ug/kg | | | | | | | | | | |
| p Dichlorobenzene | ug/kg | | | | | | | | | | |

* Concentrations not provided in the table indicate that the parameter of interest was present at a concentration less than its detection limit and possibly not present at all. The detection limit is a function of the limitations of the analytical instrumentation and the physical and chemical testing procedures.

The highest concentrations of volatile organic compounds were present in the soil samples collected at the 2-3 foot depth. Concentrations in the 4-5 foot soil sample were close to one half the concentrations in the 2-3 foot soil samples, indicating a decrease in degree of contamination with increasing depth. The 7-8 foot sample contained minimal amounts of two volatile organic compounds, while the 20-21 foot depth sample had only one contaminant which was just at the detectable limit. No contaminants were found in soil sample collected at the 16 foot depth by NCDH.

Boring No. 3, located southwest of Boring No. 2, contained volatile organic compounds. However, these compounds were present at concentrations significantly less than those found in Boring No. 2. Soil samples were collected for analysis at the 2-3 foot, 4-5 foot and 9-10 foot depth. Concentrations of contaminants similarly decreased with increasing depth. Only one of the constituents tested was present in the 9-10 foot sample, slightly above detectable limits. Analysis of the NCDH 8 foot depth sample showed no contaminants, indicating that the contaminated soil is concentrated near the surface and to approximately 6-7 feet below grade.

In summary, the contaminated soil at 233-5 Robbins Lane is located immediately outside the rear entrance door and extends about 10 feet in a southwesterly direction. The level of contamination is greatest just outside the rear door and diminishes with distance away from this area. Soil contamination is greatest near the surface and decreases to background condition at a depth of 8 feet.

see fig 3-1

As set forth in the approved Work Plan, if results of the laboratory analysis indicated significant levels of contaminants in the deep samples, additional borings would be drilled to the groundwater table and monitoring wells installed. As discussed above, the contamination at the site is found near ground surface and extends to only 8 feet below grade. Therefore, additional deeper borings were not required.

SECTION VI

REMEDIAL ALTERNATIVES AND ASSOCIATED COSTS

Data generated from the boring program indicate that an area of soil at the SMC site is contaminated with halogenated and non-halogenated volatile organic compounds. Remedial activities should be conducted at the site to eliminate possible impacts of the contaminated soils on the environment. Remedial activities considered for the site are 1) removal of the contaminated soils off-site to a secure hazardous waste landfill, 2) surface sealing or capping, 3) no-action, and 4) treatment in-place alternatives.

Excavation and off-site disposal of the material is a common remedial technique and is widely used with contaminated soil and sludge. Excavation is usually performed by mechanical means (backhoe or dragline) and the material loaded onto trucks and carted to a licensed facility designated to receive hazardous wastes. This remedial measure is recommended for control of the contaminated soils at the SMC site.

Surface sealing or capping is the method by which contaminated materials are covered to prevent air pollution, and surface water infiltration and subsequent seepage to the underlying aquifers. This method is also recommended as a remedial activity at this site.

The no action alternative is the do nothing option, which does not reduce or eliminate the impact of the contaminated soils on the environment. Therefore this alternative is not recommended at the SMC site.

The treatment-in-place alternative would require recycling water through the contaminated soils which would cause a degradation of ground water quality. Environmentally and economically this alternative is detrimental and undesirable at this site.

As discussed in Section 5, data collected during the boring program indicate that soil contamination in the vicinity of SMC is concentrated near the rear door of the premises and extends horizontally about 10 feet in a southeasterly direction. Vertically, contaminated soils are present from near surface to approximately 8 feet below grade.

Following an attempted cleanup along the rear building wall of their premises, SMC had a concrete sidewalk installed between the rear wall and the asphalt roadway on the remaining portion of the alley. Spillage of solvents by SMC, prior to the placement of concrete, primarily affected the five foot unpaved area adjacent to the building wall. Considering the lateral spread of contaminants in the soil as a result of surface water infiltration, it is recommended that soil outside the SMC facility be removed from near the wall to approximately one foot beyond the asphalt and concrete interface. Along the wall, it is recommended that excavation take place from midway between Boring Nos. 1 and 2, which is approximately 4 feet from Boring No. 2, to 14 feet beyond Boring No. 2, which is approximately 5 feet beyond Boring No.3. Vertically, soil should be excavated

from surface to no greater than 4 feet below grade at the building wall so as not to undermine the structural integrity of the building foundation. Excavation below the bottom of the foundation footing should be no closer than one foot from the footing. Excavation depth should increase a foot with each foot and a half of distance from the building footing reaching no lower than 7 foot depth at 5.5 feet from the building. During excavation, selected soil specimens should be collected and tested in the field using a TIP or OVA meter to ascertain that all contaminated soils outside the building stability zone have been removed. All contaminated soils excavated shall be placed in drums and hauled away by a licensed hauler of hazardous waste to a secure landfill.

Upon removal of the contaminated soil and replacement by clean fill, unpaved areas in the vicinity of Space Machines Corp. should be paved or asphalted to prevent percolation of any remaining minimal concentration contaminants and to preclude seepage should accidental spillage occur in the future. A cost estimate for removal of contaminated soils and subsequent asphaltting is given in Table 6-1.



FRANCIS T. PURCELL
County Executive

NASSAU COUNTY DEPARTMENT OF HEALTH

240 OLD COUNTRY ROAD, MINEOLA, N.Y. 11501

JOHN J. DOWLING, M.D., M.P.H.
Commissioner

FRANCIS V. PADAR, P.E., M.C.E.
Deputy Commissioner
Division of Environmental Health

September 11, 1985

K.L.W.R.L. Co.
c/o Lazarus Associates
6901 Jericho Turnpike
Syosset, NY 11791

Att: Mr. Arthur Field

Re: Violations at 233-5
Robbins Lane, Syosset, NY 11791
(Space Machines Corp.)
Section 15, Block 161, Lot 29

Dear Mr. Field:

This is in confirmation of my telephone discussion with you of August 29, 1985 and my meeting at the above referenced site with your representative, Mr. Dominick Vissichelli on September 3, 1985.

Nassau County records indicate your organization is the owner of the above referenced property. This was confirmed by Mr. Vissichelli. During the course of a routine survey on November 29, 1984 of the Space Machines Corp., tenants on site, a representative of this department noted an area of discolored soil outside the rear entrance of the facility.

On April 22, 1985 our representatives sampled the soil from the area noted above. The sample was analyzed by the Nassau County Department of Health Laboratories and found to be heavily contaminated with chemicals as follows:

| <u>Contaminant</u> | <u>Concentration (parts per billion)</u> |
|-----------------------|--|
| 1,1-Dichloroethane | 380,000 |
| 1,1,1-Trichloroethane | 67,000 |
| Trichloroethylene | 570 |
| 1,1,2-Trichloroethane | 160 |
| Tetrachloroethylene | 9700 |
| Benzene | 1600 |
| Toluene | 14,000 |
| Ethylbenzene | 1100 |
| Xylene | 5000 |

The presence of the chlorinated contaminants makes this soil a hazardous waste. The potential leaching of these contaminants to the groundwater poses a significant threat to the environment. The presence of these chemicals in the soil

constitutes a violation of Article 27 of the Environmental Conservation Law as follows:

Section 27-0913 - Storing hazardous wastes on site without a permit.

Consequently, it will be necessary for you to perform an immediate cleanup of the obvious contamination, to have the site investigated to determine the extent of the contamination and for a remedial plan to be developed and implemented. A professional engineer licensed to practice in the State of New York must be retained to assist you in the investigative planning and implementation of this work. The soil cleanup must be done within two weeks of this letter date.


The visibly contaminated soil is to be removed immediately and disposed of properly by an industrial waste transporter registered with the New York State Department of Environmental Conservation. To verify the extent of cleanup and/or the need for further investigation and cleanup, a soil sample is to be then taken and analyzed for contaminants found by this department and as noted above. Further work will be dependent on the results of the soil sample and will be the subject of additional directives to you.

This department is to be notified at least 3 days in advance of any site investigation or remedial activity in order to observe such activity and to have the opportunity to split samples for analysis.

Should this work not be done expeditiously and in accordance with our directives, then it will be necessary for us to refer this case to the New York State Department of Environmental Conservation for appropriate legal action.

If you have any questions please contact this office at 535-2406.

Very truly yours,



Stanley Juczak, P.E.

Director

Bureau of Land Resources Management

SJ:LS:dm

cc: T. Sanford - DEC
P. Barbato - DEC
M. Hamann - NCDH ✓
M. Narducci - Space Machines Corp.
Roy N. Cacciatore, Commissioner
Dept. of Commerce & Industry

Rev. 5/84

Please print or type. (Form designed for use on elite (12-pitch) typewriter.) Form Approved. OMB No. 2000-0404. Expires 7-31-86

**UNIFORM HAZARDOUS
WASTE MANIFEST**

1. Generator's US EPA ID No.

Manifest
Document No.

2. Page 1
of

Information in the shaded areas
is not required by Federal law.

3. Generator's Name and Mailing Address

Basarn Associates

233 Robbins Lane, Syosset, NY 11791

4. Generator's Phone (516) 364-2000

5. Transporter 1 Company Name

John Pfromm, Inc.

7. Transporter 2 Company Name

6. US EPA ID Number

PA-0008781072

8. US EPA ID Number

10. US EPA ID Number

9. Designated Facility Name and Site Address

Waste Conversion Inc.

2869 Sandstone Drive

Hartfield, PA 19440

A. State Manifest Document Number

PAB 00407735

B. State Gen. ID

SAME

C. State Trans. ID

PA-AH

D. Transporter's Phone (215) 383-3051

E. State Trans. ID

PA-AH

F. Transporter's Phone ()

G. State Facility's ID

Not Required

H. Facility's Phone (215) 822-8826

11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)

a.

Hazardous Waste Solid H02

ORM-X

HA9189

12. Containers

No.

Type

13. Total
Quantity

14. Unit
Wt/Vol

1. Waste No.

001 RT 40,000 2002

c.

d.

Additional Descriptions for Materials Listed Above (Include physical state and hazard code)

K. Handling Codes for Wastes Listed Above

a.

c.

b.

d.

15. Special Handling Instructions and Additional Information

WC-1912 Soil contaminated with trace solvent

16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations, and all applicable State laws/regulations.

Printed/Typed Name

To DOMINICK VISSICHELLI

Signature

Date

Month Day Year

17. Transporter 1 Acknowledgement of Receipt of Materials

Printed/Typed Name

DAVID L. HEARBY

Signature

Date

Month Day Year

18. Transporter 2 Acknowledgement of Receipt of Materials

Printed/Typed Name

Signature

Date

Month Day Year

9. Discrepancy Indication Space

20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.

Printed/Typed Name

Signature

Date

Month Day Year

PAB00407735

INSTRUCTIONS: Complete all information for those chemicals your facility has used, stored, distributed, or otherwise disposed of since January 1, 1977. Do not include chemicals used only in analytical laboratory work.

RECOMMENDED ACTION

9 ☐ Other (specify)

| | | |
|---|---|-------------------------------------|
| Chemical Solvent Waste Report Nassau County Department of Health Bureau of Environmental Management 240 Old Country Road Mineola, N.Y. 11501 | Name: Loral Fairchild Systems | Article XI Permit Number: 006 |
| | Address: 300 Robbins Lane, Syosset, NY 11791 | Report Period: 1993 |

List all chemicals and/or solvents purchase during the reporting period.
 Indicate for each the purpose or use, trade name or supplier, and the quantity purchased.

| Name of Chemical or Solvent | How is the Chemical or Solvent Used? | Trade Name or Supplier | Quantity Purchased |
|----------------------------------|--|------------------------|--------------------|
| 1,1,1-trichloroethane | Degreasing & Printed Circuit Board Fabrication | Captree Chemical | 1210 gallons |
| Blaco-Solv 404 | Degreasing & Printed Circuit Board Fabrication | Baron-Blakeslee | 495 gallons |
| Flux Thinner #120 | Printed Circuit Board Fabrication | Kester | 400 gallons |
| Flux # 186 | Printed Circuit Board Fabrication | Kester | 202 gallons |
| 1A33 Polyurethane Coating | Printed Circuit Board Fabrication | Humiseal | 16 gallons |
| 601 Acrylic Thinner | Printed Circuit Board Fabrication | Humiseal | 55 gallons |
| Acetone | Spray Painting | Captree Chemical | 59 gallons |
| 1B31-66 Acrylic Coating | Printed Circuit Board Fabrication | Humiseal | 11 gallons |
| Deoxidizer 7 | Alodine Plating | Parker-Amchem | 225 pounds |
| Alodine 1200 | Alodine Plating | Parker-Amchem | 20 pounds |
| 1B31 Acrylic Coating | Printed Circuit Board Fabrication | Humiseal | 17 gallons |
| 521 Thinner | Printed Circuit Board Fabrication | Humiseal | 23 gallons |
| Flux-Off NR 2000 (Alcohol Blend) | Printed Circuit Board Fabrication | Chemtronics | 60 gallons |
| Ethyl Alcohol | Printed Circuit Board Fabrication | Captree Chemical | 220 gallons |
| Denatured Alcohol | Printed Circuit Board Fabrication | Captree Chemical | 55 gallons |
| Isopropyl Alcohol | Printed Circuit Board Fabrication | Fisher Scientific | |

CHEMICAL/SOLVENT WASTE REPORT

For each shipment of wastes, complete the following table with the indicated information. ATTACH COPIES OF MANIFESTS OR RECEIPTS FROM SCAVENGER FOR EACH SHIPMENT MADE.

| Date of Shipment | Description of Waste | Amount Removed | Shipped by | | | Shipped To (Final Disposal Site for Waste) |
|------------------|------------------------------|----------------|-------------------------------------|--|--------------------|--|
| | | | Transporter's Name | Transporter's Address | D.E.C. Reg. Number | |
| 01/06/93 | Askarel(PCB Transformer Oil) | 9704 Kg | ENSR Operations | 4160 Perimeter Drive, Columbus OH 43228 | T24-762 KY | 4160 Perimeter Drive, Columbus OH 43228 |
| 02/18/93 | Machine Lube Oil | 55 G | Chemical Pollution Control, Inc. | 120 South Fourth Street, Bay Shore NY 11706 | HM3506 | 120 South Fourth Street, Bay Shore NY 11706 |
| | 111TCA/Isopropyl Alcohol | 110 G | | | | |
| | 1,1,1-trichloroethane | 215 G | | | | |
| | Solvent Wipes & Rags | 63 P | | | | |
| 05/11/93 | Alodine Solution | 250 G | Chemical Pollution Control, Inc. | 120 South Fourth Street, Bay Shore NY 11706 | HM3506 | 120 South Fourth Street, Bay Shore NY 11706 |
| | Deoxidizer Solution | 165 G | | | | |
| | Fluoboric Acid Solution | 5 G | | | | |
| 05/13/93 | 1,1,1-trichloroethane | 385 G | Chemical Pollution Control, Inc. | 120 South Fourth Street, Bay Shore NY 11706 | HM3506 | 120 South Fourth Street, Bay Shore NY 11706 |
| | Machine Lube Oil | 55 G | | | | |
| | 111TCA/Isopropyl Alcohol | 55 G | | | | |
| | Solvent Lab Waste | 5 G | | | | |
| | Paint Cans & Mixing Cups | 127 P | | | | |

List any accidental spills that occurred during the reporting period:

| Date of Spill | Amount of Spill | Describe the nature of the spill |
|---------------|-----------------|----------------------------------|
| | | |
| | | |

Signature of Company
Representative

Robert W. Bendy, Jr.

Title
Sr. Environmental/Safety Specialist

Date
February 7, 1994

CHEMICAL/SOLVENT WASTE REPORT

For each shipment of wastes, complete the following table with the indicated information. ATTACH COPIES OF MANIFESTS OR RECEIPTS FROM SCAVENGER FOR EACH SHIPMENT MADE.

| Date of Shipment | Description of Waste | Amount Removed | Shipped by | | | Shipped To (Final Disposal Site for Waste) |
|------------------|------------------------------|----------------|----------------------------------|--|--------------------|--|
| | | | Transporter's Name | Transporter's Address | D.E.C. Reg. Number | |
| 07/14/93 | Flammable Liquids (Lab Pack) | 108 G | Chemical Pollution Control, Inc. | 120 South Fourth Street, Bay Shore NY 11706 | HM3506 | 120 South Fourth Street, Bay Shore NY 11706 |
| | Corrosive Liquids (Lab Pack) | 32 G | | | | |
| | Alkaline Liquids (Lab Pack) | 52 G | | | | |
| | Aerosol Cans (Lab Pack) | 7 P | | | | |
| | Organic Peroxide (Lab Pack) | 2 P | | | | |
| | 1,1,1-trichloroethane | 220 G | | | | |
| | Paint Thinner | 55 G | | | | |
| | 111TCA/Isopropyl Alcohol | 55 G | | | | |
| | Oil/Water Mixture | 55 G | | | | |
| | Sulfuric Acid Solution | 55 G | | | | |
| | Photographic Waste | 5 G | | | | |
| | Solvent Wipes & Rags | 68 P | | | | |
| | Flammable Solids (Lab Pack) | 150 P | | | | |
| | Haz. Waste Solids (Lab Pack) | 50 P | | | | |
| | Haz. Waste Solids (Lab Pack) | 59 P | | | | |

List any accidental spills that occurred during the reporting period:

| Date of Spill | Amount of Spill | Describe the nature of the spill |
|---------------|-----------------|----------------------------------|
| | | |
| | | |

Signature of Company Representative

Robert W. Bendy, Jr.

Title
Sr. Environmental/Safety Specialist

Date
February 7, 1994

CHEMICAL/SOLVENT WASTE REPORT

For each shipment of wastes, complete the following table with the indicated information. ATTACH COPIES OF MANIFESTS OR RECEIPTS FROM SCAVENGER FOR EACH SHIPMENT MADE.

| Date of Shipment | Description of Waste | Amount Removed | Transporter's Name | Transporter's Address | D.E.C. Reg. Number | Shipped To (Final Disposal Site for Waste) |
|------------------|----------------------|----------------|--------------------|-----------------------|--------------------|--|
| | | | | | | |

| | | | | | | |
|----------|-----------------------------|-------|---------------------------------|---|--------|---|
| 08/12/93 | 111TCA/isopropyl Alcohol | 55 G | Chemical Pollution Control, Inc | 120 South Fourth Street, Bay Shore NY 11706 | HM3506 | 120 South Fourth Street, Bay Shore NY 11706 |
| | Nitric Acid Lab Waste | 5 G | | | | |
| 10/19/93 | Solder Flux | 55 G | Chemical Waste Management of NJ | 100 Lister Avenue, Newark NJ 07105 | S10331 | 100 Lister Avenue, Newark NJ 07105 |
| | 1,1,1-trichloroethane | 165 G | | | | |
| | Paint Cans & Mixing Cups | 98 P | | | | |
| 11/24/93 | Trichlorofluoroethane/Water | 55 G | Chemical Waste Management of NJ | 100 Lister Avenue, Newark NJ 07105 | S10331 | 100 Lister Avenue, Newark NJ 07105 |
| | Photographic Waste | 5 G | | | | |
| | Photographic Waste | 5 G | | | | |
| | Deoxidizer | 30 G | | | | |
| | Photographic Waste | 15 G | | | | |
| | Solder Flux | 55 G | | | | |
| | Solvent Lab Waste | 5 G | | | | |
| | 1,1,1-trichloroethane | 110 G | | | | |

List any accidental spills that occurred during the reporting period:

| Date of Spill | Amount of Spill | Describe the nature of the spill |
|---------------|-----------------|----------------------------------|
| | | |
| | | |
| | | |

| | | |
|--|--|--------------------------|
| Signature of Company Representative <i>Robert W. Bendy, Jr.</i> | Title Sr. Environmental/Safety Specialist | Date February 7, 1994 |
|--|--|--------------------------|

CHEMICAL/SOLVENT WASTE REPORT

For each shipment of wastes, complete the following table with the indicated information. ATTACH COPIES OF MANIFESTS OR RECEIPTS FROM SCAVENGER FOR EACH SHIPMENT MADE.

| Date of Shipment | Description of Waste | Amount Removed | Shipped by | | | Shipped To (Final Disposal Site for Waste) |
|------------------|----------------------|----------------|--------------------|-----------------------|--------------------|--|
| | | | Transporter's Name | Transporter's Address | D.E.C. Reg. Number | |

| | | | | | | |
|----------|--------------------------|------|------------------------------------|---------------------------------------|--------|---------------------------------------|
| 12/23/93 | 111TCA/Isopropyl Alcohol | 5 G | Chemical Waste Management of NJ | 100 Lister Avenue, Newark NY 07105 | S10331 | 100 Lister Avenue, Newark NY 07105 |
| | Solvent Rags & Wipes | 71 P | | | | |
| | Photographic Waste | 55 G | | | | |
| | Machine Lube Oil | 55 G | | | | |

List any accidental spills that occurred during the reporting period:

| Date of Spill | Amount of Spill | Describe the nature of the spill |
|---------------|-----------------|----------------------------------|
| | | |
| | | |

| | | |
|---|--|--------------------------|
| Signature of Company Representative Robert W. Bandy, Jr. | Title Sr. Environmental/Safety Specialist | Date February 7, 1994 |
|---|--|--------------------------|



NASSAU COUNTY DEPARTMENT of HEALTH

Page 1

TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT

| | | | | | | | | | |
|-----------------------|--------|----------------|--|-------------------------------|----------|----------------|----------|------------------|----------|
| Facility Number | 000006 | Type of Permit | <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Construction | Date Issued: | 05/01/93 | Date Modified: | 05/01/93 | Expiration Date: | 05/01/98 |
| Name of Permittee: | | | | LORAL FAIRCHILD SYSTEMS | | | | | |
| Address of Permittee: | | | | 300 ROBBINS LA. SYOSSET NY | | | | | |

GENERAL CONDITIONS

1. By acceptance of this permit, the permittee agrees that the permit is contingent upon strict compliance with Article XI, Nassau County Public Health Ordinance.
2. All work carried out under this permit shall conform to the approved plans and specifications. Any amendments must be approved by the Nassau County Department of Health prior to their implementation. The permittee shall notify the Health Department 48 hours in advance of the start of construction.

3. As a condition of the issuance of this permit, the applicant has accepted expressly, by the execution of the application, the full legal responsibility for all damages direct or indirect, of whatever nature, and by whomever suffered, arising out of the project described herein and has agreed to defend, indemnify and save harmless the County from suits, actions, damages and costs of every name and description resulting from the said project.

** NOT TRANSFERABLE *

| | | |
|-------------------|--------------------------------------|-------------------------------------|
| Name of Facility: | LORAL FAIRCHILD SYSTEMS | FACILITY ADDRESS: |
| Mailing Address: | 300 ROBBINS LA. SYOSSET NY 11791- | 300 ROBBINS LA. SYOSSET NY 11791 |

THIS FACILITY CONSISTS OF STORAGE AREAS AS LISTED ON PLANS AND APPLICATIONS FILED WITH THIS DEPARTMENT

| Tank/Storage Area Number | Capacity | Type of Toxic or Hazardous Material Stored | REPLACE DATE |
|--------------------------|--------------|--|--------------|
| BULK 0001 | 150 POUNDS | MULTIPLE CHEMICALS STORED | |
| BULK 0001 | 2750 GALLONS | MULTIPLE CHEMICALS STORED | |
| BULK 0002 | 120 POUNDS | MULTIPLE CHEMICALS STORED | |
| BULK 0002 | 330 GALLONS | MULTIPLE CHEMICALS STORED | |
| TANK 0005 | 220 GALLONS | TANK, WATER RINSE | |
| TANK 0006 | 220 GALLONS | TANK, WATER RINSE | |
| TANK 0007 | 169 GALLONS | TANK, WATER RINSE | |
| TANK 0008 | 220 GALLONS | CAUSTICS | |

CONTINUED

Authorizing Officer Marlene M. HamannGEORGE PICKETT, M.D., M.P.H.
John J. Dowling, M.D., M.P.H. Commissioner of Health

EH 768 9/86

THIS PERMIT MUST BE POSTED IN A CONSPICUOUS PLACE AT THE FACILITY



NASSAU COUNTY DEPARTMENT of HEALTH

Page 2

TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT

| | | | | | | | | | |
|-----------------------|--------|----------------|--|-------------------------------|----------|----------------|----------|------------------|----------|
| Facility Number | 000006 | Type of Permit | <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Construction | Date Issued: | 05/01/93 | Date Modified: | 05/01/93 | Expiration Date: | 05/01/98 |
| Name of Permittee: | | | | LORAL FAIRCHILD SYSTEMS | | | | | |
| Address of Permittee: | | | | 300 ROBBINS LA. SYUSSET NY | | | | | |

GENERAL CONDITIONS

1. By acceptance of this permit, the permittee agrees that the permit is contingent upon strict compliance with Article XI, Nassau County Public Health Ordinance.
2. All work carried out under this permit shall conform to the approved plans and specifications. Any amendments must be approved by the Nassau County Department of Health prior to their implementation. The permittee shall notify the Health Department 48 hours in advance of the start of construction.
3. As a condition of the issuance of this permit, the applicant has accepted expressly, by the execution of the application, the full legal responsibility for all damages direct or indirect, of whatever nature, and by whomever suffered, arising out of the project described herein and has agreed to defend, indemnify and save harmless the County from suits, actions, damages and costs of every name and description resulting from the said project.

**** NOT TRANSFERABLE ****

| | | | |
|-------------------|--------------------------------------|-------------------------------------|--|
| Name of Facility: | LORAL FAIRCHILD SYSTEMS | FACILITY ADDRESS: | |
| Mailing Address: | 300 ROBBINS LA. SYUSSET NY 11791- | 300 ROBBINS LA. SYUSSET NY 11791 | |

THIS FACILITY CONSISTS OF STORAGE AREAS AS LISTED ON PLANS AND APPLICATIONS FILED WITH THIS DEPARTMENT

| <u>Tank/Storage Area Number</u> | <u>Capacity</u> | <u>Type of Toxic or Hazardous Material Stored</u> | <u>REPLACE DATE</u> |
|---------------------------------|-----------------|---|---------------------|
| TANK 0009 | 220 GALLONS | ALODINE | |
| TANK 0010 | 169 GALLONS | CHROMIC ACID | |
| TANK 0011 | 10 GALLONS | FLUOBORIC ACID | |
| TANK 0012 | 05 GALLONS | TANK, WATER RINSE | |
| TANK 0013 | 05 GALLONS | TANK, WATER RINSE | |
| TANK 0014 | 05 GALLONS | TANK, WATER RINSE | |
| TANK 0015 | 15000 GALLONS | OIL, FUEL #2 | |

Authorizing Officer

Marlene M. Hamann

GEORGE PICKETT, M.D., M.P.H.

[Signature] Commissioner of Health

EH 768 9/86

THIS PERMIT MUST BE POSTED IN A CONSPICUOUS PLACE AT THE FACILITY

FAIRCHILD WESTON

Schlumberger

FAIRCHILD WESTON SYSTEMS INC.
SYOSSET, NEW YORK

August 4, 1981

Chief of P.D.E.S.
Permit Section
N.Y.S. Dept. of
Environmental Conservation
50 Wolf Road
Albany, N.Y. 12233

ATT: Mr. George K. Hansen

Subject: Supplement to letter dated June 30, 1981 Modification
of State Pollutant Discharge Elimination System Permit
No. NY007 6155, Ref. No. 28-0084

Gentlemen;

The attached letter, dated June 30, 1981 stated a change in
our Waste Treatment Control as well as planned future changes.
Additional information and expected dates of completion are
hereby provided.

The re-routing of the Process Waste Water to the County Sewer
System was approved by the County of Nassau Department of Public
Works, Permit No. S 36533 issued September 20, 1979

Boiler Blow Down Water will be connected to the County Sewer
System by December, 1981

Cooling Tower Blow Down Water will be connected to the County
Sewer System by June, 1982

If you have any questions or if additional information is re-
quired, please contact me.

Yours truly,

James F. Herrmann
James F. Herrmann
Supervisor
Failure Analysis Lab

cc:- Joseph Schechter
H. Weinstein
R. Underwood
T. Greean

JH/jk

RECEIVED

AUG 5 1981

NCDH
BLRM

FAIRCHILD SYSTEMS

300 ROBBINS LANE • SYOSSET, NEW YORK 11791 • TEL. (516) 931-4500 • TWX 510-221-1836

FIRM NAME

Fairchild Camera - Syosset

#1

| | .1 Cr ⁺⁶ | 1.0 Cr ^{tot} | 3 F | 1.0 Cu | 1.0 Ni | .1 Pb | .02 Cd | 6.5 pH |
|---------------------------------|------------------------|--------------------------|--------|-----------|-----------|----------|-----------|-----------|
| 6-29-77 | <.01 | .04 | .1 | .23 | * | * | .008 | 7.5 |
| 7-27-77 | * | * | * | * | * | .09 | * | 9.6 |
| 4 Drainage sump. 8-1-78 | <.01 | .01 | .27 | .21 | * | * | * | 8.7 |
| Recharge sump 3-5-79 | * | <.001 | .83 | * | * | * | * | 7.1 |
| treatment room tank 10-18-79 | * | .02 | 1.95 | 3.45 | <.05 | .40 | .01 | 10.3 |

12/63)

NEW YORK STATE DEPARTMENT OF HEALTH

INDUSTRIAL WATER USE AND WASTE WATER DISPOSAL PRACTICES SURVEY

Name of Establishment Fairchild Camera & Instrument Corp.Mailing Address Space & Defense Systems Division
300 Robbins Lane, Syosset, New YorkPlant Address 300 Robbins Lane, Syosset, New YorkLocation of Plant Syosset ~~XXXXXXXXXX~~ village (circle) Nassau CountyNumber of employees 1000 Average 1340 MaximumMonths Plant Operated (circle) ⑥ ⑦ ⑧ ⑨ ⑩ ⑪ ⑫ ① ② ③ ④ ⑤Number of days plant operated per week 5 Normal 6 PeakNumber of hours plant operated per day 16 Normal 24 PeakManufacturing Process or service fabrication (including electroplating)
and assembly of camers and electronic instrumentation, photo processing,
research and development.

| 10. Raw Materials | Quantities | Primary Products | Quantities |
|-------------------|------------|------------------|------------|
| 1. | | | |
| 2. | | | |
| 3. | | | |

11. Water Sources

Gallons per day

a. Public Water Supply (Municipal or Private)

Name of Water Supply Co. Jericho Water Dist.

b. Plant's surface water intake (rivers, lakes, etc.)

Name of river, lake, etc. N/A

Location of intake _____

c. Plant's ground water source (wells, springs, etc.)

d. Other sources of water (quarries, mines, etc.)

Name and location none

| average | maximum |
|---------|---------|
| 0 0 | 0 |
| N/A | |
| 85,343 | 119,773 |
| | |

12. Source of Aux. Fire Protection Jericho Water District13. Briefly describe treatment of incoming water by your company and indicate whether
or not water is treated for reuse No treatment required for incoming water.Only boiler water is treated for reuse or recirculation.

(over please)

Incoming water analysis performed by plant Yes Frequency Quarterly

15. Water Use and Recirculation

| Purpose of Water Intake | Water Use Gallons per day | | Water Recirculation Gallons per day | |
|-------------------------|------------------------------|---------|--|---------|
| | Average | Maximum | Average | Maximum |
| Potable | 42,600 | 60,000 | None | None |
| Process | 42,743 | 59,733 | | |
| Cooling | | | | |
| Other | | | | |

| 16. Type of Waste | Process A | Process B | Process C | Cooling Water | Sanitary Sewerage | Total Plant Waste |
|---|-----------------------|-----------|-----------|---------------|-----------------------|-------------------|
| 17. Origin of Wastes | Plating | | | None | Sanitary | Over All Plant |
| 18. Description of Waste | | | | Heated | Sanitary | |
| 19. Average Volume of Waste Water, gallons/day | 43,000 | | | | 43,000 | 86,000 |
| 20. Waste treated yes or no (If yes, answer question #22) | Yes | | | | | |
| 21. Where waste water is discharged: | | | | | | |
| To Sewers | | | | | | |
| Name of Municipality | None | | | None | None | |
| To Local Watercourse | | | | | | |
| Name of River/Lake | None | | | | | |
| To Land incl. ground water (Describe) | 43,000 Recharge Basin | | | | 43,000 Sanitary Pools | |
| Other (Describe) | | | | | | |

22. Briefly describe waste water treatment by types of waste (Question No. 20) _____
Use additional sheets for supplementary information and sketches

Chlorination of Cyanides, Permunit of Chromates, Adjustment of Ph

23. If discharge is to watercourse, give location of discharge None

24. Waste Water analysis performed by plant _____ Frequency _____

SEP 3 1954

MATERIALS LABORATORY REPORT

COPY

TO

cc Emmett Archbold

DATE January 6, 1955

[illegible]

Remarks: Cyanide shows no traces in the basin water. Chrome concentration still 2 times greater than maximum 0.05. No trace of other metals.

Report by:

A. P. Ingraham.

Approved by:

Singet Surala
Metallurgist

Date _____

2/18/65

PART I

Chemco Photoproducts
 NAME: **Charles Glen Cove phone # 676-4000**
Chemco Powers Chemco
 MAILING ADDRESS: **7 Aerial Way** CITY: **Syosset** STATE: **N.Y.** ZIP CODE:
 CONTACT NAME: **Marty Bilicki (Faman)** TELEPHONE: **Area 433-4000**
 CITY: STATE: **676-** ZIP CODE: **4000**
 STREET:
 NUMBER OF EMPLOYEES AT THIS FACILITY: **65**
 TYPE OF BUSINESS OF PLANT: **Photo**
 (If parent company, give name and addresses of all divisions, subsidiaries, etc. located in New York State. A separate questionnaire is to be completed and submitted for each.)

PART II
Discharge Information

1. Does your plant discharge liquid wastes to a municipally owned sanitary sewer system? ☐ Yes ☒ No
 Name of System: _____
2. Is your facility permitted to discharge liquid wastes under a State (SPDES) or Federal (NPDES) permit? ☐ Yes ☒ No
 Permit Number:
3. Do you discharge liquid wastes in any other manner? ☐ Yes ☒ No
 Explain: _____
- Many of the above are "Yes":
- a. Do you discharge process or chemical wastes — (i.e. water used in manufacturing including direct contact cooling water and scrubber water)? ☐ Yes ☒ No
- b. Do you discharge non-contact cooling water? ☐ Yes ☒ No
- c. Do you discharge collected storm drainage only? ☐ Yes ☒ No
- d. Do you discharge sanitary wastes only? ☒ Yes ☐ No

1. Does your facility have sources of possible emissions to the atmosphere? **Paint Spray Booth** ☒ Yes ☐ No
2. Enter Location and Facility Code as shown on your Air Pollution Control Application for Permits and Certification (If applicable)

1. List Name and Address of Firm (including yourself) removing wastes other than office and cafeteria refuse.

| | | | |
|---------|------|-------|----------|
| Name | | | |
| Address | City | State | Zip Code |
| Name | | | |
| Address | City | State | Zip Code |

2. List Location(s) of Landfill(s) owned and used by your facility.

1

2

Active ☐ Inactive ☐

- Does this facility:
- Manufacture Pesticides or Pesticide Product Ingredients? ☐ Yes ☒ No
- Produce Pesticides or Pesticide Product Ingredients? ☐ Yes ☒ No
- Formulate Pesticides? ☐ Yes ☒ No
- Repackage Pesticides? ☐ Yes ☒ No

2. EPA Establishment Number

- -

(include gases and waste oils)

Complete all information for those substances your facility has used, produced, stored, distributed or otherwise disposed of since January 1, 1971. Do not include chemicals used only in analytical laboratory work.

| Name Of Substance/Trade Name Supplier and Address | CODE | AVERAGE ANNUAL USAGE | AMOUNT NOW ON HAND | GAL. | LB. | PURPOSE OF USE (State whether produced, reacted, blended, packaged, distributed, no longer used, etc.) |
|--|------|-------------------------|-----------------------|------|-----|--|
| Isopar Exxon | | | 2 (55 gal) | | | Processing Camera |
| Fixer & Developer Reprocessed | | cull office | | | | Waste is Take Away and Reprocessed |
| Tuluel Valplex, Rochester | | 110 | 55 | | | |
| Solvent 10-20 Valplex, Rochester | | 110 | 55 | | | |

Final Discharge Point

- ☐ Sewers
☐ Cesspools
☐ Sumps or basins
☐ Drums
☐ Landfills
☐ Other

Recommended Action

- ☐ Immediate abatement
☐ Sample
☒ SPDES Application
☒ Reinspection
☐ Referred to _____
☒ No Action

STATIONARY COMBUSTION AND INCINERATION

- A. Heating System ☐ None ☒ Boiler ☐ Space Heaters
B. Fuel ☐ Electric ☒ Gas ☐ Oil
C. Incinerator ☐ Yes ☒ No

I hereby affirm under penalty of perjury that information provided on this form is true to the best of my knowledge and belief. False statements shall be punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law.

Owner, Partner, or Officer of

DATE _____

DATE 2/15/22

(Printed or Typed)

Marty Bilicki

TITLE

Freeman

Inspectors Name

Gay Gul

**INDUSTRIAL CHEMICAL SURVEY
REAU OF WATER POLLUTION CONTROL**

Nassau County Department of Health
40 Old Country Road, Mineola, N.Y. 11501

Tel. 535-2404

4SR

Part I

| | | | |
|--|--------------|--|----------|
| Company Name PMI MOTORS (P) | | SIC (if known) Code 3621 | |
| Company Mailing Address 5 Aerial Way | | | Zip |
| Plant Name (if different) | Contact Name | Tel. 938-8000 | |
| Plant Address | Village | Water Distr. | Code Zip |
| Principal Business of Plant Mfg. Electric Motors | | No. Employees at this Facility 150 | |

Part II

COMPLETE LIST OF CHEMICALS USED (See attached)

PART III - DISCHARGE INFORMATION

| | | | | |
|--|--|------------------------------------|--|---|
| WATER | 1. Does your plant discharge liquid wastes to a municipally owned sanitary sewer system? If yes, name of system: Cesspool, Septic Tank | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 2. Is your facility permitted to discharge liquid wastes under a State (SPDES) or Federal (NPDES) permit? If yes, enter Permit No. <div style="border: 1px solid black; display: inline-block; width: 100px; height: 1.2em; vertical-align: middle;"></div> | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 3. Do you discharge liquid industrial wastes in any other manner? If yes, explain: | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 4. If any of the above are yes: a. Do you discharge process or chemical wastes, i.e., water used in manufacturing, including direct contact cooling water and scrubber water? b. Do you discharge non-contact cooling water? c. Do you discharge sanitary wastes? | | <input type="checkbox"/> Yes <input type="checkbox"/> Yes <input type="checkbox"/> Yes | <input type="checkbox"/> No <input type="checkbox"/> No <input type="checkbox"/> No |
| AIR | 1. Does your facility have sources of possible emissions to the atmosphere? | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 2. Enter location and facility code as shown on your Air Pollution Control Application for Permits & Certification (if applicable) <div style="border: 1px solid black; display: inline-block; width: 150px; height: 1.2em; vertical-align: middle;"></div> | | | |
| | 3. Heating System <input type="checkbox"/> None <input checked="" type="checkbox"/> Boiler <input checked="" type="checkbox"/> Space Heater | | Type of Fuel <input type="checkbox"/> Electric <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil | |
| SOLID & CONCENTRATED LIQUID WASTES | 1. List name and address of firm (incl. yourself) removing wastes other than office and cafeteria refuse (industrial scavenger) | | | |
| | Name JAMAICA ASH | | Name | |
| | Address | | Address | |
| | 2. List location(s) of landfills owned and used by your Facility | | Active | Inactive |
| PEST | Does this facility manufacture, produce, formulate or repackage pesticides? | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | Signature (owner, partner, or officer) R. F. Wilson | | Date 11/10/77 | |
| Name (printed or typed) Richard F. Wilson | | Title Facilities Mgr | | |
| Inspector's Name RZ DB | | Date of Inspection 11/10/77 | | |

INSTRUCTIONS: Complete all information for those chemicals your facility has used, stored, distributed, or otherwise disposed of since January 1, 1977. Do not include chemicals used only in analytical laboratory work.

| Name of Chemical/Trade Name, Supplier and Address | Code | Avg Annual Usage | Gal | Lbs | Use of Chemical | Final Disposition of Chemical |
|--|------|------------------|-----|-----|----------------------------------|--|
| Blase (1,1,1 Trichloroethane) | | 250 | ✓ | | clean gunnaries, contacts, parts | sent to Glen Cove + reclaimed stored in drums |
| Methylene Chloride | | 1320 | ✓ | | vapor degreaser | " |
| 55 4 206 B 20 | | | | | | |
| → waste drums taken to Photocircuits in Glen Cove for disposal, methylene chloride 1,1,1 Trichloroethane | | | | | | |

RECOMMENDED ACTION

FOR
OFFICE
USE
ONLY

- 2 ☐ Immediate Abatement
3 ☐ Sample
4 ☒ SPDES Application

 $S + K$

- 5 ☐ Refer To: _____ 9 ☐ Other (specify)
- 6 ☐ Re-inspection
- 7 ☐ Action



INDUSTRIAL CHEMICAL SURVEY
BUREAU OF WATER POLLUTION CONTROL

Nassau County Department of Health
240 Old Country Road, Mineola, N.Y. 11501

Tel. 535-2404

11-423

Part I

| | | | |
|--|---|-------------------------|----------|
| Company Name CENTROID INC. | | SIC (if known) Code | |
| Company Mailing Address 2 ARIEL WAY 54055ET | | Zip 11791 | |
| Plant Name (if different) | Contact Name BURT DWORIN | Tel. 800-4770 | |
| Plant Address | Village | Water Distr. | Code Zip |
| Principal Business of Plant HFG. ELECTRONICS | No. Employees at this Facility 35 | | |

Part II

COMPLETE LIST OF CHEMICALS USED (See attached)

PART III - DISCHARGE INFORMATION

| | | | |
|---|---|--|---|
| WATER | 1. Does your plant discharge liquid wastes to a municipally owned sanitary sewer system? If yes, name of system: | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 2. Is your facility permitted to discharge liquid wastes under a State (SPDES) or Federal (NPDES) permit? If yes, enter Permit No. | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 3. Do you discharge liquid industrial wastes in any other manner? If yes, explain: | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 4. If any of the above are yes: a. Do you discharge process or chemical wastes, i.e., water used in manufacturing, including direct contact cooling water and scrubber water? b. Do you discharge non-contact cooling water? c. Do you discharge sanitary wastes? | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> Yes | <input checked="" type="checkbox"/> No <input checked="" type="checkbox"/> No <input type="checkbox"/> No |
| AIR | 1. Does your facility have sources of possible emissions to the atmosphere? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No |
| | 2. Enter location and facility code as shown on your Air Pollution Control Application for Permits & Certification (if applicable) | | |
| | 3. Heating System <input type="checkbox"/> None <input type="checkbox"/> Boiler <input checked="" type="checkbox"/> Space Heater Type of Fuel <input type="checkbox"/> Electric <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil Incinerator <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | |
| SOLID & CONCENTRATED LIQUID WASTES | 1. List name and address of firm (incl. yourself) removing wastes other than office and cafeteria refuse (industrial scavenger) | | |
| | Name CHEM. POLLUTION CONTROL INC. Name Address BAYSHOLE Address | | |
| PEST | 2. List location(s) of landfills owned and used by your Facility | | |
| | a. NONE b. | | |
| Does this facility manufacture, produce, formulate or repackage pesticides? | | | |
| <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | |
| Signature (owner, partner, or officer) | | Date | |
| BURT DWORIN | | 1/9/89 | |
| Name (printed or typed) | | Title | |
| BURT DWORIN | | | |
| Inspector's Name | | Date of Inspection | |
| Michael Schuta | | 1-9-84 | |

INSTRUCTIONS: Complete all information for those chemicals your facility has used, stored, distributed, or otherwise disposed of since January 1, 1977. Do not include chemicals used only in analytical laboratory work.

RECOMMENDED ACTION

2 ☐ Immediate Abatement
3 ☐ Sample
4 ☒ SPDES Application

5 ☐ Refer To: _____

9 ☐ Other (specify)

6 ☐ Re-inspection

7 ☐ No Action

APPLICATION FOR APPROVAL TO OPERATE A SOLID WASTE MANAGEMENT FACILITY

Nassau County Department of Health

140

Instructions

Complete all Sections

Fill this Application Form, along with your Plot Sketch and Material Flow Sketch, within 2 weeks to:

Bureau of Land Resources Management
Nassau County Department of Health
240 Old Country Road
Mineola, N.Y. 11501

For Health Department Use Only

Facility
Number:

Date
Received:

3/11/85

Department Action

☒ Approved

☐ Interim

☐ Not
Required

By:

[Signature]

Permit
Number

Start
Date:

Exp.
Date:

| | | |
|---------------------------------------|--|----------------------------|
| 1. Facility Name CENTROID, INC. | 2. Address 3 AERIAL WAY, SYOSSET, NEW YORK 11791 | 3. Tel. # 516-822-4770 |
| 4. Owner's Name GERALD STARR | 5. Address 120 BACON ROAD, OLD WESTBURY, NY 11568 | 6. Tel. # 516-621-2190 |
| 7. On-Site Supervisor BURT DWORKIN | 8. Address 843 OAKLAND CT., NO. BELLMORE NY 11710 | 9. Tel. # 516-TA 6-3727 |
| 10. Engineer (if applicable) | 11. Address | 12. Tel. # |

13. Has this department ever approved plans and specifications and or engineering reports for this facility?

☒ Yes

Date 3/27/84

☐ No

14. List Wastes Generated (use additional sheet if needed).

| Name of Constituents | Check One | | # of Gals. Generated Per Month | | Maximum # of Gals. Accumulated Before Disposal |
|-------------------------------------|-----------|---------------|--------------------------------|---------|--|
| | Hazardous | Non-Hazardous | Maximum | Average | |
| TRICHOLORETHANE SOLUTION (SPENT) | X | | 10 | 8 | 55 |
| METHELENE CHLORIDE SOLUTION (SPENT) | X | | 05 | 4 | 55 |
| | | | | | |
| | | | | | |
| | | | | | |

15. Names of Waste Haulers
CHEMICAL POLLUTION CONTROL, INC.

16. Briefly describe facility operation: (use additional sheet if needed)

"No Change"

I hereby affirm under penalty of perjury, that the information provided on this form and attached statements and exhibits is true to the best of my knowledge and belief.

Signature

[Signature]

Title GENERAL MANAGER

Date 3/7/85

JAN 21 1987

NASSAU COUNTY DEPARTMENT OF HEALTH
 APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT
 FORM 1 - GENERAL INFORMATION
 SEE INSTRUCTION SHEET

NASSAU COUNTY PUBLIC HEALTH ORDINANCE - ARTICLE XI

RECEIVED

JAN 21 1987

For Office Use Only

Facility I.D. 158

☐ Municipal
☒ Non-Municipal

Check all that apply
 to your facility:

☐ Tank Storage☒ Container Storage☐ Bulk Storage☐ Storage of Road De-icing Materials

NCDH-BLRM

Reason for submitting application:

☒ New☐ Renewal☐ Change☐ Construction

| | | | | | |
|--|----------------------------------|---|-------------------|--------------|-----------------------|
| Facility Name CENTROID, INC. | Street Address 3 AERIAL WAY | Village SYOSSET | State NEW YORK | Zip 11791 | Phone 516-822-4770 |
| Facility Mailing Address (If different from above) SAME | | Facility Contact Person (Name & Title) BURT DWORKIN, GENERAL MANAGER | | | Phone 516-822-4770 |
| Facility Owner GERALD STARR | Street Address 120 BACON ROAD | Village OLD WESTBURY | State NEW YORK | Zip 11568 | Phone 516-621-2190 |
| Property Owner (If not Facility Owner) SAME | Street Address | Village | State | Zip | Phone |
| Tank Owner (If not Facility Owner) NO TANKS | Street Address | Village | State | Zip | Phone |

Name that should appear on Permit (Permittee)
 (If different from Facility Owner)

CENTROID, INC.

| | | | | |
|--|--------------------|-------------------|--------------|-----------------------|
| Permittee's Street Address 3 AERIAL WAY | Village SYOSSET | State NEW YORK | Zip 11791 | Phone 516-822-4770 |
|--|--------------------|-------------------|--------------|-----------------------|

Permittee's Relationship
 to Facility Owner:

☒ Same☐ Operator of Facility☐ Other (Specify):

| | | | | |
|------------------------------|----------------------------|---------------|--------------|-------------|
| Principal Property Tax Code: | School District No. 014 | Section 15 | Block 157 | Lot 0021 |
|------------------------------|----------------------------|---------------|--------------|-------------|

Forms Attached (Check all that apply) ☐ Form 2 - Tank Registration ☒ Form 3 - Bulk & Container Storage Registration ☐ Form 4 - Storage of Road De-icing Materials

I hereby affirm under penalty of perjury that the information provided on this form and on any attached forms, statements and exhibits is true to the best of my knowledge and belief.

| | | | |
|----------------------------|---|--------------------------|------------------|
| Print Name BURT DWORKIN | Signature  | Title GENERAL MANAGER | Date 01/16/87 |
|----------------------------|---|--------------------------|------------------|

EH 857 1/86

☐ D.P.

DEPARTMENT OF HEALTH
 ON FOR A TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT
 - BULK AND CONTAINER STORAGE REGISTRATION
 INSTRUCTION SHEETS

Facility Name CENTROID, INC.
 Facility Address 3 AERIAL WAY, SYOSSET, NEW YORK 11791

For Office Use Only

Date Application Received JAN 27 1987 Facility 118
 Reviewed By NCDH - BLRM Date Review 1/28
 Action: ☐ Not Req'd. ☐ Approved ☐ Disapproved No. of Months 1

Action: ☒ Register Existing Area ☐ Add Area ☐ Remove Area ☐ Modify Area Area No. S1
 Location: ☒ Indoors ☐ Outdoors Bulk Storage Max. Quantity Stored: NONE Container Storage Max. No. 8 Max. Vol. 300 GAL
 Secondary Containment: ☐ Impervious Berm/Dike ☒ Impervious Floor/Pad ☐ Roof ☒ Walls ☐ Floor Drain & Storage Tank ☐ None ☐ Other (Specify)
 Construction Material (Check all of Dike & Pad that Apply) ☒ Concrete ☐ Steel ☐ Other (Specify)
 Security ☐ Yes ☐ No

| Type | NCDH. Number | Material Name | Phys- ical State | Amount Stored | | Storage Method | |
|------|--------------|--------------------------------------|------------------------|---------------------|-------|-------------------|-----|
| | | | | Average Quantity | Units | Average Number | Typ |
| 1 | 4062 | FREON TMS (TRICHLORO-TRIFLUORETHANE) | 1 | 50 | GAL | 1 | DRU |
| 1 | 9122 | TRICHLOROETHANE 111 | 1 | 50 | GAL | 1 | DRU |
| 1 | 5781 | METHYL ETHYL KETONE (F) | 1 | 50 | GAL | 1 | DRU |
| 1 | 5772 | METHELENE CHLORIDE | 1 | 50 | GAL | 1 | DRU |
| 2 | 4062 | WASTE FREON (SPENT SOLVENT) | 1 | 50 | GAL | 1 | DRU |
| 2 | 5781 | WASTE METHYL ETHYL KETONE (F) | 1 | 05 | GAL | 1 | DRU |
| 2 | 5772 | WASTE METHELENE CHLORIDE SOLUTION | 1 | 50 | GAL | 1 | DRU |
| 2 | 9122 | WASTE TRICHLOROETHANE | 1 | 50 | GAL | 1 | DRU |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | | |
|---|--|-----------------------|
| <div style="text-align: center;"> RECEIVED For Office Use Only </div> | | Facility # |
| Date Application Received | JAN 21 1987 | 198 |
| Reviewed By | HS | Date Review |
| Action: | <input checked="" type="checkbox"/> Not Req'd. <input type="checkbox"/> Approved <input type="checkbox"/> Disapproved | 1/28 No. of Months |

Facility Address 3 AERIAL WAY, SYOSSET, NEW YORK 11791

| | | | | | | |
|-------------------------------------|--|--|--------------------------------------|---|---|--|
| Action: | <input checked="" type="checkbox"/> Register Existing Area | <input type="checkbox"/> Add Area | <input type="checkbox"/> Remove Area | <input type="checkbox"/> Modify Area | Area No. | S2 |
| Location: | <input checked="" type="checkbox"/> Indoors <input type="checkbox"/> Outdoors | Bulk Storage | Max.Quantity Stored: | NONE | Container Storage | Max.No. 140 Max.Vol. 90 GAL |
| Secondary Containment: | <input type="checkbox"/> Impervious Berm/Dike | <input checked="" type="checkbox"/> Impervious Floor/Pad | <input type="checkbox"/> Roof | <input checked="" type="checkbox"/> Walls | <input type="checkbox"/> Floor Drain & Storage Tank | <input type="checkbox"/> None <input type="checkbox"/> Other (Specify) |
| Construction Material of Dike & Pad | (Check all that Apply) | <input checked="" type="checkbox"/> Concrete | <input type="checkbox"/> Steel | <input type="checkbox"/> Other (Specify): | | Security <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |

[illegible]

BUREAU OF WATER POLLUTION CONTROL

Nassau County Department of Health
240 Old Country Road, Mineola, N.Y. 11501

Tel. 535-2404

4

Part I

| | | | |
|--|--|--|------------------|
| Company Name GREAT EASTERN PRINTING CO INC. | | SIC (if known) Code | |
| Company Mailing Address 7 AERIAL WAY SYOSSET SYOSSET | | | Zip 11791 |
| Plant Name (if different) SAME | Contact Name MR DENNIS DRISCOLL | Tel. 931-3900 | |
| Plant Address | Village | Water Distr. | Code Zip |
| Principal Business of Plant PHOTO DEVELOPING | | No. Employees at this Facility 80 | |

Part II

COMPLETE LIST OF CHEMICALS USED (See attached)

PART III - DISCHARGE INFORMATION

| | | | | |
|---|--|--|------------------------------|--|
| WATER | 1. Does your plant discharge liquid wastes to a municipally owned sanitary sewer system? If yes, name of system: 6/81 HAS hooked to sewer | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 2. Is your facility permitted to discharge liquid wastes under a State (SPDES) or Federal (NPDES) permit? If yes, enter Permit No. <div style="border: 1px solid black; width: 100px; height: 20px; display: inline-block;"></div> | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 3. Do you discharge liquid industrial wastes in any other manner? If yes, explain: | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 4. If any of the above are yes: a. Do you discharge process or chemical wastes, i.e., water used in manufacturing, including direct contact cooling water and scrubber water? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No b. Do you discharge non-contact cooling water? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No c. Do you discharge sanitary wastes? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | | | |
| AIR | 1. Does your facility have sources of possible emissions to the atmosphere? | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| | 2. Enter location and facility code as shown on your Air Pollution Control Application for Permits & Certification (if applicable) <div style="border: 1px solid black; width: 150px; height: 20px; display: inline-block;"></div> | | | |
| | 3. Heating System HOT WATER Type of Fuel <input type="checkbox"/> None <input type="checkbox"/> Boiler <input type="checkbox"/> Space Heater <input type="checkbox"/> Electric <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil Incinerator <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | |
| SOLID & CONCENTRATED LIQUID WASTES | 1. List name and address of firm (incl. yourself) removing wastes other than office and cafeteria refuse (industrial scavenger) | | | |
| | Name NONE | | Name | |
| | Address | | Address | |
| PESTICIDES | 2. List location(s) of landfills owned and used by your Facility | | Active | Inactive |
| | NONE | | | |
| | Does this facility manufacture, produce, formulate or repackage pesticides? | | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |

| | | |
|---|------------------------------------|------|
| Signature (owner, partner, or officer) <i>Dennis Driscoll</i> | | Date |
| Name (printed or typed) MR DENNIS DRISCOLL | Title PRESIDENT | |
| Inspector's Name <i>A. Fitzgerald</i> | Date of Inspection 12/28/79 | |

INSTRUCTIONS: Complete all information for those chemicals your facility has used, stored, distributed, or otherwise disposed of since January 1, 1977. Do not include chemicals used only in analytical laboratory work.

| Name of Chemical/Trade Name, Supplier and Address | Code | Avg Annual Usage | Gal | Lbs | Use of Chemical | Final Disposition |
|---|------|------------------|-----|-----|-----------------|----------------------|
| HUNT STAR FIX | | 400 | ✓ | | NEGATIVE STOP | DIRECTLY TO LANDFILL |
| AGFA GAFART LYTIX DEVELOPER | | 400 | ✓ | | DEVELOPING | AFTER SILVER RECON |
| | | | | | | DIRECTLY TO LANDFILL |
| | | | | | | AFTER USE |
| FOUNTAIN SOLUTION PRO 3 | | 400 | ✓ | | ETCHING | RAGS TO RAG SERVICE |
| ODM ARABIC | | 3 | ✓ | | PRESERVE PLATES | " " " " |
| ROGERSOL JK-162 (BLANKET HARDNER) | | 3 | ✓ | | BLANKET COATING | REMAINS ON BLANKET |
| COPPER PLATING SOLUTION | | 3 | ✓ | | COAT PLATE | RAGS TO RAG SERVICE |
| EXCO FPL FINISHED/PRESERVER | | 7 | ✓ | | PLATE CLEAN | RAGS TO RAG SERVICE |
| CLNR | | | | | | |
| ROLLER WASH (PRINTERS SERVICE) | | 200 | ✓ | | CLEAN ROLLERS | RAGS TO RAG SERVICE |
| 26 BLANCHARD ST N.Y. | | | | | | |
| VALU PHOTO ROLLER WASH | | 500 | ✓ | | " " | " " " " |
| 175 ROUTE 208 OAKLAND N.Y. | | | | | | |
| ANGELOR SILVERANT | | 200 | ✓ | | " " | " " " " |
| HICKSVILLE N.Y. | | | | | | |
| DEGREASER | | 50 | ✓ | | " " | " " " " |
| CITAM PLATE INC BROOKLYN N.Y. | | | | | | |

RECOMMENDED ACTION

FOR
OFFICE
USE
ONLY

- 2 ☐ Immediate Abatement
3 ☐ Sample
4 ☒ SPDES Application

- 5 ☐ Refer To: _____
6 ☐ Re-inspection
7 ☐ No Action
9 ☐ Other (specify)

SUBSTANCES OF CONCERN

(include gases and waste oils)

Provide all information for those substances your facility has used, produced, stored, distributed or otherwise disposed of since January 1, 1971. Do not include chemicals used only in analytical laboratory work.

| of Substance/Trade Name Supplier and Address | CODE | AVERAGE ANNUAL USAGE | AMOUNT NOW ON HAND | (✓) GAL. LB. | PURPOSE OF USE (State whether produced, reacted, blended, packaged, distributed, no longer used, etc.) |
|---|----------|---|-----------------------|-----------------|--|
| Photo Chemical Developing | | | | | Deposited in Drum |
| NMD Developer Amer Hoechst, Haverhill, Mass. | 60120350 | 12 (25 gal) | 2 Gal | | 11 |
| Pricco Web Wash Printers Services Newark, N.J. | | 12 (55 gal) | 55 gal | | Applied Towel |
| Print Blacket Roller Varn Products Co. Flushing, N.Y. | | 6-12 (55 gal) | 5.5 gal | | Applied Towel |
| | | 20% Fluorotrichloromethane 80% Hydrocarbon | | | 55 gal 330 - 660 gal |
| Poly Chemical Co. Spring Valley, N.Y. | | | 55 gal | | 300 * .20 60 gal code 65 |
| | | | | | 240 (F) 300 (L) 540 |

code 4

Final Discharge Point

- ☐ Sewers
☐ Cesspools
☐ Sumps or basins
☐ Drums
☐ Landfills
☐ Other

Recommended Action

- ☐ Immediate abatement
☒ Sample
☒ SPDES Application
☐ Reinspection
☐ Referred to _____
☐ No Action

STATIONARY COMBUSTION AND INCINERATION

- A. Heating System ☐ None ☒ Boiler
 B. Fuel ☐ Electric ☒ Gas
 C. Incinerator ☐ Yes ☒ No

- ☒ Space Heaters
☒ Oil

I hereby affirm under penalty of perjury that information provided on this form is true to the best of my knowledge and belief. False statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law.

| | |
|---|---------------------|
| Owner, Partner, or Agent (Printed or Typed): <i>Dennis J. Driscoll</i> | DATE 2/15/77 |
| Signature: <i>Dennis J. Driscoll</i> | TITLE Exec. V.P. |
| Factors Name: <i>Hughes</i> | |

NASSAU COUNTY DEPARTMENT OF HEALTH
APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT
FORM 3 - BULK AND CONTAINER STORAGE REGISTRATION
SEE INSTRUCTION SHEETS

| | |
|---------------------------|--|
| For Office Use Only | |
| Date Application Received | 11/20/93 5/2/95 |
| Reviewed By | MS |
| Action: | <input type="checkbox"/> Not Req'd. <input type="checkbox"/> Approved <input type="checkbox"/> Disapproved |
| Facility I.D. | 1412 |
| Date Reviewed | |
| No. of Months | 60 |

Facility Name
Great Eastern Printing Co., Inc.

Facility Address
7 Aerial Way, Syosset NY 11791

Action: ☒ Register Existing Area ☐ Add Area ☐ Remove Area ☐ Modify Area Area No. 2

Location: ☒ Indoors ☐ Outdoors Bulk Storage Max. Quantity Stored: Container Storage Max. No. 127121 Max. Vol. 1578.76 gal. 1293.76

Secondary Containment: ☐ Impervious Berm/Dike ☐ Impervious Floor/Pad ☐ Roof ☐ Walls ☐ Floor Drain & Storage Tank ☒ None ☐ Other (Specify):

Construction Material (Check all of Dike & Pad that Apply) ☐ Concrete ☐ Steel ☐ Other (Specify): Security ☒ Yes ☐ No

| Type | NCDH Number | Material Name | Phys- ical State | Amount Stored | | Storage Method | |
|------|---------------------------|--|------------------------|---------------------|-------|-------------------|------|
| | | | | Average Quantity | Units | Average Number | Type |
| 1 | 5772 | Enco RC 791 Finisher | 1 | 5 | 1 | 1 | 2 |
| 1 | 15693 | Copper Plate ^{methylethylchloride} in solution. | 1 | 2 1/2 | 1 | 10 | 2 |
| 1 | 27242 | FDC Finisher | 1 | 1 1/2 | 1 | 5 | 2 |
| 1 | 27052 | Smooth Litho | 1 | 1/2 | 1 | 2 | 2 |
| 1 | 27262 | Roger Sol JKL63-162 | 1 | 5 | 1 | 5 | 2 |
| 1 | 10271 27052 | Roller Wash #1 | 1 | 5 | 1 | 5 | 2 |
| 1 | 27282 | Meter Roller Clean | 1 | 2 | 1 | 2 | 2 |
| 1 | 27292 | MRC Roller Cleaner | 1 | 5 | 1 | 5 | 2 |
| 1 | 27302 | Emerald JR2637 | 1 | 11 | 1 | 11 | 2 |
| 1 | "F" | Press Wash M30 ? | 1 | 30 | 1 | 1 | 1 |
| 1 | "(F)" | Web Wash ? R-228 ^{Carbon / Hydrocarbon} | 1 | 55 | 1 | 1 | 1 |
| 1 | | ILW M Wash ^{Wash} | 1 | 55 | 1 | 1 | 1 |

Nassau County Department of Health
NASSAU COUNTY PUBLIC HEALTH ORDINANCE - ARTICLE XI
APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS
STORAGE FACILITY PERMIT

FORM I-GENERAL INFORMATION (SEE INSTRUCTION SHEET)

If applicable,
check the following:
☐ Municipality
☐ Public School
☐ Other tax-supported
institutions

If tax exempt facility,
enter N.Y. State Exempt
Organization Certificate
No. and enclose a copy:

For Office Use Only

| | |
|--|------------------------|
| Facility I.D. 1412 | Date Rec'd. 1/20/93 |
| Fec Exempt Fac. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Permit Months: |

Check all that apply
to your facility:

☐ Tank Storage ☒ Container Storage ☐ Bulk Storage ☐ Storage of Road De-icing Materials

Reason for submitting application: ☒ New ☐ Renewal ☐ Change ☐ Construction

| | | | | | |
|---|--------------------------------|------------------------|-------------|--------------|-------------------|
| Facility Name Great Eastern Printing Co., Inc. | Street Address 7 Aerial Way | Post Office Syosset | State NY | Zip 11791 | Phone WE1-3900 |
|---|--------------------------------|------------------------|-------------|--------------|-------------------|

| | | |
|--|---|-------------------|
| Facility Mailing Address (If different from above) | Facility Contact Person (Name & Title) Dennis Driscoll, Pres | Phone WE1-3900 |
|--|---|-------------------|

| | | | | | |
|-----------------------------------|----------------|-------------|-------|-----|-------|
| Facility Owner Dennis Driscoll | Street Address | Post Office | State | Zip | Phone |
|-----------------------------------|----------------|-------------|-------|-----|-------|

| | | | | | |
|--|----------------|-------------|-------|-----|-------|
| Property Owner (If not Facility Owner) | Street Address | Post Office | State | Zip | Phone |
|--|----------------|-------------|-------|-----|-------|

| | | | | | |
|------------------------------------|----------------|-------------|-------|-----|-------|
| Tank Owner (If not Facility Owner) | Street Address | Post Office | State | Zip | Phone |
|------------------------------------|----------------|-------------|-------|-----|-------|

Name that should appear on Permit (Permittee)
(If different from Facility Owner)

| | | | | |
|----------------------------|-------------|-------|-----|-------|
| Permittee's Street Address | Post Office | State | Zip | Phone |
|----------------------------|-------------|-------|-----|-------|

Permittee's Relationship
to Facility Owner: ☒ Same ☐ Operator of Facility ☐ Other (Specify):

| | | | | |
|---|---------------------------|---------------|--------------|-------------|
| Principal Property Tax Code: 71024 282489 | School District No. 14 | Section 15 | Block 157 | Lot 0032 |
|---|---------------------------|---------------|--------------|-------------|

Forms Attached (Check all that apply) ☐ Form 2 - Tank Registration ☐ Form 3 - Bulk & Container Storage Registration ☐ Form 4 - Storage of Road De-icing Materials

I hereby affirm under penalty of perjury that the information provided on this form and on any attached forms, statements and exhibits is true and correct to the best of my knowledge and belief.

| | | | |
|----------------------------------|---------------------------------|--------------------|------------------|
| Print Name DENNIS J. DRISCOLL | Signature <i>[Signature]</i> | Title President | Date 10/21/92 |
|----------------------------------|---------------------------------|--------------------|------------------|

COUNTY DEPARTMENT OF HEALTH
 APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT
 - BULK AND CONTAINER STORAGE REGISTRATION
 INSTRUCTIONS SHEETS

Name
 at Eastern Printing Co., Inc.
 Address
 Serial Way Syosset, NY 11791

FOR OFFICE USE ONLY

| | | | |
|---------------------------|--|---------------|------|
| Date Application Received | 1/20/93 6/9/93 | Facility I.D. | 1412 |
| Reviewed By | RS | Date Reviewed | |
| Action: | <input type="checkbox"/> Not Req'd. | No. of Months | |
| | <input type="checkbox"/> Approved <input type="checkbox"/> Disapproved | | |

☒ Register Existing Area ☐ Add Area ☐ Remove Area ☐ Modify Area Area No. 2

Indoors ☒ Bulk Storage Max. Quantity Stored: Container Storage Max. No. 12/12/ Max. Vol. 1293.76 gal.
 Outdoors ☐ Max. Quantity Stored: Floor Drain & Storage Tank ☒ None ☐ Other (Specify):

Impervious ☐ Berm/Dike ☐ Impervious Floor/Pad ☐ Roof ☐ Walls ☐ Floor Drain & Storage Tank ☒ None ☐ Other (Specify):

Construction Material (Check all that Apply) ☐ Concrete ☐ Steel ☐ Other (Specify): Security ☒ Yes ☐ No

| NCDH Number | Material Name | Physical State | Amount Stored | | Storage Method | |
|------------------------|--|----------------|------------------|-------|----------------|------|
| | | | Average Quantity | Units | Average Number | Type |
| 4561 | Printer's Ink | 4 | 1200 | 1 | 2000 50 | 2 |
| 24581 | Kodak Fixer A ^{Ammonium bisulfate} _{active and bisulfate} | 1 | 10 | 1 | 2 | 2 |
| 24571 | Developer | 1 | 5 | 1 | 2 | 2 |
| 783 | Al ₂ (SO ₄) ₃ | 1 | 6 | 1 | 2 | 2 |
| 8493 | H ₂ SO ₄ | 1 | 1 1/2 | 1 | 2 | |
| 9291 | Tri Ethylene Glycol (alcha) | 1 | 10 | 1 | 2 | 2 |
| 7051 | Alpha Replenisher B | 1 | 2 | 1 | 2 | 2 |
| 10163 | Hunt Potassium Thocyanate | 1 | 15 | 1 | 3 | 2 |
| 11831 | Hunt Developer | 1 | 5 | 1 | 1 | 2 |
| 11831 | 143 Developer - | 1 | 15 | 1 | 3 | 2 |
| 10651 | Filmclean Pit-50 ^{sodium (T rexp)} | 1 | 2 | 1 | 2 | 2 |
| Surfactant. Sol. 27312 | EN 220 Developer ^{2-phenox ethand.} | 1 | 15 | 1 | 3 | 2 |

| For Office Use Only | | | |
|---|--|---------------|--|
| Date Application Received | | Facility I.D. | |
| 1/20/93 | | 1412 | |
| Reviewed By | | Date Reviewed | |
| MS | | | |
| Action: | | No. of Months | |
| <input type="checkbox"/> Approved <input type="checkbox"/> Not Req'd. | | | |
| <input type="checkbox"/> Disapproved | | | |

Facility Address 7 Aerial Way, Syosset NY 11791

Area No. 1

Container
Storage Max.No. 6 Max.Vol. 285 Gal

| | | | | | | |
|-------------------------------------|------------------------|-----------------------------------|--------------------------------|---|----------|---|
| Construction Material of Dike & Pad | (Check all that Apply) | <input type="checkbox"/> Concrete | <input type="checkbox"/> Steel | <input type="checkbox"/> Other (Specify): | Security | <input type="checkbox"/> Yes <input type="checkbox"/> No |
|-------------------------------------|------------------------|-----------------------------------|--------------------------------|---|----------|---|

EH 859 4/86
DH-27 11/86

Page 3 of 3

☒ D.P.

"F" = Flammable

PART I

| | | | | | |
|---|--|---|--|-----------------------------------|--|
| COMPANY NAME Bertani Associates Inc. | | SIC CODE (if known) 3671 | | OFFICE USE ONLY | |
| COMPANY MAILING ADDRESS 3 Aerial Way | | CITY Syosset | | STATE NY | |
| CONTACT NAME (if different) Walter Check | | CONTACT NAME Walter Check | | TELEPHONE Area 433 3110 | |
| STREET ADDRESS (if different) Electronics | | CITY Syosset | | STATE NY | |
| PRINCIPAL BUSINESS OF PLANT Electronics | | Number of Employees at this Facility 50 | | | |

(If parent company, give name and addresses of all divisions, subsidiaries, etc. located in New York State. A separate questionnaire is to be completed and submitted for each.)

1. Does your plant discharge liquid wastes to a municipally owned sanitary sewer system?
Name of System _____ ☐ Yes ☒ No

2. Is your facility permitted to discharge liquid wastes under a State (SPDES) or Federal (NPDES) permit? Permit Number

| | | | | | | | |
|--|--|--|--|--|--|--|--|
| | | | | | | | |
|--|--|--|--|--|--|--|--|

☐ Yes ☒ No

3. Do you discharge liquid wastes in any other manner? ☐ Yes ☒ No
Explain _____
Any of the above are "Yes":

a. Do you discharge process or chemical wastes — (i.e. water used in manufacturing including direct contact cooling water and scrubber water)? ☐ Yes ☒ No

b. Do you discharge non-contact cooling water? ☐ Yes ☒ No

c. Do you discharge collected storm drainage only? ☐ Yes ☒ No

d. Do you discharge sanitary wastes only? ☒ Yes ☐ No

1. Does your facility have sources of possible emissions to the atmosphere? Cleaning Agents Under Hood ☒ Yes ☐ No

2. Enter Location and Facility Code as shown on your Air Pollution Control Application for Permits and Certification (If applicable)

| | | | | | | | |
|--|--|--|--|--|--|--|--|
| | | | | | | | |
|--|--|--|--|--|--|--|--|

| | | | |
|---------|------|-------|----------|
| Name | | | |
| | | | |
| Address | City | State | Zip Code |
| Name | | | |
| | | | |
| Address | City | State | Zip Code |

1 _____

2 _____

| | | |
|--|------------------------------|--|
| Manufacture Pesticides or Pesticide Product Ingredients? | <input type="checkbox"/> Yes | |
| Produce Pesticides or Pesticide Product Ingredients? | <input type="checkbox"/> Yes | |
| Formulate Pesticides? | <input type="checkbox"/> Yes | |
| Repackage Pesticides? | <input type="checkbox"/> Yes | |

2. EPA Establishment Number

(include gases and waste oils)

Complete all information for those substances your facility has used, produced, stored, distributed or otherwise disposed of since January 1, 1971. Do not include chemicals used only in analytical laboratory work.

Final Discharge Point

- ☐ Sewers
☐ Cesspools
☐ Sumps or basins
☐ Drums
☐ Landfills
☐ Other

☐ Immediate abatement
☒ Sample
☒ SPDES Application
☐ Reinspection
☐ Referred to _____
☐ No Action

A. Heating System

- ☐
- None

☐ ~~Boiler~~

B. Fuel

- ☐ Electric

☒ Gas

C. Incinerator

- ☐
- Yes

☒ No

☒ Space Heaters

POIL

by affirm under penalty of perjury that information provided on this form is true to the best of my knowledge and belief. False statements are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law.

AT'S (Owner, Partner, or Officer)

DATE

L. Walter Child
(Printed or Typed).

2/15/77

(Printed or Typed).

TITLE

Walter Check

Sector's Name



FRANCIS T. PURCELL
County Executive

NASSAU COUNTY DEPARTMENT OF HEALTH

240 OLD COUNTRY ROAD, MINEOLA, N.Y. 11501

JOHN J. DOWLING, M.D., M.P.H.
Commissioner

FRANCIS V. PADAR, P.E., M.C.E.
Deputy Commissioner
Division of Environmental Health

July 22, 1983

Bertan Associates
3 Aerial Way
Syosset, N.Y. 11791

Att: Mr. Walter Check, Manager

Re: Application for Approval
to Operate a Solid Waste
Management Facility

Gentlemen:

Your facility may require a Solid Waste Management Facility permit, in accordance with Article IX of the Nassau County Public Health Ordinance, effective August 1, 1983.

It is necessary that you obtain a permit if your facility falls into either of the following categories:

- . The facility generates or accumulates or stores at any time 100 kilograms or more of hazardous wastes
and/or
- . The facility accumulates or stores at any time more than 27.5 gallons of liquid industrial wastes which, according to State law, cannot be discharged into the ground

Please complete the enclosed application form and return it to the Nassau County Department of Health within two weeks of the date of this letter. Include the following supplemental data:


- . Plot Sketch (see sample enclosed)
- . Material Flow Sketch (see sample enclosed)

Should an Engineering Report also be required, you will be contacted by our staff.

If your facility does not fall into either of the categories listed above, please indicate this on the enclosed application form or in a letter to this Department.

If you have any questions concerning the application, please call me at (516) 535-2285.

Very truly yours,


Lawrence Sama
Public Health Engineer
Bureau of Land Resources

Enclosures

APPLICATION FOR APPROVAL TO OPERATE A SOLID WASTE MANAGEMENT FACILITY

Nassau County Department of Health

Instructions

For Health Department Use Only

Complete all Sections

Fill this Application Form, along with your Plot Sketch and Material Flow Sketch, within 2 weeks to:

Bureau of Land Resources Management
Nassau County Department of Health
240 Old Country Road
Mineola, N.Y. 11501

Facility
Number:Date
Received:

Department Action

☐ Approved☐ Interim☐ Not
Required

By:

Permit
NumberStart
Date:Exp.
Date:

1. Facility Name

BERTAN ASSOCIATES INC.

2. Address

3 AERIAL WAY, SYOSSET, NY, 11791

3. Tel. #

516-433-3110

4. Owner's Name

AERIAL WAY REALTY

5. Address

3 AERIAL WAY, SYOSSET, NY, 11791

6. Tel. #

516-822-4770

7. On-Site Supervisor

WALTER CHECK, PROD. MGR.

8. Address

3 AERIAL WAY, SYOSSET, NY, 11791

9. Tel. #

516-433-3110

10. Engineer (if applicable)

11. Address

12. Tel. #

13. Has this department ever approved plans and specifications and or engineering reports for this facility?

☐ Yes

Date

☒ No

14. List Wastes Generated (use additional sheet if needed).

| Name of Constituents | Check One | | # of Gals. Generated Per Month | | Maximum # of Gals. Accumulated Before Disposal |
|---|-----------|---------------|--------------------------------|---------|--|
| | Hazardous | Non-Hazardous | Maximum | Average | |
| CHLOROTHENE | ✓ | | 30 | 20 | 120 |
| M.E.K. | ✓ | | 0 | 0 | 0 |
| ISOPROPYL ALCOHOL | | ✓ | 0 | 0 | 0 |
| FERRIC CHLORIDE | | ✓ | 5 | 1 | 30 |
| DEVELOPER (MIXTURE OF KEYTONE & AROMATIC HYDROCARBON) | | ✓ | 5 | 1 | 30 |

15. Names of Waste Haulers

ATLAS ASSOC., 109 FIFTH AVE, PATTERSON, N.J., 07524

SCAVENGER # NJ D06 5825341.

16. Briefly describe facility operation: (use additional sheet if needed)

BERTAN ASSOC. INC. IS AN ELECTRONICS CO. MANUFACTURING HIGH VOLTAGE POWER SUPPLIES. THE CHEMICALS, CHLOROTHENE, M.E.K. & ISOPROPYL ALCOHOL ARE USED IN THESE ASSEMBLIES TO CLEAN THE COMPONENT PARTS. THE CHEMICALS FERRIC CHLORIDE & DEVELOPER (MIXTURE OF KEYTONE & AROMATIC HYDROCARBON) ARE USED IN MAKING PROTOTYPE PRINTED CIRCUIT BOARDS, IN VERY SMALL QUANTITIES.

RECEIVED

JUN 26 1983

I hereby affirm under penalty of perjury, that the information provided on this form and attached statements and exhibits is true to the best of my knowledge and belief.

Signature

Walter Check

Title

PRODUCTION MANAGER


Date

8/23/83

FAIRCHILD CAMERA
FACTORY



ROBBIN LANE

CHILD
EN
ATORY



TO
JER
TP

ACTORY



FLOW DESCRIPTION.

ARE RECEIVED AND STORED IN CHEMICAL STORAGE
THEY ARE USED UNDER EXHAUST SYSTEMS #1 & 2.
E STORED AT EXHAUST SYSTEM #2 AWAITING

NOTE: EXHAUST SYSTEMS NO. 1 & 2
SIDE OF BUILDING. EXHAUST SYSTEMS
NO. 3 & 4 ON ROOF OF BUILDING.

PLOT SKETCH &
MATERIAL FLOW SKETCH
BERTHA ASSOCIATES
3 AERIAL WAY
SYOSSET, N.Y., 11791
SIB-433-3110
PLANNER - WALTER CHEN
APPROVATE - LECTURE

Nassau County Department of Health
NASSAU COUNTY PUBLIC HEALTH ORDINANCE - ARTICLE XI
APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS
STORAGE FACILITY PERMIT

FORM I-GENERAL INFORMATION (SEE INSTRUCTION SHEET)

If applicable, check the following:
☐ Municipality
☐ Public School
☐ Other tax-supported institutions

If tax exempt facility, enter N.Y. State Exempt Organization Certificate No. and enclose a copy:

| | |
|---|-----------------------|
| For Office Use Only | |
| Facility I.D. 1385 | Date Rec'd 8/17/92 |
| Fee Exempt Fac. <input type="checkbox"/> Yes <input type="checkbox"/> No | Permit Months: |

Check all that apply to your facility:

☐ Tank Storage ☒ Container Storage ☐ Bulk Storage ☐ Storage of Road De-icing Materials

Reason for submitting application: ☒ New ☐ Renewal ☐ Change ☐ Construction

| | | | | | |
|---|-----------------------------------|--|-------------|-------------------|-------------------------|
| Facility Name PAX SURFACE CHEMICALS INC. | Street Address 235A Robbins La | Post Office Syosset | State NY | Zip 11791 | Phone 822-7860 |
| Facility Mailing Address (If different from above) | | Facility Contact Person (Name & Title) GENE PACKMAN PRES. | | Phone 822-7860 | |
| Facility Owner PAX SURFACE CHEMICALS INC. | Street Address 235A Robbins La | Post Office Syosset | State NY | Zip 11791 | Phone 822-7860 |
| Property Owner (If not Facility Owner) BLACKSTONE Realty | Street Address 166-40 89th Ave | Post Office Jamaica | State NY | Zip 11432 | Phone (718) 291-6709 |
| Tank Owner (If not Facility Owner) | Street Address | Post Office | State | Zip | Phone |

Name that should appear on Permit (Permittee)
(If different from Facility Owner)

| | | | | |
|---|------------------------|-------------|--------------|-------------------|
| Permittee's Street Address 235A Robbins La | Post Office Syosset | State NY | Zip 11791 | Phone 822-7860 |
|---|------------------------|-------------|--------------|-------------------|

Permittee's Relationship to Facility Owner: ☒ Same ☐ Operator of Facility ☐ Other (Specify):

| | | | | |
|------------------------------|--------------------------------|--------------------|------------------|----------------|
| Principal Property Tax Code: | School District No. Unknown | Section Unknown | Block Unknown | Lot Unknown |
|------------------------------|--------------------------------|--------------------|------------------|----------------|

Forms Attached ☐ Form 2 - Tank Registration ☒ Form 3 - Bulk & Container Storage Registration ☐ Form 4 - Storage of Road De-icing Materials

I hereby affirm under penalty of perjury that the information provided on this form and on any attached forms, statements and exhibits is true and correct to the best of my knowledge and belief.

| | | | |
|----------------------------|----------------------------------|--------------------|-----------------|
| Print Name Gene Packman | Signature <i>Gene Packman</i> | Title President | Date 8-13-92 |
|----------------------------|----------------------------------|--------------------|-----------------|

NASSAU COUNTY DEPARTMENT OF HEALTH
APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT
FORM 3 - BULK AND CONTAINER STORAGE REGISTRATION
SEE INSTRUCTION SHEETS

For Office Use Only

| | | | |
|-----------------------------------|--------------------------------------|---------------|------|
| Date Application Received | 8/17/92 | Facility I.D. | 1385 |
| Reviewed By | REG | Date Reviewed | |
| Action: | <input type="checkbox"/> Not Req'd. | No. of Months | |
| <input type="checkbox"/> Approved | <input type="checkbox"/> Disapproved | | |

Facility Name PAX SURFACE CHEMICALS, INC.
Facility Address 235A Robbins Rd Syosset, NY 11791

Action: ☒ Register Existing Area ☐ Add Area ☐ Remove Area ☐ Modify Area Area No. /

Location: ☒ Indoors Bulk Storage ☐ Outdoors Max. Quantity Stored: Container Storage Max. No. 12 * ^{AS 55 gal drums} Max. Vol. 644 gal

Secondary Containment: ☒ Impervious Berm/Dike ☒ Impervious Floor/Pad ☒ Roof ☒ Walls ☐ Floor Drain & Storage Tank ☐ None ☐ Other (Specify):


Construction Material (Check all that Apply) ☒ Concrete ☐ Steel ☒ Other (Specify): EPOXY SEAL UNDER TOP Security ☒ Yes ☐ No

| Type | NCDH Number | Material Name | Physical State | Amount Stored | | Storage Method | |
|------|-------------|----------------------|----------------|------------------|-------|----------------|------|
| | | | | Average Quantity | Units | Average Number | Type |
| 1 | 26253 | D-TARNISH 1364 | 1 | 25 | 1 | 5 | 2 |
| 1 | 26263 | PAXSTRIP 330 | 1 | 25 | 1 | 5 | 2 |
| 1 | 26273 | PAXTIQUE 1401 | 1 | 10 | 1 | 2 | 2 |
| 1 | 26283 | PAXTIQUE 1420 | 1 | 20 | 1 | 4 | 2 |
| 1 | 26293 | PAXBRITE 408 | 1 | 40 | 1 | 8 | 2 |
| 1 | 26293 | PAXBRITE 408 | 1 | 110 | 1 | 2 | 1 |
| 1 | 26303 | CHEMSEAL 330 | 1 | 5 | 1 | 1 | 2 |
| 1 | 26313 | CHEMMAX 836 | 1 | 220 | 1 | 4 | 1 |
| 1 | 8430 | Anionic Surfactant 4 | 1 | 40 | 1 | less than 1 | 1 |
| 1 | 10111 | Ethylenediamine | 1 | 40 | 1 | less than 1 | 1 |
| 1 | 9493 | Sulfonic Acid | 1 | 10 | 1 | 1 | 2 |
| 1 | 883 | Ammonium Hydroxide | 1 | 30 | 1 | less than 1 | 1 |

Facility Address

☐ Approved ☐ Disapproved

☐ D.P.



PAX SURFACE CHEMICALS

235A ROBBINS LA

SYOSSET, NY 11791

Estimated property lines

ESTIMATED DISTANCE TO PROPERTY LINE 900' +

ATTACHED BUILDINGS

S i - Container Storage Area

TO ROBBINS LANE 1,000 FEET (APPROX)

ALL DIMENSIONS TO STREETS AND PROPERTY LINES ARE ESTIMATED



NASSAU COUNTY DEPARTMENT of HEALTH

Page 1

TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT

| | | | | | | | | | |
|--------------------|---------------|----------------|--|-----------------------|--------------------------------|----------------|----------|------------------|----------|
| Facility Number | 000980 | Type of Permit | <input checked="" type="checkbox"/> Operation <input type="checkbox"/> Construction | Date Issued: | 08/01/90 | Date Modified: | 12/01/90 | Expiration Date: | 08/01/95 |
| Name of Permittee: | EMRO CLEANERS | | | Address of Permittee: | 235 ROBBINS LANE SYOSSET NY | | | | |

GENERAL CONDITIONS

1. By acceptance of this permit, the permittee agrees that the permit is contingent upon strict compliance with Article XI, Nassau County Public Health Ordinance.
2. All work carried out under this permit shall conform to the approved plans and specifications. Any amendments must be approved by the Nassau County Department of Health prior to their implementation. The permittee shall notify the Health Department 48 hours in advance of the start of construction.

3. As a condition of the issuance of this permit, the applicant has accepted expressly, by the execution of the application, the full legal responsibility for all damages direct or indirect, of whatever nature, and by whomever suffered, arising out of the project described herein and has agreed to defend, indemnify and save harmless the County from suits, actions, damages and costs of every name and description resulting from the said project.

| | | |
|-------------------|---------------------------------------|--------------------------------------|
| Name of Facility: | EMRO CLEANERS | FACILITY ADDRESS: |
| Mailing Address: | 235 ROBBINS LANE SYOSSET NY 11791- | 235 ROBBINS LANE SYOSSET NY 11791 |

THIS FACILITY CONSISTS OF STORAGE AREAS AS LISTED ON PLANS AND APPLICATIONS FILED WITH THIS DEPARTMENT

| <u>Tank/Storage Area Number</u> | <u>Capacity</u> | <u>Type of Toxic or Hazardous Material Stored</u> |
|---------------------------------|-----------------|---|
| BULK 0001 | 100 POUNDS | MULTIPLE CHEMICALS STORED |
| BULK 0001 | 345 GALLONS | MULTIPLE CHEMICALS STORED |

Authorizing Officer

John J. Dowling, M.D., M.P.H. Commissioner of Health

Nassau County Department of Health
 NASSAU COUNTY PUBLIC HEALTH ORDINANCE - ARTICLE XI
 APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS
 STORAGE FACILITY PERMIT

FORM 1-GENERAL INFORMATION (SEE INSTRUCTION SHEET)

If applicable, check the following:
☐ Municipality
☐ Public School
☐ Other tax-supported institutions

If tax exempt facility, check N.Y. State Exempt Organization Certificate No. and attach copy:
 1/9/90

For Office Use Only
 Facility I.D. 280
 Fee Exempt Fac. ☐ Yes ☐ No
 Permit Months:

Check all that apply to your facility: ☐ Tank Storage ☒ Container Storage ☐ Bulk Storage ☐ Storage of Road De-icing Materials

Reason for submitting application: ☒ New ☐ Renewal ☐ Change ☐ Construction

| | | | | | |
|---|--|--|--------------------|---------------------|--------------------------|
| Facility Name <i>USA</i> | Street Address <i>235 85th Ave</i> | Post Office <i>Sisseton</i> | State <i>NY</i> | Zip <i>11791</i> | Phone <i>931-3350</i> |
| Facility Mailing Address (If different from above) | | Facility Contact Person (Name & Title) <i>William Van Dyke - Pres</i> | | | Phone <i>931-3350</i> |
| Facility Owner | Street Address | Post Office | State | Zip | Phone |
| Property Owner (If not Facility Owner) <i>Mike L. Lasker</i> | Street Address <i>235 85th Street</i> | Post Office <i>B'klyn</i> | State <i>NY</i> | Zip <i>11209</i> | Phone |
| Tank Owner (If not Facility Owner) | Street Address | Post Office | State | Zip | Phone |

Name that should appear on Permit (Permittee)
 (If different from Facility Owner)

| | | | | |
|----------------------------|-------------|-------|-----|-------|
| Permittee's Street Address | Post Office | State | Zip | Phone |
|----------------------------|-------------|-------|-----|-------|

Permittee's Relationship to Facility Owner: ☐ Same ☐ Operator of Facility ☐ Other (Specify):

| | | | | |
|------------------------------|---------------------|---------|-------|-----|
| Principal Property Tax Code: | School District No. | Section | Block | Lot |
|------------------------------|---------------------|---------|-------|-----|

Forms Attached ☐ Form 2 - Tank Registration ☐ Form 3 - Bulk & Container Storage Registration ☐ Form 4 - Storage of Road De-icing Materials

I hereby affirm under penalty of perjury that the information provided on this form and on any attached forms, statements and exhibits is true and correct to the best of my knowledge and belief.

| | | | |
|---------------------------------------|--------------------------------------|----------------------|-----------------------|
| Print Name <i>William Van Dyke</i> | Signature <i>William Van Dyke</i> | Title <i>Pres</i> | Date <i>2/5/87</i> |
|---------------------------------------|--------------------------------------|----------------------|-----------------------|

RECEIVED

For Office Use Only

Date Aug 09 1990
Received

Facility I.D.
780

Reviewed
By **NCDH - BLRM**

Date Reviewed

Action: ☐ Not Req'd.
☐ Approved ☐ Disapproved

| | |
|---------------|----|
| No. of Months | 60 |
|---------------|----|

Facility Name FIM 10 Inc. 2500 Highway 10, Ames

Facility Address
235 Robbins Lane, Dunstable, PA

Date Submitted 7/5/80

Page 2 of 3

☐ D.P.

For Office Use Only

Facility I.D.

980

Date Reviewed

[illegible]

☐ Disapproved

60

Area No.

Max.Vol.

(Specify):

☐ Yes

☒ No

☐ D.P.

Nassau County Department of Health
240 Old Country Road
Mineola, NY 11501

Name _____

Enro Clamers

Article XI Permit Number

Address

235 Robbins Lane

Report Period

1954

Indicate for each the purpose or use, trade name or supplier and the quantity purchased.

| Name of Chemical or Solvent | How is Chemical or Solvent used? | Trade Name or Supplier | Quantity Purchased |
|-----------------------------|----------------------------------|--------------------------|--------------------|
| Perchloroethylene | Dry Cleaning | Kliceman Bros | 63.36 gal |
| " | " | " | 75.56 gal |
| Inst. Soap | " | FABRICAM FABRIC CLEAN | 15 240 gal |
| " | " | " | " |
| " | " | " | " |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| Total | | | |

Chemical/Solvent Waste Report

For each shipment of wastes, complete the following table with the indicated information.
ATTACH COPIES OF MANIFESTS OR RECEIPTS FROM SCAVENGER FOR EACH SHIPMENT MADE.

| Date of Shipment | Description of waste | Amount Removed | Shipped By | | | Shipped to (Final disposal site for waste) |
|------------------|----------------------|----------------|--------------------|------------------------------------|----------------------------|---|
| | | | Transporter's name | Transporter's Address | D.E.C. Registration Number | |
| 1/31/97 | Tetrachloroethylene | 210 lbs | SAFETY RECYCLE | 80 Seaboard No Amityville, N.Y. | TLD- 984908202 | Heb. Co., Ohio |
| 5/11 | " | 140 lbs | " | " " | " | " |
| 8/3 | " | 405 lbs | " | " " | " | " |
| 10/2 | " | 140 | " | " " | " | " |
| 12/14 | " | 350 lbs | " | " " | " | " |
| 14/12 | " | 560 lbs | " | " " | " | " |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Total

List any spills that occurred during the reporting period.

| Date of Spill | Amount of spill | Describe the nature of the spill. |
|--------------------------------------|-----------------|-----------------------------------|
| | | |
| | | |
| Signature of Company Representative. | | Date |



NASSAU COUNTY DEPARTMENT OF HEALTH

240 OLD COUNTRY ROAD
MINEOLA, N.Y. 11501

FRANCIS T. PURCELL
COUNTY EXECUTIVE

JOHN J. DOWLING, M.D., M.P.H.
COMMISSIONER

FRANCIS V. PADAR, P.E.
ASST. DEPUTY COMMISSIONER
DIV. OF ENVIRONMENTAL SERVICES

Certified

August 23, 1978

Mr. Louis Perlman
c/o Metallurgical Processing Corp.
180 Michael Drive
Syosset, N. Y. 11791

Dear Mr. Perlman:

At our meeting on August 17, 1978, several items were discussed regarding the removal of various chemicals and liquid wastes from the premises. The following items were discussed:

1. No liquid wastes are to be discharged into underground wells or cesspools until it has been demonstrated to this Department that the effluent meets those standards set forth in your SPDES permit #NY- 0076244.
2. Liquid wastes on the floor of the treatment room are to be properly removed on or before Sept. 1, 1978.
3. The chemical storage area in rear of main building must be cleared of all chemicals on or before Sept. 1, 1978. This must be in a proper and acceptable manner and in accordance with discharge restrictions set forth in item #1 above.
4. Information regarding the removal of all liquid waste from tanks in the treatment room must be forwarded to this Department on or before Sept. 11, 1978.
5. Liquid wastes in the treatment tanks must be removed by licensed scavenger or treated prior to disposal and must be removed from the premises on or before Sept. 30, 1978.

Mr. Louis Perlman

-2-

August 23, 1978

If you have any questions or comments regarding the above, please do not hesitate to contact me as soon as possible.

Very truly yours,

A handwritten signature in dark ink, appearing to read 'Michael Mangino', with a large, stylized flourish extending from the end of the signature.

Michael Mangino
Chief, Enforcement Section
Bureau of Wastewater Management

MM:ceg:r

Missoula County Department of Health

COL. BY
Gene M

17 SPECIAL

NAME OF OWNER OR DISTRICT

LOCATION

POINT OF COLLECTION

TAP PLAYEO:

☒ YES ☐ NC NCW?

CHLORINE RESIDUAL:

OT OT+A pH

IF SAMPLE IS FROM WELL, IS SANITARY SURVEY

☐ SATISFACTORY? ☐ UNSATISFACTORY? (Explain)

REMARKS, EXPLANATIONS:

$\text{Cd}, \text{Co}, \text{Cr}^{+6}, \text{Cu}, \text{F}, \text{Fe}, \text{Ni}$
 $\text{Se}, \text{SO}_4, \text{Zn}, \text{Cl}, \text{pH}$

Treated Waste from:

NUMBER (2-6) Note: Plating
Operation hasn't been
run in approx. 1 mo.
Dry well down
to 2-3 ft of
bottom. ~~There is still~~
claims that the
water in dry well
may show high levels
of inorganics.

[illegible]

NAME OF PLANT

LOCATION

METALLURGICAL PROCESSING CORP.

180 MICHAEL DRIVE, SYOSSET,

| DAYS | DAY OF MONTH | FLOW (GPD) | | | | | PH | | CR 06 | |
|----------|--------------|----------------------|---------------|---------------|-------|--------|----|--|------------|--------|
| | | Discharge No. 001 | Discharge No. | Discharge No. | Daily | Weekly | | | 0.1 (mg/l) | |
| | | | | | | | | | Daily | Weekly |
| | 1 | 13,710 | | | 7.3 | | | | 0.1 | |
| | 2 | 13,350 | | | 7.7 | | | | 0.0 | |
| | 3 | 13,610 | | | 7.1 | | | | 0.0 | |
| | 4 | 13,320 | | | 7.9 | | | | 0.1 | |
| | 5 | 13,490 | | | 7.5 | | | | 0.0 | |
| | 6 | | | | | | | | | |
| | 7 | | | | | | | | | |
| | 8 | 12,880 | | | 8.1 | | | | 0.0 | |
| | 9 | 13,170 | | | 8.3 | | | | 0.0 | |
| | 10 | 13,440 | | | 7.5 | | | | 0.0 | |
| | 11 | 13,210 | | | 7.3 | | | | 0.1 | |
| | 12 | 13,750 | | | 7.5 | | | | 0.1 | |
| | 13 | | | | | | | | | |
| | 14 | | | | | | | | | |
| | 15 | 12,900 | | | 7.6 | | | | 0.0 | |
| | 16 | 13,370 | | | 7.8 | | | | 0.0 | |
| | 17 | 13,820 | | | 7.5 | | | | 0.2 | |
| | 18 | 13,690 | | | 7.7 | | | | 0.0 | |
| | 19 | 13,850 | | | 8.0 | | | | 0.1 | |
| | 20 | | | | | | | | | |
| | 21 | | | | | | | | | |
| | 22 | 13,700 | | | 7.6 | | | | 0.1 | |
| | 23 | 13,430 | | | 7.5 | | | | 0.1 | |
| | 24 | 13,650 | | | 7.2 | | | | 0.0 | |
| | 25 | 13,900 | | | 7.8 | | | | 0.0 | |
| | 26 | 13,600 | | | 7.5 | | | | 0.1 | |
| | 27 | | | | | | | | | |
| | 28 | | | | | | | | | |
| | 29 | 13,450 | | | 7.7 | | | | 0.1 | |
| | 30 | 12,910 | | | 7.3 | | | | 0.1 | |
| | 31 | 13,050 | | | 7.9 | | | | 0.1 | |
| AVERAGES | | 13,295 | | | 7.5 | | | | .06 | |

FORM NAME

metallurgical Process
180 Michael Dr, Syosset

NY0076244

| | .1 | 1.0 | 1.0 | .02 | 2.0 | 500 | 3.0 | 6.5 8.5 | .6 | 590 | 5 |
|--------------------|------------------|------------------|-----|------|-----|------|-----|------------|------|-----------------|-----|
| | Cr ⁶⁺ | Cr ⁶⁺ | Cu | Cd | Ni | Cl | F | pH | Fe | SO ₄ | Zn |
| 10-27-77 | .01 | .01 | .7 | 2.05 | * | 50 | * | 7.1 | 1.17 | 5 | 1.9 |
| 11-9-77 | * | * | * | * | * | 10 | 14 | 7.4 | * | * | * |
| 2-1-78 | .01 | .20 | .05 | .013 | .22 | * | .17 | 8.2 | .35 | 13 | 4 |
| Treatment facility | | | | | | | | | | | |
| 7-18-78 | .01 | .09 | .30 | .022 | .74 | 34.0 | .72 | 6.6 | .76 | * | 6 |
| Drywell | | | | | | | | | | | |

USE THIS FORM

New York State Department of Environmental Conservation

30 Wolf Road, Albany, New York 12233 (Room 201)

November 15, 1977



CERTIFIED MAIL

RETURN RECEIPT REQUESTED

Peter A. A. Deane
Commissioner

Metallurgical Processing Corp.

180 Michael Drive
Syosset, New York 11791

Attention: Mr. William Foster, Finishing Supt.

Re: MODIFICATION OF POLLUTANT
DISCHARGE ELIMINATION SYSTEM
PERMIT NO. NY-0076244 (GWI)
Oyster Bay (T), Nassau Co.

Dear Mr. Foster:

This is to inform you that pursuant to Environmental Conservation Law ("ECL"), Article 17, Title 8 (McKinney's) and 6 NYCRR, Part 757, the New York State Department of Environmental Conservation has made a determination to modify your referenced Pollutant Discharge Elimination System Permit as indicated in the enclosed revised permit page entitled Final Effluent Limitations and Monitoring Requirements which supersede (and/or supplement) previous corresponding page. The remainder of the Permit continues in full force and effect.

The following effluent parameters have been added to the list:
Cyanide, Iron, Sulfate, Tin and Chlorine.

Unless otherwise specified, this modification will become effective immediately unless you petition, pursuant to ECL Section 17-0907, that you be given an opportunity to be heard in connection with this determination and where applicable, if no written objection is received by this office within 30 days after receipt of this modification by the Regional Administrator of EPA. Any such petition for a hearing shall contain specific evidence to support your contention that a hearing is necessary and that you were not previously given an opportunity to be heard.

Enclosure

cc: Region #1
Mr. Crandall - BMS
Nassau Co. H.D. ✓
File

Very truly yours,

George K. Hansen, P.E.
Chief, P.D.E.S. Permit Section
Division of Pure Waters

MODIFIED - 11/15/77

FINAL EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS

During the period beginning Nov. 15, 1977 and lasting until April 17, 1980 the discharges from the permitted facility shall be limited and monitored by the permittee as specified below:

| Outfall Effluent Number Parameter | Discharge Limitations | | | | Monitoring Reqmts. | |
|--------------------------------------|-----------------------|-------------------------|---------------------------|-------------------------|--------------------------|----------------|
| | kg/day Daily Avg. | (lbs/day) Daily Max. | Other Units Daily Avg. | (Specify) Daily Max. | Measurement Frequency | Sample Type |
| 001 Flow | | | | | Weekly | |
| Cadmium | | | | .02 mg/l | " | Composite |
| Chromium - Total | | | | 1 " | " | " |
| Chromium - Hexavalent | | | | .1 " | " | " |
| Copper | | | | .4 " | " | " |
| Cyanide | | | | .4 " | " | " |
| Fluoride | | | | 3 " | " | " |
| Iron | | | | .6 " | " | " |
| Nickel | | | | 2 " | " | " |
| Sulfate | | | | 500 " | " | " |
| Tin | | | | 1 " | " | " |
| Zinc | | | | .6 " | " | " |
| Chlorine | | | | .1 " | " | Grab |

Also Subject to Schedule "B"

The pH shall not be less than 6.0 standard units nor greater than 8.5 standard units and shall be monitored as follows: daily grab

Samples taken in compliance with the monitoring requirements specified above shall be taken at the following location(s):

The daily average discharge is the total discharge by weight or in other appropriate unit as specified herein, during a calendar month divided by the number of days in the month that the production or commercial facility was operating. Where less than daily sampling is required by this permit, the daily average discharge shall be determined by the summat of all the measured daily discharges in appropriate units as specified herein divided by number of days during the calendar month when the measurements were made.

The daily maximum discharge means the total discharge by weight or in other appropriate unit as specified herein, during any calendar day.

cc: SPDES File
Region I - Ref. #28-0079
Nassau Co. Dept. of Health
Mr. Crandall - BMS
Mr. Quinn - BIP

Application No. : N 007 6244
Name of Permittee : Metallurgical Processing
Effective Date : April 17, 1975
Expiration Date : April 17, 1980

STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM (SPDES)
DISCHARGE PERMIT

Special Conditions
(Part I)

This SPDES permit is issued in compliance with Title 8 of Article 17 of the Environmental Conservation Law of New York State and in compliance with the provisions of the Federal Water Pollution Control Act, as amended by the Federal Water Pollution Control Act Amendments of 1972, P. L. 92-500, October 18, 1972 (33 U.S.C. § 1251 et. seq.) (hereinafter referred to as "the Act").

Metallurgical Processing Corp.
(Full Name of Permittee)

is authorized by William L. Garvey, P.E., Director, Bureau of Standards & Compliance
(Designated Representative of Commissioner of the
Department of Environmental Conservation)

to discharge from 180 Michael Drive
(Street Address of Discharging Facility)
Syosset, New York 11791
Oyster Bay (T), Nassau County

to Ground water
(Name of Receiving Waters)

in accordance with the following special and general conditions:

The specific effluent limitations and other pollution controls applicable to the discharge permitted herein are set forth in the special conditions. Also set forth are self-monitoring and reporting requirements. Unless otherwise specified, the permittee shall submit original copies of all reports to the Central Office and the appropriate Regional Office of the Department of Environmental Conservation and the EPA Region II Regional Administrator. Except for data determined to be confidential under Section 17-0805 of the Environmental Conservation Law or Section 308 of the Act, all such reports shall be available for public inspection at the offices of the Department of Environmental Conservation and the Regional Administrator of EPA Region II. Knowingly making any false statement on any such report may result in the imposition of criminal penalties as provided for in Section 71-1933 of the Environmental Conservation Law or Section 309 of the Act.

Final Effluent Limitations

During the period beginning EDP and lasting
(Give Date)
until the date of expiration of this permit, discharges from outfalls 001
(Specify Outfall Number)
shall be limited and monitored by the permittee as specified below:

(a) The following shall be limited and monitored by the permittee as specified:

| Outfall Number | Effluent Characteristic | Discharge Limitation in kg/day (lbs./day) | | Other Limitations (Specify Units) | | Monitoring Requirements | |
|-------------------|----------------------------|--|------------------|--------------------------------------|---------|----------------------------|----------------|
| | | Daily Average | Daily Maximum | Average | Maximum | Measurement Frequency | Sample Type |
| 001 | Flow | | | N/A | | Weekly | |
| | Chromium (Hexavalent) | | | .1 mg/l | | " | Compo |
| | Chromium (Total) | | | 1.0 mg/l | | " | " |
| | Copper | | | .4 mg/l | | " | " |
| | Cadmium | | | .02 mg/l | | " | " |
| | Nickel | | | 1.0 mg/l | | " | " |
| | Fluoride | | | 3.0 mg/l | | " | " |

Also subject to attached Schedule "B"

For the purposes of this subsection, the daily average discharge is the total discharge by weight during a calendar month divided by the number of days in the month that the production or commercial facility was operating.

For the purposes of this subsection, the daily maximum discharge means the total discharge by weight during any calendar day.

(b) The pH shall not be less than 5.5 nor greater than 8.5.
The pH shall be monitored as follows: Daily

ENVIRONMENTAL
HEALTH

Continuation Sheet

Nassau County Health Department

Owner or

Agent :

Address:

Inspector

DATE

COMMENTS

8/18/78

TO: L. Sama

From: J. Schecter

Subject: Conference at Metallurgical Processing Corporation
180 Michael Drive Syosset

On 8/17/78 at 11:15 AM a conference was held at
M.P.C., 180 Michael Drive Syosset. Those attending
the conference included:

M. Mangino, Nassau County Dept. Health
J. Schecter, " " " "

Louis Perlman, President, M.P.C.

Rick Klein, PLANT Engineer, Thermo National Industries
Dan Muller, Maintenance Engineer, M.P.C.

201-589-3032

M.P.C. is a division of Thermo National Industries,
108 Johnson St., Newark, N.J.; Herb Doblin, President.

IT is being closed down. Current operations include
copper plating and heat treating.

The conference was held to discuss the poor condition
of the plant grounds, spillage of dry chemicals upon
floor of storage room at the rear of the plant, and
the cleanup of the wastewater treatment room.

IT was agreed that:

- ① The chemical storage room, ~~the~~ plant grounds
and treatment room floor would be

ENVIRONMENTAL
HEALTH

Continuation Sheet

Nassau County Health Department

Owner or

Agent :

Address:

Inspector

DATE

COMMENTS

cleaned by August 28, 1978 (Final disposition of chemicals would be verified by M.P.C. + copies of records given to N.C.D.H.)

(2) After Labor Day, 9/8/78, a final decision would be made to either treat the wastewater ~~chem~~ in the treatment room tanks, or have it removed by a licensed industrial scavenger. A list of scavengers was supplied to Rick Klein.

(3) ~~to be~~ Treated wastewater would ^{not} be discharged to groundwaters without first sampling to determine whether effluent limits were met, and notifying NCDH for verification. In addition, wastewater ^{or chemicals} would only be removed by a licensed scavenger + copies of records supplied to N.C.D.H. for verification of final disposal site.

J. Scherhorn

ENVIRONMENTAL
HEALTH

Continuation Sheet

Nassau County Health Department

Owner or

Agent :

Address:

Inspector

DATE

COMMENTS

TO: L. SAMA

FROM: J. Schechter

SUBJECT: INSPECTION OF Metallurgical Processing Corp.

180 Michael Drive

SYOSSET

8/16/78

On 8/15/78 an inspection was conducted at
The above firm. Those attending the inspection
included:

J. Schechter, Nassau County Dept. Health

G. Mauleos, NCDH

DAN Mutter, Heat Treatment Supervisor -

Metallurgical Processing Corp.

The inspection revealed that plating and heat
treating is continuing at this firm, although
plating is done at a reduced level. At the
time of inspection the plating area was not in
use. Mr. Mutter stated that ~~only~~ only copper
plating was currently being done. No plating
employees were available to verify this. Mr. Mutter
stated that the plant is closing down within
a few months. The plant manager, plant chemist
and president of the firm were not available at
the time of inspection for verification.

ENVIRONMENTAL
HEALTH

Continuation Sheet

ssau County Health Department

Owner or

Agent :

Address:

Inspector

DATE

COMMENTS

Several violations were noted:

- ① The Treatment room floor was covered with ~~eff~~ chemical waste which had overflowed from the non-functioning Treatment Tanks. (wastes from the plating area drain to these tanks.) The plant chemist is no longer employed at the firm.
- ② The chemical storage room roof was ~~open~~ ~~in~~ in disrepair - spillage of chemicals was noted on the floor. Dry chemicals were water soaked:
- ③ PLANT grounds were in poor condition - carboys of acids were stored in the open, a drum containing waste sludge/chemicals was open at the top and beginning to leak.

The inspection also revealed 3 underground tanks on the premises. These contained:

- ① Quenching oil -
- ② Degreasing fluid ← not presently filled according to Mr. Mutter
- ③ Gasoline

Three vapor degreasing units are used in the heat treating area. ~~Two~~ Two are presently not operating - one of which is filled with water.

ENVIRONMENTAL
HEALTH

Continuation Sheet

Nassau County Health Department

Owner or

Agent :

Address:

Inspector

DATE

COMMENTS

An inspection of the leaching pool to which
the treated wastewater is discharged revealed no
flow. ~~ME~~

Mr. Mutter was requested to have representatives of
the corporation ~~to~~ call this office concerning
correction of the violations. He was told not
to operate the treatment tank pumps, as
discharge of untreated waste would be a violation
of groundwater standards + effluent limits as
set forth in the SPDES permit.

J. Schechter

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

NYS INDUSTRIAL INSPECTION

AND

STATUS REPORT FORM

Company Name : *Metallurgical Plating Corp*
 Permit No. : *NY 0076244*
 Location : *Warren County*
 Mailing Address : *180 Michael Drive*
Lyons, N.Y.
11791

Date of Inspection: *1-16-78*
 Date(s) of Previous: *10-21-75*
 Inspection(s): *John F. Wilson*
 Previous Inspector(s): *John F. Wilson*
 Receiving Waters: *Warren County*
 W.Q. Classification: *GA*
 Weather Condition: *Clear & Cold*

Company Representative(s), Title (s):

John Kelley - Plant Chemist

Number of Discharges Reported: *1*

Number of Discharges Observed: *1*

Action Taken or Planned on Unreported Discharges:

(1) PROCESS

- (a) Industrial Process: *Plating*
 (b) Reported Production:
 (c) Current Production
 (d) Rated Production:
 (e) Raw Materials Used: *Plating solutions*
 (f) What process modification, expansions, etc. have been made that would either increase or decrease raw waste loads, water usage, etc. that have not been previously reported:
at time of inspection no plating being done - no work in shop
 (g) Industrial process flow diagram indicating wastewater sources (attach copy if on file and verify with company):
on file
 (h) Continuity of Operation: ✓ Batch Semi-Continuous
 Continuous

(2) EFFLUENT LIMITATIONS VIOLATIONS (Based upon Self-Monitoring Data)

| <u>Discharge</u> <u>No.</u> | <u>Parameter</u> | <u>Permit</u> <u>Limitation</u> | <u>Reported</u> <u>Discharge</u> | <u>Date/Period</u> <u>of Violation</u> |
|--------------------------------|------------------|------------------------------------|-------------------------------------|---|
|--------------------------------|------------------|------------------------------------|-------------------------------------|---|

92-15-1 (7/75)

Inspection & Statu
Permit No. 0070229

(2.1) EFFLUENT DISCHARGE NO. 001

- (a) Wastewater Flow: 7200 gpd
 (b) Measuring Device used for Flow: meter
 (c) Wastewater Characteristics: clear
 (d) Type of treatment units and treatment sequence sketch (attach copy if on file and verify with company): *Sanitary integrated system*

- (e) Appearance of Effluent(s):
- | | | | |
|----------------------|-------------|-------------|-------------|
| (1) visible oil | <i>None</i> | (5) color | <i>None</i> |
| (2) foam | <i>None</i> | (6) Temper- | |
| (3) floating solids | <i>None</i> | ature | |
| (4) Suspended Solids | <i>None</i> | (7) Odor | <i>None</i> |
| | | (8) other | |
- (f) Appearance of Receiving waters:
- | | | | |
|---------------------|--|-------------|--|
| (1) visible oil | | (6) color | |
| (2) foam | | (7) temper- | |
| (3) floating solids | | ature | |
| (4) turbidity | | (8) odor | |
| (5) sludge deposits | | (9) other | |

(2.2) EFFLUENT DISCHARGE NO.

Picture Taken:

- (a) Wastewater Flow:
 (b) Measuring Device used for Flow:
 (c) Wastewater Characteristics:
 (d) Type of treatment units and treatment sequence sketch (attach copy if on file and verify with company):

- (e) Appearance of Effluent(s):
- | | | | |
|----------------------|--|-------------|--|
| (1) visible oil | | (5) color | |
| (2) foam | | (6) temper- | |
| (3) floating solids | | ature | |
| (4) suspended solids | | (7) odor | |
| | | (8) other | |
- (f) Appearance of Receiving waters:
- | | | | |
|---------------------|--|-------------|--|
| (1) visible oil | | (6) color | |
| (2) foam | | (7) temper- | |
| (3) floating solids | | ature | |
| (4) turbidity | | (8) odor | |
| (5) sludge deposits | | (9) other | |

(2.3) EFFLUENT DISCHARGE NO.

- (a) Wastewater Flow:
 (b) Measuring Device used for Flow:
 (c) Wastewater Characteristics:
 (d) Type of treatment units and treatment sequence sketch (attach copy if on file and verify with company):

- (e) Appearance of Effluent(s):
- | | | | |
|----------------------|--|-------------|--|
| (1) visible oil | | (5) color | |
| (2) foam | | (6) temper- | |
| (3) floating solids | | ature | |
| (4) suspended solids | | (7) odor | |
| | | (8) other | |
- (f) Appearance of Receiving waters:
- | | | | |
|---------------------|--|-------------|--|
| (1) visible oil | | (6) color | |
| (2) foam | | (7) temper- | |
| (3) floating solids | | ature | |
| (4) turbidity | | (8) odor | |
| (5) sludge deposits | | (9) other | |

(3) COMPLIANCE

- (a) Is company complying with schedule of compliance? *NA*
- (b) What is the current projection of the company regarding compliance with future dates in Compliance Schedule?
- (c) Is company complying with any additional compliance requirements such as a special report submittal to the proper regulatory agency? *NA*
- (d) Has company notified the proper regulatory agency of any non-compliance with permit conditions? *No*
- *(e) Has company requested modification of any permit conditions other than permit sampling schedules? *No*
- *(f) Are any modifications appropriate? *NA*

(4) SELF-MONITORING PROGRAM

- (a) Does quantity of reported self-monitoring data and signing official comply with requirements of permit? *No* *see comment*
- (b) What is the apparent quality of plant records that are required under the conditions of the permit? *None*
- (c) If net values are applicable, is the surface water intake sampled and analyzed? *NA*
- (d) Is there any additional monitoring being performed by the plant that has not been reported? *No* If yes, what parameters and frequency is involved and what conclusions can be drawn from data?
- (e) Do sampling locations appear to be adequate to obtain representative samples? *yes*
- (f) Has company identified effluent sampling point used for each discharge pipe by providing a sketch of flow diagram?
- (g) How frequently and accurately is continuous monitoring equipment calibrated, and how well is the equipment maintained?

- (h) In your judgement, do sampling procedures, frequency and type of sample typify plant's daily discharge (i.e. are maximum production periods, batch discharges, etc. reflected in monitoring data)? *Yes*
- (i) Does plant perform its own analysis? *Yes*
 If not, what laboratory is analysis contracted to?
 If yes, what is the appearance of plant's laboratory?
Laboratory need cleaning - condition poor
- (j) Do all sampling and analytical methods conform to the guidelines published pursuant to Section 304(g) of 1972 FWPCA? *Yes*
- (k) Has plant requested modification to permit sampling schedules?
Yes - Permit Modified - 11-15-77
- (l) Are modifications appropriated?
Yes

(5) MISCELLANEOUS

- (a) Did the permit application truly represent conditions at the plant site? *Yes*
- (b) Are any of the following toxic pollutants or compounds containing them, being discharged that would require modification of the permit: No X Yes _____ (Check those Applicable)

Aldrin _____
 Dieldren _____
 Benzidine _____
 Cadmium _____
 Cyanide _____
 DDD (TDE) _____

DDE _____
 DDT _____
 Endrin _____
 Mercury _____
 Polychlorinated biphenyls _____
 Toxaphene _____

If yes, what modifications are necessary?

- (c) Is sludge being generated at plant? *Yes*
 If yes, is plant reporting on its disposal? *Yes*
 If sludge disposal is at plant site, is there any visual evidence or hazards associated with entry of pollutants into surface or ground waters? *No*
 If not at plant, where is the disposal site, and is it acceptable to regulatory agencies? *Sludge hauled away by New Stone Chemical Waste Hauler*
- (d) What is the appearance of plant grounds?
Poor

-
- (e) Is there any discharge of unreported contaminated storm runoff?
No
- (f) Is the treatment system maintained in good working order and operated efficiently? *No*
- (g) What alternate power supply provisions exist for waste treatment facilities? *None*
If none, what happens to the wastewater when there is a power failure? *generators, diesel*
- (h) Have all bypasses of waste treatment facilities been eliminated? *yes*
If not, why? If not, is flow monitoring installed in bypass?
- (i) Are there any obvious air emission, noise, radiation, pesticides, or solid wastes problems at the plant? *No*
What are they?
If yes, send copy of this report to the appropriate personnel.
- (j) Does plant require a Spill Prevention Control Countermeasure Plan? *No*
NOTE: SPCC plan is required if the permittee stores more than;
1. 1,320 gallons of oil above ground;
2. 660 gallons of oil in a single container above ground;
3. 42,000 gallons of oil underground.

If so, is the plant approved by a licensed P.E.?

SUMMARY AND RECOMMENDATIONSViolations and/or ProblemsRecommended Action

1. testing for Cadmium not being accomplished
2. operation reports not filed for Nov 1977
3. treatment facilities not in good condition.

None

Comments

1. General condition of entire plant are poor.
2. Plant ceased operations in August 1976 returned to operation November '77.
3. Suggested entire shop and stacking area be cleaned and maintained properly.

Inspector Signature: John F. WeisichName: John F. WeisichTitle: SANITARIAN IIDate: 1-16-78

NYS. INDUSTRIAL INSPECTION
AND
STATUS REPORT FORM

92-15-1 (7/75)

Inspection & State
Permit No.

NY0076244

(2.1) EFFLUENT DISCHARGE NO. 001

- (a) Wastewater Flow: 13,500 gpd
(b) Measuring Device used for Flow: Flow Meter
(c) Wastewater Characteristics:
(d) Type of treatment units and treatment sequence sketch (attach copy if on file and verify with company):
Lancy System

- | | | | | |
|-------------------------------------|---------------------|----|-------------|------|
| (e) Appearance of Effluent(s): | (1) visible oil | NO | (5) color | NONE |
| | (2) foam | NO | (6) Temper- | |
| | (3) floating solids | NO | ature | NA |
| | (4) Suspended | | (7) Odor | NONE |
| | Solids | NO | (8) other | |
| (f) Appearance of Receiving waters: | (1) visible oil | | (6) color | |
| | (2) foam | | (7) temper- | |
| | (3) floating solids | | ature | |
| | (4) turbidity | | (8) odor | |
| | (5) sludge deposits | | (9) other | |

(2.2) EFFLUENT DISCHARGE NO. 002

Sanitary-Sewage Picture Taken:

- (a) Wastewater Flow:
(b) Measuring Device used for Flow:
(c) Wastewater Characteristics:
(d) Type of treatment units and treatment sequence sketch (attach copy if on file and verify with company):

- | | | | | |
|-------------------------------------|---------------------|--|-------------|--|
| (e) Appearance of Effluent(s): | (1) visible oil | | (5) color | |
| | (2) foam | | (6) temper- | |
| | (3) floating solids | | ature | |
| | (4) suspended | | (7) odor | |
| | solids | | (8) other | |
| (f) Appearance of Receiving waters: | (1) visible oil | | (6) color | |
| | (2) foam | | (7) temper- | |
| | (3) floating solids | | ature | |
| | (4) turbidity | | (8) odor | |
| | (5) sludge deposits | | (9) other | |

(2.3) EFFLUENT DISCHARGE NO.

- (a) Wastewater Flow:
(b) Measuring Device used for Flow:
(c) Wastewater Characteristics:
(d) Type of treatment units and treatment sequence sketch (attach copy if on file and verify with company):

- | | | | | |
|-------------------------------------|---------------------|--|-------------|--|
| (e) Appearance of Effluent(s): | (1) visible oil | | (5) color | |
| | (2) foam | | (6) temper- | |
| | (3) floating solids | | ature | |
| | (4) suspended | | (7) odor | |
| | solids | | (8) other | |
| (f) Appearance of Receiving waters: | (1) visible oil | | (6) color | |
| | (2) foam | | (7) temper- | |
| | (3) floating solids | | ature | |
| | (4) turbidity | | (8) odor | |
| | (5) sludge deposits | | (9) other | |

(3) COMPLIANCE

- (a) Is company complying with schedule of compliance? NA
- (b) What is the current projection of the company regarding compliance with future dates in Compliance Schedule? NA
- (c) Is company complying with any additional compliance requirements such as a special report submittal to the proper regulatory agency? NA
- (d) Has company notified the proper regulatory agency of any non-compliance with permit conditions? NA
- *(e) Has company requested modification of any permit conditions other than permit sampling schedules? NO
- *(f) Are any modifications appropriate? NO

(4) SELF-MONITORING PROGRAM

- (a) Does quantity of reported self-monitoring data and signing official comply with requirements of permit? YES
- (b) What is the apparent quality of plant records that are required under the conditions of the permit? NOT AVAILABLE
- (c) If net values are applicable, is the surface water intake sampled and analyzed? NA
- (d) Is there any additional monitoring being performed by the plant that has not been reported? If yes, what parameters and frequency is involved and what conclusions can be drawn from data? NA
- (e) Do sampling locations appear to be adequate to obtain representative samples? YES
- (f) Has company identified effluent sampling point used for each discharge pipe by providing a sketch of flow diagram? YES
- (g) How frequently and accurately is continuous monitoring equipment calibrated, and how well is the equipment maintained?

NA

- (h) In your judgement, do sampling procedures, frequency and type of sample typify plant's daily discharge (i.e. are maximum production periods, batch discharges, etc. reflected in monitoring data)? NO - CD-Testing not being done.
- (i) Does plant perform its own analysis? YES
If not, what laboratory is analysis contracted to?
If yes, what is the appearance of plant's laboratory?
- (j) Do all sampling and analytical methods conform to the guidelines published pursuant to Section 304(g) of 1972 FWPCA? YES
- (k) Has plant requested modification to permit sampling schedules? NO
- (l) Are modifications appropriated?

(5) NO
MISCELLANEOUS

- (a) Did the permit application truly represent conditions at the plant site? YES
- (b) Are any of the following toxic pollutants or compounds containing them, being discharged that would require modification of the permit: No X Yes _____ (Check those Applicable)

| | | | |
|-----------|-------|---------------------------|-------|
| Aldrin | _____ | DDE | _____ |
| Dieldren | _____ | DDT | _____ |
| Benzidine | _____ | Endrin | _____ |
| Cadmium | _____ | Mercury | _____ |
| Cyanide | _____ | Polychlorinated biphenyls | _____ |
| DDD (TDE) | _____ | Toxaphane | _____ |

If yes, what modifications are necessary?

- (c) Is sludge being generated at plant? YES
If yes, is plant reporting on its disposal? NO
If sludge disposal is at plant site, is there any visual evidence or hazards associated with entry of pollutants into surface or ground waters? NO
If not at plant, where is the disposal site, and is it acceptable to regulatory agencies? NONE REMOVED
- (d) What is the appearance of plant grounds? POOR

- (e) Is there any discharge of unreported contaminated storm runoff?
NO
- (f) Is the treatment system maintained in good working order and operated efficiently? NO
- (g) What alternate power supply provisions exist for waste treatment facilities? NO
If none, what happens to the wastewater when there is a power failure? Plant Shuts Down
- (h) Have all bypasses of waste treatment facilities been eliminated? YES
If not, why? If not, is flow monitoring installed in bypass?
- (i) Are there any obvious air emission, noise, radiation, pesticides, or solid wastes problems at the plant? NO
What are they?
If yes, send copy of this report to the appropriate personnel.
- (j) Does plant require a Spill Prevention Control Countermeasure Plan? NA
NOTE: SPCC plan is required if the permittee stores more than;
1. 1,320 gallons of oil above ground;
2. 660 gallons of oil in a single container above ground;
3. 42,000 gallons of oil underground.

If so, is the plant approved by a licensed P.E.?

SUMMARY AND RECOMMENDATIONS

| <u>Violations and/or Problems</u> | <u>Recommended Action</u> |
|---|---------------------------|
| 1). Permit not available at time of inspection. | |
| 2). Operating records not available. | |
| 3). Plant grounds not clean. | |
| 4). General housekeeping poor. | |
| 5). Treatment area & facilities kept poorly. | |
| 6). Testing for Cadmium not being performed. | |

Comments

General condition of plant unsatisfactory.

Inspector Signature: _____

Name: John F. Welsch

Title: Chief Industrial Programs

Date: 10/21/75

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM

APPLICATION FOR PERMIT TO DISCHARGE - SHORT FORM C

To be filed only by persons engaged in manufacturing and mining

Do not attempt to complete this form before reading accompanying instructions

Please print or type

1. Name, address, location, and telephone number of facility producing discharge

A. Name Metallurgical Processing Corp.

B. Mailing address

1. Street address 180 Michael Drive

2. Post Office Syosset

3. State New York

4. County Nassau

5. ZIP 11791

C. Location:

1. Street same as above

2. (C, T, V) _____

3. County _____

4. State _____

D. Telephone No. 516 / 921-6800

Area
Code

2. SIC

| | | | |
|--|--|--|--|
| | | | |
|--|--|--|--|

(Leave Blank)

3. Number of employees 66

If all your waste is discharged to a publicly owned waste treatment facility and to the best of your knowledge you are not required to obtain a discharge permit, proceed to item 4. Otherwise proceed directly to item 5.

9. (a) Check here if discharge occurs all year ☒ , or

(b) Check the month(s) discharge occurs:

1. ☐ January 2. ☐ February 3. ☐ March 4. ☐ April 5. ☐ May
6. ☐ June 7. ☐ July 8. ☐ August 9. ☐ September 10. ☐ October
11. ☐ November 12. ☐ December

(c) Check how many days per week:

1. ☐ 1 2. ☐ 2-3 3. ☒ 4-5 4. ☐ 6-7

10. Types of waste water discharged to surface waters only (check as applicable)

| Discharge per operating day | Flow, gallons per operating day | | | | | Volume treated before discharging (percent) | | | | |
|--|---------------------------------|------------------|------------------|----------------------|------------------------|---|-----------------|----------------|----------------|----------------|
| | 0.1-999 (1) | 1000-4999 (2) | 5000-9999 (3) | 10,000-49,999 (4) | 50,000- or more (5) | None (6) | 0.1-29.9 (7) | 30-64.9 (8) | 65-94.9 (9) | 95-100 (10) |
| A. Sanitary, daily average | | | | | | | | | | |
| B. Cooling water, etc. daily average | | | | | | | | | | |
| C. Process water, daily average | | | | X | | | | | | X |
| D. Maximum per operating day for total discharge (all types) | | | | | | | | | | |

11. If any of the three types of waste identified in item 10, either treated or untreated, are discharged to places other than surface waters, check below as applicable.

| Waste water is discharged to: | Average flow, gallons per operating day | | | | |
|-------------------------------------|---|------------------|------------------|----------------------|-----------------------|
| | 0.1-999 (1) | 1000-4999 (2) | 5000-9999 (3) | 10,000-49,999 (4) | 50,000 or more (5) |
| A. Municipal sewer system | | | | | |
| B. Underground well | | | | | |
| C. Septic tank | | | | | |
| D. Evaporation lagoon or pond | | | | | |
| E. Other, specify Leaching pools | | | | X | |

APPLICATION FORM "C" FOR A STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM (SPDES) PERMIT
INDUSTRIAL OR MINING

| | |
|--|--|
| 1. APPLICANT DATA | |
| APPLICATION TYPE <input checked="" type="checkbox"/> New <input type="checkbox"/> Renewal <input checked="" type="checkbox"/> Modification | IF RENEWAL OR MODIFICATION, GIVE PREVIOUS APPLICATION NO., EFFECTIVE DATE, EXPIRATION DATE No. <u>NY-0076244</u> Effective Date <u>APRIL 17, 1979</u> Expiration Date <u>APRIL 17, 1981</u> |
| OWNER'S NAME (Corporate, Partnership or Individual) <u>METALLURGICAL PROCESSING CORP.</u> | TYPE OF OWNERSHIP <input checked="" type="checkbox"/> Corporate <input type="checkbox"/> Individual <input type="checkbox"/> Partnership <input type="checkbox"/> Public |
| OWNER'S MAILING ADDRESS (Street, City, State, Zip Code) <u>180 MICHAEL DRIVE, SYOSSET, NY 11791</u> | |
| REFER ALL CORRESPONDENCE TO: (Name, Title and Address) <u>WILLIAMS FOSTER, FINISHING SUPT.</u> | TELEPHONE NO. (Include Area Code) <u>516</u> <u>921-6800</u> |
| FACILITY NAME <u>SAME</u> | FACILITY LOCATION (Street or Road) <u>NASSAU</u> |
| CITY, TOWN OR VILLAGE <u>SYOSSET</u> | NO. OF EMPLOYEES <u>50</u> |
| NATURE OF BUSINESS OR TYPE OF FACILITY <u>PLATE TREATING & PLATING</u> | NO. OF SHIFTS <u>3</u> |
| 2. IF ALL YOUR WASTE IS DISCHARGED TO A PUBLICLY OWNED WASTE TREATMENT FACILITY AND/OR A LICENSED WASTE SCAVENGER AND TO THE BEST OF YOUR KNOWLEDGE YOU ARE NOT REQUIRED TO OBTAIN AN SPDES PERMIT, COMPLETE THIS SECTION ONLY, SIGN APPLICATION AND RETURN. AND/OR NAME AND ADDRESS OF MUNICIPALITY RESPONSIBLE FOR RECEIVING WASTE _____ NAME AND ADDRESS OF LICENSED WASTE SCAVENGER _____ | |
| 3. PRODUCTION DATA (Use additional forms, if necessary) PRINCIPAL TYPES OF PROCESSING DONE AT THIS FACILITY <u>HEAT TREATING)</u> <u>PLATING)</u> <u>JOB SHOP</u> | |
| PRINCIPAL PRODUCTS AND AMOUNTS PRODUCED PER TIME UNIT | RAW MATERIALS AND AMOUNTS CONSUMED PER TIME UNIT |
| 1. | 1. |
| 2. | 2. |
| 3. | 3. |
| 4. | 4. |
| 5. | 5. |
| 4. DOES ANY OF YOUR DISCHARGES CONTAIN OR IS IT POSSIBLE FOR ANY DISCHARGE TO CONTAIN ONE OR MORE OF THE FOLLOWING SUBSTANCES ADDED AS A RESULT OF YOUR OPERATIONS, ACTIVITIES OR PROCESSES? | |
| <input type="checkbox"/> Aluminum <input type="checkbox"/> Arsenic <input type="checkbox"/> Boron <input checked="" type="checkbox"/> Chromium <input checked="" type="checkbox"/> Fluorides <input type="checkbox"/> Lead <input checked="" type="checkbox"/> Nickel <input type="checkbox"/> Selenium <input checked="" type="checkbox"/> Tin <input type="checkbox"/> Ammonia <input type="checkbox"/> Barium <input checked="" type="checkbox"/> Cadmium <input checked="" type="checkbox"/> Copper <input type="checkbox"/> Gold <input type="checkbox"/> Manganese <input type="checkbox"/> Oil & Grease <input type="checkbox"/> Silver <input checked="" type="checkbox"/> Zinc <input type="checkbox"/> Antimony <input type="checkbox"/> Beryllium <input checked="" type="checkbox"/> Chlorine <input checked="" type="checkbox"/> Cyanide <input checked="" type="checkbox"/> Iron <input type="checkbox"/> Mercury <input type="checkbox"/> Phenols <input checked="" type="checkbox"/> Sulfides <input type="checkbox"/> Corrosion control chemicals (specify) _____ <input type="checkbox"/> Halogenated organics or halogenated hydrocarbons (e.g. chlorinated, fluorinated or brominated) (specify) _____ <input type="checkbox"/> Herbicides or pesticides (specify) _____ <input type="checkbox"/> Radioactivity (specify) _____ <input type="checkbox"/> Slimeicides, biocides or algacides (specify) _____ <input type="checkbox"/> Substituted aromatics (e.g. derivatives of benzene, pyridene, biphenyl, naphthalene, coal or petroleum tar, etc.) (specify) _____ <input type="checkbox"/> Surfactants (specify) _____ <input type="checkbox"/> None of the above | |
| Specify the trade names and manufacturer of any chemicals used at this facility which are not listed above and whose specific constituents are not known to you. _____ | |
| Explanation of above: (Attach additional sheets, if necessary) _____ | |



INDUSTRIAL CHEMICAL SURVEY
BUREAU OF WATER POLLUTION CONTROL

Nassau County Department of Health
240 Old Country Road, Mineola, N.Y. 11501

Tel. 535-2404

Part I

| | | | |
|--|--------------------------------|--|----------|
| Company Name Metallurgical Processing Corp. | | SIC (if known) Code | |
| Company Mailing Address 180 Michael Drive Syosset, New York | | Zip 11791 | |
| Plant Name (if different) | Contact Name John Kelly | Tel. 516 921-6800 | |
| Plant Address same | Village | Water Distr. | Code Zip |
| Principal Business of Plant Heat Treating & Plating | | No. Employees at this Facility 50 | |

Part II

COMPLETE LIST OF CHEMICALS USED (See attached)

PART III - DISCHARGE INFORMATION

| | | | | | | | | | | |
|--|--|--|---|-----------------------------|------------------------------|-----------------------------|------------------------------|-----------------------------|--|--|
| WATER | 1. Does your plant discharge liquid wastes to a municipally owned sanitary sewer system? If yes, name of system: | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | | | | | |
| | 2. Is your facility permitted to discharge liquid wastes under a State (SPDES) or Federal (NPDES) permit? If yes, enter Permit No. | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No N.Y. 0 0 7 6 2 4 4 | | | | | | | | |
| | 3. Do you discharge liquid industrial wastes in any other manner? If yes, explain: | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | | | | | |
| | 4. If any of the above are yes: a. Do you discharge process or chemical wastes, i.e., water used in manufacturing, including direct contact cooling water and scrubber water? b. Do you discharge non-contact cooling water? c. Do you discharge sanitary wastes? | <table border="0"><tr><td><input type="checkbox"/> Yes</td><td><input type="checkbox"/> No</td></tr><tr><td><input type="checkbox"/> Yes</td><td><input type="checkbox"/> No</td></tr><tr><td><input type="checkbox"/> Yes</td><td><input type="checkbox"/> No</td></tr></table> | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input type="checkbox"/> Yes | <input type="checkbox"/> No | <input type="checkbox"/> Yes | <input type="checkbox"/> No | | |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | | | | | | | | | |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | | | | | | | | | |
| <input type="checkbox"/> Yes | <input type="checkbox"/> No | | | | | | | | | |
| AIR | 1. Does your facility have sources of possible emissions to the atmosphere? | <input type="checkbox"/> Yes <input type="checkbox"/> No | | | | | | | | |
| | 2. Enter location and facility code as shown on your Air Pollution Control Application for Permits & Certification (if applicable) | <table border="1"><tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr></table> | | | | | | | | |
| | | | | | | | | | | |
| 3. Heating System <input type="checkbox"/> None <input type="checkbox"/> Boiler <input type="checkbox"/> Space Heater | Type of Fuel <input type="checkbox"/> Electric <input type="checkbox"/> Gas <input type="checkbox"/> Oil | Incinerator <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | | | | | |
| SOLID & CONCENTRATED LIQUID WASTES | 1. List name and address of firm (incl. yourself) removing wastes other than office and cafeteria refuse (industrial scavenger) | | | | | | | | | |
| | Name Thomas Patterson, Inc. | Name | | | | | | | | |
| | Address | Address | | | | | | | | |
| PEST | 2. List location(s) of landfills owned and used by your Facility | Active Inactive | | | | | | | | |
| | a. <table border="1"><tr><td> </td></tr></table> | | <table border="1"><tr><td> </td></tr></table> | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | b. <table border="1"><tr><td> </td></tr></table> | | <table border="1"><tr><td> </td></tr></table> | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | Does this facility manufacture, produce, formulate or repackage pesticides? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | | | | | | |
| Signature (owner, partner, or officer) <i>Louis Perlman</i> | | Date 8/30/77 | | | | | | | | |
| Name (printed or typed) Louis Perlman | | Title President | | | | | | | | |
| Inspector's Name | | Date of Inspection | | | | | | | | |

PART II - CHEMICALS USED (include gases and oils)

INSTRUCTIONS: Complete all information for those chemicals your facility has used, stored, distributed, or otherwise disposed of since January 1, 1977.
Do not include chemicals used only in analytical laboratory work.

| Name of Chemical/Trade Name, Supplier and Address | Code | Avg Annual Usage | Gal | Lbs | Use of Chemical | Final Disposition of Chemical |
|---|--------------|------------------|-----|-----|-----------------|-------------------------------|
| SODIUM BISULFITE ALLIED CHEM | | 100 | | ✓ | WASTE-DISPOSAL | |
| AUSTIC POTASH DIAMOND SHAMROCK | | 150 | | ✓ | " PLATING | |
| LIT CHLOR PPG | | 200 | | ✓ | WASTE-DISPOSAL | |
| AUSTIC SODA | | 750 | ✓ | | " PLATING | |
| SULPHURIC ACID | | 75 | ✓ | | " " | |
| DAKITE #164 | | 250 | | ✓ | CLEANING | |
| ENBAND- 408 | | 1000 | | ✓ | " | |
| ENTHON- 980 | | 75 | | ✓ | PLATING | |
| " 983 | | 75 | | ✓ | " | |
| " 985 | ENTHONE CHEM | 75 | ✓ | | " | |
| FLUMON'D | | 50 | ✓ | | " | |
| ENPLATE 415 B | | 150 | ✓ | | " | |
| " 415 C | | 150 | ✓ | | " | |
| ENSTRIP C | | 1200 | | ✓ | METAL STRIP | |
| ACTANE 70 | | 100 | | ✓ | CLEANING | |
| AMMONIUM NITRATE | | 100 | | ✓ | PLATING | |
| NITRIC ACID | | 150 | ✓ | | " | |
| HYDROCHLORIC ACID | | 750 | ✓ | | " | |
| SODIUM CYANIDE | | 400 | | ✓ | " | |
| POTASSIUM CYANIDE | | 300 | | ✓ | " | |
| COPPER CYANIDE | | 300 | | ✓ | " | |

RECOMMENDED ACTION

FOR
OFFICE
USE
ONLY

- 2 ☐ Immediate Abatement
3 ☐ Sample
4 ☐ SPDES Application

- 5 ☐ Refer To: _____
6 ☐ Re-inspection
7 ☐ No Action

9 ☐ Other (specify)

INSTRUCTIONS: Complete all information for those chemicals your facility has used, stored, distributed, or otherwise disposed of since January 1, 1977. Do not include chemicals used only in analytical laboratory work.

[illegible]

RECOMMENDED ACTION

**FOR
OFFICE
USE
ONLY**

- 2 ☐ Immediate Abatement
3 ☐ Sample
4 ☐ SPDES Application

- 5 ☐ Refer To: _____
6 ☐ Re-Inspection
7 ☐ No Action

9. ☐ Other (specify)

84



New York State Department of Environmental Conservation
Albany, N Y 12201
Division of Pure Waters

Henry L. Diamond
Commissioner

September 15, 1971

Mr. J. J. Martin, Jr., P.E.
60 Connoily Parkway
Hamden, Connecticut 06514

Re: Metallurgical Processing Corp.
Oyster Bay (T), Nassau County

Dear Mr. Martin:

Your final report has been received from the Nassau County Department of Health with the notation that the facility has been constructed and is in operation at the present time. This is not in accordance with the State law and permits for construction must be referred to this office.

In reviewing the report and plans, some of the data is either missing or needs clarification.

1. Manufacturing details (raw materials, processes products) have not been given. These must be defined sufficiently to judge the probable wastes.
2. In the various cleaning processes the solutions and contamination involved have not been given. Any oils must be treated and removed if State specifications are exceeded. This is not shown.
3. The passivation solution is not described.
4. There are no analyses of present effluents given.

5. Your treatment for Cadmium is not completely defined. It also is vague and contradictory. On the print sodium sulfide is shown. In the write-up, it is described as sodium sulfate (pg.3). It is listed as a catalyst, which is probably not its function. Clarification is required.
6. There are no instructions given for Cadmium treatment.
7. The stripping aid is not characterized.
8. The prints are not clear on the curbing detail. If curbs around acid tanks do not separate from spills contained by the curbing around the tanks containing cyanide solutions, possibility of acidification of spills or leaks containing cyanide present a problem of possible generation of lethal cyanide gases. This point needs clarifying.
9. Automatic high level alarms are not shown, but there are provisions for emergency overflows from treatment Tank "A" (cyanide) to clarifier and from Tank "B" (chromium) to the rinse water neutralization tank. This is not satisfactory as it permits untreated material to flow to discharge with no treatment, but neutralization. If high level alarms and solenoid water or flow shut-off valves in case of power failure are not sufficient, then emergency reservoirs should be provided from which material can be returned through proper treatment equipment.
10. Solenoid valves on rinse water and in the case of gravity flows on treatment reservoirs should be provided to shut-off automatically in case of power failure. Such devices go a long way in the prevention of overflows.
11. From the prints, it could not be determined if duplicate pumps were provided in critical areas such as circulation through treatment reservoirs. Without them, the temptation to operate without proper treatment is too great in case of pump breakdown.

12. In some of the treatment tanks, acid treatment may have copper if parts treated are of copper or brass. If this is the case, then cuprous copper could be precipitated in the acid neutralization as well as in the alkaline cyanide treatment. This would give the undesirable gelatinous precipitate described, giving clarification problems and plugging of the leaching tanks. Further definition is required as well as a separate copper treatment system if needed.
13. There is no plot plan indicating location and distance to any private wells in the vicinity.
14. Basis of design for leaching pits should be given.

Any plans to be approved, must be sufficiently complete and detailed so that these points can be ascertained. There must be enough description of the system (source and character of waste) to assure that controls proposed are appropriate.

The high zinc content reported by Nassau County is also a matter of concern. If the passivation is zinc phosphate, then analyses for zinc and phosphates should be given.


Very truly yours,

Thomas E. Quinn, P.E., Chief
Industrial Facility Section

TEQ/NAC:sp

cc: Ronkonkoma Region
cc: Metallurgical Processing Corp.

Lancy



LABORATORIES, INC.

METAL FINISHING AND WASTE TREATMENT ENGINEERS

Ync 7/3/69
REPLY TO:
JOHN J. MARTIN JR., VICE PRESIDENT
60 CONNOLLY PARKWAY
HAMDEN, CONN. 06514
PHONE: AREA 203-248-2550
203-248-3353

P. O. BOX 98, ZELIENOPLE, PA. 16063
PHONE: AREA 412 452-9360

July 2, 1969

Department of Health
Nassau County
Mineola, New York

Attention: Mr. Welsch

Ref: Metallurgical Processing Corporation

Dear Mr. Welsch:

On May 15th, and on June 2nd, we wrote to you concerning our activities at the subject account. We recognize that we are to resubmit plans and specifications for your review as soon as we feel confident that we have the effluent within the standards of Nassau County.

Our laboratory received samples taken on May 28th and another sample, both of which were received at Zelienople on June 6th. In both samples, which was the effluent from the settling tank, the pH was 9.75/9.80, suspended solids 11.42/9.67 ppm, cadmium, nickel, copper, cyanide, none detected.

A sample dated June 11th, indicated pH 9.95, cadmium .02, nickel none, copper .28, CN .4, suspended solids 17.1. We do not understand the cyanide indication and we are advised that the sample, analyzed by your department, indicated 1.2 cadmium. We are naturally disappointed in this cyanide trace, and also in the discrepancy between your analysis and ours.

Lancy LABORATORIES, INC.

Department of Health

-2-


July 2, 1969

Our chief chemist, Mr. Fred Stevens, will be at Metallurgical Processing on July 8th & 9th, and we would appreciate a meeting of you and your chemist with him either at Metallurgical Processing or at your office during this period. We would hope to resolve the discrepancies in analysis that seem to plague us and to establish if any additional work is required to insure that the effluent meets your standards.

As soon as we can establish a firm basis we plan to resubmit the plans and reports for your review. We appreciate your continued cooperation, and hope that with you we can provide a suitable effluent from this waste treatment system.

Yours very truly,

LANCY LABORATORIES, INC.


John J. Martin, Jr. P.E.
Vice President

JJM:jd1

c.c. Mr. Peerlman
Metallurgical Processing Corp.
Mr. G. Hill
Fisher & Porter



April 17, 1969

Nassau County Department of Health
240 Old Country Road
Mineola, New York 11501

Attention: Mr. John F. Welsch, Supervisor Industrial Waste,
Bureau of Water Pollution Control

Gentlemen:

We are herewith submitting a report regarding the progress toward the successful operation of our waste treatment system.

On 28 March past, we received the enclosed letter from the Fischer & Porter Company summarizing their findings to that date. We have taken the following action relative to their recommendations:

1. We have eliminated the described nitric acid tanks from our process.
2. We have arranged to have our settling tank drained and cleaned.


As a result of these operations, we feel confident that we can meet the proper standards of operation. We intend to sample our effluent on April 23rd and send same to Lancy laboratories. We will withdraw a quantity sufficient to satisfy Lancy Laboratories. We will, at the same time, withdraw an additional sample for your use - if you so choose. We realize that official samples must be taken by your people but it is sometimes difficult to coordinate our efforts and Lancy Labs requires their sample by the end of next week.

If you cannot use the sample withdrawn by us, we respectfully request that you make arrangements for your own sampling on April 23rd or shortly thereafter.

We are making every effort to achieve the required effluent composition. Our consultants feel quite confident in their present endeavors. We welcome any suggestions you might have for the improvement of our process.

Very truly yours,

METALLURGICAL PROCESSING CORP.

A handwritten signature in dark ink, appearing to read "Burton Z. Chertok", with a stylized flourish at the end.

Burton Z. Chertok
Vice President

BZC:pas

Encosure



LESLIE E. LANCY, PH.D., PRESIDENT
FRANK J. KENNEDY, VICE PRESIDENT
ROBERT L. RICE, P.E., VICE PRESIDENT

LABORATORIES, INC.

METAL FINISHING AND WASTE TREATMENT ENGINEERS

P. O. BOX 98, ZELIENOPLE, PA. 16063
PHONE: AREA CODE 412-452-9360

October 15, 1968

Metallurgical Processing Corp.
180 Michael Drive
Syosset, New York 11791

Attention: Mr. B. Z. Chertok

Dear Mr. Chertok:

Attached is our analysis report on your waste effluent taken October 8th and received by us October 10th. We have analyzed for both soluble and total metals in the sample and pH.

The sample is quite cloudy and slow settling. As we have discussed with you on the telephone, this can be caused by wet tumbling waste water being discharged to your final settling tank.

Our Mr. John Martin will be advising you on our recommendations for improving your waste treatment facilities to meet the Health Department requirements.

Very truly yours,

LANCY LABORATORIES, INC.

Fred Stevens,
Vice President

FS:vjv

cc: Mr. Welsch, Senior Sanitarian
Mr. John J. Martin, Jr.

Lancy LABORATORIES, INC.

Metallurgical Processing
Syosset, New York

Oct. 14, 1968

Effluent Rec. 10/11/68 (Sampled 10/8/68)

| | | |
|--------------------------------|---|----------|
| pH | = | 9.0 |
| Hex. Chrome as CrO_3 | = | 0.08 ppm |
| Total Chrome as CrO_3 | = | 0.15 ppm |
| Soluble Copper | = | 0.01 ppm |
| Total Copper | = | 0.11 ppm |
| Soluble Cadmium | = | 0.94 ppm |
| Total Cadmium | = | 2.14 ppm |
| Soluble Nickel | = | 2.75 ppm |
| Total Nickel | = | 18.0 ppm |

SJ 11/20/67
JW 11/16/67

November 16, 1967

Metallurgical Processing Company
180 Michael Drive
Syosset, New York

Att: Mr. Burton Z. Chertok

Re: Industrial Waste Treatment
and Disposal System.

Gentlemen:

This office has reviewed the plans and reports submitted on your behalf by Mr. J. Martin, P.E. Plans have been reviewed and a conference was held on November 2, 1967 at which Mr. Martin was present together with representatives of this office. Further action on your plans and application for permit must await receipt of further information and or comments on the following:

1. The leaching system as shown on drawing MPC-01 cannot be approved by this office because of non-conformance with our standards. We understand from Mr. Martin that the system has been installed and upon request by your firm for approval of an "as built" leaching system we will consider same for a conditional approval. The areas of particular concern are;
 - a) The soils evaluation and leaching application of 8 gpd/sq.ft. which is stated in your letter of October 30, 1967.
 - b) The distance between the pools of 20' o-c does not conform with our requirements.
 - c) According to statements in your letter of October 30, 1967 the maximum number of pools that can be placed in this area is five (5). This raises serious questions as to the adequacy of the system and the availability of room for future expansion of the leaching system should it become necessary.

Metallurgical Processing Co.
Att: Mr. Burton Z. Chertok

- 2 -

November 16, 1967

2. Additional information is to be supplied to this office by Mr. Martin relative to the removal of cadmium and zinc from your waste effluent. Operating data from plants now treating waste waters for the removal of these metals should be submitted. ✓
3. Additional information is to be furnished on the chlorination equipment including the storage facilities of the one (1) ton containers and details on the chlorinating room itself. You are advised that the approval of the gas chlorination facilities as outlined to us by Mr. Martin may not conform with future departmental policy on storage and use of one (1) ton gas cylinders. The current practice in the chlorination field where large containers of chlorine gas are used, is to change to the liquid form to eliminate a hazardous situation to the surrounding community. NG
4. Mr. Martin has been informed of the effluent characteristics that must be met by your discharge. The table of expected chemical concentrations on page 2 of your report is to be revised in accordance with the information supplied to Mr. Martin.

The writer apologizes for the length of this letter and realizes that there may be questions concerning the statements herein. Please feel free to contact this office should the need arise. Further action on your plans will await receipt of the information requested.

Very truly yours,
For
Stanley Juczak, Jr., P.E.
Sr. Public Health Engineer
Water Pollution Control Section

JFW
By
John F. Welsch
Sr. Sanitarian

JFW:sk
cc: Mr. John Martin

30 October 1967

Lancey Laboratories, Inc.
60 Connolly Parkway
Hamden, Connecticut

Attention: Mr. John Martin

Gentlemen;

Per your request, we are herein submitting the background and design criteria for the leaching system shown on drawing MPC-G1.

Prior to the time of your involvement in this matter, the ground which would contain the leaching pools was in a partially excavated state due to other construction. Our architect, Mr. Robert Nelson, of Risso Nelson and Pope, from Huntington, New York, was consulted as to the necessary requirements for leaching systems. He contacted the Department of Health and was told that for pure water, containing no solids etc., a formula of eight (8) gallons per day per square foot of side wall area was applicable.

We then contacted Mr. Greer Hill of the Fischer and Porter Co., who were licensees of your company's patent rights and engaged in the design of the entire waste treatment system. He stated that with the installation of the system, as shown, with the necessary waste treatment reservoirs and chemical additives together with the 30,000 gallon capacity settling tank in series would give use to a drinking water equivalent exhausting to the leaching pools. Since the full plating plant will not operate on a 24 hour basis the 30,000 gallon output will have ample opportunity to settle any remaining solids in the tank. The clean effluent concept seems reasonable providing proper and adequate chemical treatment had previously taken place.

Metallurgical Processing Corp.

The maximum numbers of pools that could be placed in the area without interference with existing footings etc., was 5. The ground elevation in the area was 198 feet. Due to the fact that the waste treatment effluent exhausts from the building at an invert of 190.1, the entrance to the leaching system had to be even lower. The actual pool begins approximately 10 feet below the ground surface.

In the case of the Northernmost three (3) pools, we were successful in gaining a full 28 feet of useful depth (7 sections) which bottom out at almost 40 feet below the ground surface. The remaining two (2) pools are 24 feet deep due to difficulties encountered during the excavation. In all instances, man ways have been provided so that inspection can be made of each pool.

Our actual total wall footage, stemming from 132 running feet of 10 foot diameter sections is 4140 square feet. Since our water flow is 30,000 gallons per day, we have a wall loading of 7.25 gallons per square foot per day. A calculation stemming from 120 running feet of 10 foot diameter sections yields a wall loading of 8 gallons per square foot per day. This 120 foot figure based on five (5) pools at 24 feet each appeared on the Risso, Nelson & Pope drawing as minimally acceptable. We exceeded this figure wherever physically possible.

The piping to one pool and subsequent distribution was suggested to us as good practice both for dispersal of liquids and protection against possible connecting pipe failure. This, too, transpired after consultation with the architect.

Metallurgical Processing Corp.

We trust that the foregoing information answers your questions and that it meets with the approval of all cognizant parties.

**Very truly yours,
Metallurgical Processing Corp.**

Burton Z. Chertok

**Burton Z. Chertok
Vice President, Engineering**

**N. YORK STATE DEPARTMENT OF HEALTH...
DIVISION OF ENVIRONMENTAL HEALTH SERVICES
BUREAU OF WATER RESOURCE SERVICES**

APPLICATION for Approval of Plans and/or for Permit to Construct
and operate Waste Treatment Works and to Discharge Wastes into Waters of the State

| | | | | | | | | | | | | | | | |
|---|-----------------------------|---|-----------------------------|--|---------------------------|--|------|--|-----------------------------|-----------------|--------|---|------|------------|--|
| 1. Name of Board, Individual, Corporation or Office making application Metallurgical Processing Corp., Inc. | | 2. City, Village, Sewer District or establishment served by proposed works Corporations Plant located at 180 Michael Drive, Syosset, N.Y. | | 3. Date of Application September 13, 1967 | | | | | | | | | | | |
| 5. Check type of works <input type="checkbox"/> Municipal <input type="checkbox"/> Private (individual) <input type="checkbox"/> Private (other) <input type="checkbox"/> Institutional <input checked="" type="checkbox"/> Industrial Waste | | 6. Check type of project <input type="checkbox"/> Sewers <input type="checkbox"/> Pumping Station <input checked="" type="checkbox"/> Treatment Works <input type="checkbox"/> Additions or Alterations | | 4. County Nassau | | | | | | | | | | | |
| 8. Name of receiving watercourse, if surface waters: If subsurface, name of watercourse to which ground water is tributary Ground Water | | 9. Name of City, Village or Town in which point of discharge is located Syosset, N. Y. | | 7. Check type of discharge <input type="checkbox"/> Surface Water <input checked="" type="checkbox"/> Ground Water | | | | | | | | | | | |
| 11. Engineer's N.Y. State License Number 33734 Engineer's telephone number 203-248-2550 | | 12. For existing treatment works, give: <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">Present Average Daily Flow</td> <td style="width: 50%;">Design Average Daily Flow</td> </tr> <tr> <td style="text-align: center;">None</td> <td style="text-align: center;">----</td> </tr> </table> | | Present Average Daily Flow | Design Average Daily Flow | None | ---- | 13. Number of persons to be served <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">Present</td> <td style="width: 50%;">Future</td> </tr> <tr> <td style="text-align: center;">----</td> <td style="text-align: center;">----</td> </tr> <tr> <td colspan="2" style="text-align: right;">Year: A.D.</td> </tr> </table> | | Present | Future | ---- | ---- | Year: A.D. | |
| Present Average Daily Flow | Design Average Daily Flow | | | | | | | | | | | | | | |
| None | ---- | | | | | | | | | | | | | | |
| Present | Future | | | | | | | | | | | | | | |
| ---- | ---- | | | | | | | | | | | | | | |
| Year: A.D. | | | | | | | | | | | | | | | |
| 14. Water consumption in gallons per day <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">Present 50,000 GPD (95% for cooling H₂O)</td> <td style="width: 50%;">Future 80,000 GPD</td> </tr> <tr> <td colspan="2" style="text-align: right;">Year: 1970 A.D.</td> </tr> </table> | | Present 50,000 GPD (95% for cooling H₂O) | Future 80,000 GPD | Year: 1970 A.D. | | 15. For new works, give estimated sewage or waste flow in gallons per day <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">Present 0 <i>Proposed</i></td> <td style="width: 50%;">Future 30,000 GPD</td> </tr> <tr> <td colspan="2" style="text-align: right;">Year: 1970 A.D.</td> </tr> </table> | | Present 0 <i>Proposed</i> | Future 30,000 GPD | Year: 1970 A.D. | | 16. State how storm water is to be disposed of and cooling water Four existing leaching pools | | | |
| Present 50,000 GPD (95% for cooling H₂O) | Future 80,000 GPD | | | | | | | | | | | | | | |
| Year: 1970 A.D. | | | | | | | | | | | | | | | |
| Present 0 <i>Proposed</i> | Future 30,000 GPD | | | | | | | | | | | | | | |
| Year: 1970 A.D. | | | | | | | | | | | | | | | |
| 17. Source of water supply (If private well, give location; type; depth and character of soil) Jericho Water District | | | | 18. Give street location of proposed works or existing works 180 Michael Drive Syosset, N. Y. | | | | | | | | | | | |
| 19. Give number, character and distance of any buildings which may be affected by the proposed treatment works Proposed plant is located in an Industrial Park. Nearest adjacent industrial building is 100 feet away. No known private wells in this area. | | | | | | | | | | | | | | | |
| Additional information must be submitted for private and institutional systems. | | | | | | | | | | | | | | | |
| 20. Indicate on U.S.G.S. Topographic Map exact location of sewage treatment works and adjacent buildings. Show location of all wells or other sources of water supply within 200' of the proposed works. Give description of these sources and character of soil. See 19. | | | | | | | | | | | | | | | |
| State depth below existing ground surface at which ground water is encountered 100 feet | | 22. Describe soil at site of proposed works. Give design basis and observed soil percolation rate data (use additional sheet, if necessary) Sand and gravel. | | | | | | | | | | | | | |

ENGINEERING REPORT
ON
WASTE TREATMENT FACILITY
FOR
METALLURGICAL PROCESSING CORPORATION
SYOSSET, LONG ISLAND, NEW YORK

Prepared by: John J. Martin, Jr. P.E.
Vice President
60 Connolly Parkway
Hamden, Connecticut

Date: August 22, 1967

Revision 1., October 1, 1967

FEB 5 1971




TABLE OF CONTENTS

General

Anticipated Analysis of Effluent From Settling Basin

Treatment

Appendix:


Intermittent Cyanide Treatment System (Chlorine)

Intermittent Chromium Treatment System II

Acid-Alkali Neutralization-D

Test Procedures:

WCR-ST, WCR-HST, WCN-ST, WCN-CTSI, WCN-pH, WCN-CIP, WCR-HIP. ^{books (disposal)}




GENERAL

Metallurgical Processing Corporation, located in Syosset, Long Island, proposes to install a plating and metal finishing department incorporating a waste treatment facility which will produce an effluent having a quality to meet the standards of State of New York Department of Health, where discharge will be to underground leaching pools.

The various metal finishing operations involved include cleaning, acid dipping, plating, stripping, and the application of conversion coatings. Process water which is used in the metal finishing operations, without proper treatment, would produce an effluent containing cyanide, cadmium, zinc, copper, nickel and both trivalent and hexavalent chromium.

The proposed Waste Treatment System discussed herein will provide for two types discharge:


- a. Completely treated waters discharging to the leaching pools (~~diffusion wells~~).
- b. Inert sludges from the various treatment processes which will be periodically discharged to a chemical scavenger service truck.



ANALYZED ANALYSIS OF EFFLUENT FROM SETTLING BASIN

Cyanide.....less than 0.4 PPM
Chromium, hexavalent.....less than 0.1 PPM
Chromium, trivalent.....less than 0.5 PPM
Cadmium.....less than 0.02PPM
Copper.....less than 0.4 PPM
Zinc.....less than 0.5 PPM
Oil.....less than 10 PPM
Suspended solids.....Approx. 20 PPM
pH.....6.5 to 8.5
Temperature.....Ambient
Flowrate.....Approx. 65 GPM

Metallics are in soluble ppm.



TREATMENT

It is proposed to use an integrated waste treatment system for containment and elimination of toxics in the rinse waters and batch treatment for spent processing solutions. The treatment methods are as follows:

COPPER, CADMIUM AND CYANIDE

These would be introduced into the rinse water as drag-out on the work and carriers from the processing solutions. This will be eliminated by using recirculated chemical rinse station connected to a reservoir tank. This is the "Integrated Cyanide Treatment System", appended.

CHROMIUM

Hexavalent chromium in the rinse waters (from dragout on the work and work carriers) will be eliminated by using a chemical rinse after chromium solutions. This is the "Integrated Chromium II Treatment System", appended.

ACIDS AND ALKALIES

All spent acids and alkalies are collected in acid and alkali collecting tanks respectively and treated as batches.

Spent cyanide solutions are collected in the alkali collecting tank "D" and treated as a batch in the alkali collecting tank "D" with sodium hydroxide and sodium hypochlorite.

Spent chromate solutions are collected in the acid collecting tank "A" and treated as a batch with sodium bisulfite and then sodium hydroxide.

Floor spillage is collected in the alkali collecting tank "D" and treated with the batch wastes.

This is the Acid-Alkali Neutralization-D, appended. After treatment, the batches are transferred to tank "A", which could also be used for batch treatment, for settling and then decanting the supernatant to the rinse waters and, eventually, the sludges to a sludge holding tank for periodic scavenger disposal.

RINSE WATERS

All rinse waters are collected and led to a flash mixing sump where sodium hydroxide is automatically added with a pH Indicating-Controlling-Recording instrument which adjusts the pH to 6.5 - 8.5. After adjustment the rinse waters go to a large retention and clarifying tank and thence to leaching fields. A proportioning pump adds 2.2 gph of a stock solution of 6.6 oz/gal. of ferric sulfate and 1 oz/gal of sodium sulfate as a catalyst for the oxidation precipitation of traces of soluble cadmium.



TREATMENT cont'd

OTHER CONSIDERATIONS

1. Sludge Disposal


Periodic discharges of all spent treatment solutions and sludge bearing solutions will be taken by a chemical scavenger service. For this purpose, the services of Chemical Waste Disposal have been tentatively secured. They are located at P.O. Box 232, East Elmhurst, New York. All waste materials discharged by M.P.C. will be brought to Chemical Waste Disposal's New York plant for further treatment as may be required. All liabilities will be assumed by Chemical Waste Disposal after material leaves M.P.C. plant. The physical location of ultimate disposal is as yet undetermined.

2. Safety Operating Procedures

Fresh water additions to tanks containing toxic materials such as acid, alkali, plating solutions and bright dip solutions shall be made only by means of spring-loaded, hand-operated valve on hoses so that constant attendance will be insured and that accident over-flow of process tanks will be eliminated.

As far as automatic control instrumentation is concerned, due to the closed loop nature of the integrated treatment systems for cyanide and chromium, the need for such automatic controls is eliminated. One of the basic features of the integrated treatment system is the fact that proper operation of this closed loop type of system insures the continual presence of excess treatment chemicals. For this reason, it is known from many years of past experience that periodic checks on solution pH, residual chlorine, etc., are entirely adequate for the proper maintenance of controlled conditions. The same basic considerations also apply to the possible requirements for automatic control instrumentation on the batch treatment operations described herein.

Automatic control instrumentation is provided, however, for the measurement and control of the effluent rinse water pH. In that this is a continuous flow through part of the treatment system, it is essential that the effluent rinse water pH be controlled automatically. To this end, a pH recorder equipped with electrical contacts, as already previously described, will be utilized for the operation of the chemical feed pumps required for the neutralization of effluent rinse water. Additionally, as previously described, the same pH measuring instrument will provide for high and low pH conditions.




Safety Operating Procedures (cont'd)

An instrument panel board, which will contain the pH measuring equipment and the pH recorder with its various alarm switches, will also contain an alarm annunciator for visual and audible readout of high and low effluent rinse water pH conditions, as well as a low chlorine gas pressure condition which will indicate a shortage of chlorine gas in the cyanide destruction system. All of these alarms will serve to notify the operator of the waste treatment system that a condition must be corrected in order for the system to return to normal and these specific alarm condition to shut off.

3. Records and Reports

It is essential for proper operation of the waste treatment system that adequate records be kept of the chemical control of the integrated treatment solutions, as well as a record of the treatment of batch dumps. In this manner, repetitious operations can be simplified by comparing daily analyses with the history of operation. Keeping a record will also simplify supervision of the operation.

It is understood that periodic reports of the waste treatment system operation will be required by the state of New York Department of Health for their review and analysis. To this end, the appended sample records form under Appendix B is submitted as a suggested means of keeping satisfactory records. Additionally, daily chart records of the effluent rinse water pH will be available for review.



Acid-Alkali Neutralization - D

All spent acids are drained to an acid collecting tank where they are treated and neutralized as a batch. The capacity of the tank is such that once, or twice, per week a batch will require treatment.

When the tank is about 3/4 full the batch is tested for chromium as described under WCR-ST appended and pH with test paper.

- A. If no chromium is present add Caustic (or spent alkali) to increase pH to a range of 6 to 8. The sludge pump is used to mix the solution. After pH adjustment the batch can be pumped to the sludge bed.
- B. If chromium is present and pH is above 4, add caustic until pH 6 is reached and add sodium hydrosulfite until an excess of reducing agent is reached as determined by WCR-HST. The batch can then be pumped to the sludge bed.
- C. If chromium is present and pH is below 4, add sulfuric acid until pH range is 2 to 3. Then add sodium bisulfite until an excess is reached as per WCR-HST, appended. At this point add caustic to adjust pH to range 6 to 8 and pump to sludge bed.

50% liquid caustic is purchased in 55 gal. drums and transferred to the caustic storage tank. After pumping out a drum of caustic, the drum is filled with water and the contents also pumped to the storage tank. Thus, we have about a 25% caustic solution.

Spent alkalies, such as cleaners, are drained to an alkali collecting tank. This tank also collects any floor spills and is arranged so that there is always a 4" blanket of spent alkali in the bottom. When the tank is about 3/4 full the batch is tested for cyanide and chromium as per test procedures WCN-ST and WCR-ST appended.


- A. If cyanide is present, raise the pH to about 11 with caustic and add sodium hypochlorite. Recirculate with the sludge pump and continue with additions until spot test shows no cyanide.
- B. If chromium is present, adjust pH to 6. - 9.0 and add sodium hydrosulfite until an excess of reducing agent is present as indicated by WCR-HST, appended, or chromium is eliminated as indicated by WCR-ST, appended.



- C. Upon elimination of cyanide and chromium, the batch is pumped to tank F, for settling. The supernatant is pumped to the rinse waters and eventually the sludges are transferred to a collecting tank for periodic pickup by a scavenger truck.



APPENDIX



INTEGRATED CYANIDE TREATMENT SYSTEM (CHLORINE)

INTRODUCTION

The Integrated Cyanide Treatment System is of the alkaline chlorination type designed to completely oxidize highly toxic cyanide into harmless carbon dioxide and nitrogen.

The reaction proceeds in two stages. The first stage, which takes place at an extremely rapid rate under the conditions specified, yields the considerably less toxic cyanate along with insoluble metal oxides and hydroxides. The second stage, which takes place at a lesser rate, yields carbon dioxide and nitrogen, the products of the oxidation of cyanate.

FUNCTIONAL DESCRIPTION


The integrated system consists of treatment wash tanks located in the plating lines; and a treatment solution reservoir, a solution feed, vacuum-type chlorinator, a caustic feed pump, and treatment solution pumps, all external to, but integrated with the plating lines.

The arrangement of the equipment is such as to provide the addition of treatment chemicals to the treatment solution; and to provide recirculation of the treatment solution in this order: through the reservoir, the ejector of the solution feed, vacuum-type chlorinator, and the treatment wash tanks, and back to the reservoir.

The treatment solution reservoir is sized to serve three important functions. The first function is to serve as the all-important buffering component in the system to neutralize the shock loading caused by sudden and irregular changes in the quantity of plating solution drag-out treated. The second function is to serve as a clarifier, dettling out the insoluble metal oxides and hydroxides formed in the first stage of the reaction. The third function is to serve as a retention tank providing adequate time for the second stage of the reaction, the oxidation of the cyanate to carbon dioxide and nitrogen, to take place.

To provide satisfactory treatment, the treatment solution for the system used after cyanide plating must be maintained at a strength of 800-1,500 ppm available chlorine and at a pH of 11.5-12.8.

In operation, the clear supernatant from the treatment solution reservoir is passed (via the ejector of the solution feed, vacuum-type chlorinator) to the treatment wash tanks where it is distributed in excessive quantities over the surface of the



FUNCTIONAL DESCRIPTION cont'd

work pieces. Upon contact, all cyanide in the plating solution drag-out is immediately oxidized to cyanate and the products of this stage of the reaction are washed from the surface of the work pieces by the excess treatment solution.

Thus, the work pieces leave the treatment wash tanks wetted only with harmless treatment solution which is removed in subsequent rinse tanks and discharged with other non-toxic rinse waters to a flash neutralization tank.


The partially spent treatment solution is returned from the treatment wash tanks to the treatment solution reservoir where the insoluble metal oxides and hydroxides settle out and the second stage of the reaction, the oxidation to carbon dioxide and nitrogen, occurs.

Prior to return to the treatment wash tanks, the alkalinity and available chlorine strength of the treatment solution is replenished by the addition of caustic (sodium hydroxide) and chlorine. Caustic addition is by means of a manually-set, positive displacement metering pump. Chlorine addition is by means of a manually-set, solution-feed, vacuum-type chlorinator, operating when the treatment solution is directed through its ejector.

In a system used for treatment after copper plating, it is imperative that the chlorine concentration in the treatment solution does not under any circumstances fall below the level of 500 ppm excess chlorine. At a lower chlorine concentration, the copper precipitates in the form of cuprous salts and the treatment solution takes on a blue color instead of the normal grayish-black which is the color of the desired cupric oxide precipitate. If the blue copper precipitates (copper hydroxides or copper carbonates) are present, these tend to form a gelatinous film over the copper plated surface and will impair the adhesion of the subsequent nickel plate.

To insure that the available free chlorine is more than 500 ppm at the surface of the plated work which enters the treatment solution, and to insure that it will not be reduced below this figure by the chlorine demand of the plating solution film, we recommend that the free chlorine level not be permitted to drop below 600 ppm in the body of the treatment solution.

To avoid the slight darkening of the copper and/or silver plated surface which occurs when the chlorine concentration is above 600 ppm, we have developed Inhibitor LD which we recommend as an addition to the cyanide treatment solution. The use of the inhibitor will permit a much wider range of chlorine concentrations and will thus avoid the need for close control.



FUNCTIONAL DESCRIPTION (cont'd)

With the exception of drag-out losses, the inhibitor is not consumed during normal operation of the treatment system. If, however, plating solution is dragged into the treatment solution when the chlorine concentration is below 300 to 500 ppm and the blue copper precipitates begin to form, the inhibitor will be immediately lost.

DESCRIPTION OF THE TREATMENT


The oxidation of cyanide complexes through chlorination has been thoroughly explored. The chemical reaction may be assumed to take place in two steps.

The first step:




is a very rapid reaction converting the cyanides into cyanates, compounds of considerably lesser toxicity. At the recommended pH and high excess of chlorine, the above reaction is almost instantaneous.

The second reaction:



proceeds at a somewhat slower rate. At the stated pH and excess chlorine, and at room temperature, the cyanates are broken down into nitrogen and carbon dioxide gases in approximately two to four hours. The relatively high chlorine excess accelerates the break-down of cyanates and allows the quantitative precipitation of the non-toxic, heavy metal salts.



OPERATION

1. General

Chlorine in contact with cyanide under the conditions of depressed pH gives rise to the formation of toxic hydrogen cyanide and/or cyanogen chloride gases. THEREFORE, NEVER, UNDER ANY CIRCUMSTANCES, ALLOW THE PH OF THE TREATMENT SOLUTION TO FALL BELOW 9.5.

2. Solution Make-up

To prevent formation of the blue copper precipitates which are mentioned under Functional Description when making up a new treatment solution, it is necessary to start with a reservoir containing only fresh water or water containing old treatment solution. An attempt to make up the solution from water containing copper ions will result in the formation of the blue precipitates. These are extremely difficult to convert to the proper, black form and should be pumped to the sludge bed before any attempt is made to use the treatment solution. The solution should be made up by starting with fresh water and adding caustic soda and chlorine until the specified ranges for pH and chlorine concentration are reached. Then copper ions are then dragged into the solution, they will immediately precipitate as the proper, black cupric oxide form. Only after the pH and chlorine concentration are within the proper ranges, and all blue precipitate has been eliminated, should the inhibitor LD be added. After the addition of the inhibitor, the solution may be put into use.

3. Chemical Feed Rates

a. Chlorine Feed Rate

Chlorine feed rate must be adjusted to provide approximately eight (8) pounds of chlorine per pound of cyanide compound dragged out to maintain 800-1,500 ppm available chlorine in the solution.

b. Caustic Feed Rate

Caustic (sodium hydroxide) feed rate must be adjusted to provide approximately one (1) pound of caustic per pound of chlorine to maintain the pH of the treatment solution between 11.5 and 12.3.

c. Inhibitor LD

Inhibitor LD is added at the rate of one gallon per each 1,000 gallons of treatment solution when making up a new treatment solution. The drag-out losses are made up by adding approximately one-half pint of Inhibitor LD per 1,000 gallons each week.



Operation cont'd

4. Chemical Control

a. Treatment Solution

The following chemical tests are performed on samples of the treatment solution taken from the influent to the treatment wash tanks before the solution comes in contact with the work pieces.

i. pH

Check the pH at least once every four hours using narrow range pH test paper. A pH meter or other pH measuring device may be used if desired.

ii. Available Chlorine

Check the available chlorine concentration at least once every two hours using the Indicator Paper Test described in Test Procedure WCN-CIP appended, and at least once every day using a chlorine comparator such as a Taylor Chlorine Slide Colorimeter, or by analysis as described in Test Procedure WCN-CTSI. As mentioned earlier, it is imperative that the chlorine concentration be maintained at all times at 800 ppm or higher to avoid loss of the inhibitor.

b. Effluent Rinse Water

Check for cyanide in the effluent from the rinse tanks immediately following the treatment wash tanks once every day using the spot test in Test Procedure WCN-ST, appended. This check is necessary to make certain that no cyanide is being dragged out of the treatment wash tanks.

5. Dumping

Generally, the treatment solution should be dumped at 2 - 3 month intervals; however, the exact frequency of dumping would be dependent on the quantity of plating solution drag-out treated. When it is deemed necessary to dump the spent treatment solution, the excess available chlorine is reduced by manual addition of sodium metabisulfite as controlled by Test Procedure WCN-CIP. The amount required will be approximately thirteen pounds $\text{Na}_2\text{S}_2\text{O}_5$ per 1,000 ppm available chlorine per 1,000 gallons. When the chlorine test paper shows a negative test, the solution may be dumped to the sludge beds. When an Integrated Chrome I Treatment Solution is available, it can be used in place of metabisulfite.

Test Procedures:

WCN-CIP, WCN-CTSI, WCN-ST, WCN-pH



CHROMIUM TREATMENT II

The aim of this treatment is to provide a reducing potential for hexavalent chromium and precipitate trivalent chromium.

Hexavalent chromium compounds if dragged in are reduced by the sodium hydrosulfite ($\text{Na}_2\text{S}_2\text{O}_4$) dissolved in the treatment solution. An excess of reducing chemical is maintained in this solution and a concentration of 50-100 ppm sodium hydrosulfite is proposed.

The chromium which has been reduced to the trivalent state is precipitated as an insoluble hydroxide at the pH maintained between 7.8-8.5. For the maintenance of the alkaline pH, soda ash is used.

The treatment chemicals, sodium hydrosulfite and soda ash, are dissolved in a common storage tank and fed into the treatment reservoir tank through a variable rate feed positive displacement pump. The consumption of the various chemicals will depend on the dragout rate from the treatment solution and only experience will develop the proper balance in makeup for the treatment chemicals.

Chemical Control


Tentatively, it is proposed that the sodium hydrosulfite and soda ash chemical solution should be made up in a concentration of 50-60 g/l (6-8 oz/gal.) soda ash, 15 g/l, (2-3 oz/gal.) sodium hydrosulfite. As the sodium hydrosulfite loses its strength, it is best to make up a sufficient quantity only for one day and make a fresh solution daily. If soda ash solution remains from the previous day, replenish the sodium hydrosulfite content by assuming that 30% was lost in 24 hrs.

- A. Check for the sodium hydrosulfite concentration in the treatment solution twice daily by using the WCR-HIP Indicator Paper Test, appended. The coloration should be bleached from the paper in approximately 20-30 seconds.

In the first few weeks of operation, the sodium hydrosulfite spot test should also be used to become familiar with the solution test procedure WCR-HST, as appended.

- B. The pH should be maintained using Narrow Range pH papers.

After a few weeks of operation, the proper balance of the treatment solution will be evident from the color itself which should be bluish-white without any yellow coloration.



C. Effluent Rinse Water

Check for hexavalent chromium in the effluent from the rinse tank immediately following the treatment wash tank once every day using the Spot Test described in Test Procedure WCR-ST, appended.


Dumping

The entire treatment solution, or part of it, is dumped periodically approximately once every 2-4 weeks depending upon the quantity of dragout treated. The sludge level in the treatment reservoir should not be allowed to become higher than 10-15 centimeters, (4"-6").

The Chromium Treatment II solution to be dumped may be dumped directly to a sludge bed.

Test Procedures:

WCR-HIP, WCR-HST, WCR-ST.



LANEY LABORATORIES, INC.

TEST PROCEDURE SERIES

TEST: CHROMIC ACID SPOT TEST

TEST PROCEDURE WOP-ST

SPECIFICATIONS:

| | |
|------------------------------|------------------------|
| Type----- | Qualitative |
| Limit of Identification----- | 0.5 ppm CrO_3 |
| Color----- | Pink-Violet |

Reagents:

1. 1% Diphenylcarbazide Indicator (Dissolve contents (0.25 g.) of one ampoule of Diphenylcarbazide in 25 ml 0.1% Acetone).*
2. Acetic Acid Buffer (N-39)

Procedure:


(1) Place one drop of sample and one drop of distilled water (for blank) on a white spot plate.

(2) To each drop add one drop of Diphenylcarbazide Indicator and stir with a clean stirring rod.

(3) To each drop add one drop of Acetic Acid Buffer (N-39) and stir with a clean stirring rod. The sample spot will turn pink to violet depending upon the chromic acid concentration. If no chromic is present, the sample spot will turn yellow. The blank spot will also turn yellow.

(4) If the sample is alkaline, the addition of the Indicator may result in a strong pink-violet color. However, if with continued additions of acetic acid, the sample turns yellow, no chromic acid is present. If the pink-violet color remains, chromic acid is present.

*NOTE: If EPC Indicator is furnished as powder in small jar rather than in ampoule, use 1/2 "V" measuring spoon which equals 0.25G.



LANOV LABORATORIES, INC.



TEST PROCEDURE SERIES

TEST: SODIUM HYDROSULFITE SPOT TEST. TEST PROCEDURE: WCP-HST

SPECIFICATIONS:

Type-----Quantitative
Color at End Point-----Violet

REAGENTS:

1. Chromic Acid Solution (12.0 g/liter CrO_3)
2. Diphenylcarbazide Indicator 1% (Dissolve contents (0.25 g.) of one ampoule of Diphenylcarbazide in 25 ml C.P. Acetone).
3. Acetic Acid Buffer: 6 g. Sodium Acetate, 30 ml Glacial Acetic Acid and 75 ml water.

PROCEDURE:


1. Using a pipet or 100 ml graduated cylinder, transfer 100 ml sample of the treatment solution into a 250 ml beaker and heat to 140-160 F.
2. Place one drop of solution on a clean white spot plate.
3. Add one drop of diphenylcarbazide indicator and stir with a clean stirring rod. The sample spot will be orange red due to the alkalinity of the treatment solution.
4. Add one drop acetic acid buffer solution to the sample spot and again stir with the stirring rod. The mixture will be the color of the original sample after one minute if sodium hydrosulfite is present. If hexavalent chromium is present, the spot will turn pink to violet.
5. To determine the excess sodium hydrosulfite present in the sample, add 3 drops of chromic acid solution to the hot sample, mix and retest as in Steps 2 through 4. Continue the procedure of adding 3 drops of chromic acid to the sample and checking for the hexavalent chromium until a positive test is obtained. Record the number times the 3 drop increment was added to the hot sample.

CALCULATIONS:

Each 3 drops of chromic acid added is equivalent to approximately 50 ppm sodium hydrosulfite; therefore,

No. of 3 drop increments x 50 = ppm $\text{Na}_2\text{S}_2\text{O}_4$ excess

LANCY LABORATORIES, INC.



TEST PROCEDURE SERIES

TEST: CYANIDE SPOT TEST

TEST PROCEDURE WCN-ST

SPECIFICATIONS:

Type-----Qualitative
Limit of Identification-----1 ppm CN-
Color-----Orange-Pink

REAGENTS:

- (N33) Saturated Bromine Water (3ml Bromine/100 ml water).
- (N33) 1.5% Sodium Arsenite (1.5 g Sodium Arsenite/100 ml water).
- (N34) Pyriline Reagent (25 ml Pyriline and 2 ml concentrated Hydrochloric Acid/100 ml water).
- (N35) 2% Benzidine Hydrochloride (2 g Benzidine Hydrochloride/100 ml water).
- (N34-35) Mixed Reagent (5 ml Pyriline Reagent and 2 ml 2% Benzidine Hydrochloride). Prepare fresh every three days.

Note: Distilled water should be used for reagent preparation.
Reagents as furnished with test sets require no further dilution.

PROCEDURE:

- (1) Place one drop of sample and one drop of distilled water (for blank) on a white spot plate.
- (2) To each drop add one drop of Saturated Bromine Water; stir with a clean stirring rod; and allow to stand for one minute.
- (3) To each drop add two drops of 1.5% Sodium Arsenite and stir with a clean stirring rod. The orange color of the Bromine will now disappear.
- (4) To each drop add one drop of Mixed Reagent and stir with a clean stirring rod. The sample spot will turn pale orange-pink to red depending upon the cyanide concentration. If no cyanide is present, the sample spot will remain colorless. The blank spot will also remain colorless.

Note: 1. Bromine will evaporate unless solution is well stoppered. To insure a saturated solution, excess free bromine should be always present on the bottom of a reagent solution. Bromine fumes will oxidize the benzidine indicator to a blue color; therefore, keep the bromine reagent and the spot plate under the exhaust hood until the sodium arsenite is added.

Note 2: If the solution to be checked is alkaline, pH greater than 10, neutralize a portion of the solution using Procedure WCN-STM attached.

LANCY LABORATORIES, INC.



TEST PROCEDURE SERIES

TEST: AVAILABLE CHLORINE TITRATION
(STARCH IODIDE METHOD)

TEST PROCEDURE WCN-CESI

CHARACTERISTICS:

Type-----Quantitative
Limit of Identification-----None
Color at End Point-----Colorless

REAGENTS:

1. 10% Potassium Iodide (10 g Potassium Iodide/100 ml water)
2. A. Starch Solution (dissolve 5 g soluble starch in cold water; dilute to 1000 ml, then boil for a few minutes). Keep in glass-stoppered bottle; or
B. Thyodene Indicator
Either Indicator A (Starch Solution) or Indicator B (Thyodene) may be used.
3. 0.10 N Sodium Thiosulfate
4. Acetic Acid Buffer - 6 g sodium acetate, 30 ml glacial acetic acid and 75 ml water

Note: Distilled water should be used for reagent preparation.

PROCEDURE:


- (1) Using a pipette, transfer a 10 ml sample into a 250 ml Erlenmeyer flask. Add 90 ml of distilled water to dilute sample 1:10.
- (2) Add 5 ml of the acetic acid buffer solution.
- (3) Add 15 ml of 10% Potassium Iodide solution and 2-3 ml of starch solution, or 0.5 g Thyodene (one pinch). The sample should turn deep blue upon the addition of the starch or Thyodene if free chlorine is present.
- (4) Swirling the flask to provide constant mixing, titrate with 0.10 N Sodium Thiosulfate solution until the blue color completely disappears. For the titration use a micro buret such as Kimax No. 150 with 63 sec. tip and solution reservoir or equivalent.

CALCULATIONS:

_____ ml Sodium Thiosulfate x 354.6 = _____ ppm available chlorine.

ML Sodium Thiosulfate x 354.5 = ppm CL_2

| <u>ML</u> | <u>ppm</u> | <u>ML</u> | <u>ppm</u> | <u>ML</u> | <u>ppm</u> |
|-----------|------------|-----------|------------|-----------|------------|
| 0.0 | - | 4.6 | 1630.7 | 9.2 | 3261.4 |
| 0.1 | 35.4 | 4.7 | 1666.2 | 9.3 | 3296.9 |
| 0.2 | 71.0 | 4.8 | 1701.6 | 9.4 | 3332.3 |
| 0.3 | 106.4 | 4.9 | 1737.1 | 9.5 | 3367.8 |
| 0.4 | 141.8 | 5.0 | 1772.5 | 9.6 | 3403.2 |
| 0.5 | 177.3 | 5.1 | 1807.9 | 9.7 | 3438.7 |
| 0.6 | 212.7 | 5.2 | 1843.2 | 9.8 | 3474.1 |
| 0.7 | 248.2 | 5.3 | 1878.9 | 9.9 | 3509.5 |
| 0.8 | 283.6 | 5.4 | 1914.3 | 10.0 | 3545.0 |
| 0.9 | 319.1 | 5.5 | 1949.8 | 10.1 | 3580.5 |
| 1.0 | 354.5 | 5.6 | 1985.2 | 10.2 | 3615.9 |
| 1.1 | 390.0 | 5.7 | 2020.7 | 10.3 | 3651.4 |
| 1.2 | 425.4 | 5.8 | 2056.1 | 10.4 | 3686.9 |
| 1.3 | 460.9 | 5.9 | 2091.6 | 10.5 | 3722.3 |
| 1.4 | 496.3 | 6.0 | 2127.0 | 10.6 | 3757.7 |
| 1.5 | 531.8 | 6.1 | 2162.5 | 10.7 | 3793.2 |
| 1.6 | 567.2 | 6.2 | 2197.9 | 10.8 | 3828.6 |
| 1.7 | 602.7 | 6.3 | 2233.4 | 10.9 | 3864.1 |
| 1.8 | 638.1 | 6.4 | 2268.8 | 11.0 | 3899.5 |
| 1.9 | 673.6 | 6.5 | 2304.3 | 11.1 | 3935.0 |
| 2.0 | 709.0 | 6.6 | 2339.7 | 11.2 | 3970.4 |
| 2.1 | 744.5 | 6.7 | 2375.2 | 11.3 | 4005.9 |
| 2.2 | 779.9 | 6.8 | 2410.6 | 11.4 | 4041.3 |
| 2.3 | 815.4 | 6.9 | 2446.1 | 11.5 | 4076.7 |
| 2.4 | 850.8 | 7.0 | 2481.5 | 11.6 | 4112.2 |
| 2.5 | 886.3 | 7.1 | 2516.9 | 11.7 | 4147.7 |
| 2.6 | 921.7 | 7.2 | 2552.4 | 11.8 | 4183.1 |
| 2.7 | 957.2 | 7.3 | 2587.9 | 11.9 | 4218.6 |
| 2.8 | 992.6 | 7.4 | 2623.3 | | |
| 2.9 | 1028.1 | 7.5 | 2658.8 | | |
| 3.0 | 1063.5 | 7.6 | 2694.2 | | |
| 3.1 | 1099.0 | 7.7 | 2729.7 | | |
| 3.2 | 1134.4 | 7.8 | 2765.1 | | |
| 3.3 | 1169.9 | 7.9 | 2800.6 | | |
| 3.4 | 1205.3 | 8.0 | 2836.0 | | |
| 3.5 | 1240.8 | 8.1 | 2871.5 | | |
| 3.6 | 1276.2 | 8.2 | 2906.9 | | |
| 3.7 | 1311.7 | 8.3 | 2942.4 | | |
| 3.8 | 1347.1 | 8.4 | 2977.8 | | |
| 3.9 | 1382.5 | 8.5 | 3013.3 | | |
| 4.0 | 1418.0 | 8.6 | 3048.7 | | |
| 4.1 | 1453.5 | 8.7 | 3084.2 | | |
| 4.2 | 1478.9 | 8.8 | 3119.6 | | |
| 4.3 | 1524.4 | 8.9 | 3155.1 | | |
| 4.4 | 1559.8 | 9.0 | 3190.5 | | |
| 4.5 | 1595.3 | 9.1 | 3226.0 | | |



LANCY LABORATORIES, INC.

FOR THE USE OF NARROW RANGE PH PAPER 11.0-13.1 WITH
CHLORINATED WASTE TREATMENT SOLUTION


WON-PH

1. Add one dropper-full (approximately 1 ml) of 2N Sodium Thiosulfate (500 g/l) solution to approximately 100 ml sample of cyanide treatment solution. Stir.
2. Dip pH paper into solution for 2-3 seconds and compare color.

(paper reads 0.4 units lower than electrometric pH reading)

NOTE: If the chlorine concentration is more than 3,000 ppm, add a second dropper (1 ml) of the thiosulfate solution, and if the chlorine concentration is more than 5,000 ppm, a third dropper-full may be needed.

12/4/69



LANCY LABORATORIES, INC.

TEST PROCEDURE SERIES

TEST: AVAILABLE CHLORINE INDICATOR
PAPER TEST

TEST PROCEDURE WCN-CIP

CHARACTERISTICS:

Type-----Quantitative Approximation
Limit of Identification-----None
Color-----Purple

REAGENTS:

1. Chlorine Test Paper (low pH potassium iodide-starch)


PROCEDURE:

Place a drop of the sample to be tested on a piece of chlorine test (low pH potassium iodide-starch) paper and observe the color of the wetted portion of the paper.

The color will be pinkish-blue at an available chlorine concentration of approximately 15 ppm or less, increasing to a deep purple as the concentration approaches 200 ppm and above. Above 500 ppm, however, while the wetted spot will be a lighter purple surrounded by a bleached white ring, the outer periphery of the wetted portion of the paper will show a dark purple.

For closer approximation of the chlorine content of the sample at these higher concentrations, dilute the sample 1:10 and retest. If the bleached white ring around the wetted spot appears again, the chlorine concentration is high (approximately 2,500 ppm).

If the wetted portion of the paper turns purple, the approximate available chlorine concentration must be determined by diluting the sample and retesting. For example: a sample which gives a pinkish-blue color after being diluted 20:1 has an available chlorine concentration of approximately (20×15) 300 ppm.



LANCY LABORATORIES, INC.

TEST PROCEDURE SERIES

TEST: SODIUM HYDROSULFITE INDICATOR TEST PROCEDURE WCR-HIP
PAPER TEST

SPECIFICATIONS:

Type. Quantitative Approximation
Limit of Identification. . . . 50-1000 ppm Sodium Hydrosulfite
Color. Purple - White

REAGENTS:

1. 200 ppm Chlorine Water (4 ml 5% Sodium Hypochlorite
(Chlorox)/1000 ml water).
2. Chlorine Test (Starch Iodide) paper

Note: Distilled water should be used for reagent preparation.

PROCEDURE:

(1) Dip the end of a piece of chlorine test (Starch Iodide) paper into the 200 ppm Chlorine water. The wetted portion of the paper will turn purple.

(2) Remove the paper from the Chlorine Water and dip the wetted (purple) portion into the sample to be tested. Observe the time required to bleach the purple color from the paper.

The concentration of Sodium Hydrosulfite is approximated by the time required for the purple color to disappear.

| | | |
|---------------|---|-------------------------------|
| 3 - 5 seconds | = | 1,000 ppm Sodium Hydrosulfite |
| 5 -10 seconds | = | 500 ppm Sodium Hydrosulfite |
| 25 seconds | = | 100 ppm Sodium Hydrosulfite |
| 60 seconds | = | 50 ppm Sodium Hydrosulfite |



PRELIMINARY REPORT OF INDUSTRIAL WASTES
NASSAU COUNTY HEALTH DEPARTMENT

Date:

Name of Company METALLURGICAL PROCESSING CORP.
Present location 100 Marshall Dr Syosset Tel. No. WA 1-6200
Information Supplied by L. Pearlman No. of Employees 50
Operations started 1960
Waste disposal methods DIFFUSION WELL INC Separate from sanitary Yes
Processes employed HEAT TREATING

PROCEDURES:

1. Chemicals used ULTRAPEX 109

2. Step by step procedure (1) ULTRAPEX 109 - COLD WATER RINSE

(2) HOT WATER RINSE (3) RUST PREVENTIVE OIL

3. Volume and No. of tanks or vats and conc. of chemicals (1) ULTRAPEX 109 (Inhibitor)
Hydrochloric acid 3 COLD WATER RINSE 1 HOT WATER RINSE 1 RUST
PREVENTIVE OIL

4. Dumping of vats (frequency) _____

5. Water Supply _____ Public ☒ Private _____ Consumption _____

Waste Disposal Systems DIFFUSION WELL FOR METAL TREATMENT
(describe - use reverse side for sketch)

Solids or sludge disposal _____

Chemical analysis of wastes
(composite waste, if possible)

Remarks _____

APPENDIX P

NOVEMBER 9, 1995 GROUNDWATER SAMPLING RESULTS MEMO



MEMORANDUM

TO: Theresa Heneveld, P.E., Lockwood, Kessler & Bartlett, Inc.

FROM: Michael Wolfert, Geraghty & Miller, Inc. *MW*

DATE: November 9, 1995

SUBJECT: Groundwater Sampling Results from the Syosset Landfill and Conclusions Regarding Off-Site Groundwater Conditions

Attached to this memo is Table 1 that summarizes the groundwater sampling results from the two OU-2 RI sampling rounds in November and December 1993 and the supplemental partial sampling round in July 1995. Seven wells (not all wells) were sampled for volatile organic compounds (VOCs) during the July supplemental round as explained in our May 31, 1995 letter and, therefore, only volatile results from the November and December 1993 rounds for the same seven wells are presented for comparison. The same sampling and analytical protocols were followed for all three sampling rounds.

Review of the data in Table 1 indicates that total VOC concentrations remained essentially the same during all three sampling rounds with most of the same compounds showing up each time at approximately the same concentrations.

Furthermore, review of Table 1 shows that the total VOC concentration in Well RW-12I during July 1995 was very similar to the total VOC concentration in this well in December 1993. Although the July and December totals are higher than the November concentration, during each of the three sampling rounds essentially the same compounds are present and make up the same percentage of the total each time. Moreover, in Well RW-12I, in all three rounds, tetrachloroethene had the highest concentration of any individual compound and made up approximately 47 percent of the total, while 1,1,1-trichloroethane was the compound with the next highest concentration, making up about 26 percent of the total.



Based on these three sampling rounds, neither an upward or downward trend in total VOCs is evident in Well RW-12I. The consistency of constituent concentrations in Well RW-12I over the 20-month period between the first and third samplings suggests that either the source(s) of these constituents to groundwater may still be active or that the mass of constituents in the aquifer is sufficient, combined with the relatively flat horizontal hydraulic gradient and correspondingly slow groundwater velocity, to preclude any short-term decrease in constituent levels in Well RW-12I.



Now that three rounds of data are available for both on-site and off-site wells, a detailed review and evaluation of the data for upgradient and on-site versus off-site wells was undertaken. For the three sampling rounds (November and December 1993 and July 1995), six results are available for upgradient wells, 22 results are available for on-site wells, and 26 results for off-site wells; this includes replicate results.

Tetrachloroethene (PCE) and 1,1,1-trichloroethane (TCA), the two most prominent compounds in Well RW-12I, are known to breakdown (degrade) in the environment to other chlorinated compounds, and if conditions are right and enough time passes, these breakdown products will eventually be converted to carbon dioxide and water.

Laboratory studies have been conducted to determine what the breakdown end products will be and also the rate of degradation. Because field conditions cannot be accurately reproduced in the laboratory, laboratory degradation rates cannot be confidently transferred to the field and, generally speaking, field degradation rates tend to be slower than laboratory-derived ones.

Based on an article in the July/August 1990 edition of the journal HMC by Olsen and Davis entitled, "Predicting the Fate and Transport of Organic Compounds in Groundwater, Part II," the degradation pathways and breakdown and end products for PCE and TCA are given below.



PCETCA

—————> Primary pathway
—————> Secondary pathway



Generally speaking, all else being equal, the more degradation products and the less parent compounds (PCE and TCA) present, the older the contamination is. For example, assume two plumes of contaminated groundwater exist side by side in the same hydrogeologic environment, have or had similar sources, and each plume was made up entirely of PCE and its degradation products. If plume "A" consisted of 95 percent PCE and 5 percent breakdown products while plume "B" contained 10 percent PCE and 90 percent breakdown products, it would be logical to conclude that plume "B" and its source were older. This conclusion would be based on the fact that given similar environments and source contribution, the plume with the greater percentage of breakdown products would have had to exist longer (and, likewise, its source) to allow the degradation process to proceed further.

With the above concept in mind, the average concentration of PCE, TCA, and their breakdown products was calculated. Data from the November and December 1993 and July 1995 sampling rounds were used in determining averages. Table 2 shows average total VOC concentrations per well for the three rounds in addition to average PCE, TCA, and total breakdown products concentrations. The table also has a calculated ratio for each well of total breakdown products over the sum of PCE and TCA. All data from all three rounds was used, including replicates, to obtain the broadest database per well. Wells that had neither PCE/TCA or their breakdown products were excluded from the table as they would provide no information relative to age of contaminants. Furthermore, wells with less than one part per billion total VOCs were excluded from the table because with concentrations near or actually below the method detection limit, slight inaccuracies in VOC concentration could significantly affect calculated ratios.

Ratios of substantially less than one means more PCE/TCA exists than breakdown products indicating little degradation (relatively speaking) has taken place. A ratio of one means equal amounts of PCE/TCA versus breakdown products, while a ratio well in excess of one means degradation has progressed relatively far. The higher the ratio, all else being equal, the older the contaminants.



Review of Table 2 shows that there is a wide range of ratios in upgradient/on-site wells; 0.2 to infinity, as well as in off-site wells; 0.3 to 8.0. Averaging ratios for on-site wells yields a value of 2.7, while the median value is 2.6. For off-site wells, the average value, excluding Well RW-12I, is 4.1 with a median value of 3.8. These numbers indicate that the makeup of the contamination profile is dominated by breakdown products. Well RW-12I, however, has an average ratio of 0.3 indicating a profile dominated by parent compounds as opposed to breakdown products. These numbers suggest that the contaminant mix at Well RW-12I may be derived from a different source than the other off-site wells as degradation has not progressed as far as in the other off-site wells.

Conclusions

The July 1995 sampling round was performed to obtain additional groundwater quality data to supplement the findings of the Syosset Landfill OU2 RI Report and the Industrial Survey (Geraghty & Miller, Inc., July 13, 1995) in order to formulate a conclusion regarding off-site groundwater quality conditions. The following paragraphs summarize the conclusions developed based on the available data gathered to date.

- 1) Water-quality data for Cluster 11 show that typical landfill leachate indicator parameters are present at this cluster, even though it is considerably outside the easternmost limiting flow line from the landfill. While volatile organics detected in this cluster may be landfill derived, they are consistent with regional background groundwater quality deterioration.
- 2) Water-quality data for Cluster 10, which is directly downgradient of the landfill, show typical landfill leachate indicator parameters are present at this cluster. While volatile organics at this cluster may be landfill derived, they are consistent with regional background groundwater quality deterioration.



3) Water-quality data for Cluster 12 show that typical landfill leachate indicator parameters are present at this cluster, which is approximately at the westernmost limiting flow line from the landfill. While volatile organics in Well RW-12D may be landfill derived, the concentrations here are also consistent with regional background groundwater quality deterioration. Volatile organics in Well RW-12I appear to be from a source other than the landfill. This is based on an assessment of available information gathered as part of the OU1 RI and OU2 RI, including on-site and off-site groundwater quality data, Industrial Survey data, regional hydrogeological data, and soil boring data obtained during the OU1 RI. This conclusion is based on the following:

- The elevated concentrations of PCE and TCA in Well RW-12I do not appear to be from the landfill and may be caused by a more recent or currently active source since the ratio of breakdown products versus PCE and TCA at Well RW-12I show a mix dominated by parent compounds not breakdown products, which is the converse of other off-site wells and the fact that volatile organics are nearly 10 times higher in Well RW-12I than on-site, not what would be expected if the landfill was the source. Furthermore, the concentrations of leachate indicator parameters in Wells RW-12I and RW-12D are very similar, while volatile organics in Well RW-12I are nearly 10 times greater than in Well RW-12D. This disparity between volatile organic compounds and leachate concentrations suggests that the volatile organic compounds in Well RW-12I are due to a source other than the landfill.
- The industrial area survey (Geraghty & Miller memo of July 13, 1995) identified five off-site properties which are potential sources of the volatile organic compounds detected in Well RW-12I. These properties are located on Robbins Lane and Aerial Way, between 1,400 and 2,100 feet southwest of Well RW-12I. Each of these properties used one or more of the volatile compounds detected in Well RW-12I, and two, Space Machine Corp. and Spiegel Associates, had releases which required soil remediation. In addition, these properties likely discharged



wastewater to on-site septic systems and leaching fields prior to the construction of sewers in the 1980s. It is therefore reasonable to expect that releases of volatile organic compounds to groundwater have occurred at one or more of these properties.

- Regional hydrogeologic data indicate that the potential off-site sources identified in the industrial area survey are located hydraulically upgradient of Well RW-12I, and are situated between the well and the regional groundwater divide. Specifically, the regional horizontal flow direction for the Magothy Aquifer in the vicinity of the Syosset Landfill is northeast, and the regional groundwater divide is located approximately 3,100 feet south of Well RW-12I and is oriented west to east (Figure 3-3 of OU2 RI Report). Moreover, because the vertical gradient is 3 to 5 times the horizontal gradient (Section 3.1.4 of OU2 RI Report) in the vicinity of the landfill, releases from these potential off-site sources could migrate to the intermediate zone of the Magothy Aquifer at Well RW-12I.
- Data from on-site soil borings and monitoring wells indicate that the landfill is not the source of the elevated levels of volatile organic compounds detected in Well RW-12I. Specifically, if the landfill was the source of these VOCs, it is expected that substantial residual contamination would be present. Instead, these VOCs (specifically PCE, TCA, TCE, 1,1-DCE, and 1,1-DCA) were only detected at low concentrations (5 to 9 ppb) in three of 44 samples from 10 soil borings, including samples of the fill and the soil directly underlying the landfill (Tables 16 and 17 of OU1 RI Report). Similarly, these VOCs were only detected at low concentrations (0.11 to 30 ppb) in 27 of 56 groundwater samples from 16 on-site monitoring wells (Table 9 of OU1 RI Report, Table 1 of OU2 RI Report, and Table 1 of this memo).

In summary, we can conclude that: based on the lack of degradation of PCE and TCA in Well RW-12I; the identification of properties within the previously unsewered Industrial Park who used and/or are using PCE and TCA and have had reported releases; regional hydrogeologic data indicating the Industrial Park is upgradient of Well RW-12I; and the low



levels of these compounds found on-site in both the soil and groundwater during the OU1 RI; the high concentrations of volatile organic compounds (particularly PCE and TCA) in Well RW-12I appear to be from a source(s) located in the Industrial Park west of the LIRR tracks.

G:\APROJECT\LOCKESBA\NY0029.099\CORRES\RES2.DOC



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During the Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | SY-3D 11/2/93 | SY-3D 12/3/93 | SY-3D 7/28/95 | SY-8 11/4/93 | SY-8 12/1/93 |
|---------------------------------------|------------------|------------------|------------------|-----------------|-----------------|
| Parameter (concentrations in ug/L) | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <1 | <1 J | <1 |
| Chloromethane | <1 | <1 | <1 | <1 | <1 |
| Vinyl chloride | 0.6 J | 0.6 J | <1 | <1 | <1 |
| Bromomethane | <1 | <1 | <1 | <1 J | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 J | <1 | <1 |
| Acetone | <17 J | <21 | <5 | <10 J | <18 J |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 |
| Methylene chloride | <2 | <2 | <2 | <2.2 | <1 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | 1.5 | 1.6 | 0.91 J | 1.3 | 1.2 |
| 2-Butanone | R | R | <5 | R | R |
| cis-1,2-Dichloroethene | 0.7 J | 0.6 J | <1 | 1.1 | 0.4 J |
| Chloroform | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | 0.8 J | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 |
| Benzene | 1.8 | 1.8 | 1.4 | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | 0.9 J | 0.9 J | <1 | 2.8 | 1.5 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | R | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 |
| Toluene | 0.4 J | 0.2 J | <1 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | 17 | 10 |
| 2-Hexanone | <5 | R | <5 | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | 5.5 | 5.4 | 5.1 | 0.1 J | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | 0.1 J | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 11.4 | 11.1 | 7.41 | 23.2 | 13.1 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: | SY-8 | PK-10S | PK-10S | PK-10S | PK-10I |
|---------------------------------------|---------|---------|---------|---------|---------|
| Sample Date: | 7/28/95 | 11/4/93 | 12/1/93 | 7/28/95 | 11/4/93 |
| Parameter (concentrations in ug/L) | | | | | |
| Dichlorodifluoromethane | <1 | <1 J | 0.2 J | <1 | <1 J |
| Chloromethane | <1 | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 | 0.7 J |
| Bromomethane | <1 | <1 J | <1 | <1 | <1 J |
| Chloroethane | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | 0.8 J | 0.9 J | <1 | 0.5 J |
| Acetone | <5 | <14 J | <18 J | <5 | <29 J |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 |
| Methylene chloride | <2 | <2 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | 0.87 J | 5.4 | 6.7 | 3.2 | 6.6 |
| 2-Butanone | <5 | R | R | <5 | R |
| cis-1,2-Dichloroethene | <1 | <1 | <1 | <1 | 2.7 |
| Chloroform | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | 2.5 | 3.3 | 1.8 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 | 0.5 J |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | 0.97 J | 0.5 J | 0.7 J | <1 | 1.2 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | R | <1 | <1 | R | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 |
| Toluene | <1 | 0.3 J | 0.8 J | <1 | 0.3 J |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | 17 | 1.3 | 1.3 | 1.1 | 3.3 |
| 2-Hexanone | <5 | <5 | R | <5 | <5 |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 | 20 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 18.84 | 10.8 | 13.9 | 6.1 | 35.8 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | PK-10I (Rep-2) 11/4/93 | PK-10I 12/1/93 | PK-10I (Rep-2) 12/1/93 | PK-10I 7/28/95 | PK-10D 11/4/93 |
|---------------------------------------|------------------------------|-------------------|------------------------------|-------------------|-------------------|
| Parameter (concentrations in ug/L) | | | | | |
| Dichlorodifluoromethane | <1 J | <1 | 0.2 J | <1 | <1 J |
| Chloromethane | <1 | <1 | <1 | <1 | <1 |
| Vinyl chloride | 0.8 J | 0.6 J | 0.7 J | <1 | <1 |
| Bromomethane | <1 J | <1 | <1 | <1 | <1 J |
| Chloroethane | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | 0.2 J | <1 | <1 |
| Acetone | <26 J | <23 J | <30 J | <5 | <16 J |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 |
| Methylene chloride | <2 | <2 | <2 | <2 | <2 |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | 6.3 | 5.4 | 5.6 | 4.5 | 0.4 J |
| 2-Butanone | R | R | R | <5 | R |
| cis-1,2-Dichloroethene | 2.5 | 1.3 | 1.4 | 2.2 | 0.4 J |
| Chloroform | <1 | <1 | <1 | <1 | <1 |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 |
| Benzene | 0.5 J | <1 | <1 | 0.34 J | 0.4 J |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | 1.2 | 0.9 J | 0.9 J | 1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | R | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <1 | <5 | <5 |
| Toluene | <1 | 0.8 J | 1.0 | <1 | 0.7 J |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | 3.3 | 1.4 | 1.5 | 3.1 | <1 |
| 2-Hexanone | <5 | R | R | <5 | <5 |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | 17 | 5.2 | 5.3 | 20 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 31.6 | 15.6 | 16.8 | 31.14 | 1.9 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | PK-10D 12/1/93 | PK-10D 7/28/95 | RW-12I 11/5/93 | RW-12I (Rep-3) 11/5/93 | RW-12I 12/2/93 |
|---------------------------------------|-------------------|-------------------|-------------------|------------------------------|-------------------|
| Parameter (concentrations in ug/L) | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <2 | <2 | <5 |
| Chloromethane | <1 | <1 | <2 | <2 | <5 |
| Vinyl chloride | <1 | <1 | <2 | <2 | 0.6 J |
| Bromomethane | <1 | <1 | <2 | <2 | <5 |
| Chloroethane | <1 | <1 | <2 | <2 | <5 |
| 1,1-Dichloroethane | <1 | <1 | 13 | 15 | 26 |
| Acetone | <25 J | <5 | R | R | <130 J |
| Carbon disulfide | <1 | <1 | <2 J | <2 J | <5 J |
| Methylene chloride | <2 | <2 | <2 | <4 | <10 |
| trans-1,2-Dichloroethene | <1 | <1 | <2 | <2 | <5 |
| 1,1-Dichloroethane | 0.5 J | 0.37 J | 11 | 13 | 17 |
| 2-Butanone | R | <5 | R | R | R |
| cis-1,2-Dichloroethene | 0.3 J | 0.39 J | 5.2 | 5.7 | 5.7 |
| Chloroform | <1 | <1 | <2 | <2 | <5 |
| 1,1,1-Trichloroethane | <1 | <1 | 40 | 40 | 75 |
| Carbon tetrachloride | <1 | <1 | <2 | <2 | <5 |
| Benzene | <1 | <1 | <2 | <2 | 0.6 J |
| 1,2-Dichloroethane | <1 | <1 | <2 | <2 | <5 |
| Trichloroethene | <1 | <1 | 6.2 | 6.3 | 9.8 |
| 1,2-Dichloropropane | <1 | <1 | <2 | <2 | <5 |
| Bromodichloromethane | <1 | <1 | <2 | <2 | <5 |
| 2-Chloroethylvinylether | <1 | R | <2 J | <2 J | <5 |
| cis-1,3-Dichloropropene | <1 | <1 | <2 | <2 | <5 |
| 4-Methyl-2-pentanone | <5 | <5 | <10 | <10 | <25 |
| Toluene | 5.7 | <1 | <2 | <2 | 13 |
| trans-1,3-Dichloropropene | <1 | <1 | <2 | <2 | <5 |
| 1,1,2-Trichloroethane | <1 | <1 | <2 | <2 | <5 |
| Tetrachloroethene | <1 | 0.25 J | 68 | 71 | 110 |
| 2-Hexanone | R | <5 | R | R | R |
| Dibromochloromethane | <1 | <1 | <2 | <2 | <5 |
| Chlorobenzene | <1 | <1 | 1.1 J | 1.3 J | 0.9 J |
| Ethylbenzene | <1 | <1 | <2 | <2 | <5 |
| meta and/or para-Xylene | <1 | <1 | <2 | <2 | <5 |
| ortho-Xylene | <1 | <1 | <2 | <2 | <5 |
| Styrene | <1 | <1 | <2 | <2 | <5 |
| Bromoform | <1 | <1 | <2 | <2 | <5 |
| Trichlorofluoromethane | <1 | <1 | <2 | <2 | 1.2 J |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <2 | <2 | <5 |
| Total VOCs: | 6.5 | 1.01 | 144.5 | 152.3 | 259.7 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| | Sample ID: Sample Date: | RW-12I (Rep-3) 12/2/93 | RW-12I 7/27/95 | RW-12I Rep-1 7/27/95 | RW-12D 11/5/93 | RW-12D 12/2/93 |
|---------------------------------------|----------------------------|------------------------------|-------------------|----------------------------|-------------------|-------------------|
| Parameter (concentrations in ug/L) | | | | | | |
| Dichlorodifluoromethane | | <5 | <10 | <10 | <1 | <1 |
| Chloromethane | | <5 | <10 | <10 | <1 | <1 |
| Vinyl chloride | | <5 | <10 | <10 | 9.2 | 17 |
| Bromomethane | | <5 | <10 | <10 | <1 | <1 J |
| Chloroethane | | <5 | <10 | <10 | <1 | <1 J |
| 1,1-Dichloroethane | | 27 | 31 | 28 | <1 | <1 |
| Acetone | | <130 J | <50 | <50 | <29 J | <21 J |
| Carbon disulfide | | <5 J | <10 | <10 | <1 J | <1 J |
| Methylene chloride | | <12 | <20 | <20 | <2 | <2 |
| trans-1,2-Dichloroethene | | <5 | <10 | <10 | <1 | <1 |
| 1,1-Dichloroethane | | 17 | 14 | 13 | <1 | 0.3 J |
| 2-Butanone | | R | <50 | <50 | R | R |
| cis-1,2-Dichloroethene | | 5.9 | 6 J | <10 | 2.6 | 2.3 |
| Chloroform | | <5 | 22 | 17 | <1.3 | <1.4 |
| 1,1,1-Trichloroethane | | 75 | 64 | 56 | <1 | <1 |
| Carbon tetrachloride | | <5 | <10 | <10 | <1 | <1 |
| Benzene | | 0.5 J | <10 | <10 | 0.4 J | 0.9 J |
| 1,2-Dichloroethane | | <5 | <10 | <10 | <1 | <1.8 |
| Trichloroethene | | 9.9 | 7.1 J | 6 J | 0.9 J | 1.1 |
| 1,2-Dichloropropane | | <5 | <10 | <10 | <1 | 1.0 |
| Bromodichloromethane | | <5 | 3 J | <10 | <1 | <1 |
| 2-Chloroethylvinylether | | <5 | R | R | <1 J | <1 |
| cis-1,3-Dichloropropene | | <5 | <10 | <10 | <1 | <1 |
| 4-Methyl-2-pentanone | | <25 | <50 | <50 | <5 | <5 |
| Toluene | | 12 | <10 | <10 | 0.7 J | 6.6 |
| trans-1,3-Dichloropropene | | <5 | <10 | <10 | <1 | <1 |
| 1,1,2-Trichloroethane | | <5 | <10 | <10 | <1 | <1 |
| Tetrachloroethene | | 110 | 150 | 140 | 2.6 | 2.4 |
| 2-Hexanone | | R | <50 | <50 | R | R |
| Dibromochloromethane | | <5 | <10 | <10 | <1 | <1 |
| Chlorobenzene | | 0.9 J | <10 | <10 | <1 | 0.3 J |
| Ethylbenzene | | <5 | <10 | <10 | <1 | <1 |
| meta and/or para-Xylene | | <5 | <10 | <10 | <1 | <1 |
| ortho-Xylene | | <5 | <10 | <10 | <1 | <1 |
| Styrene | | <5 | <10 | <10 | <1 | <1 |
| Bromoform | | <5 | <10 | <10 | <1 | <1 |
| Trichlorofluoromethane | | 1.2 J | <10 | <10 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | | <5 | <10 | <10 | <1 | <1 |
| Total VOCs: | | 259.4 | 297.1 | 260 | 16.4 | 31.9 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | RW-12D 7/27/95 | Trip Blank 11/2/93 | Trip Blank 11/4/93 | Trip Blank 11/5/93 | Trip Blank 12/1/93 |
|---------------------------------------|-------------------|-----------------------|-----------------------|-----------------------|-----------------------|
| Parameter (concentrations in ug/L) | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <1 J | <1 J | <1 |
| Chloromethane | <1 | <1 J | <1 | <1 | <1 |
| Vinyl chloride | 12 | <1 | <1 | <1 | <1 |
| Bromomethane | <1 | <1 J | <1 J | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| Acetone | <5 | 34 JB | 14 J | 35 J | 14 JB |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 |
| Methylene chloride | <2 | 1 JB | 0.4 JB | 0.5 JB | 0.8 JB |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <1 | <1 | <1 |
| 2-Butanone | <5 | R | R | R | R |
| cis-1,2-Dichloroethene | 2.9 | <1 | <1 | <1 | <1 |
| Chloroform | <1.5 | 1.1 | 1.0 B | 0.8 JB | 1.0 B |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 |
| Benzene | 1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | <1 | <1 | <1 | <1 | <1 |
| Trichloroethene | 1.1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | R | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | <1 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | 3 | <1 | <1 | <1 | <1 |
| 2-Hexanone | <5 | R | <5 | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | 0.47 J | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 J | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 20.47 | 36.1 | 15.4 | 36.3 | 15.8 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Trip Blank 12/2/93 | Trip Blank 12/3/93 | Trip Blank 7/27/95 | Trip Blank 7/28/95 | Field Blank 11/2/93 |
|---------------------------------------|-----------------------|-----------------------|-----------------------|-----------------------|------------------------|
| Parameter (concentrations in ug/L) | | | | | |
| Dichlorodifluoromethane | <1 | <1 | <1 | <1 | <1 |
| Chloromethane | <1 | <1 | <1 | <1 | <1 J |
| Vinyl chloride | <1 | <1 | <1 | <1 | <1 |
| Bromomethane | <1 J | <1 | <1 | <1 | <1 J |
| Chloroethane | <1 J | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| Acetone | 24 J | 50 JB | <5 | <5 | 21 JB |
| Carbon disulfide | <1 J | <1 | <1 | <1 | <1 |
| Methylene chloride | 0.7 JB | 0.7 JB | <2 | 0.22 J | 0.8 JB |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <1 | <1 | <1 |
| 2-Butanone | R | R | <5 | <5 | R |
| cis-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| Chloroform | 0.9 JB | 0.9 JB | <1 | 0.86 J | 1.1 |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | 0.8 J | 1.5 | <1 | <1 | 0.4 J |
| Trichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | R | R | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | <1 | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | <1 | <1 |
| 2-Hexanone | R | R | <5 | <5 | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 | <1 | <1 | <1 |
| Total VOCs: | 26.4 | 53.1 | 0 | 1.08 | 23.3 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Field Blank 11/4/93 | Field Blank 11/5/93 | Field Blank 12/1/93 | Field Blank 12/2/93 | Field Blank 12/3/93 |
|---------------------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|
| Parameter (concentrations in ug/L) | | | | | |
| Dichlorodifluoromethane | 1.0 J | <1 J | <1 | <1 | <1 |
| Chloromethane | 0.4 J | <1 | <1 | <1 | <1 |
| Vinyl chloride | <1 | <1 | <1 | <1 | <1 |
| Bromomethane | <1 J | <1 | <1 | <1 | <1 |
| Chloroethane | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| Acetone | 55 J | 29 J | 31 JB | 34 JB | 34 JB |
| Carbon disulfide | <1 | <1 | <1 | <1 | <1 |
| Methylene chloride | 0.3 JB | 0.5 JB | 2.1 JB | 2.4 JB | 2.1 B |
| trans-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 | <1 | <1 | <1 |
| 2-Butanone | R | R | R | R | R |
| cis-1,2-Dichloroethene | <1 | <1 | <1 | <1 | <1 |
| Chloroform | 1.2 B | 1.0 B | 0.8 JB | 0.9 JB | 0.8 JB |
| 1,1,1-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Carbon tetrachloride | <1 | <1 | <1 | <1 | <1 |
| Benzene | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloroethane | 0.4 J | <1 | 0.8 J | 0.5 J | <1 |
| Trichloroethene | <1 | <1 | <1 | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 | <1 | <1 | <1 |
| Bromodichloromethane | <1 | <1 | <1 | <1 | <1 |
| 2-Chloroethylvinylether | <1 | <1 | <1 | <1 | <1 |
| cis-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 4-Methyl-2-pentanone | 5.3 | <5 | <5 | <5 | <5 |
| Toluene | <1 | <1 | <1 | 0.2 J | <1 |
| trans-1,3-Dichloropropene | <1 | <1 | <1 | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 | <1 | <1 | <1 |
| Tetrachloroethene | <1 | <1 | <1 | <1 | <1 |
| 2-Hexanone | <5 | <5 | R | R | R |
| Dibromochloromethane | <1 | <1 | <1 | <1 | <1 |
| Chlorobenzene | <1 | <1 | <1 | <1 | <1 |
| Ethylbenzene | <1 | <1 | <1 | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 | <1 | <1 | <1 |
| ortho-Xylene | <1 | <1 | <1 | <1 | <1 |
| Styrene | <1 | <1 | <1 | <1 | <1 |
| Bromoform | <1 | <1 J | <1 | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 | <1 | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | 0.6 J | <1 | <1 | <1 | <1 |
| Total VOCs: | 64.2 | 30.5 | 34.7 | 38 | 36.9 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 1. Concentrations of Volatile Organic Compounds Detected in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Sample ID: Sample Date: | Field Blank 7/27/95 | Field Blank 7/28/95 |
|---------------------------------------|------------------------|------------------------|
| Parameter (concentrations in ug/L) | | |
| Dichlorodifluoromethane | <1 | <1 |
| Chloromethane | <1 | <1 |
| Vinyl chloride | <1 | <1 |
| Bromomethane | <1 | <1 |
| Chloroethane | <1 | <1 |
| 1,1-Dichloroethene | <1 | <1 |
| Acetone | <5 | <5 |
| Carbon disulfide | <1 | <1 |
| Methylene chloride | 0.57 J | 0.42 J |
| trans-1,2-Dichloroethene | <1 | <1 |
| 1,1-Dichloroethane | <1 | <1 |
| 2-Butanone | <5 | <5 |
| cis-1,2-Dichloroethene | <1 | <1 |
| Chloroform | 1.9 | 1.9 |
| 1,1,1-Trichloroethane | <1 | <1 |
| Carbon tetrachloride | <1 | <1 |
| Benzene | <1 | <1 |
| 1,2-Dichloroethane | 1 | <1 |
| Trichloroethene | <1 | <1 |
| 1,2-Dichloropropane | <1 | <1 |
| Bromodichloromethane | <1 | <1 |
| 2-Chloroethylvinylether | R | R |
| cis-1,3-Dichloropropene | <1 | <1 |
| 4-Methyl-2-pentanone | <5 | <5 |
| Toluene | <1 | <1 |
| trans-1,3-Dichloropropene | <1 | <1 |
| 1,1,2-Trichloroethane | <1 | <1 |
| Tetrachloroethene | <1 | <1 |
| 2-Hexanone | <5 | <5 |
| Dibromochloromethane | <1 | <1 |
| Chlorobenzene | <1 | <1 |
| Ethylbenzene | <1 | <1 |
| meta and/or para-Xylene | <1 | <1 |
| ortho-Xylene | <1 | <1 |
| Styrene | <1 | <1 |
| Bromoform | <1 | <1 |
| Trichlorofluoromethane | <1 | <1 |
| 1,1,2,2-Tetrachloroethane | <1 | <1 |
| Total VOCs: | 3.47 | 2.32 |

ug/L Micrograms per liter.

VOCs Volatile organic compounds.

J Estimated value.

B Compound was also detected in the associated method blank.

R Unusable value.



Table 2. Average PCE, TCA, Total Breakdown Products, and Total Volatile Organic Compounds in Groundwater Samples Collected from Monitoring Wells During Three Sampling Rounds, Syosset Landfill, Syosset, New York.

| Well | PCE, ppb | TCA, ppb | Total Breakdown Products, ppb | Ratio of Total Breakdown Products, ppb | Total VOC's ppb |
|-------|----------|----------|-------------------------------|--|-----------------|
| | | | | PCE and TCA, pbb | |
| | | | Upgradient Well | | |
| SY-4 | 0.0 | 0.0 | 2.8 | - | 12.3 |
| | | | On-Site Wells | | |
| SY-1D | 2.0 | 0.0 | 10.6 | 5.3 | 26.6 |
| SY-2D | 0.5 | 1.1 | 4.2 | 2.6 | 6.5 |
| SY-3 | 0.0 | 0.0 | 7.8 | - | 11.2 |
| SY-3D | 0.0 | 0.0 | 1.7 | - | 6.2 |
| SY-8 | 14.7 | 0.3 | 3.4 | 0.2 | 18.4 |
| SY-9 | 0.0 | 0.0 | 0.2 | - | 1.6 |
| | | | Off-Site Wells | | |
| 10S | 1.2 | 2.5 | 6.1 | 1.6 | 10.3 |
| 10I | 2.5 | 0.0 | 9.6 | 3.8 | 26.2 |
| 10D | 0.1 | 0.0 | 0.8 | 8.0 | 3.1 |
| 11I | 21.0 | 4.1 | 18.9 | 0.8 | 47.0 |
| 12I | 108.3 | 58.4 | 49.9 | 0.3 | 229.0 |
| 12D | 2.7 | 0.0 | 16.4 | 6.1 | 23.0 |

ppb - Parts per billion

Three sampling rounds - November and December 1993 and July 1995

- Cannot calculate ratio due to zero in denominator